

(12) **United States Patent**
Henry et al.

(10) **Patent No.:** US 10,594,039 B2
(45) **Date of Patent:** *Mar. 17, 2020

(54) **APPARATUS AND METHODS FOR SENDING OR RECEIVING ELECTROMAGNETIC SIGNALS**

(71) Applicant: **AT&T Intellectual Property I, L.P.**,
Atlanta, GA (US)

(72) Inventors: **Paul Shala Henry**, Holmdel, NJ (US);
Thomas M. Willis, III, Tinton Falls,
NJ (US); **Robert Bennett**, Southold,
NY (US); **Farhad Barzegar**,
Branchburg, NJ (US); **Irwin**
Gerszberg, Kendall Park, NJ (US);
Donald J. Barnickel, Flemington, NJ
(US)

(73) Assignee: **AT&T Intellectual Property I, L.P.**,
Atlanta, GA (US)

(*) Notice: Subject to any disclaimer, the term of this
patent is extended or adjusted under 35
U.S.C. 154(b) by 0 days.

This patent is subject to a terminal dis-
claimer.

(21) Appl. No.: **16/198,120**

(22) Filed: **Nov. 21, 2018**

(65) **Prior Publication Data**

US 2019/0097324 A1 Mar. 28, 2019

Related U.S. Application Data

(60) Division of application No. 15/274,987, filed on Sep.
23, 2016, now Pat. No. 10,170,840, which is a
(Continued)

(51) **Int. Cl.**
H01P 5/08 (2006.01)
H01Q 13/06 (2006.01)
(Continued)

(52) **U.S. Cl.**
CPC **H01Q 13/06** (2013.01); **H01P 3/16**
(2013.01); **H01P 5/087** (2013.01); **H01Q 1/50**
(2013.01);
(Continued)

(58) **Field of Classification Search**
CPC H01P 5/00; H01P 5/04; H01P 5/08; H01P
5/087

(Continued)

(56) **References Cited**

U.S. PATENT DOCUMENTS

2,419,205 A 4/1947 Feldman et al.
2,542,980 A 2/1951 Barrow
(Continued)

FOREIGN PATENT DOCUMENTS

CA 2515560 A1 2/2007
CA 2927054 A1 5/2015
(Continued)

OTHER PUBLICATIONS

“WO Amendment Under Article 34 and Response to Written
Opinion Filed May 15, 2017”, Application No. PCT/US16/41561
filed Jul. 8, 2016, 1-14.

(Continued)


Primary Examiner — Stephen E. Jones

(74) *Attorney, Agent, or Firm* — Guntin & Gust, PLC;
Matthew Tropper

(57) **ABSTRACT**

Aspects of the subject disclosure may include a generator
that facilitates generation of an electromagnetic wave, a
core, and a waveguide that facilitates guiding the electro-
magnetic wave towards the core to induce a second elec-
tromagnetic wave that propagates along the core. The core
and/or the waveguide can be configured to reduce radiation
loss of the second electromagnetic wave, propagation loss of
the second electromagnetic wave, or a combination thereof.
Other embodiments are disclosed.

20 Claims, 80 Drawing Sheets



Related U.S. Application Data

continuation-in-part of application No. 14/965,523, filed on Dec. 10, 2015, now Pat. No. 10,033,107, which is a continuation-in-part of application No. 14/885,463, filed on Oct. 16, 2015, now Pat. No. 9,722,318, which is a continuation-in-part of application No. 14/799,272, filed on Jul. 14, 2015, now Pat. No. 9,628,116.

(51) Int. Cl.

H01Q 1/50 (2006.01)
H01P 3/16 (2006.01)
H01Q 19/08 (2006.01)
H04B 3/52 (2006.01)
H01P 1/16 (2006.01)
H01Q 3/08 (2006.01)
H01Q 3/36 (2006.01)
H01Q 13/02 (2006.01)
H01Q 21/20 (2006.01)
H04B 3/00 (2006.01)
H04B 5/00 (2006.01)
H04B 3/54 (2006.01)
H01R 3/00 (2006.01)

(52) U.S. Cl.

CPC **H01Q 19/08** (2013.01); **H04B 3/52** (2013.01); **H01P 1/16** (2013.01); **H01P 5/08** (2013.01); **H01Q 3/08** (2013.01); **H01Q 3/36** (2013.01); **H01Q 13/02** (2013.01); **H01Q 21/205** (2013.01); **H01R 3/00** (2013.01); **H04B 3/00** (2013.01); **H04B 3/54** (2013.01); **H04B 5/0018** (2013.01)

(58) Field of Classification Search

USPC ... 333/251, 21 R, 21 A, 24 R, 239, 242, 248
 See application file for complete search history.

(56) References Cited**U.S. PATENT DOCUMENTS**

2,596,190 A 5/1952 Wiley
 2,659,817 A 11/1953 Cutler et al.
 2,685,068 A 7/1954 Goubau
 2,852,753 A 9/1958 Walter et al.
 2,867,776 A 1/1959 Wilkinson, Jr.
 2,912,695 A 11/1959 Cutler
 2,921,277 A 1/1960 Goubau
 3,025,478 A 3/1962 Marcatili et al.
 3,201,724 A 8/1965 Hafner
 3,321,763 A 5/1967 Ikrath et al.
 3,389,394 A 6/1968 Lewis et al.
 3,411,112 A 11/1968 Honig et al.
 3,414,903 A 12/1968 Bartlett et al.
 3,522,560 A 8/1970 Hayany
 3,566,317 A 2/1971 Theodore
 3,796,970 A 3/1974 Snell
 3,858,214 A 12/1974 Jones
 3,935,577 A 1/1976 Hansen et al.
 4,246,584 A 1/1981 Noerpel et al.
 4,333,082 A 6/1982 Susman et al.
 4,589,424 A 5/1986 Vaguine et al.
 4,604,627 A 8/1986 Saad et al.
 4,660,050 A 4/1987 Phillips et al.
 4,665,660 A 5/1987 Krall et al.
 4,783,665 A 11/1988 Lier et al.
 4,788,553 A 11/1988 Phillips et al.
 4,825,221 A 4/1989 Suzuki et al.
 4,873,534 A 10/1989 Wohlleben et al.
 4,929,962 A 5/1990 Begout et al.
 4,989,011 A 1/1991 Rosen et al.
 5,017,936 A 5/1991 Massey et al.
 5,488,380 A 1/1996 Harvey et al.

5,557,283 A 9/1996 Sheen
 5,640,168 A 6/1997 Heger et al.
 5,642,121 A 6/1997 Martek et al.
 5,684,495 A 11/1997 Dyott et al.
 5,706,017 A 1/1998 Buttgenbach
 5,769,879 A 6/1998 Levay et al.
 5,854,608 A 12/1998 Leisten
 5,889,449 A 3/1999 Fiedziuszek
 5,937,335 A 8/1999 Park et al.
 5,955,992 A 9/1999 Shattil
 6,014,110 A 1/2000 Bridges et al.
 6,023,201 A 2/2000 Lamesch et al.
 6,026,173 A 2/2000 Svenson et al.
 6,163,296 A 12/2000 Lier et al.
 6,208,308 B1 3/2001 Lemons et al.
 6,208,903 B1 3/2001 Richards et al.
 6,211,837 B1 4/2001 Crouch et al.
 6,239,377 B1 5/2001 Nishikawa et al.
 6,292,139 B1 9/2001 Yamamoto et al.
 6,320,553 B1 11/2001 Ergene et al.
 6,362,788 B1 3/2002 Louzir
 6,469,676 B1 10/2002 Fehrenbach et al.
 6,522,305 B2 2/2003 Sharman et al.
 6,531,991 B2 3/2003 Adachi et al.
 6,535,169 B2 3/2003 Fourdeux et al.
 6,573,813 B1 6/2003 Joannopoulos et al.
 6,590,544 B1 7/2003 Filipovic
 6,661,389 B2 12/2003 Griessbaum et al.
 6,728,439 B2 4/2004 Weisberg et al.
 6,809,633 B2 10/2004 Cern et al.
 6,812,895 B2 11/2004 Anderson et al.
 6,861,998 B2 3/2005 Louzir
 6,864,853 B2 3/2005 Judd et al.
 6,867,744 B2 3/2005 Toncich et al.
 6,943,553 B2 9/2005 Zimmermann et al.
 6,992,639 B1 1/2006 Lier et al.
 7,009,471 B2 3/2006 Elmore
 7,042,416 B2 5/2006 Kingsley et al.
 7,043,271 B1 5/2006 Seto et al.
 7,075,414 B2 7/2006 Giannini et al.
 7,109,939 B2 9/2006 Lynch et al.
 7,122,012 B2 10/2006 Bouton et al.
 7,138,767 B2 11/2006 Chen et al.
 7,180,459 B2 2/2007 Damini et al.
 7,280,033 B2 10/2007 Berkman et al.
 7,301,424 B2 11/2007 Suarez-gartner et al.
 7,301,440 B2 11/2007 Mollenkopf
 7,307,357 B2 12/2007 Kopp et al.
 7,345,623 B2 3/2008 McEwan et al.
 7,369,095 B2 5/2008 Thudor et al.
 7,379,030 B1 5/2008 Lier
 7,382,232 B2 6/2008 Gidge et al.
 7,443,334 B2 10/2008 Rees et al.
 7,453,393 B2 11/2008 Duivenvoorden et al.
 7,525,501 B2 4/2009 Black et al.
 7,551,921 B2 6/2009 Petermann et al.
 7,567,154 B2 7/2009 Elmore
 7,590,404 B1 9/2009 Johnson et al.
 7,591,792 B2 9/2009 Bouton et al.
 7,605,768 B2 10/2009 Ebling et al.
 7,656,358 B2 2/2010 Haziza et al.
 7,672,271 B2 3/2010 Lee et al.
 7,683,848 B2 3/2010 Musch et al.
 7,797,367 B1 9/2010 Girod et al.
 7,808,441 B2 10/2010 Parsche et al.
 7,872,610 B2 1/2011 Motzer et al.
 7,915,980 B2 3/2011 Hardacker et al.
 7,925,235 B2 4/2011 Konya et al.
 8,159,385 B2 4/2012 Farneth et al.
 8,212,635 B2 7/2012 Miller, II et al.
 8,237,617 B1 8/2012 Johnson et al.
 8,253,516 B2 8/2012 Miller, II et al.
 8,264,417 B2 9/2012 Snow et al.
 8,269,583 B2 9/2012 Miller, II et al.
 8,284,102 B2 10/2012 Hayes et al.
 8,344,829 B2 1/2013 Miller, II et al.
 8,736,502 B1 5/2014 Mehr et al.
 8,773,312 B1 7/2014 Diaz et al.
 8,836,503 B2 9/2014 Girod et al.

(56)

References Cited

U.S. PATENT DOCUMENTS

8,878,740 B2	11/2014	Coupland et al.	10,051,488 B1	8/2018	Vannucci et al.
8,897,697 B1	11/2014	Bennett et al.	10,062,970 B1	8/2018	Vannucci et al.
8,947,258 B2	2/2015	Pant et al.	10,069,535 B2	9/2018	Vannucci et al.
8,948,690 B2	2/2015	Duerksen et al.	10,079,661 B2	9/2018	Gerszberg et al.
8,957,819 B2	2/2015	Lin et al.	10,090,606 B2	10/2018	Henry et al.
9,024,831 B2	5/2015	Wang et al.	10,096,883 B2	10/2018	Henry et al.
9,091,584 B2	7/2015	Vogt et al.	10,103,777 B1	10/2018	Henry et al.
9,099,787 B2	8/2015	Blech	10,103,801 B2	10/2018	Bennett et al.
9,113,347 B2	8/2015	Paul Shala	10,123,217 B1	11/2018	Barzegar et al.
9,209,902 B2	12/2015	Willis, III et al.	10,129,057 B2	11/2018	Willis, III et al.
9,276,304 B2	3/2016	Behan	10,135,145 B2	11/2018	Henry et al.
9,287,605 B2	3/2016	Daughenbaugh et al.	10,136,434 B2	11/2018	Gerszberg et al.
9,293,801 B2	3/2016	Courtney et al.	10,142,086 B2	11/2018	Bennett et al.
9,312,919 B1	4/2016	Barzegar et al.	10,148,016 B2	12/2018	Johnson et al.
9,461,706 B1	10/2016	Bennett et al.	10,154,493 B2	12/2018	Bennett et al.
9,479,241 B2	10/2016	Pabla	10,170,840 B2 *	1/2019	Henry H01Q 13/06
9,490,869 B1	11/2016	Henry	10,171,158 B1	1/2019	Barzegar et al.
9,509,415 B1	11/2016	Henry et al.	10,200,106 B1	2/2019	Barzegar et al.
9,520,945 B2	12/2016	Gerszberg et al.	10,205,212 B2	2/2019	Henry et al.
9,525,524 B2	12/2016	Barzegar et al.	10,205,231 B1	2/2019	Henry et al.
9,544,006 B2	1/2017	Henry et al.	10,205,655 B2	2/2019	Barzegar et al.
9,564,947 B2	2/2017	Stuckman et al.	10,224,981 B2	3/2019	Henry et al.
9,577,306 B2	2/2017	Willis, III et al.	10,230,426 B1	3/2019	Henry et al.
9,608,692 B2	3/2017	Willis, III et al.	10,230,428 B1	3/2019	Barzegar et al.
9,608,740 B2	3/2017	Henry et al.	10,243,270 B2	3/2019	Henry et al.
9,615,269 B2	4/2017	Henry et al.	10,244,408 B1	3/2019	Vannucci et al.
9,627,768 B2	4/2017	Henry et al.	10,264,586 B2	4/2019	Beattie, Jr. et al.
9,628,116 B2	4/2017	Willis, III et al.	10,276,907 B2	4/2019	Bennett et al.
9,640,850 B2	5/2017	Henry et al.	10,284,261 B1	5/2019	Barzegar et al.
9,653,770 B2	5/2017	Henry et al.	10,291,286 B2	5/2019	Henry et al.
9,680,670 B2	6/2017	Henry et al.	10,305,190 B2	5/2019	Britz et al.
9,692,101 B2	6/2017	Henry et al.	10,305,192 B1	5/2019	Rappaport
9,705,561 B2	7/2017	Henry et al.	10,305,197 B2	5/2019	Henry et al.
9,705,571 B2	7/2017	Gerszberg et al.	10,305,545 B2	5/2019	Adriazola et al.
9,722,318 B2	8/2017	Adriazola et al.	10,312,567 B2	6/2019	Bennett et al.
9,742,462 B2	8/2017	Bennett et al.	10,320,046 B2	6/2019	Bennett et al.
9,748,626 B2	8/2017	Henry et al.	10,340,573 B2	7/2019	Johnson et al.
9,749,053 B2	8/2017	Henry et al.	10,340,600 B2	7/2019	Henry et al.
9,768,833 B2	9/2017	Fuchs et al.	10,340,979 B1	7/2019	Barzegar et al.
9,769,020 B2	9/2017	Henry et al.	10,348,391 B2	7/2019	Bennett et al.
9,780,834 B2	10/2017	Henry et al.	10,355,745 B2	7/2019	Henry et al.
9,793,951 B2	10/2017	Henry et al.	10,361,489 B2	7/2019	Britz et al.
9,793,954 B2	10/2017	Bennett et al.	10,371,889 B1	8/2019	Barzegar et al.
9,847,566 B2	12/2017	Henry et al.	10,374,277 B2	8/2019	Henry et al.
9,853,342 B2	12/2017	Henry et al.	10,374,278 B2	8/2019	Henry et al.
9,860,075 B1	1/2018	Gerszberg et al.	10,374,281 B2	8/2019	Henry et al.
9,865,911 B2	1/2018	Henry et al.	10,374,316 B2	8/2019	Bennett et al.
9,866,309 B2	1/2018	Bennett et al.	10,389,029 B2	8/2019	Henry et al.
9,871,282 B2	1/2018	Henry et al.	10,389,037 B2	8/2019	Johnson et al.
9,871,283 B2	1/2018	Henry et al.	10,389,403 B2	8/2019	Henry et al.
9,876,264 B2	1/2018	Barnickel et al.	10,389,419 B2	8/2019	Johnson et al.
9,876,570 B2	1/2018	Henry et al.	10,405,199 B1	9/2019	Henry et al.
9,876,605 B1	1/2018	Henry et al.	10,411,356 B2	9/2019	Johnson et al.
9,882,257 B2	1/2018	Henry et al.	10,411,920 B2	9/2019	Henry et al.
9,882,608 B2	1/2018	Adriazola et al.	10,424,845 B2	9/2019	Johnson et al.
9,893,795 B1	2/2018	Willis et al.	2002/0030632 A1	3/2002	Popa et al.
9,912,381 B2	3/2018	Bennett et al.	2003/0022694 A1	1/2003	Olsen et al.
9,917,341 B2	3/2018	Henry et al.	2003/0151548 A1	8/2003	Kingsley et al.
9,929,755 B2	3/2018	Henry et al.	2004/0106140 A1	6/2004	Thill
9,991,580 B2	6/2018	Henry et al.	2004/0110469 A1	6/2004	Judd et al.
9,997,819 B2	6/2018	Bennett et al.	2004/0113756 A1	6/2004	Mollenkopf et al.
9,998,172 B1	6/2018	Barzegar et al.	2004/0218688 A1	11/2004	Santhoff et al.
9,998,870 B1	6/2018	Bennett et al.	2005/0017825 A1	1/2005	Hansen
9,999,038 B2	6/2018	Barzegar et al.	2005/0042989 A1	2/2005	Ho et al.
10,003,364 B1	6/2018	Willis, III et al.	2005/0074208 A1	4/2005	Badcock et al.
10,009,063 B2	6/2018	Gerszberg et al.	2005/0111533 A1	5/2005	Berkman et al.
10,009,065 B2	6/2018	Henry et al.	2005/0190101 A1	9/2005	Hiramatsu et al.
10,009,067 B2	6/2018	Birk et al.	2005/0249245 A1	11/2005	Hazani et al.
10,009,901 B2	6/2018	Gerszberg	2005/0258920 A1	11/2005	Elmore et al.
10,027,397 B2	7/2018	Kim	2006/0083269 A1	4/2006	Kang et al.
10,027,427 B2	7/2018	Vannucci et al.	2006/0202909 A1	9/2006	Nagai
10,033,107 B2	7/2018	Henry et al.	2008/0064331 A1	3/2008	Washiro et al.
10,033,108 B2	7/2018	Henry et al.	2008/0125036 A1	5/2008	Konya et al.
10,044,409 B2	8/2018	Barzegar et al.	2008/0211727 A1	9/2008	Elmore et al.
10,051,483 B2	8/2018	Barzegar et al.	2008/0252541 A1	10/2008	Diaz et al.
			2008/0309571 A1	12/2008	Diaz et al.
			2009/0012768 A1	1/2009	Son et al.
			2009/0079660 A1	3/2009	Elmore et al.
			2009/0212996 A1	8/2009	Chen et al.

(56)

References Cited

U.S. PATENT DOCUMENTS

2009/0258652 A1	10/2009	Lambert et al.	2018/0048497 A1	2/2018	Henry et al.
2010/0026607 A1	2/2010	Imai et al.	2018/0054232 A1	2/2018	Henry et al.
2010/0214185 A1	8/2010	Sammoura et al.	2018/0054233 A1	2/2018	Henry et al.
2010/0220024 A1	9/2010	Snow et al.	2018/0054234 A1	2/2018	Stuckman et al.
2010/0225426 A1	9/2010	Unger et al.	2018/0062886 A1	3/2018	Paul et al.
2010/0277003 A1	11/2010	Von Novak et al.	2018/0069594 A1	3/2018	Henry et al.
2011/0036617 A1	2/2011	Kokurin	2018/0069731 A1	3/2018	Henry et al.
2011/0109499 A9	5/2011	Kienzle et al.	2018/0074568 A1	3/2018	Priyadarshi et al.
2011/0110404 A1	5/2011	Washiro	2018/0076982 A1	3/2018	Henry et al.
2011/0132658 A1	6/2011	Miller, II et al.	2018/0076988 A1	3/2018	Willis, III et al.
2011/0136432 A1	6/2011	Miller, II et al.	2018/0077709 A1	3/2018	Gerszberg
2011/0140911 A1	6/2011	Pant et al.	2018/0108997 A1	4/2018	Henry et al.
2011/0187578 A1	8/2011	Farneth et al.	2018/0108998 A1	4/2018	Henry et al.
2011/0220394 A1	9/2011	Szylakowski et al.	2018/0108999 A1	4/2018	Henry et al.
2011/0311231 A1	12/2011	Ridgway et al.	2018/0115040 A1	4/2018	Bennett et al.
2012/0098726 A1	4/2012	Gottl et al.	2018/0115044 A1	4/2018	Henry et al.
2012/0099112 A1	4/2012	Alphonse et al.	2018/0115058 A1	4/2018	Henry et al.
2012/0133373 A1	5/2012	Ali et al.	2018/0115060 A1	4/2018	Bennett et al.
2012/0206312 A1	8/2012	Coupland et al.	2018/0115075 A1	4/2018	Bennett et al.
2012/0306587 A1	12/2012	Strid et al.	2018/0115081 A1	4/2018	Johnson et al.
2013/0064311 A1	3/2013	Turner et al.	2018/0123207 A1	5/2018	Henry et al.
2013/0099989 A1	4/2013	Pantea et al.	2018/0123208 A1	5/2018	Henry et al.
2013/0169499 A1	7/2013	Lin et al.	2018/0123643 A1	5/2018	Henry et al.
2013/0234904 A1	9/2013	Blech et al.	2018/0123836 A1	5/2018	Henry et al.
2014/0047917 A1	2/2014	Vogt et al.	2018/0131406 A1	5/2018	Adriazola et al.
2014/0285277 A1	9/2014	Herbsommer et al.	2018/0151957 A1	5/2018	Bennett et al.
2014/0334773 A1	11/2014	Mathai et al.	2018/0159195 A1	6/2018	Henry et al.
2015/0008996 A1	1/2015	Jessup et al.	2018/0159196 A1	6/2018	Henry et al.
2015/0102972 A1	4/2015	Scire-Scappuzzo et al.	2018/0159197 A1	6/2018	Henry et al.
2015/0188584 A1	7/2015	Laurent-Michel et al.	2018/0159228 A1	6/2018	Britz et al.
2015/0276577 A1	10/2015	Ruege et al.	2018/0159229 A1	6/2018	Britz
2015/0325913 A1	11/2015	Vagman	2018/0159230 A1	6/2018	Henry et al.
2015/0346440 A1	12/2015	Craddock et al.	2018/0159232 A1	6/2018	Henry et al.
2016/0064794 A1	3/2016	Henry et al.	2018/0159235 A1	6/2018	Wolniansky
2016/0080035 A1	3/2016	Fuchs et al.	2018/0159238 A1	6/2018	Wolniansky
2016/0080839 A1	3/2016	Fuchs et al.	2018/0159240 A1	6/2018	Henry et al.
2016/0094879 A1	3/2016	Gerszberg et al.	2018/0159243 A1	6/2018	Britz et al.
2016/0105218 A1	4/2016	Henry et al.	2018/0159615 A1	6/2018	Kim
2016/0112092 A1	4/2016	Henry et al.	2018/0166761 A1	6/2018	Henry et al.
2016/0112093 A1	4/2016	Barzegar	2018/0166784 A1	6/2018	Johnson et al.
2016/0112132 A1	4/2016	Henry et al.	2018/0166785 A1	6/2018	Henry et al.
2016/0112133 A1	4/2016	Henry et al.	2018/0166787 A1	6/2018	Johnson et al.
2016/0149312 A1	5/2016	Henry et al.	2018/0167130 A1	6/2018	Vannucci
2016/0149665 A1	5/2016	Henry et al.	2018/0167927 A1	6/2018	Beattie, Jr. et al.
2016/0164571 A1	6/2016	Bennett et al.	2018/0175892 A1	6/2018	Henry et al.
2016/0164573 A1	6/2016	Birk et al.	2018/0249342 A1	8/2018	Rappaport
2016/0182096 A1	6/2016	Panioukov et al.	2018/0301812 A1	10/2018	Henry et al.
2016/0221039 A1	8/2016	Fuchs et al.	2018/0302162 A1	10/2018	Gerszberg et al.
2016/0226681 A1	8/2016	Henry et al.	2018/0309206 A1	10/2018	Henry et al.
2016/0261310 A1	9/2016	Fuchs et al.	2019/0013577 A1	1/2019	Henry et al.
2016/0315662 A1	10/2016	Henry	2019/0013837 A1	1/2019	Henry et al.
2016/0359541 A1	12/2016	Bennett	2019/0074563 A1	3/2019	Henry et al.
2016/0359546 A1	12/2016	Bennett	2019/0074564 A1	3/2019	Henry et al.
2016/0360533 A1	12/2016	Bennett et al.	2019/0074565 A1	3/2019	Henry et al.
2016/0365966 A1	12/2016	Bennett et al.	2019/0074580 A1	3/2019	Henry et al.
2017/0012667 A1	1/2017	Bennett	2019/0074864 A1	3/2019	Henry et al.
2017/0018851 A1	1/2017	Henry et al.	2019/0074865 A1	3/2019	Henry et al.
2017/0018852 A1	1/2017	Adriazola et al.	2019/0074878 A1	3/2019	Henry et al.
2017/0019130 A1	1/2017	Henry et al.	2019/0081747 A1	3/2019	Barzegar et al.
2017/0019131 A1	1/2017	Henry et al.	2019/0089063 A1	3/2019	Johnson et al.
2017/0019150 A1	1/2017	Henry	2019/0104012 A1	4/2019	Barzegar et al.
2017/0033465 A1	2/2017	Henry et al.	2019/0104419 A1	4/2019	Barzegar et al.
2017/0033466 A1	2/2017	Henry et al.	2019/0104420 A1	4/2019	Barzegar et al.
2017/0033953 A1	2/2017	Shala et al.	2019/0115642 A1	4/2019	Henry et al.
2017/0033954 A1	2/2017	Henry et al.	2019/0123442 A1	4/2019	Vannucci et al.
2017/0079037 A1	3/2017	Gerszberg et al.	2019/0123783 A1	4/2019	Henry et al.
2017/0079039 A1	3/2017	Gerszberg et al.	2019/0131717 A1	5/2019	Vannucci
2017/0085003 A1	3/2017	Johnson et al.	2019/0131718 A1	5/2019	Vannucci
2017/0093693 A1	3/2017	Barzegar et al.	2019/0140679 A1	5/2019	Vannucci et al.
2017/0110795 A1	4/2017	Henry	2019/0140871 A1	5/2019	Henry et al.
2017/0110804 A1	4/2017	Henry et al.	2019/0140938 A1	5/2019	Barzegar et al.
2017/0179608 A1	6/2017	Henry et al.	2019/0141714 A1	5/2019	Willis, III et al.
2017/0229782 A1	8/2017	Adriazola et al.	2019/0150072 A1	5/2019	Barzegar
2017/0230083 A1	8/2017	Adriazola et al.	2019/0173151 A1	6/2019	Henry et al.
2018/0013452 A9	1/2018	Henry et al.	2019/0173542 A1	6/2019	Johnson et al.
			2019/0174506 A1	6/2019	Willis, III et al.
			2019/0181532 A1	6/2019	Vannucci et al.
			2019/0181683 A1	6/2019	Vannucci et al.
			2019/0238184 A1	8/2019	Adriazola et al.

(56)

References Cited

U.S. PATENT DOCUMENTS

2019/0253278 A1 8/2019 Henry et al.
 2019/0253279 A1 8/2019 Henry et al.
 2019/0296430 A1 9/2019 Bennett et al.
 2019/0305805 A1 10/2019 Henry et al.
 2019/0305820 A1 10/2019 Barzegar et al.

FOREIGN PATENT DOCUMENTS

DE 19939832 A1 2/2001
 EP 0136818 4/1985
 EP 0280379 8/1988
 EP 0330303 8/1989
 EP 0871241 B1 10/1998
 EP 1577687 A1 9/2005
 EP 1647072 A1 4/2006
 EP 1696509 B1 10/2009
 EP 3168580 A1 5/2017
 EP 3363071 A1 8/2018
 GB 731473 A 6/1955
 GB 2414862 A 12/2005
 GB 718597 10/2007
 JP 2003057464 A 2/2003
 JP 2003511677 A 3/2003
 JP 2010045471 A 2/2010
 WO 8301711 A1 5/1983
 WO 8605327 A1 9/1986
 WO 2003009083 1/2003
 WO 2009035285 A2 3/2009
 WO 2012171205 A1 12/2012
 WO 2016032592 A1 3/2016
 WO 2016043949 A1 3/2016
 WO 2016053572 A1 4/2016
 WO 2016060762 A1 4/2016
 WO 2016081129 A1 5/2016
 WO 2016133672 A1 8/2016
 WO 2018106455 A1 6/2018
 WO 2018106684 A1 6/2018
 WO 2018106915 A1 6/2018
 WO 2019050752 A1 3/2019

OTHER PUBLICATIONS

“WO PCT Amendment Under Article 34 Response to Written Opinion Filed May 15, 2017”, PCT Application PCT/US16/36254 filed Jun. 8, 2016, 1-11.

“Article 34 Amendment filed Oct. 8, 2018”, for Application No. PCT/US17/65250 filed Dec. 8, 2017, Oct. 8, 2018, 9 pages.

“Article 34 Amendment Filed Apr. 18, 2017 in PCT Application No. PCT/US16/57161”.

“International Preliminary Report on Patentability”, PCT/US16/41561, dated Aug. 25, 2017, 30 pages.

“International Search Report and Written Opinion”, PCT/US2018/015634, dated Jun. 25, 2018, 8 pages.

“PCT International Search Report”, PCT/US2016/057161, PCT International Search Report and Written Opinion, dated Jan. 12, 2017, 1-13, dated Jan. 12, 2017, 1-13.

“PCT/US2016/041561, PCT International Search Report and Written Opinion”, dated Oct. 10, 2016, 1-15.

Akalin, Tahsin et al., “Single-Wire Transmission Lines at Terahertz Frequencies”, IEEE Transactions on Microwave Theory and Techniques, vol. 54, No. 6, 2006, 2762-2767.

Alam, M. N. et al., “Novel Surface Wave Exciters for Power Line Fault Detection and Communications”, Department of Electrical Engineering, University of South Carolina, Antennas and Propagation (APSURSI), 2011 IEEE International Symposium, IEEE, 2011, 1-4.

Allen, Jeffrey et al., “New Concepts in Electromagnetic Materials and Antennas”, Air Force Research Laboratory, Jan. 2015, 80 pages.
 Antenna Magus, “Waveguide-fed Conical Horn”, www.antennamagus.com, Aug. 2015, 1 page.

Barlow, H. M. et al., “Surface Waves”, 621.396.11 : 538.566, Paper No. 1482 Radio Section, 1953, pp. 329-341.

Berweger, Samuel et al., “Light on the Tip of a Needle: Plasmonic Nanofocusing for Spectroscopy on the Nanoscale”, The Journal of Physical Chemistry Letters; pubs.acs.org/JPCLE, 2012, 945-952.

Bowen, Leland H. et al., “A Solid Dielectric Lens Impulse Radiating Antenna with High Dielectric Constant Surrounded by a Cylindrical Shroud”, Sensor and Simulation Note 498, Introduction, Apr. 2005, 3 pages.

Brambilla, Gilberto et al., “Ultra-low-loss optical fiber nanotapers”, Optoelectronics Research Centre, University of Southampton; http://www.orc.soton.ac.uk, vol. 12, No. 10, May 7, 2004, 2258-2263.

Campista, Miguel E. et al., “Improving the Data Transmission Throughput Over the Home Electrical Wiring”, The IEEE Conference on Local Computer Networks 30th Anniversary, 2005, 1-8.

Corridor Systems, “A New Approach to Outdoor DAS Network Physical Layer Using E-Line Technology”, Mar. 2011, 5 pages.

Elmore, Glenn et al., “A Surface Wave Transmission Line”, QEX, May/Jun. 2012, pp. 3-9.

Elmore, Glenn, “Introduction to the Propagating Wave on a Single Conductor”, www.corridor.biz, Jul. 27, 2009, 30 pages.

Eskelinen, Harri et al., “DFM (A)—aspects for a horn antenna design”, Lappeenranta University of Technology, 2004, 34 pages.

Farr Research, Inc., “An Improved Solid Dielectric Lens Impulse Radiating Antenna”, SBIR/STTR, DoD, sbir.gov, 2004, 3 pages.

Fenn, Alan J. et al., “A Terrestrial Air Link for Evaluating Dual-Polarization Techniques in Satellite Communications”, vol. 9, No. 1, The Lincoln Laboratory Journal, 1996, 3-18.

Friedman, M et al., “Low-Loss RF Transport Over Long Distances”, IEEE Transactions on Microwave Theory and Techniques, vol. 49, No. 2, Feb. 2001, 8 pages.

Goubau, Georg et al., “Investigation of a Surface-Wave Line for Long Distance Transmission”, 1952, 263-267.

Goubau, Georg et al., “Investigations with a Model Surface Wave Transmission Line”, IRE Transactions on Antennas and Propagation, 1957, 222-227.

Goubau, Georg, “Open Wire Lines”, IRE Transactions on Microwave Theory and Techniques, 1956, 197-200.

Goubau, Georg, “Single-Conductor Surface-Wave Transmission Lines”, Proceedings of the I.R.E., 1951, 619-624.

Goubau, Georg, “Surface Waves and Their Application to Transmission Lines”, Radio Communication Branch, Coles Signal Laboratory, Mar. 10, 1950, 1119-1128.

Goubau, Georg, “Waves on Interfaces”, IRE Transactions on Antennas and Propagation, Dec. 1959, 140-146.

Hanashi, Abdalla M. et al., “Effect of the Dish Angle on the Wet Antenna Attenuation”, IEEE, 2014, 1-4.

James, Graeme L. et al., “Diplexing Feed Assemblies for Application to Dual-Reflector Antennas”, IEEE Transactions on Antennas and Propagation, vol. 51, No. 5, May 2003, 1024-1029.

Karbowiak, A. E. et al., “Characteristics of Waveguides for Long-Distance Transmission”, Journal of Research of the National Bureau of Standards, vol. 65D, No. 1, Jan.-Feb. 1961, May 23, 1960, 75-88.

Koga, Hisao et al., “High-Speed Power Line Communication System Based on Wavelet OFDM”, 7th International Symposium on Power-Line Communications and Its Applications, Mar. 26-28, 2003, 226-231.

Lazaropoulos, Athanasios, “Towards Modal Integration of Overhead and Underground Low-Voltage and Medium-Voltage Power Line Communication Channels in the Smart Grid Landscape: Model Expansion, Broadband Signal Transmission Characteristics, and Statistical Performance Metrics”, International Scholarly Research Network, ISRN Signal Processing, vol. 2012, Article ID 121628, 17 pages, Mar. 26, 2012, 18 pages.

Lier, E. et al., “Simple hybrid mode horn feed loaded with a dielectric cone”, Electronics Letters 21.13: 563564, 1985, 563-564.

Lier, Erik, “A Dielectric Hybrid Mode Antenna Feed: A Simple Alternative to the Corrugated Horn”, IEEE Transactions on Antennas and Propagation, vol. AP-34, No. 1, Jan. 1986, 21-30.

McAllister, M.W. et al., “Resonant hemispherical dielectric antenna”, Electronics Letters 20.16: 657659, Abstract Only, 1984, 1 page.

(56)

References Cited

OTHER PUBLICATIONS

Menon, S.S. et al., "Propagation characteristics of guided modes in a solid dielectric pyramidal horn", Proceedings of the 2012 International Conference on Communication Systems and Network Technologies, IEEE Computer Society, Abstract Only, 2012, 2 pages.

Microwave Technologies, Ind., "Dielectric Antenna", www.microwavetechnologiesinc.co.in/microwavecommunicationlabproducts.html#dielectricantenna, May 21, 2015, 13 pages.

Mori, A. et al., "The Power Line Transmission Characteristics for an OFDM Signal", Progress in Electromagnetics Research, PIER 61, Musashi Institute of Technology, 2006, 279-290.

Mwave, "Dual Linear C-Band Horn", www.mwavelc.com/custom-Band-LS-BandTelemetryHornAntennas.php, Jul. 6, 2012, 1 page.

Nikitin, A. Y. et al., "Efficient Coupling of Light to Graphene Plasmons by Compressing Surface Polaritons with Tapered Bulk Materials", NanoLetters; pubs.acs.org/NanoLett, Apr. 28, 2014, 2896-2901.

Nikitin, Pavel V. et al., "Propagation Model for the HVAC Duct as a Communication Channel", IEEE Transactions on Antennas and Propagation 51.5, 2003, 7 pages.

Olver, A. D., "Microwave horns and feeds", vol. 39. IET, Book—description only, 1994, 1 page.

Olver, A.D. et al., "Dielectric cone loaded horn antennas", Microwaves, Antennas and Propagation, IEEE Proceedings H. vol. 135. No. 3. IET, Abstract Only, 1988, 1 page.

Patent Cooperation Treaty, "International Preliminary Report on Patentability dated Jun. 15, 2017", PCT Application No. PCT/US16/36254 filed Jun. 7, 2016, 1-21.

Patent Cooperation Treaty, "International Search Report and Written Opinion dated Mar. 8, 2018", for PCT Application No. PCT/US17/65250 filed Dec. 8, 2017, Mar. 8, 2018, 14 pages.

Pohl, Nils, "A dielectric lens-based antenna concept for high-precision industrial radar measurements at 24GHz", Radar Conference (EuRAD), 2012 9th European, IEEE, 2012, 5 pages.

Ren-Bin, Zhong et al., "Surface plasmon wave propagation along single metal wire", Chin. Phys. B, vol. 21, No. 11, May 2, 2012, 9 pages.

Ricardi, L. J., "Some Characteristics of a Communication Satellite Multiple-Beam Antenna", Massachusetts Institute of Technology, Lincoln Laboratory, Technical Note 1975-3, Jan. 28, 1975, 62 pages.

Salema, Carlos et al., "Solid Dielectric Horn Antennas", Artech House Publishers, Amazon, Book—description only, 1998, 3 pages.

Sommerfeld, A., "On the propagation of electrodynamic waves along a wire", Annals of Physics and Chemistry New Edition, vol. 67, No. 2, 1899, 72 pages.

Stancil, Daniel D. et al., "High-speed internet access via HVAC ducts: a new approach", Global Telecommunications Conference, IEEE vol. 6, 2001, 4 pages.

Steatite, "Custom Horn Antennas", Steatite QPar Antennas, steatiteqparantennas.co.uk, May 21, 2015, 1 page.

Sun, Zhi et al., "Magnetic Induction Communications for Wireless Underground Sensor Networks", IEEE Transactions on Antennas and Propagation, vol. 58, No. 7, Jul. 2010, 2426-2435.

Wang, Hao et al., "Dielectric Loaded Substrate Integrated Waveguide (SIW)—Plan Horn Antennas", IEEE Transactions on Antennas and Propagation, IEEE Service Center, Piscataway, NJ, US, vol. 56, No. 3, Mar. 1, 2010, 640-647.

Wang, Kanglin, "Dispersion of Surface Plasmon Polaritons on Metal Wires in the Terahertz Frequency Range", Physical Review Letters, PRL 96, 157401, 2006, 4 pages.

Wilkes, Gilbert, "Wave Length Lenses", Dec. 5, 1946, 49 pages.

Yeh, C. et al., "Thin-Ribbon Tapered Coupler for Dielectric Waveguides", May 15, 1994, 42-48.

Patent Cooperation Treaty, "International Preliminary Report on Patentability dated Nov. 21, 2018", for Application No. PCT/US17/65250 filed Dec. 8, 2017, Nov. 21, 2018, 20 pages.

Patent Cooperation Treaty, "International Search Report and Written Opinion dated Feb. 15, 2019", for Application No. PCT/US18/60723, Feb. 15, 2019, 13 pages.

Patent Cooperation Treaty, "International Search Report and Written Opinion mailed Mar. 12, 2019", PCT Application No. PCT/US18/62180 filed Nov. 21, 2018, dated Mar. 12, 2019, 10 pages.

Villaran, Michael et al., "Condition Monitoring of Cables Task 3 Report: Condition Monitoring Techniques for Electric Cables", Brookhaven National Laboratory, Technical Report, Nov. 30, 2009, 89 pages.

* cited by examiner


100

FIG. 1




200

FIG. 2




300

FIG. 3




400


FIG. 4



500
FIG. 5A




550
FIG. 5B




600


FIG. 6




700
FIG. 7



800
FIG. 8




900
FIG. 9A



950
FIG. 9B

1000
FIG. 10A











FIG. 10B




1300**FIG. 13**





1500
FIG. 15



1600
FIG. 16A




FIG. 16B



1700

FIG. 17A

1750**FIG. 17B**




FIG. 18A




FIG. 18B




FIG. 18C




FIG. 18D




FIG. 18E




FIG. 18F




FIG. 18G




FIG. 18H




FIG. 18I




FIG. 18J




FIG. 18K




FIG. 18L




FIG. 18M




FIG. 18N




FIG. 18O




FIG. 18P




FIG. 18Q






FIG. 18R






FIG. 18U




FIG. 18V







FIG. 18W




1900
FIG. 19A



Antenna Gain Pattern

FIG. 19B

INTEGRATED DIELECTRIC ANTENNA



ASSEMBLED DIELECTRIC ANTENNA




FIG. 19C




FIG. 19D





FIG. 19E




FIG. 19F




FIG. 19G





FIG. 19H

Frequency Switching



Polarization Switching




FIG. 19I





FIG. 19J




FIG. 19K





FIG. 19L





FIG. 19M

Antenna Array Using Pyramidal Horns

**FIG. 19N**




FIG. 190




FIG. 19P1




FIG. 19P2




FIG. 19P3




FIG. 19P4




FIG. 19P5




FIG. 19P6




FIG. 19P7









FIG. 19P8








FIG. 20C




FIG. 20D










FIG. 20E








2130**FIG. 21C**

2140**FIG. 21D**

2150**FIG. 21E**

2160**FIG. 21F**






Longitudinal Section of Cable showing e-fields of waves that include a component of TM₀₁ waves at 40 GHz


2111
FIG. 21I

Plot shows
strong e-fields
in direction of
propagation for
TM01 mode @
45 GHz




2121
FIG. 21J


Plot shows
weak e-fields in
direction of
propagation for
TM01 mode @
40 GHz




2131
FIG. 21K
Goubau Wave Mode
(Small Mode Size)




2141
FIG. 21L
HE Wave Mode
(Large Mode Size)








Hybrid mode (HE11)
2157



Goubau mode (TM00)
2159



2151
FIG. 21M






2161

FIG. 21N



Obstruction Mitigation via HE11 Mode




Horizontally polarized HE11 Mode

- Water film occupies small fraction of mode
- Water droplet is in least-intense area of mode
- Much lower propagation loss than Goubau mode

2300

FIG. 23

2400**FIG. 24**




FIG. 25A




FIG. 25B




FIG. 25C




FIG. 25D




FIG. 26





FIG. 27



2800
FIG. 28

APPARATUS AND METHODS FOR SENDING OR RECEIVING ELECTROMAGNETIC SIGNALS

CROSS-REFERENCE TO RELATED APPLICATIONS

This application is a divisional of U.S. application Ser. No. 15/274,987, filed Sep. 23, 2016, which is a continuation-in-part of U.S. application Ser. No. 14/965,523, filed Dec. 10, 2015 (now U.S. Pat. No. 10,033,107), which is a continuation-in-part of U.S. application Ser. No. 14/885,463, filed Oct. 16, 2015 (now U.S. Pat. No. 9,722,318), which is a continuation-in-part of U.S. application Ser. No. 14/799,272, filed Jul. 14, 2015 (now U.S. Pat. No. 9,628,116), which are incorporated herein by reference in their entirety.

FIELD OF THE DISCLOSURE

The subject disclosure relates to apparatus and methods for sending or receiving electromagnetic signals.

BACKGROUND

As smart phones and other portable devices increasingly become ubiquitous, and data usage increases, macrocell base station devices and existing wireless infrastructure in turn require higher bandwidth capability in order to address the increased demand. To provide additional mobile bandwidth, small cell deployment is being pursued, with microcells and picocells providing coverage for much smaller areas than traditional macrocells.

In addition, most homes and businesses have grown to rely on broadband data access for services such as voice, video and Internet browsing, etc. Broadband access networks include satellite, 4G or 5G wireless, power line communication, fiber, cable, and telephone networks.

BRIEF DESCRIPTION OF THE DRAWINGS

Reference will now be made to the accompanying drawings, which are not necessarily drawn to scale, and wherein:

FIG. 1 is a block diagram illustrating an example, non-limiting embodiment of a guided-wave communications system in accordance with various aspects described herein.

FIG. 2 is a block diagram illustrating an example, non-limiting embodiment of a transmission device in accordance with various aspects described herein.

FIG. 3 is a graphical diagram illustrating an example, non-limiting embodiment of an electromagnetic field distribution in accordance with various aspects described herein.

FIG. 4 is a graphical diagram illustrating an example, non-limiting embodiment of an electromagnetic field distribution in accordance with various aspects described herein.

FIG. 5A is a graphical diagram illustrating an example, non-limiting embodiment of a frequency response in accordance with various aspects described herein.

FIG. 5B is a graphical diagram illustrating example, non-limiting embodiments of a longitudinal cross-section of an insulated wire depicting fields of guided electromagnetic waves at various operating frequencies in accordance with various aspects described herein.

FIG. 6 is a graphical diagram illustrating an example, non-limiting embodiment of an electromagnetic field distribution in accordance with various aspects described herein.

FIG. 7 is a block diagram illustrating an example, non-limiting embodiment of an arc coupler in accordance with various aspects described herein.

FIG. 8 is a block diagram illustrating an example, non-limiting embodiment of an arc coupler in accordance with various aspects described herein.

FIG. 9A is a block diagram illustrating an example, non-limiting embodiment of a stub coupler in accordance with various aspects described herein.

FIG. 9B is a diagram illustrating an example, non-limiting embodiment of an electromagnetic distribution in accordance with various aspects described herein.

FIGS. 10A and 10B are block diagrams illustrating example, non-limiting embodiments of couplers and transceivers in accordance with various aspects described herein.

FIG. 11 is a block diagram illustrating an example, non-limiting embodiment of a dual stub coupler in accordance with various aspects described herein.

FIG. 12 is a block diagram illustrating an example, non-limiting embodiment of a repeater system in accordance with various aspects described herein.

FIG. 13 illustrates a block diagram illustrating an example, non-limiting embodiment of a bidirectional repeater in accordance with various aspects described herein.

FIG. 14 is a block diagram illustrating an example, non-limiting embodiment of a waveguide system in accordance with various aspects described herein.

FIG. 15 is a block diagram illustrating an example, non-limiting embodiment of a guided-wave communications system in accordance with various aspects described herein.

FIGS. 16A & 16B are block diagrams illustrating an example, non-limiting embodiment of a system for managing a power grid communication system in accordance with various aspects described herein.

FIG. 17A illustrates a flow diagram of an example, non-limiting embodiment of a method for detecting and mitigating disturbances occurring in a communication network of the system of FIGS. 16A and 16B.

FIG. 17B illustrates a flow diagram of an example, non-limiting embodiment of a method for detecting and mitigating disturbances occurring in a communication network of the system of FIGS. 16A and 16B.

FIGS. 18A, 18B, and 18C are block diagrams illustrating example, non-limiting embodiment of a transmission medium for propagating guided electromagnetic waves.

FIG. 18D is a block diagram illustrating an example, non-limiting embodiment of bundled transmission media in accordance with various aspects described herein.

FIG. 18E is a block diagram illustrating an example, non-limiting embodiment of a plot depicting cross-talk between first and second transmission mediums of the bundled transmission media of FIG. 18D in accordance with various aspects described herein.

FIG. 18F is a block diagram illustrating an example, non-limiting embodiment of bundled transmission media to mitigate cross-talk in accordance with various aspects described herein.

FIGS. 18G and 18H are block diagrams illustrating example, non-limiting embodiments of a transmission medium with an inner waveguide in accordance with various aspects described herein.

FIGS. 18I and 18J are block diagrams illustrating example, non-limiting embodiments of connector configurations that can be used with the transmission medium of FIG. 18A, 18B, or 18C.

3

FIG. 18K is a block diagram illustrating example, non-limiting embodiments of transmission mediums for propagating guided electromagnetic waves.

FIG. 18L is a block diagram illustrating example, non-limiting embodiments of bundled transmission media to mitigate cross-talk in accordance with various aspects described herein.

FIG. 18M is a block diagram illustrating an example, non-limiting embodiment of exposed stubs from the bundled transmission media for use as antennas in accordance with various aspects described herein.

FIGS. 18N, 18O, 18P, 18Q, 18R, 18S, 18T, 18U, 18V and 18W are block diagrams illustrating example, non-limiting embodiments of a waveguide device for transmitting or receiving electromagnetic waves in accordance with various aspects described herein.

FIGS. 19A and 19B are block diagrams illustrating example, non-limiting embodiments of a dielectric antenna and corresponding gain and field intensity plots in accordance with various aspects described herein.

FIGS. 19C and 19D are block diagrams illustrating example, non-limiting embodiments of a dielectric antenna coupled to a lens and corresponding gain and field intensity plots in accordance with various aspects described herein.

FIGS. 19E and 19F are block diagrams illustrating example, non-limiting embodiments of a dielectric antenna coupled to a lens with ridges and corresponding gain and field intensity plots in accordance with various aspects described herein.

FIG. 19G is a block diagram illustrating an example, non-limiting embodiment of a dielectric antenna having an elliptical structure in accordance with various aspects described herein.

FIG. 19H is a block diagram illustrating an example, non-limiting embodiment of near-field and far-field signals emitted by the dielectric antenna of FIG. 19G in accordance with various aspects described herein.

FIG. 19I is a block diagrams of example, non-limiting embodiments of a dielectric antenna for adjusting far-field wireless signals in accordance with various aspects described herein.

FIGS. 19J and 19K are block diagrams of example, non-limiting embodiments of a flange that can be coupled to a dielectric antenna in accordance with various aspects described herein.

FIG. 19L is a block diagram of example, non-limiting embodiments of the flange, waveguide and dielectric antenna assembly in accordance with various aspects described herein.

FIG. 19M is a block diagram of an example, non-limiting embodiment of a dielectric antenna coupled to a gimbal for directing wireless signals generated by the dielectric antenna in accordance with various aspects described herein.

FIG. 19N is a block diagram of an example, non-limiting embodiment of a dielectric antenna in accordance with various aspects described herein.

FIG. 19O is a block diagram of an example, non-limiting embodiment of an array of dielectric antennas configurable for steering wireless signals in accordance with various aspects described herein.

FIGS. 19P1, 19P2, 19P3, 19P4, 19P5, 19P6, 19P7 and 19P8 are side-view block diagrams of example, non-limiting embodiments of a cable, a flange, and dielectric antenna assembly in accordance with various aspects described herein.

4

FIGS. 19Q1, 19Q2 and 19Q3 are front-view block diagrams of example, non-limiting embodiments of dielectric antennas in accordance with various aspects described herein.

FIGS. 20A and 20B are block diagrams illustrating example, non-limiting embodiments of the transmission medium of FIG. 18A used for inducing guided electromagnetic waves on power lines supported by utility poles.

FIG. 20C is a block diagram of an example, non-limiting embodiment of a communication network in accordance with various aspects described herein.

FIG. 20D is a block diagram of an example, non-limiting embodiment of an antenna mount for use in a communication network in accordance with various aspects described herein.

FIG. 20E is a block diagram of an example, non-limiting embodiment of an antenna mount for use in a communication network in accordance with various aspects described herein.

FIG. 20F is a block diagram of an example, non-limiting embodiment of an antenna mount for use in a communication network in accordance with various aspects described herein.

FIG. 21A illustrates a flow diagram of an example, non-limiting embodiment of a method for transmitting downlink signals.

FIG. 21B illustrates a flow diagram of an example, non-limiting embodiment of a method for transmitting uplink signals.

FIG. 21C illustrates a flow diagram of an example, non-limiting embodiment of a method for inducing and receiving electromagnetic waves on a transmission medium.

FIG. 21D illustrates a flow diagram of an example, non-limiting embodiment of a method for inducing and receiving electromagnetic waves on a transmission medium.

FIG. 21E illustrates a flow diagram of an example, non-limiting embodiment of a method for transmitting wireless signals from a dielectric antenna.

FIG. 21F illustrates a flow diagram of an example, non-limiting embodiment of a method for receiving wireless signals at a dielectric antenna.

FIG. 21G illustrates a flow diagram of an example, non-limiting embodiment of a method for detecting and mitigating disturbances occurring in a communication network.

FIG. 21H is a block diagram illustrating an example, non-limiting embodiment of an alignment of fields of an electromagnetic wave to mitigate propagation losses due to water accumulation on a transmission medium in accordance with various aspects described herein.

FIGS. 21I and 21J are block diagrams illustrating example, non-limiting embodiments of electric field intensities of different electromagnetic waves propagating in the cable illustrated in FIG. 20H in accordance with various aspects described herein.

FIG. 21K is a block diagram illustrating an example, non-limiting embodiment of electric fields of a Goubau wave in accordance with various aspects described herein.

FIG. 21L is a block diagram illustrating an example, non-limiting embodiment of electric fields of a hybrid wave in accordance with various aspects described herein.

FIG. 21M is a block diagram illustrating an example, non-limiting embodiment of electric field characteristics of a hybrid wave versus a Goubau wave in accordance with various aspects described herein.

5

FIG. 21N is a block diagram illustrating an example, non-limiting embodiment of mode sizes of hybrid waves at various operating frequencies in accordance with various aspects described herein.

FIGS. 22A and 22B are block diagrams illustrating example, non-limiting embodiments of a waveguide device for launching hybrid waves in accordance with various aspects described herein.

FIG. 23 is a block diagram illustrating an example, non-limiting embodiment of a hybrid wave launched by the waveguide device of FIGS. 21A and 21B in accordance with various aspects described herein.

FIG. 24 illustrates a flow diagram of an example, non-limiting embodiment of a method for managing electromagnetic waves.

FIGS. 25A, 25B, 25C, and 25D are block diagrams illustrating example, non-limiting embodiments of a waveguide device in accordance with various aspects described herein.

FIG. 26 is a block diagram of an example, non-limiting embodiment of a computing environment in accordance with various aspects described herein.

FIG. 27 is a block diagram of an example, non-limiting embodiment of a mobile network platform in accordance with various aspects described herein.

FIG. 28 is a block diagram of an example, non-limiting embodiment of a communication device in accordance with various aspects described herein.

DETAILED DESCRIPTION

One or more embodiments are now described with reference to the drawings, wherein like reference numerals are used to refer to like elements throughout. In the following description, for purposes of explanation, numerous details are set forth in order to provide a thorough understanding of the various embodiments. It is evident, however, that the various embodiments can be practiced without these details (and without applying to any particular networked environment or standard).

In an embodiment, a guided wave communication system is presented for sending and receiving communication signals such as data or other signaling via guided electromagnetic waves. The guided electromagnetic waves include, for example, surface waves or other electromagnetic waves that are bound to or guided by a transmission medium. It will be appreciated that a variety of transmission media can be utilized with guided wave communications without departing from example embodiments. Examples of such transmission media can include one or more of the following, either alone or in one or more combinations: wires, whether insulated or not, and whether single-stranded or multi-stranded; conductors of other shapes or configurations including wire bundles, cables, rods, rails, pipes; non-conductors such as dielectric pipes, rods, rails, or other dielectric members; combinations of conductors and dielectric materials; or other guided wave transmission media.

The inducement of guided electromagnetic waves on a transmission medium can be independent of any electrical potential, charge or current that is injected or otherwise transmitted through the transmission medium as part of an electrical circuit. For example, in the case where the transmission medium is a wire, it is to be appreciated that while a small current in the wire may be formed in response to the propagation of the guided waves along the wire, this can be due to the propagation of the electromagnetic wave along the wire surface, and is not formed in response to electrical

6

potential, charge or current that is injected into the wire as part of an electrical circuit. The electromagnetic waves traveling on the wire therefore do not require a circuit to propagate along the wire surface. The wire therefore is a single wire transmission line that is not part of a circuit. Also, in some embodiments, a wire is not necessary, and the electromagnetic waves can propagate along a single line transmission medium that is not a wire.

More generally, “guided electromagnetic waves” or “guided waves” as described by the subject disclosure are affected by the presence of a physical object that is at least a part of the transmission medium (e.g., a bare wire or other conductor, a dielectric, an insulated wire, a conduit or other hollow element, a bundle of insulated wires that is coated, covered or surrounded by a dielectric or insulator or other wire bundle, or another form of solid or otherwise non-liquid or non-gaseous transmission medium) so as to be at least partially bound to or guided by the physical object and so as to propagate along a transmission path of the physical object. Such a physical object can operate as at least a part of a transmission medium that guides, by way of an interface of the transmission medium (e.g., an outer surface, inner surface, an interior portion between the outer and the inner surfaces or other boundary between elements of the transmission medium), the propagation of guided electromagnetic waves, which in turn can carry energy, data and/or other signals along the transmission path from a sending device to a receiving device.

Unlike free space propagation of wireless signals such as unguided (or unbounded) electromagnetic waves that decrease in intensity inversely by the square of the distance traveled by the unguided electromagnetic waves, guided electromagnetic waves can propagate along a transmission medium with less loss in magnitude per unit distance than experienced by unguided electromagnetic waves.

An electrical circuit allows electrical signals to propagate from a sending device to a receiving device via a forward electrical path and a return electrical path, respectively. These electrical forward and return paths can be implemented via two conductors, such as two wires or a single wire and a common ground that serves as the second conductor. In particular, electrical current from the sending device (direct and/or alternating) flows through the electrical forward path and returns to the transmission source via the electrical return path as an opposing current. More particularly, electron flow in one conductor that flows away from the sending device, returns to the receiving device in the opposite direction via a second conductor or ground. Unlike electrical signals, guided electromagnetic waves can propagate along a transmission medium (e.g., a bare conductor, an insulated conductor, a conduit, a non-conducting material such as a dielectric strip, or any other type of object suitable for the propagation of surface waves) from a sending device to a receiving device or vice-versa without requiring the transmission medium to be part of an electrical circuit (i.e., without requiring an electrical return path) between the sending device and the receiving device. Although electromagnetic waves can propagate in an open circuit, i.e., a circuit without an electrical return path or with a break or gap that prevents the flow of electrical current through the circuit, it is noted that electromagnetic waves can also propagate along a surface of a transmission medium that is in fact part of an electrical circuit. That is electromagnetic waves can travel along a first surface of a transmission medium having a forward electrical path and/or along a second surface of a transmission medium having an electrical return path. As a consequence, guided electromagnetic

waves can propagate along a surface of a transmission medium from a sending device to a receiving device or vice-versa with or without an electrical circuit.

This permits, for example, transmission of guided electromagnetic waves along a transmission medium having no conductive components (e.g., a dielectric strip). This also permits, for example, transmission of guided electromagnetic waves that propagate along a transmission medium having no more than a single conductor (e.g., an electromagnetic wave that propagates along the surface of a single bare conductor or along the surface of a single insulated conductor or an electromagnetic wave that propagates all or partly within the insulation of an insulated conductor). Even if a transmission medium includes one or more conductive components and the guided electromagnetic waves propagating along the transmission medium generate currents that, at times, flow in the one or more conductive components in a direction of the guided electromagnetic waves, such guided electromagnetic waves can propagate along the transmission medium from a sending device to a receiving device without a flow of an opposing current on an electrical return path back to the sending device from the receiving device. As a consequence, the propagation of such guided electromagnetic waves can be referred to as propagating via a single transmission line or propagating via a surface wave transmission line.

In a non-limiting illustration, consider a coaxial cable having a center conductor and a ground shield that are separated by an insulator. Typically, in an electrical system a first terminal of a sending (and receiving) device can be connected to the center conductor, and a second terminal of the sending (and receiving) device can be connected to the ground shield. If the sending device injects an electrical signal in the center conductor via the first terminal, the electrical signal will propagate along the center conductor causing, at times, forward currents and a corresponding flow of electrons in the center conductor, and return currents and an opposing flow of electrons in the ground shield. The same conditions apply for a two terminal receiving device.

In contrast, consider a guided wave communication system such as described in the subject disclosure, which can utilize different embodiments of a transmission medium (including among others a coaxial cable) for transmitting and receiving guided electromagnetic waves without an electrical circuit (i.e., without an electrical forward path or electrical return path depending on your perspective). In one embodiment, for example, the guided wave communication system of the subject disclosure can be configured to induce guided electromagnetic waves that propagate along an outer surface of a coaxial cable (e.g., the outer jacket or insulation layer of the coaxial cable). Although the guided electromagnetic waves will cause forward currents on the ground shield, the guided electromagnetic waves do not require return currents in the center conductor to enable the guided electromagnetic waves to propagate along the outer surface of the coaxial cable. Said another way, while the guided electromagnetic waves will cause forward currents on the ground shield, the guided electromagnetic waves will not generate opposing return currents in the center conductor (or other electrical return path). The same can be said of other transmission media used by a guided wave communication system for the transmission and reception of guided electromagnetic waves.

For example, guided electromagnetic waves induced by the guided wave communication system on an outer surface of a bare conductor, or an insulated conductor can propagate along the outer surface of the bare conductor or the other

surface of the insulated conductor without generating opposing return currents in an electrical return path. As another point of differentiation, where the majority of the signal energy in an electrical circuit is induced by the flow of electrons in the conductors themselves, guided electromagnetic waves propagating in a guided wave communication system on an outer surface of a bare conductor, cause only minimal forward currents in the bare conductor, with the majority of the signal energy of the electromagnetic wave concentrated above the outer surface of the bare conductor and not inside the bare conductor. Furthermore, guided electromagnetic waves that are bound to the outer surface of an insulated conductor cause only minimal forward currents in the center conductor or conductors of the insulated conductor, with the majority of the signal energy of the electromagnetic wave concentrated in regions inside the insulation and/or above the outside surface of the insulated conductor—in other words, the majority of the signal energy of the electromagnetic wave is concentrated outside the center conductor(s) of the insulated conductor.

Consequently, electrical systems that require two or more conductors for carrying forward and reverse currents on separate conductors to enable the propagation of electrical signals injected by a sending device are distinct from guided wave systems that induce guided electromagnetic waves on an interface of a transmission medium without the need of an electrical circuit to enable the propagation of the guided electromagnetic waves along the interface of the transmission medium.

It is further noted that guided electromagnetic waves as described in the subject disclosure can have an electromagnetic field structure that lies primarily or substantially outside of a transmission medium so as to be bound to or guided by the transmission medium and so as to propagate non-trivial distances on or along an outer surface of the transmission medium. In other embodiments, guided electromagnetic waves can have an electromagnetic field structure that lies primarily or substantially inside a transmission medium so as to be bound to or guided by the transmission medium and so as to propagate non-trivial distances within the transmission medium. In other embodiments, guided electromagnetic waves can have an electromagnetic field structure that lies partially inside and partially outside a transmission medium so as to be bound to or guided by the transmission medium and so as to propagate non-trivial distances along the transmission medium. The desired electronic field structure in an embodiment may vary based upon a variety of factors, including the desired transmission distance, the characteristics of the transmission medium itself, and environmental conditions/characteristics outside of the transmission medium (e.g., presence of rain, fog, atmospheric conditions, etc.).

Various embodiments described herein relate to coupling devices, that can be referred to as “waveguide coupling devices”, “waveguide couplers” or more simply as “couplers”, “coupling devices” or “launchers” for launching and/or extracting guided electromagnetic waves to and from a transmission medium at millimeter-wave frequencies (e.g., 30 to 300 GHz), wherein the wavelength can be small compared to one or more dimensions of the coupling device and/or the transmission medium such as the circumference of a wire or other cross sectional dimension, or lower microwave frequencies such as 300 MHz to 30 GHz. Transmissions can be generated to propagate as waves guided by a coupling device, such as: a strip, arc or other length of dielectric material; a horn, monopole, rod, slot or other antenna; an array of antennas; a magnetic resonant cavity, or

other resonant coupler; a coil, a strip line, a waveguide or other coupling device. In operation, the coupling device receives an electromagnetic wave from a transmitter or transmission medium. The electromagnetic field structure of the electromagnetic wave can be carried inside the coupling device, outside the coupling device or some combination thereof. When the coupling device is in close proximity to a transmission medium, at least a portion of an electromagnetic wave couples to or is bound to the transmission medium, and continues to propagate as guided electromagnetic waves. In a reciprocal fashion, a coupling device can extract guided waves from a transmission medium and transfer these electromagnetic waves to a receiver.

According to an example embodiment, a surface wave is a type of guided wave that is guided by a surface of a transmission medium, such as an exterior or outer surface of the wire, or another surface of the wire that is adjacent to or exposed to another type of medium having different properties (e.g., dielectric properties). Indeed, in an example embodiment, a surface of the wire that guides a surface wave can represent a transitional surface between two different types of media. For example, in the case of a bare or uninsulated wire, the surface of the wire can be the outer or exterior conductive surface of the bare or uninsulated wire that is exposed to air or free space. As another example, in the case of insulated wire, the surface of the wire can be the conductive portion of the wire that meets the insulator portion of the wire, or can otherwise be the insulator surface of the wire that is exposed to air or free space, or can otherwise be any material region between the insulator surface of the wire and the conductive portion of the wire that meets the insulator portion of the wire, depending upon the relative differences in the properties (e.g., dielectric properties) of the insulator, air, and/or the conductor and further dependent on the frequency and propagation mode or modes of the guided wave.

According to an example embodiment, the term “about” a wire or other transmission medium used in conjunction with a guided wave can include fundamental guided wave propagation modes such as a guided waves having a circular or substantially circular field distribution, a symmetrical electromagnetic field distribution (e.g., electric field, magnetic field, electromagnetic field, etc.) or other fundamental mode pattern at least partially around a wire or other transmission medium. In addition, when a guided wave propagates “about” a wire or other transmission medium, it can do so according to a guided wave propagation mode that includes not only the fundamental wave propagation modes (e.g., zero order modes), but additionally or alternatively non-fundamental wave propagation modes such as higher-order guided wave modes (e.g., 1st order modes, 2nd order modes, etc.), asymmetrical modes and/or other guided (e.g., surface) waves that have non-circular field distributions around a wire or other transmission medium. As used herein, the term “guided wave mode” refers to a guided wave propagation mode of a transmission medium, coupling device or other system component of a guided wave communication system.

For example, such non-circular field distributions can be unilateral or multi-lateral with one or more axial lobes characterized by relatively higher field strength and/or one or more nulls or null regions characterized by relatively low-field strength, zero-field strength or substantially zero-field strength. Further, the field distribution can otherwise vary as a function of azimuthal orientation around the wire such that one or more angular regions around the wire have an electric or magnetic field strength (or combination

thereof) that is higher than one or more other angular regions of azimuthal orientation, according to an example embodiment. It will be appreciated that the relative orientations or positions of the guided wave higher order modes or asymmetrical modes can vary as the guided wave travels along the wire.

As used herein, the term “millimeter-wave” can refer to electromagnetic waves/signals that fall within the “millimeter-wave frequency band” of 30 GHz to 300 GHz. The term “microwave” can refer to electromagnetic waves/signals that fall within a “microwave frequency band” of 300 MHz to 300 GHz. The term “radio frequency” or “RF” can refer to electromagnetic waves/signals that fall within the “radio frequency band” of 10 kHz to 1 THz. It is appreciated that wireless signals, electrical signals, and guided electromagnetic waves as described in the subject disclosure can be configured to operate at any desirable frequency range, such as, for example, at frequencies within, above or below millimeter-wave and/or microwave frequency bands. In particular, when a coupling device or transmission medium includes a conductive element, the frequency of the guided electromagnetic waves that are carried by the coupling device and/or propagate along the transmission medium can be below the mean collision frequency of the electrons in the conductive element. Further, the frequency of the guided electromagnetic waves that are carried by the coupling device and/or propagate along the transmission medium can be a non-optical frequency, e.g., a radio frequency below the range of optical frequencies that begins at 1 THz.

As used herein, the term “antenna” can refer to a device that is part of a transmitting or receiving system to transmit/radiate or receive wireless signals.

In accordance with one or more embodiments, a device includes a generator that facilitates generation of a first electromagnetic wave, a transmission medium, and a waveguide that facilitates guiding the first electromagnetic wave towards the transmission medium, wherein the core comprises a first region, a second region, and a third region, wherein the core comprises an interface in the first region, wherein the first electromagnetic wave induces at the interface a second electromagnetic wave, wherein the waveguide is configured to confine the second electromagnetic at least in part within the core in the first region, wherein the second region of the core is configured to reduce a radiation loss of the second electromagnetic wave as the second electromagnetic wave propagates into the second region, and wherein the third region of the core is configured to reduce a propagation loss of the second electromagnetic wave as the second electromagnetic wave propagates into the third region.

In accordance with one or more embodiments, a device can include a generator that facilitates generation of a first electromagnetic wave, a transmission medium, and a waveguide that facilitates guiding the first electromagnetic wave towards the transmission medium, wherein the core comprises a first region, a second region, and a third region, wherein the core comprises an interface in the first region, wherein the first electromagnetic wave induces at the interface a second electromagnetic wave, wherein the waveguide is configured to confine the second electromagnetic at least in part within the core in the first region, wherein the second region of the core is located within the waveguide, and wherein a portion of the waveguide covering the second region is configured to reduce a radiation loss of the second electromagnetic wave as the second electromagnetic wave propagates into the second region.

11

In accordance with one or more embodiments, a device can include means for generating a first electromagnetic wave, and means for guiding the first electromagnetic wave towards a transmission medium, wherein the core comprises an interface in a first region of the transmission medium, wherein the first electromagnetic wave induces at the interface a second electromagnetic wave, wherein the interface is configured to reduce a reflection by the first electromagnetic wave at a surface of the interface, wherein the means for guiding confines the second electromagnetic at least in part within the core in the first region, and wherein the means for guiding or a second region of the core is configured to reduce a radiation loss of the second electromagnetic wave as the second electromagnetic wave propagates into the second region.

Referring now to FIG. 1, a block diagram **100** illustrating an example, non-limiting embodiment of a guided wave communications system is shown. In operation, a transmission device **101** receives one or more communication signals **110** from a communication network or other communications device that includes data and generates guided waves **120** to convey the data via the transmission medium **125** to the transmission device **102**. The transmission device **102** receives the guided waves **120** and converts them to communication signals **112** that include the data for transmission to a communications network or other communications device. The guided waves **120** can be modulated to convey data via a modulation technique such as phase shift keying, frequency shift keying, quadrature amplitude modulation, amplitude modulation, multi-carrier modulation such as orthogonal frequency division multiplexing and via multiple access techniques such as frequency division multiplexing, time division multiplexing, code division multiplexing, multiplexing via differing wave propagation modes and via other modulation and access strategies.

The communication network or networks can include a wireless communication network such as a mobile data network, a cellular voice and data network, a wireless local area network (e.g., WiFi or an 802.xx network), a satellite communications network, a personal area network or other wireless network. The communication network or networks can also include a wired communication network such as a telephone network, an Ethernet network, a local area network, a wide area network such as the Internet, a broadband access network, a cable network, a fiber optic network, or other wired network. The communication devices can include a network edge device, bridge device or home gateway, a set-top box, broadband modem, telephone adapter, access point, base station, or other fixed communication device, a mobile communication device such as an automotive gateway or automobile, laptop computer, tablet, smartphone, cellular telephone, or other communication device.

In an example embodiment, the guided wave communication system **100** can operate in a bi-directional fashion where transmission device **102** receives one or more communication signals **112** from a communication network or device that includes other data and generates guided waves **122** to convey the other data via the transmission medium **125** to the transmission device **101**. In this mode of operation, the transmission device **101** receives the guided waves **122** and converts them to communication signals **110** that include the other data for transmission to a communications network or device. The guided waves **122** can be modulated to convey data via a modulation technique such as phase shift keying, frequency shift keying, quadrature amplitude modulation, amplitude modulation, multi-carrier modula-

12

tion such as orthogonal frequency division multiplexing and via multiple access techniques such as frequency division multiplexing, time division multiplexing, code division multiplexing, multiplexing via differing wave propagation modes and via other modulation and access strategies.

The transmission medium **125** can include a cable having at least one inner portion surrounded by a dielectric material such as an insulator or other dielectric cover, coating or other dielectric material, the dielectric material having an outer surface and a corresponding circumference. In an example embodiment, the transmission medium **125** operates as a single-wire transmission line to guide the transmission of an electromagnetic wave. When the transmission medium **125** is implemented as a single wire transmission system, it can include a wire. The wire can be insulated or uninsulated, and single-stranded or multi-stranded (e.g., braided). In other embodiments, the transmission medium **125** can contain conductors of other shapes or configurations including wire bundles, cables, rods, rails, pipes. In addition, the transmission medium **125** can include non-conductors such as dielectric pipes, rods, rails, or other dielectric members; combinations of conductors and dielectric materials, conductors without dielectric materials or other guided wave transmission media. It should be noted that the transmission medium **125** can otherwise include any of the transmission media previously discussed.

Further, as previously discussed, the guided waves **120** and **122** can be contrasted with radio transmissions over free space/air or conventional propagation of electrical power or signals through the conductor of a wire via an electrical circuit. In addition to the propagation of guided waves **120** and **122**, the transmission medium **125** may optionally contain one or more wires that propagate electrical power or other communication signals in a conventional manner as a part of one or more electrical circuits.

Referring now to FIG. 2, a block diagram **200** illustrating an example, non-limiting embodiment of a transmission device is shown. The transmission device **101** or **102** includes a communications interface (I/F) **205**, a transceiver **210** and a coupler **220**.

In an example of operation, the communications interface **205** receives a communication signal **110** or **112** that includes data. In various embodiments, the communications interface **205** can include a wireless interface for receiving a wireless communication signal in accordance with a wireless standard protocol such as LTE or other cellular voice and data protocol, WiFi or an 802.11 protocol, WIMAX protocol, Ultra Wideband protocol, Bluetooth protocol, Zigbee protocol, a direct broadcast satellite (DBS) or other satellite communication protocol or other wireless protocol. In addition or in the alternative, the communications interface **205** includes a wired interface that operates in accordance with an Ethernet protocol, universal serial bus (USB) protocol, a data over cable service interface specification (DOCSIS) protocol, a digital subscriber line (DSL) protocol, a Firewire (IEEE 1394) protocol, or other wired protocol. In addition to standards-based protocols, the communications interface **205** can operate in conjunction with other wired or wireless protocol. In addition, the communications interface **205** can optionally operate in conjunction with a protocol stack that includes multiple protocol layers including a MAC protocol, transport protocol, application protocol, etc.

In an example of operation, the transceiver **210** generates an electromagnetic wave based on the communication signal **110** or **112** to convey the data. The electromagnetic wave has at least one carrier frequency and at least one corresponding

13

wavelength. The carrier frequency can be within a millimeter-wave frequency band of 30 GHz-300 GHz, such as 60 GHz or a carrier frequency in the range of 30-40 GHz or a lower frequency band of 300 MHz-30 GHz in the micro-wave frequency range such as 26-30 GHz, 11 GHz, 6 GHz or 3 GHz, but it will be appreciated that other carrier frequencies are possible in other embodiments. In one mode of operation, the transceiver **210** merely upconverts the communications signal or signals **110** or **112** for transmission of the electromagnetic signal in the microwave or millimeter-wave band as a guided electromagnetic wave that is guided by or bound to the transmission medium **125**. In another mode of operation, the communications interface **205** either converts the communication signal **110** or **112** to a baseband or near baseband signal or extracts the data from the communication signal **110** or **112** and the transceiver **210** modulates a high-frequency carrier with the data, the baseband or near baseband signal for transmission. It should be appreciated that the transceiver **210** can modulate the data received via the communication signal **110** or **112** to preserve one or more data communication protocols of the communication signal **110** or **112** either by encapsulation in the payload of a different protocol or by simple frequency shifting. In the alternative, the transceiver **210** can otherwise translate the data received via the communication signal **110** or **112** to a protocol that is different from the data communication protocol or protocols of the communication signal **110** or **112**.

In an example of operation, the coupler **220** couples the electromagnetic wave to the transmission medium **125** as a guided electromagnetic wave to convey the communications signal or signals **110** or **112**. While the prior description has focused on the operation of the transceiver **210** as a transmitter, the transceiver **210** can also operate to receive electromagnetic waves that convey other data from the single wire transmission medium via the coupler **220** and to generate communications signals **110** or **112**, via communications interface **205** that includes the other data. Consider embodiments where an additional guided electromagnetic wave conveys other data that also propagates along the transmission medium **125**. The coupler **220** can also couple this additional electromagnetic wave from the transmission medium **125** to the transceiver **210** for reception.

The transmission device **101** or **102** includes an optional training controller **230**. In an example embodiment, the training controller **230** is implemented by a standalone processor or a processor that is shared with one or more other components of the transmission device **101** or **102**. The training controller **230** selects the carrier frequencies, modulation schemes and/or guided wave modes for the guided electromagnetic waves based on feedback data received by the transceiver **210** from at least one remote transmission device coupled to receive the guided electromagnetic wave.

In an example embodiment, a guided electromagnetic wave transmitted by a remote transmission device **101** or **102** conveys data that also propagates along the transmission medium **125**. The data from the remote transmission device **101** or **102** can be generated to include the feedback data. In operation, the coupler **220** also couples the guided electromagnetic wave from the transmission medium **125** and the transceiver receives the electromagnetic wave and processes the electromagnetic wave to extract the feedback data.

In an example embodiment, the training controller **230** operates based on the feedback data to evaluate a plurality of candidate frequencies, modulation schemes and/or transmission modes to select a carrier frequency, modulation

14

scheme and/or transmission mode to enhance performance, such as throughput, signal strength, reduce propagation loss, etc.

Consider the following example: a transmission device **101** begins operation under control of the training controller **230** by sending a plurality of guided waves as test signals such as pilot waves or other test signals at a corresponding plurality of candidate frequencies and/or candidate modes directed to a remote transmission device **102** coupled to the transmission medium **125**. The guided waves can include, in addition or in the alternative, test data. The test data can indicate the particular candidate frequency and/or guided-wave mode of the signal. In an embodiment, the training controller **230** at the remote transmission device **102** receives the test signals and/or test data from any of the guided waves that were properly received and determines the best candidate frequency and/or guided wave mode, a set of acceptable candidate frequencies and/or guided wave modes, or a rank ordering of candidate frequencies and/or guided wave modes. This selection of candidate frequenc(ies) or/and guided-mode(s) are generated by the training controller **230** based on one or more optimizing criteria such as received signal strength, bit error rate, packet error rate, signal to noise ratio, propagation loss, etc. The training controller **230** generates feedback data that indicates the selection of candidate frequenc(ies) or/and guided wave mode(s) and sends the feedback data to the transceiver **210** for transmission to the transmission device **101**. The transmission device **101** and **102** can then communicate data with one another based on the selection of candidate frequenc(ies) or/and guided wave mode(s).

In other embodiments, the guided electromagnetic waves that contain the test signals and/or test data are reflected back, repeated back or otherwise looped back by the remote transmission device **102** to the transmission device **101** for reception and analysis by the training controller **230** of the transmission device **101** that initiated these waves. For example, the transmission device **101** can send a signal to the remote transmission device **102** to initiate a test mode where a physical reflector is switched on the line, a termination impedance is changed to cause reflections, a loop back mode is switched on to couple electromagnetic waves back to the source transmission device **102**, and/or a repeater mode is enabled to amplify and retransmit the electromagnetic waves back to the source transmission device **102**. The training controller **230** at the source transmission device **102** receives the test signals and/or test data from any of the guided waves that were properly received and determines selection of candidate frequenc(ies) or/and guided wave mode(s).

While the procedure above has been described in a start-up or initialization mode of operation, each transmission device **101** or **102** can send test signals, evaluate candidate frequencies or guided wave modes via non-test such as normal transmissions or otherwise evaluate candidate frequencies or guided wave modes at other times or continuously as well. In an example embodiment, the communication protocol between the transmission devices **101** and **102** can include an on-request or periodic test mode where either full testing or more limited testing of a subset of candidate frequencies and guided wave modes are tested and evaluated. In other modes of operation, the re-entry into such a test mode can be triggered by a degradation of performance due to a disturbance, weather conditions, etc. In an example embodiment, the receiver bandwidth of the transceiver **210** is either sufficiently wide or swept to receive all candidate frequencies or can be selectively adjusted by

15

the training controller **230** to a training mode where the receiver bandwidth of the transceiver **210** is sufficiently wide or swept to receive all candidate frequencies.

Referring now to FIG. **3**, a graphical diagram **300** illustrating an example, non-limiting embodiment of an electromagnetic field distribution is shown. In this embodiment, a transmission medium **125** in air includes an inner conductor **301** and an insulating jacket **302** of dielectric material, as shown in cross section. The diagram **300** includes different gray-scales that represent differing electromagnetic field strengths generated by the propagation of the guided wave having an asymmetrical and non-fundamental guided wave mode.

In particular, the electromagnetic field distribution corresponds to a modal “sweet spot” that enhances guided electromagnetic wave propagation along an insulated transmission medium and reduces end-to-end transmission loss. In this particular mode, electromagnetic waves are guided by the transmission medium **125** to propagate along an outer surface of the transmission medium—in this case, the outer surface of the insulating jacket **302**. Electromagnetic waves are partially embedded in the insulator and partially radiating on the outer surface of the insulator. In this fashion, electromagnetic waves are “lightly” coupled to the insulator so as to enable electromagnetic wave propagation at long distances with low propagation loss.

As shown, the guided wave has a field structure that lies primarily or substantially outside of the transmission medium **125** that serves to guide the electromagnetic waves. The regions inside the conductor **301** have little or no field. Likewise regions inside the insulating jacket **302** have low field strength. The majority of the electromagnetic field strength is distributed in the lobes **304** at the outer surface of the insulating jacket **302** and in close proximity thereof. The presence of an asymmetric guided wave mode is shown by the high electromagnetic field strengths at the top and bottom of the outer surface of the insulating jacket **302** (in the orientation of the diagram)—as opposed to very small field strengths on the other sides of the insulating jacket **302**.

The example shown corresponds to a 38 GHz electromagnetic wave guided by a wire with a diameter of 1.1 cm and a dielectric insulation of thickness of 0.36 cm. Because the electromagnetic wave is guided by the transmission medium **125** and the majority of the field strength is concentrated in the air outside of the insulating jacket **302** within a limited distance of the outer surface, the guided wave can propagate longitudinally down the transmission medium **125** with very low loss. In the example shown, this “limited distance” corresponds to a distance from the outer surface that is less than half the largest cross sectional dimension of the transmission medium **125**. In this case, the largest cross sectional dimension of the wire corresponds to the overall diameter of 1.82 cm, however, this value can vary with the size and shape of the transmission medium **125**. For example, should the transmission medium **125** be of a rectangular shape with a height of 0.3 cm and a width of 0.4 cm, the largest cross sectional dimension would be the diagonal of 0.5 cm and the corresponding limited distance would be 0.25 cm. The dimensions of the area containing the majority of the field strength also vary with the frequency, and in general, increase as carrier frequencies decrease.

It should also be noted that the components of a guided wave communication system, such as couplers and transmission media can have their own cut-off frequencies for each guided wave mode. The cut-off frequency generally sets forth the lowest frequency that a particular guided wave mode is designed to be supported by that particular com-

16

ponent. In an example embodiment, the particular asymmetric mode of propagation shown is induced on the transmission medium **125** by an electromagnetic wave having a frequency that falls within a limited range (such as F_c to $2F_c$) of the lower cut-off frequency F_c for this particular asymmetric mode. The lower cut-off frequency F_c is particular to the characteristics of transmission medium **125**. For embodiments as shown that include an inner conductor **301** surrounded by an insulating jacket **302**, this cutoff frequency can vary based on the dimensions and properties of the insulating jacket **302** and potentially the dimensions and properties of the inner conductor **301** and can be determined experimentally to have a desired mode pattern. It should be noted however, that similar effects can be found for a hollow dielectric or insulator without an inner conductor. In this case, the cutoff frequency can vary based on the dimensions and properties of the hollow dielectric or insulator.

At frequencies lower than the lower cut-off frequency, the asymmetric mode is difficult to induce in the transmission medium **125** and fails to propagate for all but trivial distances. As the frequency increases above the limited range of frequencies about the cut-off frequency, the asymmetric mode shifts more and more inward of the insulating jacket **302**. At frequencies much larger than the cut-off frequency, the field strength is no longer concentrated outside of the insulating jacket, but primarily inside of the insulating jacket **302**. While the transmission medium **125** provides strong guidance to the electromagnetic wave and propagation is still possible, ranges are more limited by increased losses due to propagation within the insulating jacket **302**—as opposed to the surrounding air.

Referring now to FIG. **4**, a graphical diagram **400** illustrating an example, non-limiting embodiment of an electromagnetic field distribution is shown. In particular, a cross section diagram **400**, similar to FIG. **3** is shown with common reference numerals used to refer to similar elements. The example shown corresponds to a 60 GHz wave guided by a wire with a diameter of 1.1 cm and a dielectric insulation of thickness of 0.36 cm. Because the frequency of the guided wave is above the limited range of the cut-off frequency of this particular asymmetric mode, much of the field strength has shifted inward of the insulating jacket **302**. In particular, the field strength is concentrated primarily inside of the insulating jacket **302**. While the transmission medium **125** provides strong guidance to the electromagnetic wave and propagation is still possible, ranges are more limited when compared with the embodiment of FIG. **3**, by increased losses due to propagation within the insulating jacket **302**.

Referring now to FIG. **5A**, a graphical diagram illustrating an example, non-limiting embodiment of a frequency response is shown. In particular, diagram **500** presents a graph of end-to-end loss (in dB) as a function of frequency, overlaid with electromagnetic field distributions **510**, **520** and **530** at three points for a 200 cm insulated medium voltage wire. The boundary between the insulator and the surrounding air is represented by reference numeral **525** in each electromagnetic field distribution.

As discussed in conjunction with FIG. **3**, an example of a desired asymmetric mode of propagation shown is induced on the transmission medium **125** by an electromagnetic wave having a frequency that falls within a limited range (such as F_c to $2F_c$) of the lower cut-off frequency F_c of the transmission medium for this particular asymmetric mode. In particular, the electromagnetic field distribution **520** at 6 GHz falls within this modal “sweet spot” that enhances

electromagnetic wave propagation along an insulated transmission medium and reduces end-to-end transmission loss. In this particular mode, guided waves are partially embedded in the insulator and partially radiating on the outer surface of the insulator. In this fashion, the electromagnetic waves are “lightly” coupled to the insulator so as to enable guided electromagnetic wave propagation at long distances with low propagation loss.

At lower frequencies represented by the electromagnetic field distribution **510** at 3 GHz, the asymmetric mode radiates more heavily generating higher propagation losses. At higher frequencies represented by the electromagnetic field distribution **530** at 9 GHz, the asymmetric mode shifts more and more inward of the insulating jacket providing too much absorption, again generating higher propagation losses.

Referring now to FIG. **5B**, a graphical diagram **550** illustrating example, non-limiting embodiments of a longitudinal cross-section of a transmission medium **125**, such as an insulated wire, depicting fields of guided electromagnetic waves at various operating frequencies is shown. As shown in diagram **556**, when the guided electromagnetic waves are at approximately the cutoff frequency (f_c) corresponding to the modal “sweet spot”, the guided electromagnetic waves are loosely coupled to the insulated wire so that absorption is reduced, and the fields of the guided electromagnetic waves are bound sufficiently to reduce the amount radiated into the environment (e.g., air). Because absorption and radiation of the fields of the guided electromagnetic waves is low, propagation losses are consequently low, enabling the guided electromagnetic waves to propagate for longer distances.

As shown in diagram **554**, propagation losses increase when an operating frequency of the guide electromagnetic waves increases above about two-times the cutoff frequency (f_c)—or as referred to, above the range of the “sweet spot”. More of the field strength of the electromagnetic wave is driven inside the insulating layer, increasing propagation losses. At frequencies much higher than the cutoff frequency (f_c) the guided electromagnetic waves are strongly bound to the insulated wire as a result of the fields emitted by the guided electromagnetic waves being concentrated in the insulation layer of the wire, as shown in diagram **552**. This in turn raises propagation losses further due to absorption of the guided electromagnetic waves by the insulation layer. Similarly, propagation losses increase when the operating frequency of the guided electromagnetic waves is substantially below the cutoff frequency (f_c), as shown in diagram **558**. At frequencies much lower than the cutoff frequency (f_c) the guided electromagnetic waves are weakly (or nominally) bound to the insulated wire and thereby tend to radiate into the environment (e.g., air), which in turn, raises propagation losses due to radiation of the guided electromagnetic waves.

Referring now to FIG. **6**, a graphical diagram **600** illustrating an example, non-limiting embodiment of an electromagnetic field distribution is shown. In this embodiment, a transmission medium **602** is a bare wire, as shown in cross section. The diagram **300** includes different gray-scales that represent differing electromagnetic field strengths generated by the propagation of a guided wave having a symmetrical and fundamental guided wave mode at a single carrier frequency.

In this particular mode, electromagnetic waves are guided by the transmission medium **602** to propagate along an outer surface of the transmission medium—in this case, the outer surface of the bare wire. Electromagnetic waves are

“lightly” coupled to the wire so as to enable electromagnetic wave propagation at long distances with low propagation loss. As shown, the guided wave has a field structure that lies substantially outside of the transmission medium **602** that serves to guide the electromagnetic waves. The regions inside the conductor **602** have little or no field.

Referring now to FIG. **7**, a block diagram **700** illustrating an example, non-limiting embodiment of an arc coupler is shown. In particular a coupling device is presented for use in a transmission device, such as transmission device **101** or **102** presented in conjunction with FIG. **1**. The coupling device includes an arc coupler **704** coupled to a transmitter circuit **712** and termination or damper **714**. The arc coupler **704** can be made of a dielectric material, or other low-loss insulator (e.g., Teflon, polyethylene, etc.), or made of a conducting (e.g., metallic, non-metallic, etc.) material, or any combination of the foregoing materials. As shown, the arc coupler **704** operates as a waveguide and has a wave **706** propagating as a guided wave about a waveguide surface of the arc coupler **704**. In the embodiment shown, at least a portion of the arc coupler **704** can be placed near a wire **702** or other transmission medium, (such as transmission medium **125**), in order to facilitate coupling between the arc coupler **704** and the wire **702** or other transmission medium, as described herein to launch the guided wave **708** on the wire. The arc coupler **704** can be placed such that a portion of the curved arc coupler **704** is tangential to, and parallel or substantially parallel to the wire **702**. The portion of the arc coupler **704** that is parallel to the wire can be an apex of the curve, or any point where a tangent of the curve is parallel to the wire **702**. When the arc coupler **704** is positioned or placed thusly, the wave **706** travelling along the arc coupler **704** couples, at least in part, to the wire **702**, and propagates as guided wave **708** around or about the wire surface of the wire **702** and longitudinally along the wire **702**. The guided wave **708** can be characterized as a surface wave or other electromagnetic wave that is guided by or bound to the wire **702** or other transmission medium.

A portion of the wave **706** that does not couple to the wire **702** propagates as a wave **710** along the arc coupler **704**. It will be appreciated that the arc coupler **704** can be configured and arranged in a variety of positions in relation to the wire **702** to achieve a desired level of coupling or non-coupling of the wave **706** to the wire **702**. For example, the curvature and/or length of the arc coupler **704** that is parallel or substantially parallel, as well as its separation distance (which can include zero separation distance in an embodiment), to the wire **702** can be varied without departing from example embodiments. Likewise, the arrangement of arc coupler **704** in relation to the wire **702** may be varied based upon considerations of the respective intrinsic characteristics (e.g., thickness, composition, electromagnetic properties, etc.) of the wire **702** and the arc coupler **704**, as well as the characteristics (e.g., frequency, energy level, etc.) of the waves **706** and **708**.

The guided wave **708** stays parallel or substantially parallel to the wire **702**, even as the wire **702** bends and flexes. Bends in the wire **702** can increase transmission losses, which are also dependent on wire diameters, frequency, and materials. If the dimensions of the arc coupler **704** are chosen for efficient power transfer, most of the power in the wave **706** is transferred to the wire **702**, with little power remaining in wave **710**. It will be appreciated that the guided wave **708** can still be multi-modal in nature (discussed herein), including having modes that are non-fundamental or asymmetric, while traveling along a path that is parallel or substantially parallel to the wire **702**, with or without a

fundamental transmission mode. In an embodiment, non-fundamental or asymmetric modes can be utilized to minimize transmission losses and/or obtain increased propagation distances.

It is noted that the term parallel is generally a geometric construct which often is not exactly achievable in real systems. Accordingly, the term parallel as utilized in the subject disclosure represents an approximation rather than an exact configuration when used to describe embodiments disclosed in the subject disclosure. In an embodiment, substantially parallel can include approximations that are within 30 degrees of true parallel in all dimensions.

In an embodiment, the wave 706 can exhibit one or more wave propagation modes. The arc coupler modes can be dependent on the shape and/or design of the coupler 704. The one or more arc coupler modes of wave 706 can generate, influence, or impact one or more wave propagation modes of the guided wave 708 propagating along wire 702. It should be particularly noted however that the guided wave modes present in the guided wave 706 may be the same or different from the guided wave modes of the guided wave 708. In this fashion, one or more guided wave modes of the guided wave 706 may not be transferred to the guided wave 708, and further one or more guided wave modes of guided wave 708 may not have been present in guided wave 706. It should also be noted that the cut-off frequency of the arc coupler 704 for a particular guided wave mode may be different than the cutoff frequency of the wire 702 or other transmission medium for that same mode. For example, while the wire 702 or other transmission medium may be operated slightly above its cutoff frequency for a particular guided wave mode, the arc coupler 704 may be operated well above its cut-off frequency for that same mode for low loss, slightly below its cut-off frequency for that same mode to, for example, induce greater coupling and power transfer, or some other point in relation to the arc coupler's cutoff frequency for that mode.

In an embodiment, the wave propagation modes on the wire 702 can be similar to the arc coupler modes since both waves 706 and 708 propagate about the outside of the arc coupler 704 and wire 702 respectively. In some embodiments, as the wave 706 couples to the wire 702, the modes can change form, or new modes can be created or generated, due to the coupling between the arc coupler 704 and the wire 702. For example, differences in size, material, and/or impedances of the arc coupler 704 and wire 702 may create additional modes not present in the arc coupler modes and/or suppress some of the arc coupler modes. The wave propagation modes can comprise the fundamental transverse electromagnetic mode (Quasi-TEM₀₀), where only small electric and/or magnetic fields extend in the direction of propagation, and the electric and magnetic fields extend radially outwards while the guided wave propagates along the wire. This guided wave mode can be donut shaped, where few of the electromagnetic fields exist within the arc coupler 704 or wire 702.

Waves 706 and 708 can comprise a fundamental TEM mode where the fields extend radially outwards, and also comprise other, non-fundamental (e.g., asymmetric, higher-level, etc.) modes. While particular wave propagation modes are discussed above, other wave propagation modes are likewise possible such as transverse electric (TE) and transverse magnetic (TM) modes, based on the frequencies employed, the design of the arc coupler 704, the dimensions and composition of the wire 702, as well as its surface characteristics, its insulation if present, the electromagnetic properties of the surrounding environment, etc. It should be

noted that, depending on the frequency, the electrical and physical characteristics of the wire 702 and the particular wave propagation modes that are generated, guided wave 708 can travel along the conductive surface of an oxidized uninsulated wire, an unoxidized uninsulated wire, an insulated wire and/or along the insulating surface of an insulated wire.

In an embodiment, a diameter of the arc coupler 704 is smaller than the diameter of the wire 702. For the millimeter-band wavelength being used, the arc coupler 704 supports a single waveguide mode that makes up wave 706. This single waveguide mode can change as it couples to the wire 702 as guided wave 708. If the arc coupler 704 were larger, more than one waveguide mode can be supported, but these additional waveguide modes may not couple to the wire 702 as efficiently, and higher coupling losses can result. However, in some alternative embodiments, the diameter of the arc coupler 704 can be equal to or larger than the diameter of the wire 702, for example, where higher coupling losses are desirable or when used in conjunction with other techniques to otherwise reduce coupling losses (e.g., impedance matching with tapering, etc.).

In an embodiment, the wavelength of the waves 706 and 708 are comparable in size, or smaller than a circumference of the arc coupler 704 and the wire 702. In an example, if the wire 702 has a diameter of 0.5 cm, and a corresponding circumference of around 1.5 cm, the wavelength of the transmission is around 1.5 cm or less, corresponding to a frequency of 70 GHz or greater. In another embodiment, a suitable frequency of the transmission and the carrier-wave signal is in the range of 30-100 GHz, perhaps around 30-60 GHz, and around 38 GHz in one example. In an embodiment, when the circumference of the arc coupler 704 and wire 702 is comparable in size to, or greater, than a wavelength of the transmission, the waves 706 and 708 can exhibit multiple wave propagation modes including fundamental and/or non-fundamental (symmetric and/or asymmetric) modes that propagate over sufficient distances to support various communication systems described herein. The waves 706 and 708 can therefore comprise more than one type of electric and magnetic field configuration. In an embodiment, as the guided wave 708 propagates down the wire 702, the electrical and magnetic field configurations will remain the same from end to end of the wire 702. In other embodiments, as the guided wave 708 encounters interference (distortion or obstructions) or loses energy due to transmission losses or scattering, the electric and magnetic field configurations can change as the guided wave 708 propagates down wire 702.

In an embodiment, the arc coupler 704 can be composed of nylon, Teflon, polyethylene, a polyamide, or other plastics. In other embodiments, other dielectric materials are possible. The wire surface of wire 702 can be metallic with either a bare metallic surface, or can be insulated using plastic, dielectric, insulator or other coating, jacket or sheathing. In an embodiment, a dielectric or otherwise non-conducting/insulated waveguide can be paired with either a bare/metallic wire or insulated wire. In other embodiments, a metallic and/or conductive waveguide can be paired with a bare/metallic wire or insulated wire. In an embodiment, an oxidation layer on the bare metallic surface of the wire 702 (e.g., resulting from exposure of the bare metallic surface to oxygen/air) can also provide insulating or dielectric properties similar to those provided by some insulators or sheathings.

It is noted that the graphical representations of waves 706, 708 and 710 are presented merely to illustrate the principles

21

that wave 706 induces or otherwise launches a guided wave 708 on a wire 702 that operates, for example, as a single wire transmission line. Wave 710 represents the portion of wave 706 that remains on the arc coupler 704 after the generation of guided wave 708. The actual electric and magnetic fields generated as a result of such wave propagation may vary depending on the frequencies employed, the particular wave propagation mode or modes, the design of the arc coupler 704, the dimensions and composition of the wire 702, as well as its surface characteristics, its optional insulation, the electromagnetic properties of the surrounding environment, etc.

It is noted that arc coupler 704 can include a termination circuit or damper 714 at the end of the arc coupler 704 that can absorb leftover radiation or energy from wave 710. The termination circuit or damper 714 can prevent and/or minimize the leftover radiation or energy from wave 710 reflecting back toward transmitter circuit 712. In an embodiment, the termination circuit or damper 714 can include termination resistors, and/or other components that perform impedance matching to attenuate reflection. In some embodiments, if the coupling efficiencies are high enough, and/or wave 710 is sufficiently small, it may not be necessary to use a termination circuit or damper 714. For the sake of simplicity, these transmitter 712 and termination circuits or dampers 714 may not be depicted in the other figures, but in those embodiments, transmitter and termination circuits or dampers may possibly be used.

Further, while a single arc coupler 704 is presented that generates a single guided wave 708, multiple arc couplers 704 placed at different points along the wire 702 and/or at different azimuthal orientations about the wire can be employed to generate and receive multiple guided waves 708 at the same or different frequencies, at the same or different phases, at the same or different wave propagation modes.

FIG. 8, a block diagram 800 illustrating an example, non-limiting embodiment of an arc coupler is shown. In the embodiment shown, at least a portion of the coupler 704 can be placed near a wire 702 or other transmission medium, (such as transmission medium 125), in order to facilitate coupling between the arc coupler 704 and the wire 702 or other transmission medium, to extract a portion of the guided wave 806 as a guided wave 808 as described herein. The arc coupler 704 can be placed such that a portion of the curved arc coupler 704 is tangential to, and parallel or substantially parallel to the wire 702. The portion of the arc coupler 704 that is parallel to the wire can be an apex of the curve, or any point where a tangent of the curve is parallel to the wire 702. When the arc coupler 704 is positioned or placed thusly, the wave 806 travelling along the wire 702 couples, at least in part, to the arc coupler 704, and propagates as guided wave 808 along the arc coupler 704 to a receiving device (not expressly shown). A portion of the wave 806 that does not couple to the arc coupler propagates as wave 810 along the wire 702 or other transmission medium.

In an embodiment, the wave 806 can exhibit one or more wave propagation modes. The arc coupler modes can be dependent on the shape and/or design of the coupler 704. The one or more modes of guided wave 806 can generate, influence, or impact one or more guide-wave modes of the guided wave 808 propagating along the arc coupler 704. It should be particularly noted however that the guided wave modes present in the guided wave 806 may be the same or different from the guided wave modes of the guided wave 808. In this fashion, one or more guided wave modes of the

22

guided wave 806 may not be transferred to the guided wave 808, and further one or more guided wave modes of guided wave 808 may not have been present in guided wave 806.

Referring now to FIG. 9A, a block diagram 900 illustrating an example, non-limiting embodiment of a stub coupler is shown. In particular a coupling device that includes stub coupler 904 is presented for use in a transmission device, such as transmission device 101 or 102 presented in conjunction with FIG. 1. The stub coupler 904 can be made of a dielectric material, or other low-loss insulator (e.g., Teflon, polyethylene and etc.), or made of a conducting (e.g., metallic, non-metallic, etc.) material, or any combination of the foregoing materials. As shown, the stub coupler 904 operates as a waveguide and has a wave 906 propagating as a guided wave about a waveguide surface of the stub coupler 904. In the embodiment shown, at least a portion of the stub coupler 904 can be placed near a wire 702 or other transmission medium, (such as transmission medium 125), in order to facilitate coupling between the stub coupler 904 and the wire 702 or other transmission medium, as described herein to launch the guided wave 908 on the wire.

In an embodiment, the stub coupler 904 is curved, and an end of the stub coupler 904 can be tied, fastened, or otherwise mechanically coupled to a wire 702. When the end of the stub coupler 904 is fastened to the wire 702, the end of the stub coupler 904 is parallel or substantially parallel to the wire 702. Alternatively, another portion of the dielectric waveguide beyond an end can be fastened or coupled to wire 702 such that the fastened or coupled portion is parallel or substantially parallel to the wire 702. The fastener 910 can be a nylon cable tie or other type of non-conducting/dielectric material that is either separate from the stub coupler 904 or constructed as an integrated component of the stub coupler 904. The stub coupler 904 can be adjacent to the wire 702 without surrounding the wire 702.

Like the arc coupler 704 described in conjunction with FIG. 7, when the stub coupler 904 is placed with the end parallel to the wire 702, the guided wave 906 travelling along the stub coupler 904 couples to the wire 702, and propagates as guided wave 908 about the wire surface of the wire 702. In an example embodiment, the guided wave 908 can be characterized as a surface wave or other electromagnetic wave.

It is noted that the graphical representations of waves 906 and 908 are presented merely to illustrate the principles that wave 906 induces or otherwise launches a guided wave 908 on a wire 702 that operates, for example, as a single wire transmission line. The actual electric and magnetic fields generated as a result of such wave propagation may vary depending on one or more of the shape and/or design of the coupler, the relative position of the dielectric waveguide to the wire, the frequencies employed, the design of the stub coupler 904, the dimensions and composition of the wire 702, as well as its surface characteristics, its optional insulation, the electromagnetic properties of the surrounding environment, etc.

In an embodiment, an end of stub coupler 904 can taper towards the wire 702 in order to increase coupling efficiencies. Indeed, the tapering of the end of the stub coupler 904 can provide impedance matching to the wire 702 and reduce reflections, according to an example embodiment of the subject disclosure. For example, an end of the stub coupler 904 can be gradually tapered in order to obtain a desired level of coupling between waves 906 and 908 as illustrated in FIG. 9A.

In an embodiment, the fastener 910 can be placed such that there is a short length of the stub coupler 904 between

the fastener **910** and an end of the stub coupler **904**. Maximum coupling efficiencies are realized in this embodiment when the length of the end of the stub coupler **904** that is beyond the fastener **910** is at least several wavelengths long for whatever frequency is being transmitted.

Turning now to FIG. **9B**, a diagram **950** illustrating an example, non-limiting embodiment of an electromagnetic distribution in accordance with various aspects described herein is shown. In particular, an electromagnetic distribution is presented in two dimensions for a transmission device that includes coupler **952**, shown in an example stub coupler constructed of a dielectric material. The coupler **952** couples an electromagnetic wave for propagation as a guided wave along an outer surface of a wire **702** or other transmission medium.

The coupler **952** guides the electromagnetic wave to a junction at x_0 via a symmetrical guided wave mode. While some of the energy of the electromagnetic wave that propagates along the coupler **952** is outside of the coupler **952**, the majority of the energy of this electromagnetic wave is contained within the coupler **952**. The junction at x_0 couples the electromagnetic wave to the wire **702** or other transmission medium at an azimuthal angle corresponding to the bottom of the transmission medium. This coupling induces an electromagnetic wave that is guided to propagate along the outer surface of the wire **702** or other transmission medium via at least one guided wave mode in direction **956**. The majority of the energy of the guided electromagnetic wave is outside or, but in close proximity to the outer surface of the wire **702** or other transmission medium. In the example shown, the junction at x_0 forms an electromagnetic wave that propagates via both a symmetrical mode and at least one asymmetrical surface mode, such as the first order mode presented in conjunction with FIG. **3**, that skims the surface of the wire **702** or other transmission medium.

It is noted that the graphical representations of guided waves are presented merely to illustrate an example of guided wave coupling and propagation. The actual electric and magnetic fields generated as a result of such wave propagation may vary depending on the frequencies employed, the design and/or configuration of the coupler **952**, the dimensions and composition of the wire **702** or other transmission medium, as well as its surface characteristics, its insulation if present, the electromagnetic properties of the surrounding environment, etc.

Turning now to FIG. **10A**, illustrated is a block diagram **1000** of an example, non-limiting embodiment of a coupler and transceiver system in accordance with various aspects described herein. The system is an example of transmission device **101** or **102**. In particular, the communication interface **1008** is an example of communications interface **205**, the stub coupler **1002** is an example of coupler **220**, and the transmitter/receiver device **1006**, diplexer **1016**, power amplifier **1014**, low noise amplifier **1018**, frequency mixers **1010** and **1020** and local oscillator **1012** collectively form an example of transceiver **210**.

In operation, the transmitter/receiver device **1006** launches and receives waves (e.g., guided wave **1004** onto stub coupler **1002**). The guided waves **1004** can be used to transport signals received from and sent to a host device, base station, mobile devices, a building or other device by way of a communications interface **1008**. The communications interface **1008** can be an integral part of system **1000**. Alternatively, the communications interface **1008** can be tethered to system **1000**. The communications interface **1008** can comprise a wireless interface for interfacing to the host device, base station, mobile devices, a building or other

device utilizing any of various wireless signaling protocols (e.g., LTE, WiFi, WiMAX, IEEE 802.xx, etc.) including an infrared protocol such as an infrared data association (IrDA) protocol or other line of sight optical protocol. The communications interface **1008** can also comprise a wired interface such as a fiber optic line, coaxial cable, twisted pair, category 5 (CAT-5) cable or other suitable wired or optical mediums for communicating with the host device, base station, mobile devices, a building or other device via a protocol such as an Ethernet protocol, universal serial bus (USB) protocol, a data over cable service interface specification (DOCSIS) protocol, a digital subscriber line (DSL) protocol, a Firewire (IEEE 1394) protocol, or other wired or optical protocol. For embodiments where system **1000** functions as a repeater, the communications interface **1008** may not be necessary.

The output signals (e.g., Tx) of the communications interface **1008** can be combined with a carrier wave (e.g., millimeter-wave carrier wave) generated by a local oscillator **1012** at frequency mixer **1010**. Frequency mixer **1010** can use heterodyning techniques or other frequency shifting techniques to frequency shift the output signals from communications interface **1008**. For example, signals sent to and from the communications interface **1008** can be modulated signals such as orthogonal frequency division multiplexed (OFDM) signals formatted in accordance with a Long-Term Evolution (LTE) wireless protocol or other wireless 3G, 4G, 5G or higher voice and data protocol, a Zigbee, WIMAX, UltraWideband or IEEE 802.11 wireless protocol; a wired protocol such as an Ethernet protocol, universal serial bus (USB) protocol, a data over cable service interface specification (DOCSIS) protocol, a digital subscriber line (DSL) protocol, a Firewire (IEEE 1394) protocol or other wired or wireless protocol. In an example embodiment, this frequency conversion can be done in the analog domain, and as a result, the frequency shifting can be done without regard to the type of communications protocol used by a base station, mobile devices, or in-building devices. As new communications technologies are developed, the communications interface **1008** can be upgraded (e.g., updated with software, firmware, and/or hardware) or replaced and the frequency shifting and transmission apparatus can remain, simplifying upgrades. The carrier wave can then be sent to a power amplifier ("PA") **1014** and can be transmitted via the transmitter/receiver device **1006** via the diplexer **1016**.

Signals received from the transmitter/receiver device **1006** that are directed towards the communications interface **1008** can be separated from other signals via diplexer **1016**. The received signal can then be sent to low noise amplifier ("LNA") **1018** for amplification. A frequency mixer **1020**, with help from local oscillator **1012** can downshift the received signal (which is in the millimeter-wave band or around 38 GHz in some embodiments) to the native frequency. The communications interface **1008** can then receive the transmission at an input port (Rx).

In an embodiment, transmitter/receiver device **1006** can include a cylindrical or non-cylindrical metal (which, for example, can be hollow in an embodiment, but not necessarily drawn to scale) or other conducting or non-conducting waveguide and an end of the stub coupler **1002** can be placed in or in proximity to the waveguide or the transmitter/receiver device **1006** such that when the transmitter/receiver device **1006** generates a transmission, the guided wave couples to stub coupler **1002** and propagates as a guided wave **1004** about the waveguide surface of the stub coupler **1002**. In some embodiments, the guided wave **1004** can propagate in part on the outer surface of the stub coupler

1002 and in part inside the stub coupler 1002. In other embodiments, the guided wave 1004 can propagate substantially or completely on the outer surface of the stub coupler 1002. In yet other embodiments, the guided wave 1004 can propagate substantially or completely inside the stub coupler 1002. In this latter embodiment, the guided wave 1004 can radiate at an end of the stub coupler 1002 (such as the tapered end shown in FIG. 4) for coupling to a transmission medium such as a wire 702 of FIG. 7. Similarly, if guided wave 1004 is incoming (coupled to the stub coupler 1002 from a wire 702), guided wave 1004 then enters the transmitter/receiver device 1006 and couples to the cylindrical waveguide or conducting waveguide. While transmitter/receiver device 1006 is shown to include a separate waveguide—an antenna, cavity resonator, klystron, magnetron, travelling wave tube, or other radiating element can be employed to induce a guided wave on the coupler 1002, with or without the separate waveguide.

In an embodiment, stub coupler 1002 can be wholly constructed of a dielectric material (or another suitable insulating material), without any metallic or otherwise conducting materials therein. Stub coupler 1002 can be composed of nylon, Teflon, polyethylene, a polyamide, other plastics, or other materials that are non-conducting and suitable for facilitating transmission of electromagnetic waves at least in part on an outer surface of such materials. In another embodiment, stub coupler 1002 can include a core that is conducting/metallic, and have an exterior dielectric surface. Similarly, a transmission medium that couples to the stub coupler 1002 for propagating electromagnetic waves induced by the stub coupler 1002 or for supplying electromagnetic waves to the stub coupler 1002 can, in addition to being a bare or insulated wire, be wholly constructed of a dielectric material (or another suitable insulating material), without any metallic or otherwise conducting materials therein.

It is noted that although FIG. 10A shows that the opening of transmitter receiver device 1006 is much wider than the stub coupler 1002, this is not to scale, and that in other embodiments the width of the stub coupler 1002 is comparable or slightly smaller than the opening of the hollow waveguide. It is also not shown, but in an embodiment, an end of the coupler 1002 that is inserted into the transmitter/receiver device 1006 tapers down in order to reduce reflection and increase coupling efficiencies.

Before coupling to the stub coupler 1002, the one or more waveguide modes of the guided wave generated by the transmitter/receiver device 1006 can couple to the stub coupler 1002 to induce one or more wave propagation modes of the guided wave 1004. The wave propagation modes of the guided wave 1004 can be different than the hollow metal waveguide modes due to the different characteristics of the hollow metal waveguide and the dielectric waveguide. For instance, wave propagation modes of the guided wave 1004 can comprise the fundamental transverse electromagnetic mode (Quasi-TEM₀₀), where only small electrical and/or magnetic fields extend in the direction of propagation, and the electric and magnetic fields extend radially outwards from the stub coupler 1002 while the guided waves propagate along the stub coupler 1002. The fundamental transverse electromagnetic mode wave propagation mode may or may not exist inside a waveguide that is hollow. Therefore, the hollow metal waveguide modes that are used by transmitter/receiver device 1006 are waveguide modes that can couple effectively and efficiently to wave propagation modes of stub coupler 1002.

It will be appreciated that other constructs or combinations of the transmitter/receiver device 1006 and stub coupler 1002 are possible. For example, a stub coupler 1002' can be placed tangentially or in parallel (with or without a gap) with respect to an outer surface of the hollow metal waveguide of the transmitter/receiver device 1006' (corresponding circuitry not shown) as depicted by reference 1000' of FIG. 10B. In another embodiment, not shown by reference 1000', the stub coupler 1002' can be placed inside the hollow metal waveguide of the transmitter/receiver device 1006' without an axis of the stub coupler 1002' being coaxially aligned with an axis of the hollow metal waveguide of the transmitter/receiver device 1006'. In either of these embodiments, the guided wave generated by the transmitter/receiver device 1006' can couple to a surface of the stub coupler 1002' to induce one or more wave propagation modes of the guided wave 1004' on the stub coupler 1002' including a fundamental mode (e.g., a symmetric mode) and/or a non-fundamental mode (e.g., asymmetric mode).

In one embodiment, the guided wave 1004' can propagate in part on the outer surface of the stub coupler 1002' and in part inside the stub coupler 1002'. In another embodiment, the guided wave 1004' can propagate substantially or completely on the outer surface of the stub coupler 1002'. In yet other embodiments, the guided wave 1004' can propagate substantially or completely inside the stub coupler 1002'. In this latter embodiment, the guided wave 1004' can radiate at an end of the stub coupler 1002' (such as the tapered end shown in FIG. 9) for coupling to a transmission medium such as a wire 702 of FIG. 9.

It will be further appreciated that other constructs the transmitter/receiver device 1006 are possible. For example, a hollow metal waveguide of a transmitter/receiver device 1006" (corresponding circuitry not shown), depicted in FIG. 10B as reference 1000", can be placed tangentially or in parallel (with or without a gap) with respect to an outer surface of a transmission medium such as the wire 702 of FIG. 4 without the use of the stub coupler 1002. In this embodiment, the guided wave generated by the transmitter/receiver device 1006" can couple to a surface of the wire 702 to induce one or more wave propagation modes of a guided wave 908 on the wire 702 including a fundamental mode (e.g., a symmetric mode) and/or a non-fundamental mode (e.g., asymmetric mode). In another embodiment, the wire 702 can be positioned inside a hollow metal waveguide of a transmitter/receiver device 1006'" (corresponding circuitry not shown) so that an axis of the wire 702 is coaxially (or not coaxially) aligned with an axis of the hollow metal waveguide without the use of the stub coupler 1002—see FIG. 10B reference 1000"". In this embodiment, the guided wave generated by the transmitter/receiver device 1006'" can couple to a surface of the wire 702 to induce one or more wave propagation modes of a guided wave 908 on the wire including a fundamental mode (e.g., a symmetric mode) and/or a non-fundamental mode (e.g., asymmetric mode).

In the embodiments of 1000" and 1000'", for a wire 702 having an insulated outer surface, the guided wave 908 can propagate in part on the outer surface of the insulator and in part inside the insulator. In embodiments, the guided wave 908 can propagate substantially or completely on the outer surface of the insulator, or substantially or completely inside the insulator. In the embodiments of 1000" and 1000'", for a wire 702 that is a bare conductor, the guided wave 908 can propagate in part on the outer surface of the conductor and in part inside the conductor. In another embodiment, the guided wave 908 can propagate substantially or completely on the outer surface of the conductor.

Referring now to FIG. 11, a block diagram 1100 illustrating an example, non-limiting embodiment of a dual stub coupler is shown. In particular, a dual coupler design is presented for use in a transmission device, such as transmission device 101 or 102 presented in conjunction with FIG. 1. In an embodiment, two or more couplers (such as the stub couplers 1104 and 1106) can be positioned around a wire 1102 in order to receive guided wave 1108. In an embodiment, one coupler is enough to receive the guided wave 1108. In that case, guided wave 1108 couples to coupler 1104 and propagates as guided wave 1110. If the field structure of the guided wave 1108 oscillates or undulates around the wire 1102 due to the particular guided wave mode(s) or various outside factors, then coupler 1106 can be placed such that guided wave 1108 couples to coupler 1106. In some embodiments, four or more couplers can be placed around a portion of the wire 1102, e.g., at 90 degrees or another spacing with respect to each other, in order to receive guided waves that may oscillate or rotate around the wire 1102, that have been induced at different azimuthal orientations or that have non-fundamental or higher order modes that, for example, have lobes and/or nulls or other asymmetries that are orientation dependent. However, it will be appreciated that there may be less than or more than four couplers placed around a portion of the wire 1102 without departing from example embodiments.

It should be noted that while couplers 1106 and 1104 are illustrated as stub couplers, any other of the coupler designs described herein including arc couplers, antenna or horn couplers, magnetic couplers, etc., could likewise be used. It will also be appreciated that while some example embodiments have presented a plurality of couplers around at least a portion of a wire 1102, this plurality of couplers can also be considered as part of a single coupler system having multiple coupler subcomponents. For example, two or more couplers can be manufactured as single system that can be installed around a wire in a single installation such that the couplers are either pre-positioned or adjustable relative to each other (either manually or automatically with a controllable mechanism such as a motor or other actuator) in accordance with the single system.

Receivers coupled to couplers 1106 and 1104 can use diversity combining to combine signals received from both couplers 1106 and 1104 in order to maximize the signal quality. In other embodiments, if one or the other of the couplers 1104 and 1106 receive a transmission that is above a predetermined threshold, receivers can use selection diversity when deciding which signal to use. Further, while reception by a plurality of couplers 1106 and 1104 is illustrated, transmission by couplers 1106 and 1104 in the same configuration can likewise take place. In particular, a wide range of multi-input multi-output (MIMO) transmission and reception techniques can be employed for transmissions where a transmission device, such as transmission device 101 or 102 presented in conjunction with FIG. 1 includes multiple transceivers and multiple couplers.

It is noted that the graphical representations of waves 1108 and 1110 are presented merely to illustrate the principles that guided wave 1108 induces or otherwise launches a wave 1110 on a coupler 1104. The actual electric and magnetic fields generated as a result of such wave propagation may vary depending on the frequencies employed, the design of the coupler 1104, the dimensions and composition of the wire 1102, as well as its surface characteristics, its insulation if any, the electromagnetic properties of the surrounding environment, etc.

Referring now to FIG. 12, a block diagram 1200 illustrating an example, non-limiting embodiment of a repeater system is shown. In particular, a repeater device 1210 is presented for use in a transmission device, such as transmission device 101 or 102 presented in conjunction with FIG. 1. In this system, two couplers 1204 and 1214 can be placed near a wire 1202 or other transmission medium such that guided waves 1205 propagating along the wire 1202 are extracted by coupler 1204 as wave 1206 (e.g. as a guided wave), and then are boosted or repeated by repeater device 1210 and launched as a wave 1216 (e.g. as a guided wave) onto coupler 1214. The wave 1216 can then be launched on the wire 1202 and continue to propagate along the wire 1202 as a guided wave 1217. In an embodiment, the repeater device 1210 can receive at least a portion of the power utilized for boosting or repeating through magnetic coupling with the wire 1202, for example, when the wire 1202 is a power line or otherwise contains a power-carrying conductor. It should be noted that while couplers 1204 and 1214 are illustrated as stub couplers, any other of the coupler designs described herein including arc couplers, antenna or horn couplers, magnetic couplers, or the like, could likewise be used.

In some embodiments, repeater device 1210 can repeat the transmission associated with wave 1206, and in other embodiments, repeater device 1210 can include a communications interface 205 that extracts data or other signals from the wave 1206 for supplying such data or signals to another network and/or one or more other devices as communication signals 110 or 112 and/or receiving communication signals 110 or 112 from another network and/or one or more other devices and launch guided wave 1216 having embedded therein the received communication signals 110 or 112. In a repeater configuration, receiver waveguide 1208 can receive the wave 1206 from the coupler 1204 and transmitter waveguide 1212 can launch guided wave 1216 onto coupler 1214 as guided wave 1217. Between receiver waveguide 1208 and transmitter waveguide 1212, the signal embedded in guided wave 1206 and/or the guided wave 1216 itself can be amplified to correct for signal loss and other inefficiencies associated with guided wave communications or the signal can be received and processed to extract the data contained therein and regenerated for transmission. In an embodiment, the receiver waveguide 1208 can be configured to extract data from the signal, process the data to correct for data errors utilizing for example error correcting codes, and regenerate an updated signal with the corrected data. The transmitter waveguide 1212 can then transmit guided wave 1216 with the updated signal embedded therein. In an embodiment, a signal embedded in guided wave 1206 can be extracted from the transmission and processed for communication with another network and/or one or more other devices via communications interface 205 as communication signals 110 or 112. Similarly, communication signals 110 or 112 received by the communications interface 205 can be inserted into a transmission of guided wave 1216 that is generated and launched onto coupler 1214 by transmitter waveguide 1212.

It is noted that although FIG. 12 shows guided wave transmissions 1206 and 1216 entering from the left and exiting to the right respectively, this is merely a simplification and is not intended to be limiting. In other embodiments, receiver waveguide 1208 and transmitter waveguide 1212 can also function as transmitters and receivers respectively, allowing the repeater device 1210 to be bi-directional.

In an embodiment, repeater device 1210 can be placed at locations where there are discontinuities or obstacles on the

wire **1202** or other transmission medium. In the case where the wire **1202** is a power line, these obstacles can include transformers, connections, utility poles, and other such power line devices. The repeater device **1210** can help the guided (e.g., surface) waves jump over these obstacles on the line and boost the transmission power at the same time. In other embodiments, a coupler can be used to jump over the obstacle without the use of a repeater device. In that embodiment, both ends of the coupler can be tied or fastened to the wire, thus providing a path for the guided wave to travel without being blocked by the obstacle.

Turning now to FIG. **13**, illustrated is a block diagram **1300** of an example, non-limiting embodiment of a bidirectional repeater in accordance with various aspects described herein. In particular, a bidirectional repeater device **1306** is presented for use in a transmission device, such as transmission device **101** or **102** presented in conjunction with FIG. **1**. It should be noted that while the couplers are illustrated as stub couplers, any other of the coupler designs described herein including arc couplers, antenna or horn couplers, magnetic couplers, or the like, could likewise be used. The bidirectional repeater **1306** can employ diversity paths in the case of when two or more wires or other transmission media are present. Since guided wave transmissions have different transmission efficiencies and coupling efficiencies for transmission medium of different types such as insulated wires, un-insulated wires or other types of transmission media and further, if exposed to the elements, can be affected by weather, and other atmospheric conditions, it can be advantageous to selectively transmit on different transmission media at certain times. In various embodiments, the various transmission media can be designated as a primary, secondary, tertiary, etc. whether or not such designation indicates a preference of one transmission medium over another.

In the embodiment shown, the transmission media include an insulated or uninsulated wire **1302** and an insulated or uninsulated wire **1304** (referred to herein as wires **1302** and **1304**, respectively). The repeater device **1306** uses a receiver coupler **1308** to receive a guided wave traveling along wire **1302** and repeats the transmission using transmitter waveguide **1310** as a guided wave along wire **1304**. In other embodiments, repeater device **1306** can switch from the wire **1304** to the wire **1302**, or can repeat the transmissions along the same paths. Repeater device **1306** can include sensors, or be in communication with sensors (or a network management system **1601** depicted in FIG. **16A**) that indicate conditions that can affect the transmission. Based on the feedback received from the sensors, the repeater device **1306** can make the determination about whether to keep the transmission along the same wire, or transfer the transmission to the other wire.

Turning now to FIG. **14**, illustrated is a block diagram **1400** illustrating an example, non-limiting embodiment of a bidirectional repeater system. In particular, a bidirectional repeater system is presented for use in a transmission device, such as transmission device **101** or **102** presented in conjunction with FIG. **1**. The bidirectional repeater system includes waveguide coupling devices **1402** and **1404** that receive and transmit transmissions from other coupling devices located in a distributed antenna system or backhaul system.

In various embodiments, waveguide coupling device **1402** can receive a transmission from another waveguide coupling device, wherein the transmission has a plurality of subcarriers. Diplexer **1406** can separate the transmission from other transmissions, and direct the transmission to

low-noise amplifier (“LNA”) **1408**. A frequency mixer **1428**, with help from a local oscillator **1412**, can downshift the transmission (which is in the millimeter-wave band or around 38 GHz in some embodiments) to a lower frequency, such as a cellular band (~1.9 GHz) for a distributed antenna system, a native frequency, or other frequency for a backhaul system. An extractor (or demultiplexer) **1432** can extract the signal on a subcarrier and direct the signal to an output component **1422** for optional amplification, buffering or isolation by power amplifier **1424** for coupling to communications interface **205**. The communications interface **205** can further process the signals received from the power amplifier **1424** or otherwise transmit such signals over a wireless or wired interface to other devices such as a base station, mobile devices, a building, etc. For the signals that are not being extracted at this location, extractor **1432** can redirect them to another frequency mixer **1436**, where the signals are used to modulate a carrier wave generated by local oscillator **1414**. The carrier wave, with its subcarriers, is directed to a power amplifier (“PA”) **1416** and is retransmitted by waveguide coupling device **1404** to another system, via diplexer **1420**.

An LNA **1426** can be used to amplify, buffer or isolate signals that are received by the communication interface **205** and then send the signal to a multiplexer **1434** which merges the signal with signals that have been received from waveguide coupling device **1404**. The signals received from coupling device **1404** have been split by diplexer **1420**, and then passed through LNA **1418**, and downshifted in frequency by frequency mixer **1438**. When the signals are combined by multiplexer **1434**, they are upshifted in frequency by frequency mixer **1430**, and then boosted by PA **1410**, and transmitted to another system by waveguide coupling device **1402**. In an embodiment bidirectional repeater system can be merely a repeater without the output device **1422**. In this embodiment, the multiplexer **1434** would not be utilized and signals from LNA **1418** would be directed to mixer **1430** as previously described. It will be appreciated that in some embodiments, the bidirectional repeater system could also be implemented using two distinct and separate unidirectional repeaters. In an alternative embodiment, a bidirectional repeater system could also be a booster or otherwise perform retransmissions without downshifting and upshifting. Indeed in example embodiment, the retransmissions can be based upon receiving a signal or guided wave and performing some signal or guided wave processing or reshaping, filtering, and/or amplification, prior to retransmission of the signal or guided wave.

Referring now to FIG. **15**, a block diagram **1500** illustrating an example, non-limiting embodiment of a guided wave communications system is shown. This diagram depicts an exemplary environment in which a guided wave communication system, such as the guided wave communication system presented in conjunction with FIG. **1**, can be used.

To provide network connectivity to additional base station devices, a backhaul network that links the communication cells (e.g., microcells and macrocells) to network devices of a core network correspondingly expands. Similarly, to provide network connectivity to a distributed antenna system, an extended communication system that links base station devices and their distributed antennas is desirable. A guided wave communication system **1500** such as shown in FIG. **15** can be provided to enable alternative, increased or additional network connectivity and a waveguide coupling system can be provided to transmit and/or receive guided wave (e.g., surface wave) communications on a transmission medium

such as a wire that operates as a single-wire transmission line (e.g., a utility line), and that can be used as a waveguide and/or that otherwise operates to guide the transmission of an electromagnetic wave.

The guided wave communication system **1500** can comprise a first instance of a distribution system **1550** that includes one or more base station devices (e.g., base station device **1504**) that are communicably coupled to a central office **1501** and/or a macrocell site **1502**. Base station device **1504** can be connected by a wired (e.g., fiber and/or cable), or by a wireless (e.g., microwave wireless) connection to the macrocell site **1502** and the central office **1501**. A second instance of the distribution system **1560** can be used to provide wireless voice and data services to mobile device **1522** and to residential and/or commercial establishments **1542** (herein referred to as establishments **1542**). System **1500** can have additional instances of the distribution systems **1550** and **1560** for providing voice and/or data services to mobile devices **1522-1524** and establishments **1542** as shown in FIG. **15**.

Macrocells such as macrocell site **1502** can have dedicated connections to a mobile network and base station device **1504** or can share and/or otherwise use another connection. Central office **1501** can be used to distribute media content and/or provide internet service provider (ISP) services to mobile devices **1522-1524** and establishments **1542**. The central office **1501** can receive media content from a constellation of satellites **1530** (one of which is shown in FIG. **15**) or other sources of content, and distribute such content to mobile devices **1522-1524** and establishments **1542** via the first and second instances of the distribution system **1550** and **1560**. The central office **1501** can also be communicatively coupled to the Internet **1503** for providing internet data services to mobile devices **1522-1524** and establishments **1542**.

Base station device **1504** can be mounted on, or attached to, utility pole **1516**. In other embodiments, base station device **1504** can be near transformers and/or other locations situated nearby a power line. Base station device **1504** can facilitate connectivity to a mobile network for mobile devices **1522** and **1524**. Antennas **1512** and **1514**, mounted on or near utility poles **1518** and **1520**, respectively, can receive signals from base station device **1504** and transmit those signals to mobile devices **1522** and **1524** over a much wider area than if the antennas **1512** and **1514** were located at or near base station device **1504**.

It is noted that FIG. **15** displays three utility poles, in each instance of the distribution systems **1550** and **1560**, with one base station device, for purposes of simplicity. In other embodiments, utility pole **1516** can have more base station devices, and more utility poles with distributed antennas and/or tethered connections to establishments **1542**.

A transmission device **1506**, such as transmission device **101** or **102** presented in conjunction with FIG. **1**, can transmit a signal from base station device **1504** to antennas **1512** and **1514** via utility or power line(s) that connect the utility poles **1516**, **1518**, and **1520**. To transmit the signal, radio source and/or transmission device **1506** upconverts the signal (e.g., via frequency mixing) from base station device **1504** or otherwise converts the signal from the base station device **1504** to a microwave band signal and the transmission device **1506** launches a microwave band wave that propagates as a guided wave traveling along the utility line or other wire as described in previous embodiments. At utility pole **1518**, another transmission device **1508** receives the guided wave (and optionally can amplify it as needed or desired or operate as a repeater to receive it and regenerate

it) and sends it forward as a guided wave on the utility line or other wire. The transmission device **1508** can also extract a signal from the microwave band guided wave and shift it down in frequency or otherwise convert it to its original cellular band frequency (e.g., 1.9 GHz or other defined cellular frequency) or another cellular (or non-cellular) band frequency. An antenna **1512** can wireless transmit the down-shifted signal to mobile device **1522**. The process can be repeated by transmission device **1510**, antenna **1514** and mobile device **1524**, as necessary or desirable.

Transmissions from mobile devices **1522** and **1524** can also be received by antennas **1512** and **1514** respectively. The transmission devices **1508** and **1510** can upshift or otherwise convert the cellular band signals to microwave band and transmit the signals as guided wave (e.g., surface wave or other electromagnetic wave) transmissions over the power line(s) to base station device **1504**.

Media content received by the central office **1501** can be supplied to the second instance of the distribution system **1560** via the base station device **1504** for distribution to mobile devices **1522** and establishments **1542**. The transmission device **1510** can be tethered to the establishments **1542** by one or more wired connections or a wireless interface. The one or more wired connections may include without limitation, a power line, a coaxial cable, a fiber cable, a twisted pair cable, a guided wave transmission medium or other suitable wired mediums for distribution of media content and/or for providing internet services. In an example embodiment, the wired connections from the transmission device **1510** can be communicatively coupled to one or more very high bit rate digital subscriber line (VDSL) modems located at one or more corresponding service area interfaces (SAIs—not shown) or pedestals, each SAI or pedestal providing services to a portion of the establishments **1542**. The VDSL modems can be used to selectively distribute media content and/or provide internet services to gateways (not shown) located in the establishments **1542**. The SAIs or pedestals can also be communicatively coupled to the establishments **1542** over a wired medium such as a power line, a coaxial cable, a fiber cable, a twisted pair cable, a guided wave transmission medium or other suitable wired mediums. In other example embodiments, the transmission device **1510** can be communicatively coupled directly to establishments **1542** without intermediate interfaces such as the SAIs or pedestals.

In another example embodiment, system **1500** can employ diversity paths, where two or more utility lines or other wires are strung between the utility poles **1516**, **1518**, and **1520** (e.g., for example, two or more wires between poles **1516** and **1520**) and redundant transmissions from base station/macrocell site **1502** are transmitted as guided waves down the surface of the utility lines or other wires. The utility lines or other wires can be either insulated or uninsulated, and depending on the environmental conditions that cause transmission losses, the coupling devices can selectively receive signals from the insulated or uninsulated utility lines or other wires. The selection can be based on measurements of the signal-to-noise ratio of the wires, or based on determined weather/environmental conditions (e.g., moisture detectors, weather forecasts, etc.). The use of diversity paths with system **1500** can enable alternate routing capabilities, load balancing, increased load handling, concurrent bi-directional or synchronous communications, spread spectrum communications, etc.

It is noted that the use of the transmission devices **1506**, **1508**, and **1510** in FIG. **15** are by way of example only, and that in other embodiments, other uses are possible. For

instance, transmission devices can be used in a backhaul communication system, providing network connectivity to base station devices. Transmission devices **1506**, **1508**, and **1510** can be used in many circumstances where it is desirable to transmit guided wave communications over a wire, whether insulated or not insulated. Transmission devices **1506**, **1508**, and **1510** are improvements over other coupling devices due to no contact or limited physical and/or electrical contact with the wires that may carry high voltages. The transmission device can be located away from the wire (e.g., spaced apart from the wire) and/or located on the wire so long as it is not electrically in contact with the wire, as the dielectric acts as an insulator, allowing for cheap, easy, and/or less complex installation. However, as previously noted conducting or non-dielectric couplers can be employed, for example in configurations where the wires correspond to a telephone network, cable television network, broadband data service, fiber optic communications system or other network employing low voltages or having insulated transmission lines.

It is further noted, that while base station device **1504** and macrocell site **1502** are illustrated in an embodiment, other network configurations are likewise possible. For example, devices such as access points or other wireless gateways can be employed in a similar fashion to extend the reach of other networks such as a wireless local area network, a wireless personal area network or other wireless network that operates in accordance with a communication protocol such as a 802.11 protocol, WIMAX protocol, UltraWideband protocol, Bluetooth protocol, Zigbee protocol or other wireless protocol.

Referring now to FIGS. **16A** & **16B**, block diagrams illustrating an example, non-limiting embodiment of a system for managing a power grid communication system are shown. Considering FIG. **16A**, a waveguide system **1602** is presented for use in a guided wave communications system, such as the system presented in conjunction with FIG. **15**. The waveguide system **1602** can comprise sensors **1604**, a power management system **1605**, a transmission device **101** or **102** that includes at least one communication interface **205**, transceiver **210** and coupler **220**.

The waveguide system **1602** can be coupled to a power line **1610** for facilitating guided wave communications in accordance with embodiments described in the subject disclosure. In an example embodiment, the transmission device **101** or **102** includes coupler **220** for inducing electromagnetic waves on a surface of the power line **1610** that longitudinally propagate along the surface of the power line **1610** as described in the subject disclosure. The transmission device **101** or **102** can also serve as a repeater for retransmitting electromagnetic waves on the same power line **1610** or for routing electromagnetic waves between power lines **1610** as shown in FIGS. **12-13**.

The transmission device **101** or **102** includes transceiver **210** configured to, for example, up-convert a signal operating at an original frequency range to electromagnetic waves operating at, exhibiting, or associated with a carrier frequency that propagate along a coupler to induce corresponding guided electromagnetic waves that propagate along a surface of the power line **1610**. A carrier frequency can be represented by a center frequency having upper and lower cutoff frequencies that define the bandwidth of the electromagnetic waves. The power line **1610** can be a wire (e.g., single stranded or multi-stranded) having a conducting surface or insulated surface. The transceiver **210** can also receive signals from the coupler **220** and down-convert the

electromagnetic waves operating at a carrier frequency to signals at their original frequency.

Signals received by the communications interface **205** of transmission device **101** or **102** for up-conversion can include without limitation signals supplied by a central office **1611** over a wired or wireless interface of the communications interface **205**, a base station **1614** over a wired or wireless interface of the communications interface **205**, wireless signals transmitted by mobile devices **1620** to the base station **1614** for delivery over the wired or wireless interface of the communications interface **205**, signals supplied by in-building communication devices **1618** over the wired or wireless interface of the communications interface **205**, and/or wireless signals supplied to the communications interface **205** by mobile devices **1612** roaming in a wireless communication range of the communications interface **205**. In embodiments where the waveguide system **1602** functions as a repeater, such as shown in FIGS. **12-13**, the communications interface **205** may or may not be included in the waveguide system **1602**.

The electromagnetic waves propagating along the surface of the power line **1610** can be modulated and formatted to include packets or frames of data that include a data payload and further include networking information (such as header information for identifying one or more destination waveguide systems **1602**). The networking information may be provided by the waveguide system **1602** or an originating device such as the central office **1611**, the base station **1614**, mobile devices **1620**, or in-building devices **1618**, or a combination thereof. Additionally, the modulated electromagnetic waves can include error correction data for mitigating signal disturbances. The networking information and error correction data can be used by a destination waveguide system **1602** for detecting transmissions directed to it, and for down-converting and processing with error correction data transmissions that include voice and/or data signals directed to recipient communication devices communicatively coupled to the destination waveguide system **1602**.

Referring now to the sensors **1604** of the waveguide system **1602**, the sensors **1604** can comprise one or more of a temperature sensor **1604a**, a disturbance detection sensor **1604b**, a loss of energy sensor **1604c**, a noise sensor **1604d**, a vibration sensor **1604e**, an environmental (e.g., weather) sensor **1604f**, and/or an image sensor **1604g**. The temperature sensor **1604a** can be used to measure ambient temperature, a temperature of the transmission device **101** or **102**, a temperature of the power line **1610**, temperature differentials (e.g., compared to a setpoint or baseline, between transmission device **101** or **102** and **1610**, etc.), or any combination thereof. In one embodiment, temperature metrics can be collected and reported periodically to a network management system **1601** by way of the base station **1614**.

The disturbance detection sensor **1604b** can perform measurements on the power line **1610** to detect disturbances such as signal reflections, which may indicate a presence of a downstream disturbance that may impede the propagation of electromagnetic waves on the power line **1610**. A signal reflection can represent a distortion resulting from, for example, an electromagnetic wave transmitted on the power line **1610** by the transmission device **101** or **102** that reflects in whole or in part back to the transmission device **101** or **102** from a disturbance in the power line **1610** located downstream from the transmission device **101** or **102**.

Signal reflections can be caused by obstructions on the power line **1610**. For example, a tree limb may cause electromagnetic wave reflections when the tree limb is lying on the power line **1610**, or is in close proximity to the power

35

line 1610 which may cause a corona discharge. Other obstructions that can cause electromagnetic wave reflections can include without limitation an object that has been entangled on the power line 1610 (e.g., clothing, a shoe wrapped around a power line 1610 with a shoe string, etc.), a corroded build-up on the power line 1610 or an ice build-up. Power grid components may also impede or obstruct with the propagation of electromagnetic waves on the surface of power lines 1610. Illustrations of power grid components that may cause signal reflections include without limitation a transformer and a joint for connecting spliced power lines. A sharp angle on the power line 1610 may also cause electromagnetic wave reflections.

The disturbance detection sensor 1604b can comprise a circuit to compare magnitudes of electromagnetic wave reflections to magnitudes of original electromagnetic waves transmitted by the transmission device 101 or 102 to determine how much a downstream disturbance in the power line 1610 attenuates transmissions. The disturbance detection sensor 1604b can further comprise a spectral analyzer circuit for performing spectral analysis on the reflected waves. The spectral data generated by the spectral analyzer circuit can be compared with spectral profiles via pattern recognition, an expert system, curve fitting, matched filtering or other artificial intelligence, classification or comparison technique to identify a type of disturbance based on, for example, the spectral profile that most closely matches the spectral data. The spectral profiles can be stored in a memory of the disturbance detection sensor 1604b or may be remotely accessible by the disturbance detection sensor 1604b. The profiles can comprise spectral data that models different disturbances that may be encountered on power lines 1610 to enable the disturbance detection sensor 1604b to identify disturbances locally. An identification of the disturbance if known can be reported to the network management system 1601 by way of the base station 1614. The disturbance detection sensor 1604b can also utilize the transmission device 101 or 102 to transmit electromagnetic waves as test signals to determine a roundtrip time for an electromagnetic wave reflection. The round trip time measured by the disturbance detection sensor 1604b can be used to calculate a distance traveled by the electromagnetic wave up to a point where the reflection takes place, which enables the disturbance detection sensor 1604b to calculate a distance from the transmission device 101 or 102 to the downstream disturbance on the power line 1610.

The distance calculated can be reported to the network management system 1601 by way of the base station 1614. In one embodiment, the location of the waveguide system 1602 on the power line 1610 may be known to the network management system 1601, which the network management system 1601 can use to determine a location of the disturbance on the power line 1610 based on a known topology of the power grid. In another embodiment, the waveguide system 1602 can provide its location to the network management system 1601 to assist in the determination of the location of the disturbance on the power line 1610. The location of the waveguide system 1602 can be obtained by the waveguide system 1602 from a pre-programmed location of the waveguide system 1602 stored in a memory of the waveguide system 1602, or the waveguide system 1602 can determine its location using a GPS receiver (not shown) included in the waveguide system 1602.

The power management system 1605 provides energy to the aforementioned components of the waveguide system 1602. The power management system 1605 can receive energy from solar cells, or from a transformer (not shown)

36

coupled to the power line 1610, or by inductive coupling to the power line 1610 or another nearby power line. The power management system 1605 can also include a backup battery and/or a super capacitor or other capacitor circuit for providing the waveguide system 1602 with temporary power. The loss of energy sensor 1604c can be used to detect when the waveguide system 1602 has a loss of power condition and/or the occurrence of some other malfunction. For example, the loss of energy sensor 1604c can detect when there is a loss of power due to defective solar cells, an obstruction on the solar cells that causes them to malfunction, loss of power on the power line 1610, and/or when the backup power system malfunctions due to expiration of a backup battery, or a detectable defect in a super capacitor. When a malfunction and/or loss of power occurs, the loss of energy sensor 1604c can notify the network management system 1601 by way of the base station 1614.

The noise sensor 1604d can be used to measure noise on the power line 1610 that may adversely affect transmission of electromagnetic waves on the power line 1610. The noise sensor 1604d can sense unexpected electromagnetic interference, noise bursts, or other sources of disturbances that may interrupt reception of modulated electromagnetic waves on a surface of a power line 1610. A noise burst can be caused by, for example, a corona discharge, or other source of noise. The noise sensor 1604d can compare the measured noise to a noise profile obtained by the waveguide system 1602 from an internal database of noise profiles or from a remotely located database that stores noise profiles via pattern recognition, an expert system, curve fitting, matched filtering or other artificial intelligence, classification or comparison technique. From the comparison, the noise sensor 1604d may identify a noise source (e.g., corona discharge or otherwise) based on, for example, the noise profile that provides the closest match to the measured noise. The noise sensor 1604d can also detect how noise affects transmissions by measuring transmission metrics such as bit error rate, packet loss rate, jitter, packet retransmission requests, etc. The noise sensor 1604d can report to the network management system 1601 by way of the base station 1614 the identity of noise sources, their time of occurrence, and transmission metrics, among other things.

The vibration sensor 1604e can include accelerometers and/or gyroscopes to detect 2D or 3D vibrations on the power line 1610. The vibrations can be compared to vibration profiles that can be stored locally in the waveguide system 1602, or obtained by the waveguide system 1602 from a remote database via pattern recognition, an expert system, curve fitting, matched filtering or other artificial intelligence, classification or comparison technique. Vibration profiles can be used, for example, to distinguish fallen trees from wind gusts based on, for example, the vibration profile that provides the closest match to the measured vibrations. The results of this analysis can be reported by the vibration sensor 1604e to the network management system 1601 by way of the base station 1614.

The environmental sensor 1604f can include a barometer for measuring atmospheric pressure, ambient temperature (which can be provided by the temperature sensor 1604a), wind speed, humidity, wind direction, and rainfall, among other things. The environmental sensor 1604f can collect raw information and process this information by comparing it to environmental profiles that can be obtained from a memory of the waveguide system 1602 or a remote database to predict weather conditions before they arise via pattern recognition, an expert system, knowledge-based system or other artificial intelligence, classification or other weather

modeling and prediction technique. The environmental sensor **1604f** can report raw data as well as its analysis to the network management system **1601**.

The image sensor **1604g** can be a digital camera (e.g., a charged coupled device or CCD imager, infrared camera, etc.) for capturing images in a vicinity of the waveguide system **1602**. The image sensor **1604g** can include an electromechanical mechanism to control movement (e.g., actual position or focal points/zooms) of the camera for inspecting the power line **1610** from multiple perspectives (e.g., top surface, bottom surface, left surface, right surface and so on). Alternatively, the image sensor **1604g** can be designed such that no electromechanical mechanism is needed in order to obtain the multiple perspectives. The collection and retrieval of imaging data generated by the image sensor **1604g** can be controlled by the network management system **1601**, or can be autonomously collected and reported by the image sensor **1604g** to the network management system **1601**.

Other sensors that may be suitable for collecting telemetry information associated with the waveguide system **1602** and/or the power lines **1610** for purposes of detecting, predicting and/or mitigating disturbances that can impede the propagation of electromagnetic wave transmissions on power lines **1610** (or any other form of a transmission medium of electromagnetic waves) may be utilized by the waveguide system **1602**.

Referring now to FIG. 16B, block diagram **1650** illustrates an example, non-limiting embodiment of a system for managing a power grid **1653** and a communication system **1655** embedded therein or associated therewith in accordance with various aspects described herein. The communication system **1655** comprises a plurality of waveguide systems **1602** coupled to power lines **1610** of the power grid **1653**. At least a portion of the waveguide systems **1602** used in the communication system **1655** can be in direct communication with a base station **1614** and/or the network management system **1601**. Waveguide systems **1602** not directly connected to a base station **1614** or the network management system **1601** can engage in communication sessions with either a base station **1614** or the network management system **1601** by way of other downstream waveguide systems **1602** connected to a base station **1614** or the network management system **1601**.

The network management system **1601** can be communicatively coupled to equipment of a utility company **1652** and equipment of a communications service provider **1654** for providing each entity, status information associated with the power grid **1653** and the communication system **1655**, respectively. The network management system **1601**, the equipment of the utility company **1652**, and the communications service provider **1654** can access communication devices utilized by utility company personnel **1656** and/or communication devices utilized by communications service provider personnel **1658** for purposes of providing status information and/or for directing such personnel in the management of the power grid **1653** and/or communication system **1655**.

FIG. 17A illustrates a flow diagram of an example, non-limiting embodiment of a method **1700** for detecting and mitigating disturbances occurring in a communication network of the systems of FIGS. 16A & 16B. Method **1700** can begin with step **1702** where a waveguide system **1602** transmits and receives messages embedded in, or forming part of, modulated electromagnetic waves or another type of electromagnetic waves traveling along a surface of a power line **1610**. The messages can be voice messages, streaming

video, and/or other data/information exchanged between communication devices communicatively coupled to the communication system **1655**. At step **1704** the sensors **1604** of the waveguide system **1602** can collect sensing data. In an embodiment, the sensing data can be collected in step **1704** prior to, during, or after the transmission and/or receipt of messages in step **1702**. At step **1706** the waveguide system **1602** (or the sensors **1604** themselves) can determine from the sensing data an actual or predicted occurrence of a disturbance in the communication system **1655** that can affect communications originating from (e.g., transmitted by) or received by the waveguide system **1602**. The waveguide system **1602** (or the sensors **1604**) can process temperature data, signal reflection data, loss of energy data, noise data, vibration data, environmental data, or any combination thereof to make this determination. The waveguide system **1602** (or the sensors **1604**) may also detect, identify, estimate, or predict the source of the disturbance and/or its location in the communication system **1655**. If a disturbance is neither detected/identified nor predicted/estimated at step **1708**, the waveguide system **1602** can proceed to step **1702** where it continues to transmit and receive messages embedded in, or forming part of, modulated electromagnetic waves traveling along a surface of the power line **1610**.

If at step **1708** a disturbance is detected/identified or predicted/estimated to occur, the waveguide system **1602** proceeds to step **1710** to determine if the disturbance adversely affects (or alternatively, is likely to adversely affect) transmission or reception of messages in the communication system **1655**. In one embodiment, a duration threshold and a frequency of occurrence threshold can be used at step **1710** to determine when a disturbance adversely affects communications in the communication system **1655**. For illustration purposes only, assume a duration threshold is set to 500 ms, while a frequency of occurrence threshold is set to 5 disturbances occurring in an observation period of 10 sec. Thus, a disturbance having a duration greater than 500 ms will trigger the duration threshold. Additionally, any disturbance occurring more than 5 times in a 10 sec time interval will trigger the frequency of occurrence threshold.

In one embodiment, a disturbance may be considered to adversely affect signal integrity in the communication systems **1655** when the duration threshold alone is exceeded. In another embodiment, a disturbance may be considered as adversely affecting signal integrity in the communication systems **1655** when both the duration threshold and the frequency of occurrence threshold are exceeded. The latter embodiment is thus more conservative than the former embodiment for classifying disturbances that adversely affect signal integrity in the communication system **1655**. It will be appreciated that many other algorithms and associated parameters and thresholds can be utilized for step **1710** in accordance with example embodiments.

Referring back to method **1700**, if at step **1710** the disturbance detected at step **1708** does not meet the condition for adversely affected communications (e.g., neither exceeds the duration threshold nor the frequency of occurrence threshold), the waveguide system **1602** may proceed to step **1702** and continue processing messages. For instance, if the disturbance detected in step **1708** has a duration of 1 msec with a single occurrence in a 10 sec time period, then neither threshold will be exceeded. Consequently, such a disturbance may be considered as having a nominal effect on signal integrity in the communication system **1655** and thus would not be flagged as a disturbance requiring mitigation. Although not flagged, the occurrence

of the disturbance, its time of occurrence, its frequency of occurrence, spectral data, and/or other useful information, may be reported to the network management system **1601** as telemetry data for monitoring purposes.

Referring back to step **1710**, if on the other hand the disturbance satisfies the condition for adversely affected communications (e.g., exceeds either or both thresholds), the waveguide system **1602** can proceed to step **1712** and report the incident to the network management system **1601**. The report can include raw sensing data collected by the sensors **1604**, a description of the disturbance if known by the waveguide system **1602**, a time of occurrence of the disturbance, a frequency of occurrence of the disturbance, a location associated with the disturbance, parameters readings such as bit error rate, packet loss rate, retransmission requests, jitter, latency and so on. If the disturbance is based on a prediction by one or more sensors of the waveguide system **1602**, the report can include a type of disturbance expected, and if predictable, an expected time occurrence of the disturbance, and an expected frequency of occurrence of the predicted disturbance when the prediction is based on historical sensing data collected by the sensors **1604** of the waveguide system **1602**.

At step **1714**, the network management system **1601** can determine a mitigation, circumvention, or correction technique, which may include directing the waveguide system **1602** to reroute traffic to circumvent the disturbance if the location of the disturbance can be determined. In one embodiment, the waveguide coupling device **1402** detecting the disturbance may direct a repeater such as the one shown in FIGS. **13-14** to connect the waveguide system **1602** from a primary power line affected by the disturbance to a secondary power line to enable the waveguide system **1602** to reroute traffic to a different transmission medium and avoid the disturbance. In an embodiment where the waveguide system **1602** is configured as a repeater the waveguide system **1602** can itself perform the rerouting of traffic from the primary power line to the secondary power line. It is further noted that for bidirectional communications (e.g., full or half-duplex communications), the repeater can be configured to reroute traffic from the secondary power line back to the primary power line for processing by the waveguide system **1602**.

In another embodiment, the waveguide system **1602** can redirect traffic by instructing a first repeater situated upstream of the disturbance and a second repeater situated downstream of the disturbance to redirect traffic from a primary power line temporarily to a secondary power line and back to the primary power line in a manner that avoids the disturbance. It is further noted that for bidirectional communications (e.g., full or half-duplex communications), repeaters can be configured to reroute traffic from the secondary power line back to the primary power line.

To avoid interrupting existing communication sessions occurring on a secondary power line, the network management system **1601** may direct the waveguide system **1602** to instruct repeater(s) to utilize unused time slot(s) and/or frequency band(s) of the secondary power line for redirecting data and/or voice traffic away from the primary power line to circumvent the disturbance.

At step **1716**, while traffic is being rerouted to avoid the disturbance, the network management system **1601** can notify equipment of the utility company **1652** and/or equipment of the communications service provider **1654**, which in turn may notify personnel of the utility company **1656** and/or personnel of the communications service provider **1658** of the detected disturbance and its location if known.

Field personnel from either party can attend to resolving the disturbance at a determined location of the disturbance. Once the disturbance is removed or otherwise mitigated by personnel of the utility company and/or personnel of the communications service provider, such personnel can notify their respective companies and/or the network management system **1601** utilizing field equipment (e.g., a laptop computer, smartphone, etc.) communicatively coupled to network management system **1601**, and/or equipment of the utility company and/or the communications service provider. The notification can include a description of how the disturbance was mitigated and any changes to the power lines **1610** that may change a topology of the communication system **1655**.

Once the disturbance has been resolved (as determined in decision **1718**), the network management system **1601** can direct the waveguide system **1602** at step **1720** to restore the previous routing configuration used by the waveguide system **1602** or route traffic according to a new routing configuration if the restoration strategy used to mitigate the disturbance resulted in a new network topology of the communication system **1655**. In another embodiment, the waveguide system **1602** can be configured to monitor mitigation of the disturbance by transmitting test signals on the power line **1610** to determine when the disturbance has been removed. Once the waveguide system **1602** detects an absence of the disturbance it can autonomously restore its routing configuration without assistance by the network management system **1601** if it determines the network topology of the communication system **1655** has not changed, or it can utilize a new routing configuration that adapts to a detected new network topology.

FIG. **17B** illustrates a flow diagram of an example, non-limiting embodiment of a method **1750** for detecting and mitigating disturbances occurring in a communication network of the system of FIGS. **16A** and **16B**. In one embodiment, method **1750** can begin with step **1752** where a network management system **1601** receives from equipment of the utility company **1652** or equipment of the communications service provider **1654** maintenance information associated with a maintenance schedule. The network management system **1601** can at step **1754** identify from the maintenance information, maintenance activities to be performed during the maintenance schedule. From these activities, the network management system **1601** can detect a disturbance resulting from the maintenance (e.g., scheduled replacement of a power line **1610**, scheduled replacement of a waveguide system **1602** on the power line **1610**, scheduled reconfiguration of power lines **1610** in the power grid **1653**, etc.).

In another embodiment, the network management system **1601** can receive at step **1755** telemetry information from one or more waveguide systems **1602**. The telemetry information can include among other things an identity of each waveguide system **1602** submitting the telemetry information, measurements taken by sensors **1604** of each waveguide system **1602**, information relating to predicted, estimated, or actual disturbances detected by the sensors **1604** of each waveguide system **1602**, location information associated with each waveguide system **1602**, an estimated location of a detected disturbance, an identification of the disturbance, and so on. The network management system **1601** can determine from the telemetry information a type of disturbance that may be adverse to operations of the waveguide, transmission of the electromagnetic waves along the wire surface, or both. The network management system **1601** can also use telemetry information from multiple

41

waveguide systems **1602** to isolate and identify the disturbance. Additionally, the network management system **1601** can request telemetry information from waveguide systems **1602** in a vicinity of an affected waveguide system **1602** to triangulate a location of the disturbance and/or validate an identification of the disturbance by receiving similar telemetry information from other waveguide systems **1602**.

In yet another embodiment, the network management system **1601** can receive at step **1756** an unscheduled activity report from maintenance field personnel. Unscheduled maintenance may occur as result of field calls that are unplanned or as a result of unexpected field issues discovered during field calls or scheduled maintenance activities. The activity report can identify changes to a topology configuration of the power grid **1653** resulting from field personnel addressing discovered issues in the communication system **1655** and/or power grid **1653**, changes to one or more waveguide systems **1602** (such as replacement or repair thereof), mitigation of disturbances performed if any, and so on.

At step **1758**, the network management system **1601** can determine from reports received according to steps **1752** through **1756** if a disturbance will occur based on a maintenance schedule, or if a disturbance has occurred or is predicted to occur based on telemetry data, or if a disturbance has occurred due to an unplanned maintenance identified in a field activity report. From any of these reports, the network management system **1601** can determine whether a detected or predicted disturbance requires rerouting of traffic by the affected waveguide systems **1602** or other waveguide systems **1602** of the communication system **1655**.

When a disturbance is detected or predicted at step **1758**, the network management system **1601** can proceed to step **1760** where it can direct one or more waveguide systems **1602** to reroute traffic to circumvent the disturbance. When the disturbance is permanent due to a permanent topology change of the power grid **1653**, the network management system **1601** can proceed to step **1770** and skip steps **1762**, **1764**, **1766**, and **1772**. At step **1770**, the network management system **1601** can direct one or more waveguide systems **1602** to use a new routing configuration that adapts to the new topology. However, when the disturbance has been detected from telemetry information supplied by one or more waveguide systems **1602**, the network management system **1601** can notify maintenance personnel of the utility company **1656** or the communications service provider **1658** of a location of the disturbance, a type of disturbance if known, and related information that may be helpful to such personnel to mitigate the disturbance. When a disturbance is expected due to maintenance activities, the network management system **1601** can direct one or more waveguide systems **1602** to reconfigure traffic routes at a given schedule (consistent with the maintenance schedule) to avoid disturbances caused by the maintenance activities during the maintenance schedule.

Returning back to step **1760** and upon its completion, the process can continue with step **1762**. At step **1762**, the network management system **1601** can monitor when the disturbance(s) have been mitigated by field personnel. Mitigation of a disturbance can be detected at step **1762** by analyzing field reports submitted to the network management system **1601** by field personnel over a communications network (e.g., cellular communication system) utilizing field equipment (e.g., a laptop computer or handheld computer/device). If field personnel have reported that a disturbance has been mitigated, the network management system **1601** can proceed to step **1764** to determine from the field report

42

whether a topology change was required to mitigate the disturbance. A topology change can include rerouting a power line **1610**, reconfiguring a waveguide system **1602** to utilize a different power line **1610**, otherwise utilizing an alternative link to bypass the disturbance and so on. If a topology change has taken place, the network management system **1601** can direct at step **1770** one or more waveguide systems **1602** to use a new routing configuration that adapts to the new topology.

If, however, a topology change has not been reported by field personnel, the network management system **1601** can proceed to step **1766** where it can direct one or more waveguide systems **1602** to send test signals to test a routing configuration that had been used prior to the detected disturbance(s). Test signals can be sent to affected waveguide systems **1602** in a vicinity of the disturbance. The test signals can be used to determine if signal disturbances (e.g., electromagnetic wave reflections) are detected by any of the waveguide systems **1602**. If the test signals confirm that a prior routing configuration is no longer subject to previously detected disturbance(s), then the network management system **1601** can at step **1772** direct the affected waveguide systems **1602** to restore a previous routing configuration. If, however, test signals analyzed by one or more waveguide coupling device **1402** and reported to the network management system **1601** indicate that the disturbance(s) or new disturbance(s) are present, then the network management system **1601** will proceed to step **1768** and report this information to field personnel to further address field issues. The network management system **1601** can in this situation continue to monitor mitigation of the disturbance(s) at step **1762**.

In the aforementioned embodiments, the waveguide systems **1602** can be configured to be self-adapting to changes in the power grid **1653** and/or to mitigation of disturbances. That is, one or more affected waveguide systems **1602** can be configured to self-monitor mitigation of disturbances and reconfigure traffic routes without requiring instructions to be sent to them by the network management system **1601**. In this embodiment, the one or more waveguide systems **1602** that are self-configurable can inform the network management system **1601** of its routing choices so that the network management system **1601** can maintain a macro-level view of the communication topology of the communication system **1655**.

While for purposes of simplicity of explanation, the respective processes are shown and described as a series of blocks in FIGS. **17A** and **17B**, respectively, it is to be understood and appreciated that the claimed subject matter is not limited by the order of the blocks, as some blocks may occur in different orders and/or concurrently with other blocks from what is depicted and described herein. Moreover, not all illustrated blocks may be required to implement the methods described herein.

Turning now to FIG. **18A**, a block diagram illustrating an example, non-limiting embodiment of a transmission medium **1800** for propagating guided electromagnetic waves is shown. In particular, a further example of transmission medium **125** presented in conjunction with FIG. **1** is presented. In an embodiment, the transmission medium **1800** can comprise a first dielectric material **1802** and a second dielectric material **1804** disposed thereon. In an embodiment, the first dielectric material **1802** can comprise a dielectric core (referred to herein as dielectric core **1802**) and the second dielectric material **1804** can comprise a cladding or shell such as a dielectric foam that surrounds in whole or in part the dielectric core (referred to herein as

dielectric foam **1804**). In an embodiment, the dielectric core **1802** and dielectric foam **1804** can be coaxially aligned to each other (although not necessary). In an embodiment, the combination of the dielectric core **1802** and the dielectric foam **1804** can be flexed or bent at least by 45 degrees without damaging the materials of the dielectric core **1802** and the dielectric foam **1804**. In an embodiment, an outer surface of the dielectric foam **1804** can be further surrounded in whole or in part by a third dielectric material **1806**, which can serve as an outer jacket (referred to herein as jacket **1806**). The jacket **1806** can prevent exposure of the dielectric core **1802** and the dielectric foam **1804** to an environment that can adversely affect the propagation of electromagnetic waves (e.g., water, soil, etc.).

The dielectric core **1802** can comprise, for example, a high density polyethylene material, a high density polyurethane material, or other suitable dielectric material(s). The dielectric foam **1804** can comprise, for example, a cellular plastic material such as an expanded polyethylene material, or other suitable dielectric material(s). The jacket **1806** can comprise, for example, a polyethylene material or equivalent. In an embodiment, the dielectric constant of the dielectric foam **1804** can be (or substantially) lower than the dielectric constant of the dielectric core **1802**. For example, the dielectric constant of the dielectric core **1802** can be approximately 2.3 while the dielectric constant of the dielectric foam **1804** can be approximately 1.15 (slightly higher than the dielectric constant of air).

The dielectric core **1802** can be used for receiving signals in the form of electromagnetic waves from a launcher or other coupling device described herein which can be configured to launch guided electromagnetic waves on the transmission medium **1800**. In one embodiment, the transmission **1800** can be coupled to a hollow waveguide **1808** structured as, for example, a circular waveguide **1809**, which can receive electromagnetic waves from a radiating device such as a stub antenna (not shown). The hollow waveguide **1808** can in turn induce guided electromagnetic waves in the dielectric core **1802**. In this configuration, the guided electromagnetic waves are guided by or bound to the dielectric core **1802** and propagate longitudinally along the dielectric core **1802**. By adjusting electronics of the launcher, an operating frequency of the electromagnetic waves can be chosen such that a field intensity profile **1810** of the guided electromagnetic waves extends nominally (or not at all) outside of the jacket **1806**.

By maintaining most (if not all) of the field strength of the guided electromagnetic waves within portions of the dielectric core **1802**, the dielectric foam **1804** and/or the jacket **1806**, the transmission medium **1800** can be used in hostile environments without adversely affecting the propagation of the electromagnetic waves propagating therein. For example, the transmission medium **1800** can be buried in soil with no (or nearly no) adverse effect to the guided electromagnetic waves propagating in the transmission medium **1800**. Similarly, the transmission medium **1800** can be exposed to water (e.g., rain or placed underwater) with no (or nearly no) adverse effect to the guided electromagnetic waves propagating in the transmission medium **1800**. In an embodiment, the propagation loss of guided electromagnetic waves in the foregoing embodiments can be 1 to 2 dB per meter or better at an operating frequency of 60 GHz. Depending on the operating frequency of the guided electromagnetic waves and/or the materials used for the transmission medium **1800** other propagation losses may be possible. Additionally, depending on the materials used to construct the transmission medium **1800**, the transmission

medium **1800** can in some embodiments be flexed laterally with no (or nearly no) adverse effect to the guided electromagnetic waves propagating through the dielectric core **1802** and the dielectric foam **1804**.

FIG. **18B** depicts a transmission medium **1820** that differs from the transmission medium **1800** of FIG. **18A**, yet provides a further example of the transmission medium **125** presented in conjunction with FIG. **1**. The transmission medium **1820** shows similar reference numerals for similar elements of the transmission medium **1800** of FIG. **18A**. In contrast to the transmission medium **1800**, the transmission medium **1820** comprises a conductive core **1822** having an insulation layer **1823** surrounding the conductive core **1822** in whole or in part. The combination of the insulation layer **1823** and the conductive core **1822** will be referred to herein as an insulated conductor **1825**. In the illustration of FIG. **18B**, the insulation layer **1823** is covered in whole or in part by a dielectric foam **1804** and jacket **1806**, which can be constructed from the materials previously described. In an embodiment, the insulation layer **1823** can comprise a dielectric material, such as polyethylene, having a higher dielectric constant than the dielectric foam **1804** (e.g., 2.3 and 1.15, respectively). In an embodiment, the components of the transmission medium **1820** can be coaxially aligned (although not necessary). In an embodiment, a hollow waveguide **1808** having metal plates **1809**, which can be separated from the insulation layer **1823** (although not necessary) can be used to launch guided electromagnetic waves that substantially propagate on an outer surface of the insulation layer **1823**, however other coupling devices as described herein can likewise be employed. In an embodiment, the guided electromagnetic waves can be sufficiently guided by or bound by the insulation layer **1823** to guide the electromagnetic waves longitudinally along the insulation layer **1823**. By adjusting operational parameters of the launcher, an operating frequency of the guided electromagnetic waves launched by the hollow waveguide **1808** can generate an electric field intensity profile **1824** that results in the guided electromagnetic waves being substantially confined within the dielectric foam **1804** thereby preventing the guided electromagnetic waves from being exposed to an environment (e.g., water, soil, etc.) that adversely affects propagation of the guided electromagnetic waves via the transmission medium **1820**.

FIG. **18C** depicts a transmission medium **1830** that differs from the transmission mediums **1800** and **1820** of FIGS. **18A** and **18B**, yet provides a further example of the transmission medium **125** presented in conjunction with FIG. **1**. The transmission medium **1830** shows similar reference numerals for similar elements of the transmission mediums **1800** and **1820** of FIGS. **18A** and **18B**, respectively. In contrast to the transmission mediums **1800** and **1820**, the transmission medium **1830** comprises a bare (or uninsulated) conductor **1832** surrounded in whole or in part by the dielectric foam **1804** and the jacket **1806**, which can be constructed from the materials previously described. In an embodiment, the components of the transmission medium **1830** can be coaxially aligned (although not necessary). In an embodiment, a hollow waveguide **1808** having metal plates **1809** coupled to the bare conductor **1832** can be used to launch guided electromagnetic waves that substantially propagate on an outer surface of the bare conductor **1832**, however other coupling devices described herein can likewise be employed. In an embodiment, the guided electromagnetic waves can be sufficiently guided by or bound by the bare conductor **1832** to guide the guided electromagnetic waves longitudinally along the bare conductor **1832**. By

adjusting operational parameters of the launcher, an operating frequency of the guided electromagnetic waves launched by the hollow waveguide **1808** can generate an electric field intensity profile **1834** that results in the guided electromagnetic waves being substantially confined within the dielectric foam **1804** thereby preventing the guided electromagnetic waves from being exposed to an environment (e.g., water, soil, etc.) that adversely affects propagation of the electromagnetic waves via the transmission medium **1830**.

It should be noted that the hollow launcher **1808** used with the transmission mediums **1800**, **1820** and **1830** of FIGS. **18A**, **18B** and **18C**, respectively, can be replaced with other launchers or coupling devices. Additionally, the propagation mode(s) of the electromagnetic waves for any of the foregoing embodiments can be fundamental mode(s), a non-fundamental (or asymmetric) mode(s), or combinations thereof.

FIG. **18D** is a block diagram illustrating an example, non-limiting embodiment of bundled transmission media **1836** in accordance with various aspects described herein. The bundled transmission media **1836** can comprise a plurality of cables **1838** held in place by a flexible sleeve **1839**. The plurality of cables **1838** can comprise multiple instances of cable **1800** of FIG. **18A**, multiple instances of cable **1820** of FIG. **18B**, multiple instances of cable **1830** of FIG. **18C**, or any combinations thereof. The sleeve **1839** can comprise a dielectric material that prevents soil, water or other external materials from making contact with the plurality of cables **1838**. In an embodiment, a plurality of launchers, each utilizing a transceiver similar to the one depicted in FIG. **10A** or other coupling devices described herein, can be adapted to selectively induce a guided electromagnetic wave in each cable, each guided electromagnetic wave conveys different data (e.g., voice, video, messaging, content, etc.). In an embodiment, by adjusting operational parameters of each launcher or other coupling device, the electric field intensity profile of each guided electromagnetic wave can be fully or substantially confined within layers of a corresponding cable **1838** to reduce cross-talk between cables **1838**.

In situations where the electric field intensity profile of each guided electromagnetic wave is not fully or substantially confined within a corresponding cable **1838**, cross-talk of electromagnetic signals can occur between cables **1838** as illustrated by signal plots associated with two cables depicted in FIG. **18E**. The plots in FIG. **18E** show that when a guided electromagnetic wave is induced on a first cable, the emitted electric and magnetic fields of the first cable can induce signals on the second cable, which results in cross-talk. Several mitigation options can be used to reduce cross-talk between the cables **1838** of FIG. **18D**. In an embodiment, an absorption material **1840** that can absorb electromagnetic fields, such as carbon, can be applied to the cables **1838** as shown in FIG. **18F** to polarize each guided electromagnetic wave at various polarization states to reduce cross-talk between cables **1838**. In another embodiment (not shown), carbon beads can be added to gaps between the cables **1838** to reduce cross-talk.

In yet another embodiment (not shown), a diameter of cable **1838** can be configured differently to vary a speed of propagation of guided electromagnetic waves between the cables **1838** in order to reduce cross-talk between cables **1838**. In an embodiment (not shown), a shape of each cable **1838** can be made asymmetric (e.g., elliptical) to direct the guided electromagnetic fields of each cable **1838** away from each other to reduce cross-talk. In an embodiment (not shown), a filler material such as dielectric foam can be added between cables **1838** to sufficiently separate the cables **1838**

to reduce cross-talk therebetween. In an embodiment (not shown), longitudinal carbon strips or swirls can be applied to on an outer surface of the jacket **1806** of each cable **1838** to reduce radiation of guided electromagnetic waves outside of the jacket **1806** and thereby reduce cross-talk between cables **1838**. In yet another embodiment, each launcher can be configured to launch a guided electromagnetic wave having a different frequency, modulation, wave propagation mode, such as an orthogonal frequency, modulation or mode, to reduce cross-talk between the cables **1838**.

In yet another embodiment (not shown), pairs of cables **1838** can be twisted in a helix to reduce cross-talk between the pairs and other cables **1838** in a vicinity of the pairs. In some embodiments, certain cables **1838** can be twisted while other cables **1838** are not twisted to reduce cross-talk between the cables **1838**. Additionally, each twisted pair cable **1838** can have different pitches (i.e., different twist rates, such as twists per meter) to further reduce cross-talk between the pairs and other cables **1838** in a vicinity of the pairs. In another embodiment (not shown), launchers or other coupling devices can be configured to induce guided electromagnetic waves in the cables **1838** having electromagnetic fields that extend beyond the jacket **1806** into gaps between the cables to reduce cross-talk between the cables **1838**. It is submitted that any one of the foregoing embodiments for mitigating cross-talk between cables **1838** can be combined to further reduce cross-talk therebetween.

FIGS. **18G** and **18H** are block diagrams illustrating example, non-limiting embodiments of a transmission medium with an inner waveguide in accordance with various aspects described herein. In an embodiment, a transmission medium **1841** can comprise a core **1842**. In one embodiment, the core **1842** can be a dielectric core **1842** (e.g., polyethylene). In another embodiment, the core **1842** can be an insulated or uninsulated conductor. The core **1842** can be surrounded by a shell **1844** comprising a dielectric foam (e.g., expanded polyethylene material) having a lower dielectric constant than the dielectric constant of a dielectric core, or insulation layer of a conductive core. The difference in dielectric constants enables electromagnetic waves to be bound and guided by the core **1842**. The shell **1844** can be covered by a shell jacket **1845**. The shell jacket **1845** can be made of rigid material (e.g., high density plastic) or a high tensile strength material (e.g., synthetic fiber). In an embodiment, the shell jacket **1845** can be used to prevent exposure of the shell **1844** and core **1842** from an adverse environment (e.g., water, moisture, soil, etc.). In an embodiment, the shell jacket **1845** can be sufficiently rigid to separate an outer surface of the core **1842** from an inner surface of the shell jacket **1845** thereby resulting in a longitudinal gap between the shell jacket **1845** and the core **1842**. The longitudinal gap can be filled with the dielectric foam of the shell **1844**.

The transmission medium **1841** can further include a plurality of outer ring conductors **1846**. The outer ring conductors **1846** can be strands of conductive material that are woven around the shell jacket **1845**, thereby covering the shell jacket **1845** in whole or in part. The outer ring conductors **1846** can serve the function of a power line having a return electrical path similar to the embodiments described in the subject disclosure for receiving power signals from a source (e.g., a transformer, a power generator, etc.). In one embodiment, the outer ring conductors **1846** can be covered by a cable jacket **1847** to prevent exposure of the outer ring conductors **1846** to water, soil, or other environmental factors. The cable jacket **1847** can be made of an insulating material such as polyethylene. The core **1842** can be used as a center waveguide for the propagation of

electromagnetic waves. A hollow waveguide launcher **1808**, such as the circular waveguide previously described, can be used to launch signals that induce electromagnetic waves guided by the core **1842** in ways similar to those described for the embodiments of FIGS. **18A**, **18B**, and **18C**. The electromagnetic waves can be guided by the core **1842** without utilizing the electrical return path of the outer ring conductors **1846** or any other electrical return path. By adjusting electronics of the launcher **1808**, an operating frequency of the electromagnetic waves can be chosen such that a field intensity profile of the guided electromagnetic waves extends nominally (or not at all) outside of the shell jacket **1845**.

In another embodiment, a transmission medium **1843** can comprise a hollow core **1842'** surrounded by a shell jacket **1845'**. The shell jacket **1845'** can have an inner conductive surface or other surface materials that enable the hollow core **1842'** to be used as a conduit for electromagnetic waves. The shell jacket **1845'** can be covered at least in part with the outer ring conductors **1846** described earlier for conducting a power signal. In an embodiment, a cable jacket **1847** can be disposed on an outer surface of the outer ring conductors **1846** to prevent exposure of the outer ring conductors **1846** to water, soil or other environmental factors. A waveguide launcher **1808** can be used to launch electromagnetic waves guided by the hollow core **1842'** and the conductive inner surface of the shell jacket **1845'**. In an embodiment (not shown) the hollow core **1842'** can further include a dielectric foam such as described earlier.

Transmission medium **1841** can represent a multi-purpose cable that conducts power on the outer ring conductors **1846** utilizing an electrical return path and that provides communication services by way of an inner waveguide comprising a combination of the core **1842**, the shell **1844** and the shell jacket **1845**. The inner waveguide can be used for transmitting or receiving electromagnetic waves (without utilizing an electrical return path) guided by the core **1842**. Similarly, transmission medium **1843** can represent a multi-purpose cable that conducts power on the outer ring conductors **1846** utilizing an electrical return path and that provides communication services by way of an inner waveguide comprising a combination of the hollow core **1842'** and the shell jacket **1845'**. The inner waveguide can be used for transmitting or receiving electromagnetic waves (without utilizing an electrical return path) guided the hollow core **1842'** and the shell jacket **1845'**.

It is submitted that embodiments of FIGS. **18G-18H** can be adapted to use multiple inner waveguides surrounded by outer ring conductors **1846**. The inner waveguides can be adapted to use to cross-talk mitigation techniques described above (e.g., twisted pairs of waveguides, waveguides of different structural dimensions, use of polarizers within the shell, use of different wave modes, etc.).

For illustration purposes only, the transmission mediums **1800**, **1820**, **1830**, **1836**, **1841** and **1843** will be referred to herein as a cable **1850** with an understanding that cable **1850** can represent any one of the transmission mediums described in the subject disclosure, or a bundling of multiple instances thereof. For illustration purposes only, the dielectric core **1802**, insulated conductor **1825**, bare conductor **1832**, core **1842**, or hollow core **1842'** of the transmission mediums **1800**, **1820**, **1830**, **1836**, **1841** and **1843**, respectively, will be referred to herein as transmission core **1852** with an understanding that cable **1850** can utilize the dielectric core **1802**, insulated conductor **1825**, bare conductor

1832, core **1842**, or hollow core **1842'** of transmission mediums **1800**, **1820**, **1830**, **1836**, **1841** and/or **1843**, respectively.

Turning now to FIGS. **18I** and **18J**, block diagrams illustrating example, non-limiting embodiments of connector configurations that can be used by cable **1850** are shown. In one embodiment, cable **1850** can be configured with a female connection arrangement or a male connection arrangement as depicted in FIG. **18I**. The male configuration on the right of FIG. **18I** can be accomplished by stripping the dielectric foam **1804** (and jacket **1806** if there is one) to expose a portion of the transmission core **1852**. The female configuration on the left of FIG. **18I** can be accomplished by removing a portion of the transmission core **1852**, while maintaining the dielectric foam **1804** (and jacket **1806** if there is one). In an embodiment in which the transmission core **1852** is hollow as described in relation to FIG. **18H**, the male portion of the transmission core **1852** can represent a hollow core with a rigid outer surface that can slide into the female arrangement on the left side of FIG. **18I** to align the hollow cores together. It is further noted that in the embodiments of FIGS. **18G-18H**, the outer ring of conductors **1846** can be modified to connect male and female portions of cable **1850**.

Based on the aforementioned embodiments, the two cables **1850** having male and female connector arrangements can be mated together. A sleeve with an adhesive inner lining or a shrink wrap material (not shown) can be applied to an area of a joint between cables **1850** to maintain the joint in a fixed position and prevent exposure (e.g., to water, soil, etc.). When the cables **1850** are mated, the transmission core **1852** of one cable will be in close proximity to the transmission core **1852** of the other cable. Guided electromagnetic waves propagating by way of either the transmission core **1852** of cables **1850** traveling from either direction can cross over between the disjoint the transmission cores **1852** whether or not the transmission cores **1852** touch, whether or not the transmission cores **1852** are coaxially aligned, and/or whether or not there is a gap between the transmission cores **1852**.

In another embodiment, a splicing device **1860** having female connector arrangements at both ends can be used to mate cables **1850** having male connector arrangements as shown in FIG. **18J**. In an alternative embodiment not shown in FIG. **18J**, the splicing device **1860** can be adapted to have male connector arrangements at both ends which can be mated to cables **1850** having female connector arrangements. In another embodiment not shown in FIG. **18J**, the splicing device **1860** can be adapted to have a male connector arrangement and a female connector arrangement at opposite ends which can be mated to cables **1850** having female and male connector arrangements, respectively. It is further noted that for a transmission core **1852** having a hollow core, the male and female arrangements described in FIG. **18I** can be applied to the splicing device **1860** whether the ends of the splicing device **1860** are both male, both female, or a combination thereof.

The foregoing embodiments for connecting cables illustrated in FIGS. **18I-18J** can be applied to each single instance of cable **1838** of bundled transmission media **1836**. Similarly, the foregoing embodiments illustrated in FIGS. **18I-18J** can be applied to each single instance of an inner waveguide for a cable **1841** or **1843** having multiple inner waveguides.

Turning now to FIG. **18K**, a block diagram illustrating example, non-limiting embodiments of transmission mediums **1800'**, **1800''**, **1800'''** and **1800''''** for propagating guided

electromagnetic waves is shown. In an embodiment, a transmission medium **1800'** can include a core **1801**, and a dielectric foam **1804'** divided into sections and covered by a jacket **1806** as shown in FIG. **18K**. The core **1801** can be represented by the dielectric core **1802** of FIG. **18A**, the insulated conductor **1825** of FIG. **18B**, or the bare conductor **1832** of FIG. **18C**. Each section of dielectric foam **1804'** can be separated by a gap (e.g., air, gas, vacuum, or a substance with a low dielectric constant). In an embodiment, the gap separations between the sections of dielectric foam **1804'** can be quasi-random as shown in FIG. **18K**, which can be helpful in reducing reflections of electromagnetic waves occurring at each section of dielectric foam **1804'** as they propagate longitudinally along the core **1801**. The sections of the dielectric foam **1804'** can be constructed, for example, as washers made of a dielectric foam having an inner opening for supporting the core **1801** in a fixed position. For illustration purposes only, the washers will be referred to herein as washers **1804'**. In an embodiment, the inner opening of each washer **1804'** can be coaxially aligned with an axis of the core **1801**. In another embodiment, the inner opening of each washer **1804'** can be offset from the axis of the core **1801**. In another embodiment (not shown), each washer **1804'** can have a variable longitudinal thickness as shown by differences in thickness of the washers **1804'**.

In an alternative embodiment, a transmission medium **1800"** can include a core **1801**, and a strip of dielectric foam **1804"** wrapped around the core in a helix covered by a jacket **1806** as shown in FIG. **18K**. Although it may not be apparent from the drawing shown in FIG. **18K**, in an embodiment the strip of dielectric foam **1804"** can be twisted around the core **1801** with variable pitches (i.e., different twist rates) for different sections of the strip of dielectric foam **1804"**. Utilizing variable pitches can help reduce reflections or other disturbances of the electromagnetic waves occurring between areas of the core **1801** not covered by the strip of dielectric foam **1804"**. It is further noted that the thickness (diameter) of the strip of dielectric foam **1804"** can be substantially larger (e.g., 2 or more times larger) than diameter of the core **1801** shown in FIG. **18K**.

In an alternative embodiment, a transmission medium **1800'''** (shown in a cross-sectional view) can include a non-circular core **1801'** covered by a dielectric foam **1804** and jacket **1806**. In an embodiment, the non-circular core **1801'** can have an elliptical structure as shown in FIG. **18K**, or other suitable non-circular structure. In another embodiment, the non-circular core **1801'** can have an asymmetric structure. A non-circular core **1801'** can be used to polarize the fields of electromagnetic waves induced on the non-circular core **1801'**. The structure of the non-circular core **1801'** can help preserve the polarization of the electromagnetic waves as they propagate along the non-circular core **1801'**.

In an alternative embodiment, a transmission medium **1800''''** (shown in a cross-sectional view) can include multiple cores **1801"** (only two cores are shown but more are possible). The multiple cores **1801"** can be covered by a dielectric foam **1804** and jacket **1806**. The multiple cores **1801"** can be used to polarize the fields of electromagnetic waves induced on the multiple cores **1801"**. The structure of the multiple cores **1801'** can preserve the polarization of the guided electromagnetic waves as they propagate along the multiple cores **1801"**.

It will be appreciated that the embodiments of FIG. **18K** can be used to modify the embodiments of FIGS. **18G-18H**. For example, core **1842** or core **1842'** can be adapted to utilized sectionalized shells **1804'** with gaps therebetween,

or one or more strips of dielectric foam **1804"**. Similarly, core **1842** or core **1842'** can be adapted to have a non-circular core **1801'** that may have symmetric or asymmetric cross-sectional structure. Additionally, core **1842** or core **1842'** can be adapted to use multiple cores **1801"** in a single inner waveguide, or different numbers of cores when multiple inner waveguides are used. Accordingly, any of the embodiments shown in FIG. **18K** can be applied singly or in combination to the embodiments of **18G-18H**.

Turning now to FIG. **18L** is a block diagram illustrating example, non-limiting embodiments of bundled transmission media to mitigate cross-talk in accordance with various aspects described herein. In an embodiment, a bundled transmission medium **1836'** can include variable core structures **1803**. By varying the structures of cores **1803**, fields of guided electromagnetic waves induced in each of the cores of transmission medium **1836'** may differ sufficiently to reduce cross-talk between cables **1838**. In another embodiment, a bundled transmission media **1836"** can include a variable number of cores **1803'** per cable **1838**. By varying the number of cores **1803'** per cable **1838**, fields of guided electromagnetic waves induced in the one or more cores of transmission medium **1836"** may differ sufficiently to reduce cross-talk between cables **1838**. In another embodiment, the cores **1803** or **1803'** can be of different materials. For example, the cores **1803** or **1803'** can be a dielectric core **1802**, an insulated conductor core **1825**, a bare conductor core **1832**, or any combinations thereof.

It is noted that the embodiments illustrated in FIGS. **18A-18D** and **18F-18H** can be modified by and/or combined with some of the embodiments of FIGS. **18K-18L**. It is further noted that one or more of the embodiments illustrated in FIGS. **18K-18L** can be combined (e.g., using sectionalized dielectric foam **1804'** or a helix strip of dielectric foam **1804"** with cores **1801'**, **1801"**, **1803** or **1803'**). In some embodiments guided electromagnetic waves propagating in the transmission mediums **1800'**, **1800"**, **1800'''**, and/or **1800''''** of FIG. **18K** may experience less propagation losses than guided electromagnetic waves propagating in the transmission mediums **1800**, **1820** and **1830** of FIGS. **18A-18C**. Additionally, the embodiments illustrated in FIGS. **18K-18L** can be adapted to use the connectivity embodiments illustrated in FIGS. **18I-18J**.

Turning now to FIG. **18M**, a block diagram illustrating an example, non-limiting embodiment of exposed tapered stubs from the bundled transmission media **1836** for use as antennas **1855** is shown. Each antenna **1855** can serve as a directional antenna for radiating wireless signals directed to wireless communication devices or for inducing electromagnetic wave propagation on a surface of a transmission medium (e.g., a power line). In an embodiment, the wireless signals radiated by the antennas **1855** can be beam steered by adapting the phase and/or other characteristics of the wireless signals generated by each antenna **1855**. In an embodiment, the antennas **1855** can individually be placed in a pie-pan antenna assembly for directing wireless signals in various directions.

It is further noted that the terms "core", "cladding", "shell", and "foam" as utilized in the subject disclosure can comprise any types of materials (or combinations of materials) that enable electromagnetic waves to remain bound to the core while propagating longitudinally along the core. For example, a strip of dielectric foam **1804"** described earlier can be replaced with a strip of an ordinary dielectric material (e.g., polyethylene) for wrapping around the dielectric core **1802** (referred to herein for illustration purposes only as a "wrap"). In this configuration an average density of the wrap

can be small as a result of air space between sections of the wrap. Consequently, an effective dielectric constant of the wrap can be less than the dielectric constant of the dielectric core **1802**, thereby enabling guided electromagnetic waves to remain bound to the core. Accordingly, any of the embodiments of the subject disclosure relating to materials used for core(s) and wrappings about the core(s) can be structurally adapted and/or modified with other dielectric materials that achieve the result of maintaining electromagnetic waves bound to the core(s) while they propagate along the core(s). Additionally, a core in whole or in part as described in any of the embodiments of the subject disclosure can comprise an opaque material (e.g., polyethylene) that is resistant to propagation of electromagnetic waves having an optical operating frequency. Accordingly, electromagnetic waves guided and bound to the core will have a non-optical frequency range (e.g., less than the lowest frequency of visible light).

FIGS. **18N**, **18O**, **18P**, **18Q**, **18R**, **18S** and **18T** are block diagrams illustrating example, non-limiting embodiments of a waveguide device for transmitting or receiving electromagnetic waves in accordance with various aspects described herein. In an embodiment, FIG. **18N** illustrates a front view of a waveguide device **1865** having a plurality of slots **1863** (e.g., openings or apertures) for emitting electromagnetic waves having radiated electric fields (e-fields) **1861**. In an embodiment, the radiated e-fields **1861** of pairs of symmetrically positioned slots **1863** (e.g., north and south slots of the waveguide **1865**) can be directed away from each other (i.e., polar opposite radial orientations about the cable **1862**). While the slots **1863** are shown as having a rectangular shape, other shapes such as other polygons, sector and arc shapes, ellipsoid shapes and other shapes are likewise possible. For illustration purposes only, the term north will refer to a relative direction as shown in the figures. All references in the subject disclosure to other directions (e.g., south, east, west, northwest, and so forth) will be relative to northern illustration. In an embodiment, to achieve e-fields with opposing orientations at the north and south slots **1863**, for example, the north and south slots **1863** can be arranged to have a circumferential distance between each other that is approximately one wavelength of electromagnetic waves signals supplied to these slots. The waveguide **1865** can have a cylindrical cavity in a center of the waveguide **1865** to enable placement of a cable **1862**. In one embodiment, the cable **1862** can comprise an insulated conductor. In another embodiment, the cable **1862** can comprise an uninsulated conductor. In yet other embodiments, the cable **1862** can comprise any of the embodiments of a transmission core **1852** of cable **1850** previously described.

In one embodiment, the cable **1862** can slide into the cylindrical cavity of the waveguide **1865**. In another embodiment, the waveguide **1865** can utilize an assembly mechanism (not shown). The assembly mechanism (e.g., a hinge or other suitable mechanism that provides a way to open the waveguide **1865** at one or more locations) can be used to enable placement of the waveguide **1865** on an outer surface of the cable **1862** or otherwise to assemble separate pieces together to form the waveguide **1865** as shown. According to these and other suitable embodiments, the waveguide **1865** can be configured to wrap around the cable **1862** like a collar.

FIG. **18O** illustrates a side view of an embodiment of the waveguide **1865**. The waveguide **1865** can be adapted to have a hollow rectangular waveguide portion **1867** that receives electromagnetic waves **1866** generated by a transmitter circuit as previously described in the subject disclo-

sure (e.g., see FIGS. **1** and **10A**). The electromagnetic waves **1866** can be distributed by the hollow rectangular waveguide portion **1867** into a hollow collar **1869** of the waveguide **1865**. The rectangular waveguide portion **1867** and the hollow collar **1869** can be constructed of materials suitable for maintaining the electromagnetic waves within the hollow chambers of these assemblies (e.g., carbon fiber materials). It should be noted that while the waveguide portion **1867** is shown and described in a hollow rectangular configuration, other shapes and/or other non-hollow configurations can be employed. In particular, the waveguide portion **1867** can have a square or other polygonal cross section, an arc or sector cross section that is truncated to conform to the outer surface of the cable **1862**, a circular or ellipsoid cross section or cross sectional shape. In addition, the waveguide portion **1867** can be configured as, or otherwise include, a solid dielectric material.

As previously described, the hollow collar **1869** can be configured to emit electromagnetic waves from each slot **1863** with opposite e-fields **1861** at pairs of symmetrically positioned slots **1863** and **1863'**. In an embodiment, the electromagnetic waves emitted by the combination of slots **1863** and **1863'** can in turn induce electromagnetic waves **1868** on that are bound to the cable **1862** for propagation according to a fundamental wave mode without other wave modes present—such as non-fundamental wave modes. In this configuration, the electromagnetic waves **1868** can propagate longitudinally along the cable **1862** to other downstream waveguide systems coupled to the cable **1862**.

It should be noted that since the hollow rectangular waveguide portion **1867** of FIG. **18O** is closer to slot **1863** (at the northern position of the waveguide **1865**), slot **1863** can emit electromagnetic waves having a stronger magnitude than electromagnetic waves emitted by slot **1863'** (at the southern position). To reduce magnitude differences between these slots, slot **1863'** can be made larger than slot **1863**. The technique of utilizing different slot sizes to balance signal magnitudes between slots can be applied to any of the embodiments of the subject disclosure relating to FIGS. **18N**, **18O**, **18Q**, **18S**, **18U** and **18V**—some of which are described below.

In another embodiment, FIG. **18P** depicts a waveguide **1865'** that can be configured to utilize circuitry such as monolithic microwave integrated circuits (MMICs) **1870** each coupled to a signal input **1872** (e.g., coaxial cable that provides a communication signal). The signal input **1872** can be generated by a transmitter circuit as previously described in the subject disclosure (e.g., see reference **101**, **1000** of FIGS. **1** and **10A**) adapted to provide electrical signals to the MMICs **1870**. Each MMIC **1870** can be configured to receive signal **1872** which the MMIC **1870** can modulate and transmit with a radiating element (e.g., an antenna) to emit electromagnetic waves having radiated e-fields **1861**. In one embodiment, the MMIC's **1870** can be configured to receive the same signal **1872**, but transmit electromagnetic waves having e-fields **1861** of opposing orientation. This can be accomplished by configuring one of the MMICs **1870** to transmit electromagnetic waves that are 180 degrees out of phase with the electromagnetic waves transmitted by the other MMIC **1870**. In an embodiment, the combination of the electromagnetic waves emitted by the MMICs **1870** can together induce electromagnetic waves **1868** that are bound to the cable **1862** for propagation according to a fundamental wave mode without other wave modes present—such as non-fundamental wave modes. In this configuration, the electromagnetic waves **1868** can

propagate longitudinally along the cable **1862** to other downstream waveguide systems coupled to the cable **1862**.

A tapered horn **1880** can be added to the embodiments of FIGS. **18O** and **18P** to assist in the inducement of the electromagnetic waves **1868** on cable **1862** as depicted in FIGS. **18Q** and **18R**. In an embodiment where the cable **1862** is an uninsulated conductor, the electromagnetic waves induced on the cable **1862** can have a large radial dimension (e.g., 1 meter). To enable use of a smaller tapered horn **1880**, an insulation layer **1879** can be applied on a portion of the cable **1862** at or near the cavity as depicted with hash lines in FIGS. **18Q** and **18R**. The insulation layer **1879** can have a tapered end facing away from the waveguide **1865**. The added insulation enables the electromagnetic waves **1868** initially launched by the waveguide **1865** (or **1865'**) to be tightly bound to the insulation, which in turn reduces the radial dimension of the electromagnetic fields **1868** (e.g., centimeters). As the electromagnetic waves **1868** propagate away from the waveguide **1865** (**1865'**) and reach the tapered end of the insulation layer **1879**, the radial dimension of the electromagnetic waves **1868** begin to increase eventually achieving the radial dimension they would have had had the electromagnetic waves **1868** been induced on the uninsulated conductor without an insulation layer. In the illustration of FIGS. **18Q** and **18R** the tapered end begins at an end of the tapered horn **1880**. In other embodiments, the tapered end of the insulation layer **1879** can begin before or after the end of the tapered horn **1880**. The tapered horn can be metallic or constructed of other conductive material or constructed of a plastic or other non-conductive material that is coated or clad with a dielectric layer or doped with a conductive material to provide reflective properties similar to a metallic horn.

In an embodiment, cable **1862** can comprise any of the embodiments of cable **1850** described earlier. In this embodiment, waveguides **1865** and **1865'** can be coupled to a transmission core **1852** of cable **1850** as depicted in FIGS. **18S** and **18T**. The waveguides **1865** and **1865'** can induce, as previously described, electromagnetic waves **1868** on the transmission core **1852** for propagation entirely or partially within inner layers of cable **1850**.

It is noted that for the foregoing embodiments of FIGS. **18Q**, **18R**, **18S** and **18T**, electromagnetic waves **1868** can be bidirectional. For example, electromagnetic waves **1868** of a different operating frequency can be received by slots **1863** or MMIC's **1870** of the waveguides **1865** and **1865'**, respectively. Once received, the electromagnetic waves can be converted by a receiver circuit (e.g., see reference **101**, **1000** of FIGS. **1** and **10A**) for generating a communication signal for processing.

Although not shown, it is further noted that the waveguides **1865** and **1865'** can be adapted so that the waveguides **1865** and **1865'** can direct electromagnetic waves **1868** upstream or downstream longitudinally. For example, a first tapered horn **1880** coupled to a first instance of a waveguide **1865** or **1865'** can be directed westerly on cable **1862**, while a second tapered horn **1880** coupled to a second instance of a waveguide **1865** or **1865'** can be directed easterly on cable **1862**. The first and second instances of the waveguides **1865** or **1865'** can be coupled so that in a repeater configuration, signals received by the first waveguide **1865** or **1865'** can be provided to the second waveguide **1865** or **1865'** for retransmission in an easterly direction on cable **1862**. The repeater configuration just described can also be applied from an easterly to westerly direction on cable **1862**.

The waveguide **1865** of FIGS. **18N**, **18O**, **18Q** and **18S** can also be configured to generate electromagnetic fields

having only non-fundamental or asymmetric wave modes. FIG. **18U** depicts an embodiment of a waveguide **1865** that can be adapted to generate electromagnetic fields having only non-fundamental wave modes. A median line **1890** represents a separation between slots where electrical currents on a backside (not shown) of a frontal plate of the waveguide **1865** change polarity. For example, electrical currents on the backside of the frontal plate corresponding to e-fields that are radially outward (i.e., point away from a center point of cable **1862**) can in some embodiments be associated with slots located outside of the median line **1890** (e.g., slots **1863A** and **1863B**). Electrical currents on the backside of the frontal plate corresponding to e-fields that are radially inward (i.e., point towards a center point of cable **1862**) can in some embodiments be associated with slots located inside of the median line **1890**. The direction of the currents can depend on the operating frequency of the electromagnetic waves **1866** supplied to the hollow rectangular waveguide portion **1867** (see FIG. **18O**) among other parameters.

For illustration purposes, assume the electromagnetic waves **1866** supplied to the hollow rectangular waveguide portion **1867** have an operating frequency whereby a circumferential distance between slots **1863A** and **1863B** is one full wavelength of the electromagnetic waves **1866**. In this instance, the e-fields of the electromagnetic waves emitted by slots **1863A** and **1863B** point radially outward (i.e., have opposing orientations). When the electromagnetic waves emitted by slots **1863A** and **1863B** are combined, the resulting electromagnetic waves on cable **1862** will propagate according to the fundamental wave mode. In contrast, by repositioning one of the slots (e.g., slot **1863B**) inside the media line **1890** (i.e., slot **1863C**), slot **1863C** will generate electromagnetic waves that have e-fields that are approximately 180 degrees out of phase with the e-fields of the electromagnetic waves generated by slot **1863A**. Consequently, the e-field orientations of the electromagnetic waves generated by slot pairs **1863A** and **1863C** will be substantially aligned. The combination of the electromagnetic waves emitted by slot pairs **1863A** and **1863C** will thus generate electromagnetic waves that are bound to the cable **1862** for propagation according to a non-fundamental wave mode.

To achieve a reconfigurable slot arrangement, waveguide **1865** can be adapted according to the embodiments depicted in FIG. **18V**. Configuration (A) depicts a waveguide **1865** having a plurality of symmetrically positioned slots. Each of the slots **1863** of configuration (A) can be selectively disabled by blocking the slot with a material (e.g., carbon fiber or metal) to prevent the emission of electromagnetic waves. A blocked (or disabled) slot **1863** is shown in black, while an enabled (or unblocked) slot **1863** is shown in white. Although not shown, a blocking material can be placed behind (or in front) of the frontal plate of the waveguide **1865**. A mechanism (not shown) can be coupled to the blocking material so that the blocking material can slide in or out of a particular slot **1863** much like closing or opening a window with a cover. The mechanism can be coupled to a linear motor controllable by circuitry of the waveguide **1865** to selectively enable or disable individual slots **1863**. With such a mechanism at each slot **1863**, the waveguide **1865** can be configured to select different configurations of enabled and disabled slots **1863** as depicted in the embodiments of FIG. **18V**. Other methods or techniques for covering or opening slots (e.g., utilizing rotatable disks behind or in front of the waveguide **1865**) can be applied to the embodiments of the subject disclosure.

55

In one embodiment, the waveguide system **1865** can be configured to enable certain slots **1863** outside the median line **1890** and disable certain slots **1863** inside the median line **1890** as shown in configuration (B) to generate fundamental waves. Assume, for example, that the circumferential distance between slots **1863** outside the median line **1890** (i.e., in the northern and southern locations of the waveguide system **1865**) is one full wavelength. These slots will therefore have electric fields (e-fields) pointing at certain instances in time radially outward as previously described. In contrast, the slots inside the median line **1890** (i.e., in the western and eastern locations of the waveguide system **1865**) will have a circumferential distance of one-half a wavelength relative to either of the slots **1863** outside the median line. Since the slots inside the median line **1890** are half a wavelength apart, such slots will produce electromagnetic waves having e-fields pointing radially outward. If the western and eastern slots **1863** outside the median line **1890** had been enabled instead of the western and eastern slots inside the median line **1890**, then the e-fields emitted by those slots would have pointed radially inward, which when combined with the electric fields of the northern and southern would produce non-fundamental wave mode propagation. Accordingly, configuration (B) as depicted in FIG. **18V** can be used to generate electromagnetic waves at the northern and southern slots **1863** having e-fields that point radially outward and electromagnetic waves at the western and eastern slots **1863** with e-fields that also point radially outward, which when combined induce electromagnetic waves on cable **1862** having a fundamental wave mode.

In another embodiment, the waveguide system **1865** can be configured to enable a northerly, southerly, westerly and easterly slots **1863** all outside the median line **1890**, and disable all other slots **1863** as shown in configuration (C). Assuming the circumferential distance between a pair of opposing slots (e.g., northerly and southerly, or westerly and easterly) is a full wavelength apart, then configuration (C) can be used to generate electromagnetic waves having a non-fundamental wave mode with some e-fields pointing radially outward and other fields pointing radially inward. In yet another embodiment, the waveguide system **1865** can be configured to enable a northwesterly slot **1863** outside the median line **1890**, enable a southeasterly slot **1863** inside the median line **1890**, and disable all other slots **1863** as shown in configuration (D). Assuming the circumferential distance between such a pair of slots is a full wavelength apart, then such a configuration can be used to generate electromagnetic waves having a non-fundamental wave mode with e-fields aligned in a northwesterly direction.

In another embodiment, the waveguide system **1865** can be configured to produce electromagnetic waves having a non-fundamental wave mode with e-fields aligned in a southwesterly direction. This can be accomplished by utilizing a different arrangement than used in configuration (D). Configuration (E) can be accomplished by enabling a southwesterly slot **1863** outside the median line **1890**, enabling a northeasterly slot **1863** inside the median line **1890**, and disabling all other slots **1863** as shown in configuration (E). Assuming the circumferential distance between such a pair of slots is a full wavelength apart, then such a configuration can be used to generate electromagnetic waves having a non-fundamental wave mode with e-fields aligned in a southwesterly direction. Configuration (E) thus generates a non-fundamental wave mode that is orthogonal to the non-fundamental wave mode of configuration (D).

In yet another embodiment, the waveguide system **1865** can be configured to generate electromagnetic waves having

56

a fundamental wave mode with e-fields that point radially inward. This can be accomplished by enabling a northerly slot **1863** inside the median line **1890**, enabling a southerly slot **1863** inside the median line **1890**, enabling an easterly slot outside the median **1890**, enabling a westerly slot **1863** outside the median **1890**, and disabling all other slots **1863** as shown in configuration (F). Assuming the circumferential distance between the northerly and southerly slots is a full wavelength apart, then such a configuration can be used to generate electromagnetic waves having a fundamental wave mode with radially inward e-fields. Although the slots selected in configurations (B) and (F) are different, the fundamental wave modes generated by configurations (B) and (F) are the same.

It yet another embodiment, e-fields can be manipulated between slots to generate fundamental or non-fundamental wave modes by varying the operating frequency of the electromagnetic waves **1866** supplied to the hollow rectangular waveguide portion **1867**. For example, assume in the illustration of FIG. **18U** that for a particular operating frequency of the electromagnetic waves **1866** the circumferential distance between slot **1863A** and **1863B** is one full wavelength of the electromagnetic waves **1866**. In this instance, the e-fields of electromagnetic waves emitted by slots **1863A** and **1863B** will point radially outward as shown, and can be used in combination to induce electromagnetic waves on cable **1862** having a fundamental wave mode. In contrast, the e-fields of electromagnetic waves emitted by slots **1863A** and **1863C** will be radially aligned (i.e., pointing northerly) as shown, and can be used in combination to induce electromagnetic waves on cable **1862** having a non-fundamental wave mode.

Now suppose that the operating frequency of the electromagnetic waves **1866** supplied to the hollow rectangular waveguide portion **1867** is changed so that the circumferential distance between slot **1863A** and **1863B** is one-half a wavelength of the electromagnetic waves **1866**. In this instance, the e-fields of electromagnetic waves emitted by slots **1863A** and **1863B** will be radially aligned (i.e., point in the same direction). That is, the e-fields of electromagnetic waves emitted by slot **1863B** will point in the same direction as the e-fields of electromagnetic waves emitted by slot **1863A**. Such electromagnetic waves can be used in combination to induce electromagnetic waves on cable **1862** having a non-fundamental wave mode. In contrast, the e-fields of electromagnetic waves emitted by slots **1863A** and **1863C** will be radially outward (i.e., away from cable **1862**), and can be used in combination to induce electromagnetic waves on cable **1862** having a fundamental wave mode.

In another embodiment, the waveguide **1865'** of FIGS. **18P**, **18R** and **18T** can also be configured to generate electromagnetic waves having only non-fundamental wave modes. This can be accomplished by adding more MMICs **1870** as depicted in FIG. **18W**. Each MMIC **1870** can be configured to receive the same signal input **1872**. However, MMICs **1870** can selectively be configured to emit electromagnetic waves having differing phases using controllable phase-shifting circuitry in each MMIC **1870**. For example, the northerly and southerly MMICs **1870** can be configured to emit electromagnetic waves having a 180 degree phase difference, thereby aligning the e-fields either in a northerly or southerly direction. Any combination of pairs of MMICs **1870** (e.g., westerly and easterly MMICs **1870**, northwesterly and southeasterly MMICs **1870**, northeasterly and southwesterly MMICs **1870**) can be configured with opposing or aligned e-fields. Consequently, waveguide **1865'** can

be configured to generate electromagnetic waves with one or more non-fundamental wave modes, electromagnetic waves with one or more fundamental wave modes, or any combinations thereof.

It is submitted that it is not necessary to select slots **1863** in pairs to generate electromagnetic waves having a non-fundamental wave mode. For example, electromagnetic waves having a non-fundamental wave mode can be generated by enabling a single slot from the plurality of slots shown in configuration (A) of FIG. **18V** and disabling all other slots. Similarly, a single MMIC **1870** of the MMICs **1870** shown in FIG. **18W** can be configured to generate electromagnetic waves having a non-fundamental wave mode while all other MMICs **1870** are not in use or disabled. Likewise other wave modes and wave mode combinations can be induced by enabling other non-null proper subsets of waveguide slots **1863** or the MMICs **1870**.

It is further submitted that the e-field arrows shown in FIGS. **18U-18V** are illustrative only and represent a static depiction of e-fields. In practice, the electromagnetic waves may have oscillating e-fields, which at one instance in time point outwardly, and at another instance in time point inwardly. For example, in the case of non-fundamental wave modes having e-fields that are aligned in one direction (e.g., northerly), such waves may at another instance in time have e-fields that point in an opposite direction (e.g., southerly). Similarly, fundamental wave modes having e-fields that are radial may at one instance have e-fields that point radially away from the cable **1862** and at another instance in time point radially towards the cable **1862**. It is further noted that the embodiments of FIGS. **18U-18W** can be adapted to generate electromagnetic waves with one or more non-fundamental wave modes, electromagnetic waves with one or more fundamental wave modes (e.g., TM₀₀ and HE₁₁ modes), or any combinations thereof. It is further noted that such adaptations can be used in combination with any embodiments described in the subject disclosure. It is also noted that the embodiments of FIGS. **18U-18W** can be combined (e.g., slots used in combination with MMICs).

It is further noted that in some embodiments, the waveguide systems **1865** and **1865'** of FIGS. **18N-18W** may generate combinations of fundamental and non-fundamental wave modes where one wave mode is dominant over the other. For example, in one embodiment electromagnetic waves generated by the waveguide systems **1865** and **1865'** of FIGS. **18N-18W** may have a weak signal component that has a non-fundamental wave mode, and a substantially strong signal component that has a fundamental wave mode. Accordingly, in this embodiment, the electromagnetic waves have a substantially fundamental wave mode. In another embodiment electromagnetic waves generated by the waveguide systems **1865** and **1865'** of FIGS. **18N-18W** may have a weak signal component that has a fundamental wave mode, and a substantially strong signal component that has a non-fundamental wave mode. Accordingly, in this embodiment, the electromagnetic waves have a substantially non-fundamental wave mode. Further, a non-dominant wave mode may be generated that propagates only trivial distances along the length of the transmission medium.

It is also noted that the waveguide systems **1865** and **1865'** of FIGS. **18N-18W** can be configured to generate instances of electromagnetic waves that have wave modes that can differ from a resulting wave mode or modes of the combined electromagnetic wave. It is further noted that each MMIC **1870** of the waveguide system **1865'** of FIG. **18W** can be configured to generate an instance of electromagnetic waves having wave characteristics that differ from the wave char-

acteristics of another instance of electromagnetic waves generated by another MMIC **1870**. One MMIC **1870**, for example, can generate an instance of an electromagnetic wave having a spatial orientation and a phase, frequency, magnitude, electric field orientation, and/or magnetic field orientation that differs from the spatial orientation and phase, frequency, magnitude, electric field orientation, and/or magnetic field orientation of a different instance of another electromagnetic wave generated by another MMIC **1870**. The waveguide system **1865'** can thus be configured to generate instances of electromagnetic waves having different wave and spatial characteristics, which when combined achieve resulting electromagnetic waves having one or more desirable wave modes.

From these illustrations, it is submitted that the waveguide systems **1865** and **1865'** of FIGS. **18N-18W** can be adapted to generate electromagnetic waves with one or more selectable wave modes. In one embodiment, for example, the waveguide systems **1865** and **1865'** can be adapted to select one or more wave modes and generate electromagnetic waves having a single wave mode or multiple wave modes selected and produced from a process of combining instances of electromagnetic waves having one or more configurable wave and spatial characteristics. In an embodiment, for example, parametric information can be stored in a look-up table. Each entry in the look-up table can represent a selectable wave mode. A selectable wave mode can represent a single wave mode, or a combination of wave modes. The combination of wave modes can have one or dominant wave modes. The parametric information can provide configuration information for generating instances of electromagnetic waves for producing resultant electromagnetic waves that have the desired wave mode.

For example, once a wave mode or modes is selected, the parametric information obtained from the look-up table from the entry associated with the selected wave mode(s) can be used to identify which of one or more MMICs **1870** to utilize, and/or their corresponding configurations to achieve electromagnetic waves having the desired wave mode(s). The parametric information may identify the selection of the one or more MMICs **1870** based on the spatial orientations of the MMICs **1870**, which may be required for producing electromagnetic waves with the desired wave mode. The parametric information can also provide information to configure each of the one or more MMICs **1870** with a particular phase, frequency, magnitude, electric field orientation, and/or magnetic field orientation which may or may not be the same for each of the selected MMICs **1870**. A look-up table with selectable wave modes and corresponding parametric information can be adapted for configuring the slotted waveguide system **1865**.

In some embodiments, a guided electromagnetic wave can be considered to have a desired wave mode if the corresponding wave mode propagates non-trivial distances on a transmission medium and has a field strength that is substantially greater in magnitude (e.g., 20 dB higher in magnitude) than other wave modes that may or may not be desirable. Such a desired wave mode or modes can be referred to as dominant wave mode(s) with the other wave modes being referred to as non-dominant wave modes. In a similar fashion, a guided electromagnetic wave that is said to be substantially without the fundamental wave mode has either no fundamental wave mode or a non-dominant fundamental wave mode. A guided electromagnetic wave that is said to be substantially without a non-fundamental wave mode has either no non-fundamental wave mode(s) or only non-dominant non-fundamental wave mode(s). In some

embodiments, a guided electromagnetic wave that is said to have only a single wave mode or a selected wave mode may have only one corresponding dominant wave mode.

It is further noted that the embodiments of FIGS. 18U-18W can be applied to other embodiments of the subject disclosure. For example, the embodiments of FIGS. 18U-18W can be used as alternate embodiments to the embodiments depicted in FIGS. 18N-18T or can be combined with the embodiments depicted in FIGS. 18N-18T.

Turning now to FIGS. 19A and 19B, block diagrams illustrating example, non-limiting embodiments of a dielectric antenna and corresponding gain and field intensity plots in accordance with various aspects described herein are shown. FIG. 19A depicts a dielectric horn antenna 1901 having a conical structure. The dielectric horn antenna 1901 is coupled to one end 1902' of a feedline 1902 having a feed point 1902" at an opposite end of the feedline 1902. The dielectric horn antenna 1901 and the feedline 1902 (as well as other embodiments of the dielectric antenna described below in the subject disclosure) can be constructed of dielectric materials such as a polyethylene material, a polyurethane material or other suitable dielectric material (e.g., a synthetic resin, other plastics, etc.). The dielectric horn antenna 1901 and the feedline 1902 (as well as other embodiments of the dielectric antenna described below in the subject disclosure) can be adapted to be substantially or entirely devoid of any conductive materials.

For example, the external surfaces 1907 of the dielectric horn antenna 1901 and the feedline 1902 can be non-conductive or substantially non-conductive with at least 95% of the external surface area being non-conductive and the dielectric materials used to construct the dielectric horn antenna 1901 and the feedline 1902 can be such that they substantially do not contain impurities that may be conductive (e.g., such as less than 1 part per thousand) or result in imparting conductive properties. In other embodiments, however, a limited number of conductive components can be used such as a metallic connector component used for coupling to the feed point 1902" of the feedline 1902 with one or more screws, rivets or other coupling elements used to bind components to one another, and/or one or more structural elements that do not significantly alter the radiation pattern of the dielectric antenna.

The feed point 1902" can be adapted to couple to a core 1852 such as previously described by way of illustration in FIGS. 18I and 18J. In one embodiment, the feed point 1902" can be coupled to the core 1852 utilizing a joint (not shown in FIG. 19A) such as the splicing device 1860 of FIG. 18J. Other embodiments for coupling the feed point 1902" to the core 1852 can be used. In an embodiment, the joint can be configured to cause the feed point 1902" to touch an endpoint of the core 1852. In another embodiment, the joint can create a gap between the feed point 1902" and an end of the core 1852. In yet another embodiment, the joint can cause the feed point 1902" and the core 1852 to be coaxially aligned or partially misaligned. Notwithstanding any combination of the foregoing embodiments, electromagnetic waves can in whole or at least in part propagate between the junction of the feed point 1902" and the core 1852.

The cable 1850 can be coupled to the waveguide system 1865 depicted in FIG. 18S or the waveguide system 1865' depicted in FIG. 18T. For illustration purposes only, reference will be made to the waveguide system 1865' of FIG. 18T. It is understood, however, that the waveguide system 1865 of FIG. 18S or other waveguide systems can also be utilized in accordance with the discussions that follow. The waveguide system 1865' can be configured to select a wave

mode (e.g., non-fundamental wave mode, fundamental wave mode, a hybrid wave mode, or combinations thereof as described earlier) and transmit instances of electromagnetic waves having a non-optical operating frequency (e.g., 60 GHz). The electromagnetic waves can be directed to an interface of the cable 1850 as shown in FIG. 18T.

The instances of electromagnetic waves generated by the waveguide system 1865' can induce a combined electromagnetic wave having the selected wave mode that propagates from the core 1852 to the feed point 1902". The combined electromagnetic wave can propagate partly inside the core 1852 and partly on an outer surface of the core 1852. Once the combined electromagnetic wave has propagated through the junction between the core 1852 and the feed point 1902", the combined electromagnetic wave can continue to propagate partly inside the feedline 1902 and partly on an outer surface of the feedline 1902. In some embodiments, the portion of the combined electromagnetic wave that propagates on the outer surface of the core 1852 and the feedline 1902 is small. In these embodiments, the combined electromagnetic wave can be said to be guided by and tightly coupled to the core 1852 and the feedline 1902 while propagating longitudinally towards the dielectric antenna 1901.

When the combined electromagnetic wave reaches a proximal portion of the dielectric antenna 1901 (at a junction 1902' between the feedline 1902 and the dielectric antenna 1901), the combined electromagnetic wave enters the proximal portion of the dielectric antenna 1901 and propagates longitudinally along an axis of the dielectric antenna 1901 (shown as a hashed line). By the time the combined electromagnetic wave reaches the aperture 1903, the combined electromagnetic wave has an intensity pattern similar to the one shown by the side view and front view depicted in FIG. 19B. The electric field intensity pattern of FIG. 19B shows that the electric fields of the combined electromagnetic waves are strongest in a center region of the aperture 1903 and weaker in the outer regions. In an embodiment, where the wave mode of the electromagnetic waves propagating in the dielectric antenna 1901 is a hybrid wave mode (e.g., HE₁₁), the leakage of the electromagnetic waves at the external surfaces 1907 is reduced or in some instances eliminated. It is further noted that while the dielectric antenna 1901 is constructed of a solid dielectric material having no physical opening, the front or operating face of the dielectric antenna 1901 from which free space wireless signals are radiated or received will be referred to as the aperture 1903 of the dielectric antenna 1901 even though in some prior art systems the term aperture may be used to describe an opening of an antenna that radiates or receives free space wireless signals. Methods for launching a hybrid wave mode on cable 1850 is discussed below.

In an embodiment, the far-field antenna gain pattern depicted in FIG. 19B can be widened by decreasing the operating frequency of the combined electromagnetic wave from a nominal frequency. Similarly, the gain pattern can be narrowed by increasing the operating frequency of the combined electromagnetic wave from the nominal frequency. Accordingly, a width of a beam of wireless signals emitted by the aperture 1903 can be controlled by configuring the waveguide system 1865' to increase or decrease the operating frequency of the combined electromagnetic wave.

The dielectric antenna 1901 of FIG. 19A can also be used for receiving wireless signals, such as free space wireless signals transmitted by either a similar antenna or conventional antenna design. Wireless signals received by the dielectric antenna 1901 at the aperture 1903 induce electro-

61

magnetic waves in the dielectric antenna **1901** that propagate towards the feedline **1902**. The electromagnetic waves continue to propagate from the feedline **1902** to the junction between the feed point **1902**" and an endpoint of the core **1852**, and are thereby delivered to the waveguide system **1865'** coupled to the cable **1850** as shown in FIG. **18T**. In this configuration, the waveguide system **1865'** can perform bidirectional communications utilizing the dielectric antenna **1901**. It is further noted that in some embodiments the core **1852** of the cable **1850** (shown with dashed lines) can be configured to be collinear with the feed point **1902**" to avoid a bend shown in FIG. **19A**. In some embodiments, a collinear configuration can reduce an alteration in the propagation of the electromagnetic due to the bend in cable **1850**.

Turning now to FIGS. **19C** and **19D**, block diagrams illustrating example, non-limiting embodiments of a dielectric antenna **1901** coupled to or integrally constructed with a lens **1912** and corresponding gain and field intensity plots in accordance with various aspects described herein are shown. In one embodiment, the lens **1912** can comprise a dielectric material having a first dielectric constant that is substantially similar or equal to a second dielectric constant of the dielectric antenna **1901**. In other embodiments, the lens **1912** can comprise a dielectric material having a first dielectric constant that differs from a second dielectric constant of the dielectric antenna **1901**. In either of these embodiments, the shape of the lens **1912** can be chosen or formed so as to equalize the delays of the various electromagnetic waves propagating at different points in the dielectric antenna **1901**. In one embodiment, the lens **1912** can be an integral part of the dielectric antenna **1901** as depicted in the top diagram of FIG. **19C** and in particular, the lens and dielectric antenna **1901** can be molded, machined or otherwise formed from a single piece of dielectric material. Alternatively, the lens **1912** can be an assembly component of the dielectric antenna **1901** as depicted in the bottom diagram of FIG. **19C**, which can be attached by way of an adhesive material, brackets on the outer edges, or other suitable attachment techniques. The lens **1912** can have a convex structure as shown in FIG. **19C** which is adapted to adjust a propagation of electromagnetic waves in the dielectric antenna **1901**. While a round lens and conical dielectric antenna configuration is shown, other shapes include pyramidal shapes, elliptical shapes and other geometric shapes can likewise be implemented.

In particular, the curvature of the lens **1912** can be chosen in manner that reduces phase differences between near-field wireless signals generated by the aperture **1903** of the dielectric antenna **1901**. The lens **1912** accomplishes this by applying location-dependent delays to propagating electromagnetic waves. Because of the curvature of the lens **1912**, the delays differ depending on where the electromagnetic waves emanate from at the aperture **1903**. For example, electromagnetic waves propagating by way of a center axis **1905** of the dielectric antenna **1901** will experience more delay through the lens **1912** than electromagnetic waves propagating radially away from the center axis **1905**. Electromagnetic waves propagating towards, for example, the outer edges of the aperture **1903** will experience minimal or no delay through the lens. Propagation delay increases as the electromagnetic waves get close to the center axis **1905**. Accordingly, a curvature of the lens **1912** can be configured so that near-field wireless signals have substantially similar phases. By reducing differences between phases of the near-field wireless signals, a width of far-field signals generated by the dielectric antenna **1901** is reduced, which in

62

turn increases the intensity of the far-field wireless signals within the width of the main lobe as shown by the far-field intensity plot shown in FIG. **19D**, producing a relatively narrow beam pattern with high gain.

Turning now to FIGS. **19E** and **19F**, block diagrams illustrating example, non-limiting embodiments of a dielectric antenna **1901** coupled to a lens **1912** with ridges (or steps) **1914** and corresponding gain and field intensity plots in accordance with various aspects described herein are shown. In these illustration, the lens **1912** can comprise concentric ridges **1914** shown in the side and perspective views of FIG. **19E**. Each ridge **1914** can comprise a riser **1916** and a tread **1918**. The size of the tread **1918** changes depending on the curvature of the aperture **1903**. For example, the tread **1918** at the center of the aperture **1903** can be greater than the tread at the outer edges of the aperture **1903**. To reduce reflections of electromagnetic waves that reach the aperture **1903**, each riser **1916** can be configured to have a depth representative of a select wavelength factor. For example, a riser **1916** can be configured to have a depth of one-quarter a wavelength of the electromagnetic waves propagating in the dielectric antenna **1901**. Such a configuration causes the electromagnetic wave reflected from one riser **1916** to have a phase difference of 180 degrees relative to the electromagnetic wave reflected from an adjacent riser **1916**. Consequently, the out of phase electromagnetic waves reflected from the adjacent risers **1916** substantially cancel, thereby reducing reflection and distortion caused thereby. While a particular riser/tread configuration is shown, other configurations with a differing number of risers, differing riser shapes, etc. can likewise be implemented. In some embodiments, the lens **1912** with concentric ridges depicted in FIG. **19E** may experience less electromagnetic wave reflections than the lens **1912** having the smooth convex surface depicted in FIG. **19C**. FIG. **19F** depicts the resulting far-field gain plot of the dielectric antenna **1901** of FIG. **19E**.

Turning now to FIG. **19G**, a block diagram illustrating an example, non-limiting embodiment of a dielectric antenna **1901** having an elliptical structure in accordance with various aspects described herein is shown. FIG. **19G** depicts a side view, top view, and front view of the dielectric antenna **1901**. The elliptical shape is achieved by reducing a height of the dielectric antenna **1901** as shown by reference **1922** and by elongating the dielectric antenna **1901** as shown by reference **1924**. The resulting elliptical shape **1926** is shown in the front view depicted by FIG. **19G**. The elliptical shape can be formed, via machining, with a mold tool or other suitable construction technique.

Turning now to FIG. **19H**, a block diagram illustrating an example, non-limiting embodiment of near-field signals **1928** and far-field signals **1930** emitted by the dielectric antenna **1901** of FIG. **19G** in accordance with various aspects described herein is shown. The cross section of the near-field beam pattern **1928** mimics the elliptical shape of the aperture **1903** of the dielectric antenna **1901**. The cross section of the far-field beam pattern **1930** have a rotational offset (approximately 90 degrees) that results from the elliptical shape of the near-field signals **1928**. The offset can be determined by applying a Fourier Transform to the near-field signals **1928**. While the cross section of the near-field beam pattern **1928** and the cross section of the far-field beam pattern **1930** are shown as nearly the same size in order to demonstrate the rotational effect, the actual size of the far-field beam pattern **1930** may increase with the distance from the dielectric antenna **1901**.

The elongated shape of the far-field signals **1930** and its orientation can prove useful when aligning a dielectric antenna **1901** in relation to a remotely located receiver configured to receive the far-field signals **1930**. The receiver can comprise one or more dielectric antennas coupled to a waveguide system such as described by the subject disclosure. The elongated far-field signals **1930** can increase the likelihood that the remotely located receiver will detect the far-field signals **1930**. In addition, the elongated far-field signals **1930** can be useful in situations where a dielectric antenna **1901** coupled to a gimbal assembly such as shown in FIG. **19M**, or other actuated antenna mount including but not limited to the actuated gimbal mount described in the co-pending application entitled, COMMUNICATION DEVICE AND ANTENNA ASSEMBLY WITH ACTUATED GIMBAL MOUNT, and U.S. patent application Ser. No. 14/873,241, filed on Oct. 2, 2015 the contents of which are incorporated herein by reference for any and all purposes. In particular, the elongated far-field signals **1930** can be useful in situations where such as gimbal mount only has two degrees of freedom for aligning the dielectric antenna **1901** in the direction of the receiver (e.g., yaw and pitch is adjustable but roll is fixed).

Although not shown, it will be appreciated that the dielectric antenna **1901** of FIGS. **19G** and **19H** can have an integrated or attachable lens **1912** such as shown in FIGS. **19C** and **19E** to increase an intensity of the far-fields signals **1930** by reducing phase differences in the near-field signals.

Turning now to FIG. **19I**, block diagrams of example, non-limiting embodiments of a dielectric antenna **1901** for adjusting far-field wireless signals in accordance with various aspects described herein are shown. In some embodiments, a width of far-field wireless signals generated by the dielectric antenna **1901** can be said to be inversely proportional to a number of wavelengths of the electromagnetic waves propagating in the dielectric antenna **1901** that can fit in a surface area of the aperture **1903** of the dielectric antenna **1901**. Hence, as the wavelengths of the electromagnetic waves increases, the width of the far-field wireless signals increases (and its intensity decreases) proportionately. Put another way, when the frequency of the electromagnetic waves decreases, the width of the far-field wireless signals increases proportionately. Accordingly, to enhance a process of aligning a dielectric antenna **1901** using, for example, the gimbal assembly shown in FIG. **19M** or other actuated antenna mount, in a direction of a receiver, the frequency of the electromagnetic waves supplied to the dielectric antenna **1901** by way of the feedline **1902** can be decreased so that the far-field wireless signals are sufficiently wide to increase a likelihood that the receiver will detect a portion of the far-field wireless signals.

In some embodiments, the receiver can be configured to perform measurements on the far-field wireless signals. From these measurements the receiver can direct a waveguide system coupled to the dielectric antenna **1901** generating the far-field wireless signals. The receiver can provide instructions to the waveguide system by way of an omnidirectional wireless signal or a tethered interface therebetween. The instructions provided by the receiver can result in the waveguide system controlling actuators in the gimbal assembly coupled to the dielectric antenna **1901** to adjust a direction of the dielectric antenna **1901** to improve its alignment to the receiver. As the quality of the far-field wireless signals improves, the receiver can also direct the waveguide system to increase a frequency of the electro-

magnetic waves, which in turn reduces a width of the far-field wireless signals and correspondingly increases its intensity.

In an alternative embodiment, absorption sheets **1932** constructed from carbon or conductive materials and/or other absorbers can be embedded in the dielectric antenna **1901** as depicted by the perspective and front views shown in FIG. **19I**. When the electric fields of the electromagnetic waves are parallel with the absorption sheets **1932**, the electromagnetic waves are absorbed. A clearance region **1934** where absorption sheets **1932** are not present will, however, allow the electromagnetic waves to propagate to the aperture **1903** and thereby emit near-field wireless signals having approximately the width of the clearance region **1934**. By reducing the number of wavelengths to a surface area of the clearance region **1932**, the width of the near-field wireless signals is decreases, while the width of the far-field wireless signals is increased. This property can be useful during the alignment process previously described.

For example, at the onset of an alignment process, the polarity of the electric fields emitted by the electromagnetic waves can be configured to be parallel with the absorption sheets **1932**. As the remotely located receiver instructs a waveguide system coupled to the dielectric antenna **1901** to direct the dielectric antenna **1901** using the actuators of a gimbal assembly or other actuated mount, it can also instruct the waveguide system to incrementally adjust the alignment of the electric fields of the electromagnetic waves relative to the absorption sheets **1932** as signal measurements performed by the receiver improve. As the alignment improves, eventually waveguide system adjusts the electric fields so that they are orthogonal to the absorption sheets **1932**. At this point, the electromagnetic waves near the absorption sheets **1932** will no longer be absorbed, and all or substantially all electromagnetic waves will propagate to the aperture **1903**. Since the near-field wireless signals now cover all or substantially all of the aperture **1903**, the far-field signals will have a narrower width and higher intensity as they are directed to the receiver.

It will be appreciated that the receiver configured to receive the far-field wireless signals (as described above) can also be configured to utilize a transmitter that can transmit wireless signals directed to the dielectric antenna **1901** utilized by the waveguide system. For illustration purposes, such a receiver will be referred to as a remote system that can receive far-field wireless signals and transmit wireless signals directed to the waveguide system. In this embodiment, the waveguide system can be configured to analyze the wireless signals it receives by way of the dielectric antenna **1901** and determine whether a quality of the wireless signals generated by the remote system justifies further adjustments to the far-field signal pattern to improve reception of the far-field wireless signals by the remote system, and/or whether further orientation alignment of the dielectric antenna by way of the gimbal (see FIG. **19M**) or other actuated mount is needed. As the quality of a reception of the wireless signals by the waveguide system improves, the waveguide system can increase the operating frequency of the electromagnetic waves, which in turn reduces a width of the far-field wireless signals and correspondingly increases its intensity. In other modes of operation, the gimbal or other actuated mount can be periodically adjusted to maintain an optimal alignment.

The foregoing embodiments of FIG. **19I** can also be combined. For example, the waveguide system can perform adjustments to the far-field signal pattern and/or antenna orientation adjustments based on a combination of an analy-

65

sis of wireless signals generated by the remote system and messages or instructions provided by the remote system that indicate a quality of the far-field signals received by the remote system.

Turning now to FIG. 19J, block diagrams of example, non-limiting embodiments of a collar such as a flange 1942 that can be coupled to a dielectric antenna 1901 in accordance with various aspects described herein is shown. The flange can be constructed with metal (e.g., aluminum) dielectric material (e.g., polyethylene and/or foam), or other suitable materials. The flange 1942 can be utilized to align the feed point 1902" (and in some embodiments also the feedline 1902) with a waveguide system 1948 (e.g., a circular waveguide) as shown in FIG. 19K. To accomplish this, the flange 1942 can comprise a center hole 1946 for engaging with the feed point 1902". In one embodiment, the hole 1946 can be threaded and the feedline 1902 can have a smooth surface. In this embodiment, the flange 1942 can engage the feed point 1902" (constructed of a dielectric material such as polyethylene) by inserting a portion of the feed point 1902" into the hole 1946 and rotating the flange 1942 to act as a die to form complementary threads on the soft outer surface of the feedline 1902.

Once the feedline 1902 has been threaded by or into the flange 1942, the feed point 1902" and portion of the feedline 1902 extending from the flange 1942 can be shortened or lengthened by rotating the flange 1942 accordingly. In other embodiments the feedline 1902 can be pre-threaded with mating threads for engagement with the flange 1942 for improving the ease of engaging it with the flange 1942. In yet other embodiments, the feedline 1902 can have a smooth surface and the hole 1946 of the flange 1942 can be non-threaded. In this embodiment, the hole 1946 can have a diameter that is similar to diameter of the feedline 1902 such as to cause the engagement of the feedline 1902 to be held in place by frictional forces.

For alignment purposes, the flange 1942 can further include threaded holes 1944 accompanied by two or more alignment holes 1947, which can be used to align to complementary alignment pins 1949 of the waveguide system 1948, which in turn assist in aligning holes 1944' of the waveguide system 1948 to the threaded holes 1944 of the flange 1942 (see FIGS. 19K-19L). Once the flange 1942 has been aligned to the waveguide system 1948, the flange 1942 and waveguide system 1948 can be secured to each other with threaded screws 1950 resulting in a completed assembly depicted in FIG. 19L. In a threaded design, the feed point 1902" of the feedline 1902 can be adjusted inwards or outwards in relation to a port 1945 of the waveguide system 1948 from which electromagnetic waves are exchanged. The adjustment enables the gap 1943 between the feed point 1902" and the port 1945 to be increased or decreased. The adjustment can be used for tuning a coupling interface between the waveguide system 1948 and the feed point 1902" of the feedline 1902. FIG. 19L also shows how the flange 1942 can be used to align the feedline 1902 with coaxially aligned dielectric foam sections 1951 held by a tubular outer jacket 1952. The illustration in FIG. 19L is similar to the transmission medium 1800' illustrated in FIG. 18K. To complete the assembly process, the flange 1942 can be coupled to a waveguide system 1948 as depicted in FIG. 19L.

Turning now to FIG. 19N, a block diagram of an example, non-limiting embodiment of a dielectric antenna 1901' in accordance with various aspects described herein is shown. FIG. 19N depicts an array of pyramidal-shaped dielectric horn antennas 1901', each having a corresponding aperture

66

1903'. Each antenna of the array of pyramidal-shaped dielectric horn antennas 1901' can have a feedline 1902 with a corresponding feed point 1902" that couples to each corresponding core 1852 of a plurality of cables 1850. Each cable 1850 can be coupled to a different (or a same) waveguide system 1865' such as shown in FIG. 18T. The array of pyramidal-shaped dielectric horn antennas 1901' can be used to transmit wireless signals having a plurality of spatial orientations. An array of pyramidal-shaped dielectric horn antennas 1901' covering 360 degrees can enable a one or more waveguide systems 1865' coupled to the antennas to perform omnidirectional communications with other communication devices or antennas of similar type.

The bidirectional propagation properties of electromagnetic waves previously described for the dielectric antenna 1901 of FIG. 19A are also applicable for electromagnetic waves propagating from the core 1852 to the feed point 1902" guided by the feedline 1902 to the aperture 1903' of the pyramidal-shaped dielectric horn antennas 1901', and in the reverse direction. Similarly, the array of pyramidal-shaped dielectric horn antennas 1901' can be substantially or entirely devoid of conductive external surfaces and internal conductive materials as discussed above. For example, in some embodiments, the array of pyramidal-shaped dielectric horn antennas 1901' and their corresponding feed points 1902' can be constructed of dielectric-only materials such as polyethylene or polyurethane materials or with only trivial amounts of conductive material that does not significantly alter the radiation pattern of the antenna.

It is further noted that each antenna of the array of pyramidal-shaped dielectric horn antennas 1901' can have similar gain and electric field intensity maps as shown for the dielectric antenna 1901 in FIG. 19B. Each antenna of the array of pyramidal-shaped dielectric horn antennas 1901' can also be used for receiving wireless signals as previously described for the dielectric antenna 1901 of FIG. 19A. In some embodiments, a single instance of a pyramidal-shaped dielectric horn antenna can be used. Similarly, multiple instances of the dielectric antenna 1901 of FIG. 19A can be used in an array configuration similar to the one shown in FIG. 19N.

Turning now to FIG. 19O, block diagrams of example, non-limiting embodiments of an array 1976 of dielectric antennas 1901 configurable for steering wireless signals in accordance with various aspects described herein is shown. The array 1976 of dielectric antennas 1901 can be conical shaped antennas 1901 or pyramidal-shaped dielectric antennas 1901'. To perform beam steering, a waveguide system coupled to the array 1976 of dielectric antennas 1901 can be adapted to utilize a circuit 1972 comprising amplifiers 1973 and phase shifters 1974, each pair coupled to one of the dielectric antennas 1901 in the array 1976. The waveguide system can steer far-field wireless signals from left to right (west to east) by incrementally increasing a phase delay of signals supplied to the dielectric antennas 1901.

For example, the waveguide system can provide a first signal to the dielectric antennas of column 1 ("C1") having no phase delay. The waveguide system can further provide a second signal to column 2 ("C2"), the second signal comprising the first signal having a first phase delay. The waveguide system can further provide a third signal to the dielectric antennas of column 3 ("C3"), the third signal comprising the second signal having a second phase delay. Lastly, the waveguide system can provide a fourth signal to the dielectric antennas of column 4 ("C4"), the fourth signal comprising the third signal having a third phase delay. These phase shifted signals will cause far-field wireless signals

generated by the array to shift from left to right. Similarly, far-field signals can be steered from right to left (east to west) ("C4" to C1), north to south ("R1" to "R4"), south to north ("R4" to "R1"), and southwest to northeast ("C1-R4" to "C4-R1").

Utilizing similar techniques beam steering can also be performed in other directions such as southwest to northeast by configuring the waveguide system to incrementally increase the phase of signals transmitted by the following sequence of antennas: "C1-R4", "C1-R3/C2-R4", "C1-R2/C2-R3/C3-R4", "C1-R1/C2-R2/C3-R3/C4-R4", "C2-R1/C3-R2/C4-R3", "C3-R1/C4-R2", "C4-R1". In a similar way, beam steering can be performed northeast to southwest, northwest to southeast, southeast to northwest, as well in other directions in three-dimensional space. Beam steering can be used, among other things, for aligning the array 1976 of dielectric antennas 1901 with a remote receiver and/or for directivity of signals to mobile communication devices. In some embodiments, a phased array 1976 of dielectric antennas 1976 can also be used to circumvent the use of the gimbal assembly of FIG. 19M or other actuated mount. While the foregoing has described beam steering controlled by phase delays, gain and phase adjustment can likewise be applied to the dielectric antennas 1901 of the phased array 1976 in a similar fashion to provide additional control and versatility in the formation of a desired beam pattern.

Turning now to FIGS. 19P1-19P8, side-view block diagrams of example, non-limiting embodiments of a cable, a flange, and dielectric antenna assembly in accordance with various aspects described herein are shown. FIG. 19P1 depicts a cable 1850 such as described earlier, which includes a transmission core 1852. The transmission core 1852 can comprise a dielectric core 1802, an insulated conductor 1825, a bare conductor 1832, a core 1842, or a hollow core 1842' as depicted in the transmission mediums 1800, 1820, 1830, 1836, 1841 and/or 1843 of FIGS. 18A-18D, and 18F-18H, respectively. The cable 1850 can further include a shell (such as a dielectric shell) covered by an outer jacket such as shown in FIGS. 18A-18C. In some embodiments, the outer jacket can be conductorless (e.g., polyethylene or equivalent). In other embodiments, the outer jacket can be a conductive shield which can reduce leakage of the electromagnetic waves propagating along the transmission core 1852.

In some embodiments, one end of the transmission core 1852 can be coupled to a flange 1942 as previously described in relation to FIGS. 19J-19L. As noted above, the flange 1942 can enable the transmission core 1852 of the cable 1850 to be aligned with a feed point 1902 of the dielectric antenna 1901. In some embodiments, the feed point 1902 can be constructed of the same material as the transmission core 1852. For example, in one embodiment the transmission core 1852 can comprise a dielectric core, and the feed point 1902 can comprise a dielectric material also. In this embodiment, the dielectric constants of the transmission core 1852 and the feed point 1902 can be similar or can differ by a controlled amount. The difference in dielectric constants can be controlled to tune the interface between the transmission core 1852 and the feed point 1902 for the exchange of electromagnetic waves propagating therebetween. In other embodiments, the transmission core 1852 may have a different construction than the feed point 1902. For example, in one embodiment the transmission core 1852 can comprise an insulated conductor, while the feed point 1902 comprises a dielectric material devoid of conductive materials.

As shown in FIG. 19J, the transmission core 1852 can be coupled to the flange 1942 via a center hole 1946, although in other embodiments it will be appreciated that such a hole could be off-centered as well. In one embodiment, the hole 1946 can be threaded and the transmission core 1852 can have a smooth surface. In this embodiment, the flange 1942 can engage the transmission core 1852 by inserting a portion of the transmission core 1852 into the hole 1946 and rotating the flange 1942 to act as a die to form complementary threads on the outer surface of the transmission core 1852. Once the transmission core 1852 has been threaded by or into the flange 1942, the portion of the transmission core 1852 extending from the flange 1942 can be shortened or lengthened by rotating the flange 1942 accordingly.

In other embodiments the transmission core 1852 can be pre-threaded with mating threads for engagement with the hole 1946 of the flange 1942 for improving the ease of engaging the transmission core 1852 with the flange 1942. In yet other embodiments, the transmission core 1852 can have a smooth surface and the hole 1946 of the flange 1942 can be non-threaded. In this embodiment, the hole 1946 can have a diameter that is similar to the diameter of the transmission core 1852 such as to cause the engagement of the transmission core 1852 to be held in place by frictional forces. It will be appreciated that there can be several other ways of engaging the transmission core 1852 with the flange 1942, including various clips, fusion, compression fittings, and the like. The feed point 1902 of the dielectric antenna 1901 can be engaged with the other side of the hole 1946 of the flange 1942 in the same manner as described for transmission core 1852.

A gap 1943 can exist between the transmission core 1852 and the feed point 1902. The gap 1943, however, can be adjusted in an embodiment by rotating the feed point 1902 while the transmission core 1852 is held in place or vice-versa. In some embodiments, the ends of the transmission core 1852 and the feed point 1902 engaged with the flange 1942 can be adjusted so that they touch, thereby removing the gap 1943. In other embodiments, the ends of the transmission core 1852 or the feed point 1902 engaged with the flange 1942 can intentionally be adjusted to create a specific gap size. The adjustability of the gap 1943 can provide another degree of freedom to tune the interface between the transmission core 1852 and the feed point 1902.

Although not shown in FIGS. 19P1-19P8, an opposite end of the transmission core 1852 of cable 1850 can be coupled to a waveguide device such as depicted in FIGS. 18S and 18T utilizing another flange 1942 and similar coupling techniques. The waveguide device can be used for transmitting and receiving electromagnetic waves along the transmission core 1852. Depending on the operational parameters of the electromagnetic waves (e.g., operating frequency, wave mode, etc.), the electromagnetic waves can propagate within the transmission core 1852, on an outer surface of the transmission core 1852, or partly within the transmission core 1852 and the outer surface of the transmission core 1852. When the waveguide device is configured as a transmitter, the signals generated thereby induce electromagnetic waves that propagate along the transmission core 1852 and transition to the feed point 1902 at the junction therebetween. The electromagnetic waves then propagate from the feed point 1902 into the dielectric antenna 1901 becoming wireless signals at the aperture 1903 of the dielectric antenna 1901.

A frame 1982 can be used to surround all or at least a substantial portion of the outer surfaces of the dielectric antenna 1901 (except the aperture 1903) to improve trans-

mission or reception of and/or reduce leakage of the electromagnetic waves as they propagate towards the aperture **1903**. In some embodiments, a portion **1984** of the frame **1982** can extend to the feed point **1902** as shown in FIG. **19P2** to prevent leakage on the outer surface of the feed point **1902**. The frame **1982**, for example, can be constructed of materials (e.g., conductive or carbon materials) that reduce leakage of the electromagnetic waves. The shape of the frame **1982** can vary based on a shape of the dielectric antenna **1901**. For example, the frame **1852** can have a flared straight-surface shape as shown in FIGS. **19P1-19P4**. Alternatively, the frame **1852** can have a flared parabolic-surface shape as shown in FIGS. **19P5-19P8**. It will be appreciated that the frame **1852** can have other shapes.

The aperture **1903** can be of different shapes and sizes. In one embodiment, for example, the aperture **1903** can utilize a lens having a convex structure **1983** of various dimensions as shown in FIGS. **19P1**, **19P4**, and **19P6-19P8**. In other embodiments, the aperture **1903** can have a flat structure **1985** of various dimensions as shown in FIGS. **19P2** and **19P5**. In yet other embodiments, the aperture **1903** can utilize a lens having a pyramidal structure **1986** as shown in FIGS. **19P3** and **19Q1**. The lens of the aperture **1903** can be an integral part of the dielectric antenna **1901** or can be a component that is coupled to the dielectric antenna **1901** as shown in FIG. **19C**. Additionally, the lens of the aperture **1903** can be constructed with the same or a different material than the dielectric antenna **1902**. Also, in some embodiments, the aperture **1903** of the dielectric antenna **1901** can extend outside the frame **1982** as shown in FIGS. **19P7-19P8** or can be confined within the frame **1982** as shown in FIGS. **19P1-19P6**.

In one embodiment, the dielectric constant of the lens of the apertures **1903** shown in FIGS. **19P1-19P8** can be configured to be substantially similar or different from that of the dielectric antenna **1901**. Additionally, one or more internal portions of the dielectric antenna **1901**, such as section **1986** of FIG. **19P4**, can have a dielectric constant that differs from that of the remaining portions of the dielectric antenna. The surface of the lens of the apertures **1903** shown in FIGS. **19P1-19P8** can have a smooth surface or can have ridges such as shown in FIG. **19E** to reduce surface reflections of the electromagnetic waves as previously described.

Depending on the shape of the dielectric antenna **1901**, the frame **1982** can be of different shapes and sizes as shown in the front views depicted in FIGS. **19Q1**, **19Q2** and **19Q3**. For example, the frame **1982** can have a pyramidal shape as shown in FIG. **19Q1**. In other embodiments, the frame **1982** can have a circular shape as depicted in FIG. **19Q2**. In yet other embodiments, the frame **1982** can have an elliptical shape as depicted in FIG. **19Q3**.

The embodiments of FIGS. **19P1-19P8** and **19Q1-19Q3** can be combined in whole or in part with each other to create other embodiments contemplated by the subject disclosure. Additionally, the embodiments of FIGS. **19P1-19P8** and **19Q1-19Q3** can be combined with other embodiments of the subject disclosure. For example, the multi-antenna assembly of FIG. **20F** can be adapted to utilize any one of the embodiments of FIGS. **19P1-19P8** and **19Q1-19Q3**. Additionally, multiple instances of a multi-antenna assembly adapted to utilize one of the embodiments of FIGS. **19P1-19P8** **19Q1-19Q3** can be stacked on top of each other to form a phased array that functions similar to the phased array of FIG. **19O**. In other embodiments, absorption sheets **1932** can be added to the dielectric antenna **1901** as shown in FIG. **19I** to control the widths of near-field and far-field

signals. Other combinations of the embodiments of FIGS. **19P1-19P8** and **19Q1-19Q3** and the embodiments of the subject disclosure are contemplated.

Turning now to FIGS. **20A** and **20B**, block diagrams illustrating example, non-limiting embodiments of the cable **1850** of FIG. **18A** used for inducing guided electromagnetic waves on power lines supported by utility poles. In one embodiment, as depicted in FIG. **20A**, a cable **1850** can be coupled at one end to a microwave apparatus that launches guided electromagnetic waves within one or more inner layers of cable **1850** utilizing, for example, the hollow waveguide **1808** shown in FIGS. **18A-18C**. The microwave apparatus can utilize a microwave transceiver such as shown in FIG. **10A** for transmitting or receiving signals from cable **1850**. The guided electromagnetic waves induced in the one or more inner layers of cable **1850** can propagate to an exposed stub of the cable **1850** located inside a horn antenna (shown as a dotted line in FIG. **20A**) for radiating the electromagnetic waves via the horn antenna. The radiated signals from the horn antenna in turn can induce guided electromagnetic waves that propagate longitudinally on power line such as a medium voltage (MV) power line. In one embodiment, the microwave apparatus can receive AC power from a low voltage (e.g., 220V) power line. Alternatively, the horn antenna can be replaced with a stub antenna as shown in FIG. **20B** to induce guided electromagnetic waves that propagate longitudinally on a power line such as the MV power line or to transmit wireless signals to other antenna system(s).

In an alternative embodiment, the hollow horn antenna shown in FIG. **20A** can be replaced with a solid dielectric antenna such as the dielectric antenna **1901** of FIG. **19A**, or the pyramidal-shaped horn antenna **1901'** of FIG. **19N**. In this embodiment the horn antenna can radiate wireless signals directed to another horn antenna such as the bidirectional horn antennas **2040** shown in FIG. **20C**. In this embodiment, each horn antenna **2040** can transmit wireless signals to another horn antenna **2040** or receive wireless signals from the other horn antenna **2040** as shown in FIG. **20C**. Such an arrangement can be used for performing bidirectional wireless communications between antennas. Although not shown, the horn antennas **2040** can be configured with an electromechanical device to steer a direction of the horn antennas **2040**.

In alternate embodiments, first and second cables **1850A'** and **1850B'** can be coupled to the microwave apparatus and to a transformer **2052**, respectively, as shown in FIGS. **20A** and **20B**. The first and second cables **1850A'** and **1850B'** can be represented by, for example, cable **1820** or cable **1830** of FIGS. **18B** and **18C**, respectively, each having a conductive core. A first end of the conductive core of the first cable **1850A'** can be coupled to the microwave apparatus for propagating guided electromagnetic waves launched therein. A second end of the conductive core of the first cable **1850A'** can be coupled to a first end of a conductive coil of the transformer **2052** for receiving the guided electromagnetic waves propagating in the first cable **1850A'** and for supplying signals associated therewith to a first end of a second cable **1850B'** by way of a second end of the conductive coil of the transformer **2052**. A second end of the second cable **1850B'** can be coupled to the horn antenna of FIG. **20A** or can be exposed as a stub antenna of FIG. **20B** for inducing guided electromagnetic waves that propagate longitudinally on the MV power line.

In an embodiment where cable **1850**, **1850A'** and **1850B'** each comprise multiple instances of transmission mediums **1800**, **1820**, and/or **1830**, a poly-rod structure of antennas

1855 can be formed such as shown in FIG. **18K**. Each antenna **1855** can be coupled, for example, to a horn antenna assembly as shown in FIG. **20A** or a pie-pan antenna assembly (not shown) for radiating multiple wireless signals. Alternatively, the antennas **1855** can be used as stub antennas in FIG. **20B**. The microwave apparatus of FIGS. **20A-20B** can be configured to adjust the guided electromagnetic waves to beam steer the wireless signals emitted by the antennas **1855**. One or more of the antennas **1855** can also be used for inducing guided electromagnetic waves on a power line.

Turning now to FIG. **20C**, a block diagram of an example, non-limiting embodiment of a communication network **2000** in accordance with various aspects described herein is shown. In one embodiment, for example, the waveguide system **1602** of FIG. **16A** can be incorporated into network interface devices (NIDs) such as NIDs **2010** and **2020** of FIG. **20C**. A NID having the functionality of waveguide system **1602** can be used to enhance transmission capabilities between customer premises **2002** (enterprise or residential) and a pedestal **2004** (sometimes referred to as a service area interface or SAI).

In one embodiment, a central office **2030** can supply one or more fiber cables **2026** to the pedestal **2004**. The fiber cables **2026** can provide high-speed full-duplex data services (e.g., 1-100 Gbps or higher) to mini-DSLAMs **2024** located in the pedestal **2004**. The data services can be used for transport of voice, internet traffic, media content services (e.g., streaming video services, broadcast TV), and so on. In prior art systems, mini-DSLAMs **2024** typically connect to twisted pair phone lines (e.g., twisted pairs included in category 5e or Cat. 5e unshielded twisted-pair (UTP) cables that include an unshielded bundle of twisted pair cables, such as 24 gauge insulated solid wires, surrounded by an outer insulating sheath), which in turn connect to the customer premises **2002** directly. In such systems, DSL data rates taper off at 100 Mbps or less due in part to the length of legacy twisted pair cables to the customer premises **2002** among other factors.

The embodiments of FIG. **20C**, however, are distinct from prior art DSL systems. In the illustration of FIG. **20C**, a mini-DSLAM **2024**, for example, can be configured to connect to NID **2020** via cable **1850** (which can represent in whole or in part any of the cable embodiments described in relation to FIGS. **18A-18D** and **18F-18L** singly or in combination). Utilizing cable **1850** between customer premises **2002** and a pedestal **2004**, enables NIDs **2010** and **2020** to transmit and receive guided electromagnetic waves for uplink and downlink communications. Based on embodiments previously described, cable **1850** can be exposed to rain, or can be buried without adversely affecting electromagnetic wave propagation either in a downlink path or an uplink path so long as the electric field profile of such waves in either direction is confined at least in part or entirely within inner layers of cable **1850**. In the present illustration, downlink communications represents a communication path from the pedestal **2004** to customer premises **2002**, while uplink communications represents a communication path from customer premises **2002** to the pedestal **2004**. In an embodiment where cable **1850** comprises one of the embodiments of FIGS. **18G-18H**, cable **1850** can also serve the purpose of supplying power to the NID **2010** and **2020** and other equipment of the customer premises **2002** and the pedestal **2004**.

In customer premises **2002**, DSL signals can originate from a DSL modem **2006** (which may have a built-in router and which may provide wireless services such as WiFi to

user equipment shown in the customer premises **2002**). The DSL signals can be supplied to NID **2010** by a twisted pair phone **2008**. The NID **2010** can utilize the integrated waveguide **1602** to launch within cable **1850** guided electromagnetic waves **2014** directed to the pedestal **2004** on an uplink path. In the downlink path, DSL signals generated by the mini-DSLAM **2024** can flow through a twisted pair phone line **2022** to NID **2020**. The waveguide system **1602** integrated in the NID **2020** can convert the DSL signals, or a portion thereof, from electrical signals to guided electromagnetic waves **2014** that propagate within cable **1850** on the downlink path. To provide full duplex communications, the guided electromagnetic waves **2014** on the uplink can be configured to operate at a different carrier frequency and/or a different modulation approach than the guided electromagnetic waves **2014** on the downlink to reduce or avoid interference. Additionally, on the uplink and downlink paths, the guided electromagnetic waves **2014** are guided by a core section of cable **1850**, as previously described, and such waves can be configured to have a field intensity profile that confines the guided electromagnetic waves in whole or in part in the inner layers of cable **1850**. Although the guided electromagnetic waves **2014** are shown outside of cable **1850**, the depiction of these waves is for illustration purposes only. For this reason, the guided electromagnetic waves **2014** are drawn with "hash marks" to indicate that they are guided by the inner layers of cable **1850**.

On the downlink path, the integrated waveguide system **1602** of NID **2010** receives the guided electromagnetic waves **2014** generated by NID **2020** and converts them back to DSL signals conforming to the requirements of the DSL modem **2006**. The DSL signals are then supplied to the DSL modem **2006** via a set of twisted pair wires of phone line **2008** for processing. Similarly, on the uplink path, the integrated waveguide system **1602** of NID **2020** receives the guided electromagnetic waves **2014** generated by NID **2010** and converts them back to DSL signals conforming to the requirements of the mini-DSLAM **2024**. The DSL signals are then supplied to the mini-DSLAM **2024** via a set of twisted pair wires of phone line **2022** for processing. Because of the short length of phone lines **2008** and **2022**, the DSL modem **2008** and the mini-DSLAM **2024** can send and receive DSL signals between themselves on the uplink and downlink at very high speeds (e.g., 1 Gbps to 60 Gbps or more). Consequently, the uplink and downlink paths can in most circumstances exceed the data rate limits of traditional DSL communications over twisted pair phone lines.

Typically, DSL devices are configured for asymmetric data rates because the downlink path usually supports a higher data rate than the uplink path. However, cable **1850** can provide much higher speeds both on the downlink and uplink paths. With a firmware update, a legacy DSL modem **2006** such as shown in FIG. **20C** can be configured with higher speeds on both the uplink and downlink paths. Similar firmware updates can be made to the mini-DSLAM **2024** to take advantage of the higher speeds on the uplink and downlink paths. Since the interfaces to the DSL modem **2006** and mini-DSLAM **2024** remain as traditional twisted pair phone lines, no hardware change is necessary for a legacy DSL modem or legacy mini-DSLAM other than firmware changes and the addition of the NIDs **2010** and **2020** to perform the conversion from DSL signals to guided electromagnetic waves **2014** and vice-versa. The use of NIDs enables a reuse of legacy modems **2006** and mini-DSLAMs **2024**, which in turn can substantially reduce installation costs and system upgrades. For new construction, updated versions of mini-DSLAMs and DSL modems

can be configured with integrated waveguide systems to perform the functions described above, thereby eliminating the need for NIDs **2010** and **2020** with integrated waveguide systems. In this embodiment, an updated version of modem **2006** and updated version of mini-DSLAM **2024** would connect directly to cable **1850** and communicate via bidirectional guided electromagnetic wave transmissions, thereby averting a need for transmission or reception of DSL signals using twisted pair phone lines **2008** and **2022**.

In an embodiment where use of cable **1850** between the pedestal **2004** and customer premises **2002** is logistically impractical or costly, NID **2010** can be configured instead to couple to a cable **1850'** (similar to cable **1850** of the subject disclosure) that originates from a waveguide **108** on a utility pole **118**, and which may be buried in soil before it reaches NID **2010** of the customer premises **2002**. Cable **1850'** can be used to receive and transmit guided electromagnetic waves **2014'** between the NID **2010** and the waveguide **108**. Waveguide **108** can connect via waveguide **106**, which can be coupled to base station **104**. Base station **104** can provide data communication services to customer premises **2002** by way of its connection to central office **2030** over fiber **2026'**. Similarly, in situations where access from the central office **2026** to pedestal **2004** is not practical over a fiber link, but connectivity to base station **104** is possible via fiber link **2026'**, an alternate path can be used to connect to NID **2020** of the pedestal **2004** via cable **1850"** (similar to cable **1850** of the subject disclosure) originating from pole **116**. Cable **1850"** can also be buried before it reaches NID **2020**.

Turning now to FIGS. **20D-20F**, block diagrams of example, non-limiting embodiments of antenna mounts that can be used in the communication network **2000** of FIG. **20C** (or other suitable communication networks) in accordance with various aspects described herein are shown. In some embodiments, an antenna mount **2052** can be coupled to a medium voltage power line by way of an inductive power supply that supplies energy to one or more waveguide systems (not shown) integrated in the antenna mount **2052** as depicted in FIG. **20D**. The antenna mount **2052** can include an array of dielectric antennas **1901** (e.g., **16** antennas) such as shown by the top and side views depicted in FIG. **20F**. The dielectric antennas **1901** shown in FIG. **20F** can be small in dimension as illustrated by a picture comparison between groups of dielectric antennas **1901** and a conventional ballpoint pen. In other embodiments, a pole mounted antenna **2054** can be used as depicted in FIG. **20D**. In yet other embodiments, an antenna mount **2056** can be attached to a pole with an arm assembly as shown in FIG. **20E**. In other embodiments, an antenna mount **2058**, depicted in FIG. **20E**, can be placed on a top portion of a pole coupled to a cable **1850** such as the cables as described in the subject disclosure.

The array of dielectric antennas **1901** in any of the antenna mounts of FIGS. **20D-20E** can include one or more waveguide systems as described in the subject disclosure by way of FIGS. **1-20**. The waveguide systems can be configured to perform beam steering with the array of dielectric antennas **1901** (for transmission or reception of wireless signals). Alternatively, each dielectric antenna **1901** can be utilized as a separate sector for receiving and transmitting wireless signals. In other embodiments, the one or more waveguide systems integrated in the antenna mounts of FIGS. **20D-20E** can be configured to utilize combinations of the dielectric antennas **1901** in a wide range of multi-input multi-output (MIMO) transmission and reception techniques. The one or more waveguide systems integrated in the antenna mounts of FIGS. **20D-20E** can also be config-

ured to apply communication techniques such as SISO, SIMO, MISO, SISO, signal diversity (e.g., frequency, time, space, polarization, or other forms of signal diversity techniques), and so on, with any combination of the dielectric antennas **1901** in any of the antenna mounts of FIGS. **20D-20E**. In yet other embodiments, the antenna mounts of FIGS. **20D-20E** can be adapted with two or more stacks of the antenna arrays shown in FIG. **20F**.

FIGS. **21A** and **21B** describe embodiments for downlink and uplink communications. Method **2100** of FIG. **21A** can begin with step **2102** where electrical signals (e.g., DSL signals) are generated by a DSLAM (e.g., mini-DSLAM **2024** of pedestal **2004** or from central office **2030**), which are converted to guided electromagnetic waves **2014** at step **2104** by NID **2020** and which propagate on a transmission medium such as cable **1850** for providing downlink services to the customer premises **2002**. At step **2108**, the NID **2010** of the customer premises **2002** converts the guided electromagnetic waves **2014** back to electrical signals (e.g., DSL signals) which are supplied at step **2110** to customer premises equipment (CPE) such as DSL modem **2006** over phone line **2008**. Alternatively, or in combination, power and/or guided electromagnetic waves **2014'** can be supplied from a power line **1850'** of a utility grid (having an inner waveguide as illustrated in FIG. **18G** or **18H**) to NID **2010** as an alternate or additional downlink (and/or uplink) path.

At step **2122** of method **2120** of FIG. **21B**, the DSL modem **2006** can supply electrical signals (e.g., DSL signals) via phone line **2008** to NID **2010**, which in turn at step **2124**, converts the DSL signals to guided electromagnetic waves directed to NID **2020** by way of cable **1850**. At step **2128**, the NID **2020** of the pedestal **2004** (or central office **2030**) converts the guided electromagnetic waves **2014** back to electrical signals (e.g., DSL signals) which are supplied at step **2129** to a DSLAM (e.g., mini-DSLAM **2024**). Alternatively, or in combination, power and guided electromagnetic waves **2014'** can be supplied from a power line **1850'** of a utility grid (having an inner waveguide as illustrated in FIG. **18G** or **18H**) to NID **2020** as an alternate or additional uplink (and/or downlink) path.

Turning now to FIG. **21C**, a flow diagram of an example, non-limiting embodiment of a method **2130** for inducing and receiving electromagnetic waves on a transmission medium is shown. At step **2132**, the waveguides **1865** and **1865'** of FIGS. **18N-18T** can be configured to generate first electromagnetic waves from a first communication signal (supplied, for example, by a communication device such as a base station), and induce at step **2134** the first electromagnetic waves with "only" a fundamental wave mode at an interface of the transmission medium. In an embodiment, the interface can be an outer surface of the transmission medium as depicted in FIGS. **18Q** and **18R**. In another embodiment, the interface can be an inner layer of the transmission medium as depicted in FIGS. **18S** and **18T**. At step **2136**, the waveguides **1865** and **1865'** of FIGS. **18N-18T** can be configured to receive second electromagnetic waves at an interface of a same or different transmission medium described in FIG. **21C**. In an embodiment, the second electromagnetic waves can have "only" a fundamental wave mode. In other embodiments, the second electromagnetic waves may have a combination of wave modes such as a fundamental and non-fundamental wave modes. At step **2138**, a second communication signal can be generated from the second electromagnetic waves for processing by, for example, a same or different communication device. The embodiments of FIGS. **21C** and **21D** can be applied to any embodiments described in the subject disclosure.

75

Turning now to FIG. 21D, a flow diagram of an example, non-limiting embodiment of a method 2140 for inducing and receiving electromagnetic waves on a transmission medium is shown. At step 2142, the waveguides 1865 and 1865' of FIGS. 18N-18W can be configured to generate first electromagnetic waves from a first communication signal (supplied, for example, by a communication device), and induce at step 2144 second electromagnetic waves with “only” a non-fundamental wave mode at an interface of the transmission medium. In an embodiment, the interface can be an outer surface of the transmission medium as depicted in FIGS. 18Q and 18R. In another embodiment, the interface can be an inner layer of the transmission medium as depicted in FIGS. 18S and 18T. At step 2146, the waveguides 1865 and 1865' of FIGS. 18N-18W can be configured to receive electromagnetic waves at an interface of a same or different transmission medium described in FIG. 21E. In an embodiment, the electromagnetic waves can have “only” a non-fundamental wave mode. In other embodiments, the electromagnetic waves may have a combination of wave modes such as a fundamental and non-fundamental wave modes. At step 2148, a second communication signal can be generated from the electromagnetic waves for processing by, for example, a same or different communication device. The embodiments of FIGS. 21E and 21F can be applied to any embodiments described in the subject disclosure.

FIG. 21E illustrates a flow diagram of an example, non-limiting embodiment of a method 2150 for radiating signals from a dielectric antenna such as those shown in FIGS. 19A and 19N. Method 2150 can begin with step 2152 where a transmitter such as waveguide system 1865' of FIG. 18T generates first electromagnetic waves including a first communication signal. The first electromagnetic waves in turn induce at step 2153 second electromagnetic waves on a core 1852 of a cable 1850 coupled to a feed point of any of the dielectric antenna described in the subject disclosure. The second electromagnetic waves are received at the feed point at step 2154 and propagate at step 2155 to a proximal portion of the dielectric antenna. At step 2156, the second electromagnetic waves continue to propagate from the proximal portion of the dielectric antenna to an aperture of the antenna and thereby cause at step 2157 wireless signals to be radiated as previously described in relation to FIGS. 19A-19N.

FIG. 21F illustrates a flow diagram of an example, non-limiting embodiment of a method 2160 for receiving wireless signals at a dielectric antenna such as the dielectric antennas of FIG. 19A or 19N. Method 2160 can begin with step 2161 where the aperture of the dielectric antenna receives wireless signals. At step 2162, the wireless signals induce electromagnetic waves that propagate from the aperture to the feed point of the dielectric antenna. The electromagnetic waves once received at the feed point at step 2163, propagate at step 2164 to the core of the cable coupled to the feed point. At step 2165, a receiver such as the waveguide system 1865' of FIG. 18T receives the electromagnetic waves and generates therefrom at step 2166 a second communication signal.

Methods 2150 and 2160 can be used to adapt the dielectric antennas of FIGS. 19A, 19C, 19E, 19G-19I, and 19L-19O for bidirectional wireless communications with other dielectric antennas such as the dielectric antennas 2040 shown in FIG. 20C, and/or for performing bidirectional wireless communications with other communication devices such as a portable communication devices (e.g., cell phones, tablets, laptops), wireless communication devices situated in a building (e.g., a residence), and so on. A microwave appa-

76

ratus such as shown in FIG. 20A can be configured with one or more cables 1850 that couple to a plurality of dielectric antennas 2040 as shown in FIG. 20C. In some embodiments, the dielectric antennas 2040 shown in FIG. 20C can be configured with yet more dielectric antennas (e.g., 19C, 19E, 19G-19I, and 19L-19O) to further expand the region of wireless communications by such antennas.

Methods 2150 and 2160 can be further adapted for use with the phased array 1976 of dielectric antennas 1901 of FIG. 19O by applying incremental phase delays to portions of the antennas to steer far-field wireless signals emitted. Methods 2150 and 2160 can also be adapted for adjusting the far-field wireless signals generated by the dielectric antenna 1901 and/or an orientation of the dielectric antenna 1901 utilizing the gimbal depicted in FIG. 19M (which may have controllable actuators) to improve reception of the far-field wireless signals by a remote system (such as another dielectric antenna 1901 coupled to a waveguide system). Additionally, the methods 2150 and 2160 can be adapted to receive instructions, messages or wireless signals from the remote system to enable the waveguide system receiving such signals by way of its dielectric antenna 1901 to perform adjustments of the far-field signals.

While for purposes of simplicity of explanation, the respective processes are shown and described as a series of blocks in FIGS. 21A-21F, it is to be understood and appreciated that the claimed subject matter is not limited by the order of the blocks, as some blocks may occur in different orders and/or concurrently with other blocks from what is depicted and described herein. Moreover, not all illustrated blocks may be required to implement the methods described herein.

FIG. 21G illustrates a flow diagram of an example, non-limiting embodiment of a method 2170 for detecting and mitigating disturbances occurring in a communication network, such as, for example, the system of FIGS. 16A and 16B. Method 2170 can begin with step 2172 where a network element, such as the waveguide system 1602 of FIGS. 16A-16B, can be configured to monitor degradation of guided electromagnetic waves on an outer surface of a transmission medium, such as power line 1610. A signal degradation can be detected according to any number of factors including without limitation, a signal magnitude of the guided electromagnetic waves dropping below a certain magnitude threshold, a signal to noise ratio (SNR) dropping below a certain SNR threshold, a Quality of Service (QoS) dropping below one or more thresholds, a bit error rate (BER) exceeding a certain BER threshold, a packet loss rate (PLR) exceeding a certain PLR threshold, a ratio of reflected electromagnetic waves to forward electromagnetic waves exceeding a certain threshold, an unexpected change or alteration to a wave mode, a spectral change in the guided electromagnetic waves indicating an object or objects are causing a propagation loss or scattering of the guided electromagnetic waves (e.g., water accumulation on an outer surface of the transmission medium, a splice in the transmission medium, a broken tree limb, etc.), or any combinations thereof. A sensing device such as, the disturbance sensor 1604b of FIG. 16A, can be adapted to perform one or more of the above signal measurements and determine thereby whether the electromagnetic waves are experiencing signal degradation. Other sensing devices suitable for performing the above measurements are contemplated by the subject disclosure.

If signal degradation is detected at step 2174, the network element can proceed to step 2176 where it can determine which object or objects may be causing the degradation, and

once detected, report the detected object(s) to the network management system **1601** of FIGS. **16A-16B**. Object detection can be accomplished by spectral analysis or other forms of signal analysis, environmental analysis (e.g., barometric readings, rain detection, etc.), or other suitable techniques for detecting foreign objects that may adversely affect propagation of electromagnetic waves guided by the transmission medium. For example, the network element can be configured to generate spectral data derived from an electromagnetic wave received by the network element. The network element can then compare the spectral data to a plurality of spectral profiles stored in its memory. The plurality of spectral profiles can be pre-stored in a memory of the network element, and can be used to characterize or identify obstructions that may cause a propagation loss or signal degradation when such obstructions are present on an outer surface of the transmission medium.

For example, an accumulation of water on an outer surface of a transmission medium, such as a thin layer of water and/or water droplets, may cause a signal degradation in electromagnetic waves guided by the transmission medium that may be identifiable by a spectral profile comprising spectral data that models such an obstruction. The spectral profile can be generated in a controlled environment (such as a laboratory or other suitable testing environment) by collecting and analyzing spectral data generated by test equipment (e.g., a waveguide system with spectrum analysis capabilities) when receiving electromagnetic waves over an outer surface of a transmission medium that has been subjected to water (e.g., simulated rain water). An obstruction such as water can generate a different spectral signature than other obstructions (e.g., a splice between transmission mediums). A unique spectral signature can be used to identify certain obstructions over others. With this technique, spectral profiles can be generated for characterizing other obstructions such as a fallen tree limb on the transmission medium, a splice, and so on. In addition to spectral profiles, thresholds can be generated for different metrics such as SNR, BER, PLR, and so on. These thresholds can be chosen by a service provider according to desired performance measures for a communication network that utilizing guided electromagnetic waves for transport of data. Some obstructions may also be detected by other methods. For example, rain water may be detected by a rain detector coupled to a network element, fallen tree limbs may be detected by a vibration detector coupled to the network element, and so on.

If a network element does not have access to equipment to detect objects that may be causing a degradation of electromagnetic waves, then the network element can skip step **2176** and proceed to step **2178** where it notifies one or more neighboring network elements (e.g., other waveguide system(s) **1602** in a vicinity of the network element) of the detected signal degradation. If signal degradation is significant, the network element can resort to a different medium for communicating with neighboring network element(s), such as, for example, wireless communications. Alternatively, the network element can substantially reduce the operating frequency of the guided electromagnetic waves (e.g., from 40 GHz to 1 GHz), or communicate with neighboring network elements utilizing other guided electromagnetic waves operating at a low frequency, such as a control channel (e.g., 1 MHz). A low frequency control channel may be much less susceptible to interference by the object(s) causing the signal degradation at much higher operating frequencies.

Once an alternate means of communication is established between network elements, at step **2180** the network element and neighboring network elements can coordinate a process to adjust the guided electromagnetic waves to mitigate the detected signal degradation. The process can include, for example, a protocol for choosing which of the network elements will perform the adjustments to the electromagnetic waves, the frequency and magnitude of adjustments, and goals to achieve a desired signal quality (e.g., QoS, BER, PLR, SNR, etc.). If, for example, the object causing the signal degradation is water accumulation on the outer surface of the transmission medium, the network elements can be configured to adjust a polarization of the electrical fields (e-fields) and/or magnetic fields (h-fields) of the electromagnetic waves to attain a radial alignment of the e-fields as shown in FIG. **21H**. In particular, FIG. **21H** presents a block diagram **2101** illustrating an example, non-limiting embodiment of an alignment of e-fields of an electromagnetic wave to mitigate propagation losses due to water accumulation on a transmission medium in accordance with various aspects described herein. In this example, the longitudinal section of a cable, such as an insulated metal cable implementation of transmission medium **125**, is presented along with field vectors that illustrate the e-fields associated with guided electromagnetic waves that propagate at 40 GHz. Stronger e-fields are presented by darker field vectors relative to weaker e-fields.

In one embodiment, an adjustment in polarization can be accomplished by generating a specific wave mode of the electromagnetic waves (e.g., transverse magnetic (TM) mode, transverse electric (TE) mode, transverse electromagnetic (TEM) mode, or a hybrid of a TM mode and TE mode also known as an HE mode). Assuming, for example, that the network element comprises the waveguide system **1865'** of FIG. **18W**, an adjustment in a polarization of e-fields can be accomplished by configuring two or more MMIC's **1870** to alter a phase, frequency, amplitude or combinations thereof of the electromagnetic waves generated by each MMIC **1870**. Certain adjustments may cause, for example, the e-fields in the region of the water film shown in FIG. **21H** to align perpendicularly to the surface of the water. Electric fields that are perpendicular (or approximately perpendicular) to the surface of water will induce weaker currents in the water film than e-fields parallel to the water film. By inducing weaker currents, the electromagnetic waves propagating longitudinally will experience less propagation loss. Additionally, it is also desirable for the concentration of the e-fields to extend above the water film into the air. If the concentration of e-fields in the air remains high and the majority of the total field strength is in the air instead of being concentrated in the region of the water and the insulator, then propagation losses will also be reduced. For example, e-fields of electromagnetic waves that are tightly bound to an insulation layer such as, Goubau waves (or TM₀₀ waves-see block diagram **2131** of FIG. **21K**), will experience higher propagation losses even though the e-fields may be perpendicular (or radially aligned) to the water film because more of the field strength is concentrated in the region of the water.

Accordingly, electromagnetic waves with e-fields perpendicular (or approximately perpendicular) to a water film having a higher proportion of the field strength in a region of air (i.e., above the water film) will experience less propagation loss than tightly bound electromagnetic waves having more field strength in the insulating or water layers

or electromagnetic waves having e-fields in the direction of propagation within the region of the water film that generate greater losses.

FIG. 21H depicts, in a longitudinal view of an insulated conductor, e-field for TM01 electromagnetic waves operating at 40 GHz. FIGS. 21I and 21J, in contrast, depict cross-sectional views 2111 and 2121, respectively, of the insulated conductor of FIG. 21H illustrating the field strength of e-fields in the direction of propagation of the electromagnetic waves (i.e., e-fields directed out of the page of FIGS. 21I and 21J). The electromagnetic waves shown in FIGS. 21I and 21J have a TM01 wave mode at 45 GHz and 40 GHz, respectively. FIG. 21I shows that the intensity of the e-fields in the direction of propagation of the electromagnetic waves is high in a region between the outer surface of the insulation and the outer surface of the water film (i.e., the region of the water film). The high intensity is depicted by a light color (the lighter the color the higher the intensity of the e-fields directed out of the page). FIG. 21I illustrates that there is a high concentration of e-fields polarized longitudinally in the region of the water film, which causes high currents in the water film and consequently high propagation losses. Thus, under certain circumstances, electromagnetic waves at 45 GHz (having a TM01 wave mode) are less suitable to mitigate rain water or other obstructions located on the outer surface of the insulated conductor.

In contrast, FIG. 21J shows that the intensity of the e-fields in the direction of propagation of the electromagnetic waves is weaker in the region of the water film. The lower intensity is depicted by the darker color in the region of the water film. The lower intensity is a result of the e-fields being polarized mostly perpendicular or radial to the water film. The radially aligned e-fields also are highly concentrated in the region of air as shown in FIG. 21H. Thus, electromagnetic waves at 40 GHz (having a TM01 wave mode) produce e-fields that induce less current in the water film than 45 GHz waves with the same wave mode. Accordingly, the electromagnetic waves of FIG. 21J exhibit properties more suitable for reducing propagation losses due to a water film or droplets accumulating on an outer surface of an insulated conductor.

Since the physical characteristics of a transmission medium can vary, and the effects of water or other obstructions on the outer surface of the transmission medium may cause non-linear effects, it may not always be possible to precisely model all circumstances so as to achieve the e-field polarization and e-field concentration in air depicted in FIG. 21H on a first iteration of step 2182. To increase a speed of the mitigation process, a network element can be configured to choose from a look-up table at step 2186 a starting point for adjusting electromagnetic waves. In one embodiment, entries of the look-up table can be searched for matches to a type of object detected at step 2176 (e.g., rain water). In another embodiment, the look-up table can be searched for matches to spectral data derived from the affected electromagnetic wave received by the network elements. Table entries can provide specific parameters for adjusting electromagnetic waves (e.g., frequency, phase, amplitude, wave mode, etc.) to achieve at least a coarse adjustment that achieves similar e-field properties as shown in FIG. 21H. A coarse adjustment can serve to improve the likelihood of converging on a solution that achieves the desirable propagation properties previously discussed in relation to FIGS. 21H and 21J.

Once a coarse adjustment is made at step 2186, the network element can determine at step 2184 whether the adjustment has improved signal quality to a desirable target.

Step 2184 can be implemented by a cooperative exchange between network elements. For example, suppose the network element at step 2186 generates an adjusted electromagnetic wave according to parameters obtained from the look-up table and transmits the adjusted electromagnetic wave to a neighboring network element. At step 2184 the network element can determine whether the adjustment has improved signal quality by receiving feedback from a neighboring network element receiving the adjusted electromagnetic waves, analyzing the quality of the received waves according to agreed target goals, and providing the results to the network element. Similarly, the network element can test adjusted electromagnetic waves received from neighboring network elements and can provide feedback to the neighboring network elements including the results of the analysis. While a particular search algorithm is discussed above, other search algorithms such as a gradient search, genetic algorithm, global search or other optimization techniques can likewise be employed. Accordingly, steps 2182, 2186 and 2184 represent an adjustment and testing process performed by the network element and its neighbor(s).

With this in mind, if at step 2184 a network element (or its neighbors) determine that signal quality has not achieved one or more desired parametric targets (e.g., SNR, BER, PLR, etc.), then incremental adjustments can begin at step 2182 for each of the network element and its neighbors. At step 2182, the network element (and/or its neighbors) can be configured to adjust a magnitude, phase, frequency, wave mode and/or other tunable features of the electromagnetic waves incrementally until a target goal is achieved. To perform these adjustments, a network element (and its neighbors) can be configured with the waveguide system 1865' of FIG. 18W. The network element (and its neighbors) can utilize two or more MMIC's 1870 to incrementally adjust one or more operational parameters of the electromagnetic waves to achieve e-fields polarized in a particular direction (e.g., away from the direction of propagation in the region of the water film). The two or more MMIC's 1870 can also be configured to incrementally adjust one or more operational parameters of the electromagnetic waves that achieve e-fields having a high concentration in a region of air (outside the obstruction).

The iteration process can be a trial-and-error process coordinated between network elements to reduce a time for converging on a solution that improves upstream and downstream communications. As part of the coordination process, for example, one network element can be configured to adjust a magnitude but not a wave mode of the electromagnetic waves, while another network element can be configured to adjust the wave mode and not the magnitude. The number of iterations and combination of adjustments to achieve desirable properties in the electromagnetic waves to mitigate obstructions on an outer surface of a transmission medium can be established by a service provider according to experimentation and/or simulations and programmed into the network elements.

Once the network element(s) detect at step 2184 that signal quality of upstream and downstream electromagnetic waves has improved to a desirable level that achieves one or more parametric targets (e.g. SNR, BER, PLR, etc.), the network elements can proceed to step 2188 and resume communications according to the adjusted upstream and downstream electromagnetic waves. While communications take place at step 2188, the network elements can be configured to transmit upstream and downstream test signals based on the original electromagnetic waves to determine if the signal quality of such waves has improved. These test

signals can be transmitted at periodic intervals (e.g., once every 30 seconds or other suitable periods). Each network element can, for example, analyze spectral data of the received test signals to determine if they achieve a desirable spectral profile and/or other parametric target (e.g. SNR, BER, PLR, etc.). If the signal quality has not improved or has improved nominally, the network elements can be configured to continue communications at step **2188** utilizing the adjusted upstream and downstream electromagnetic waves.

If, however, signal quality has improved enough to revert back to utilizing the original electromagnetic waves, then the network element(s) can proceed to step **2192** to restore settings (e.g., original wave mode, original magnitude, original frequency, original phase, original spatial orientation, etc.) that produce the original electromagnetic waves. Signal quality may improve as a result of a removal of the obstruction (e.g., rain water evaporates, field personnel remove a fallen tree limb, etc.). At step **2194**, the network elements can initiate communications utilizing the original electromagnetic waves and perform upstream and downstream tests. If the network elements determine at step **2196** from tests performed at step **2194** that signal quality of the original electromagnetic waves is satisfactory, then the network elements can resume communications with the original electromagnetic waves and proceed to step **2172** and subsequent steps as previously described.

A successful test can be determined at step **2196** by analyzing test signals according to parametric targets associated with the original electromagnetic waves (e.g., BER, SNR, PLR, etc.). If the tests performed at step **2194** are determined to be unsuccessful at step **2196**, the network element(s) can proceed to steps **2182**, **2186** and **2184** as previously described. Since a prior adjustment to the upstream and downstream electromagnetic waves may have already been determined successfully, the network element(s) can restore the settings used for the previously adjusted electromagnetic waves. Accordingly, a single iteration of any one of steps **2182**, **2186** and **2184** may be sufficient to return to step **2188**.

It should be noted that in some embodiments restoring the original electromagnetic waves may be desirable if, for example, data throughput when using the original electromagnetic waves is better than data throughput when using the adjusted electromagnetic waves. However, when data throughput of the adjusted electromagnetic waves is better or substantially close to the data throughput of the original electromagnetic waves, the network element(s) may instead be configured to continue from step **2188**.

It is also noted that although FIGS. **21H** and **21K** describe a TM01 wave mode, other wave modes (e.g., HE waves, TE waves, TEM waves, etc.) or combination of wave modes may achieve the desired effects shown in FIG. **21H**. Accordingly, a wave mode singly or in combination with one or more other wave modes may generate electromagnetic waves with e-field properties that reduce propagation losses as described in relation to FIGS. **21H** and **21J**. Such wave modes are therefore contemplated as possible wave modes the network elements can be configured to produce.

It is further noted that method **2170** can be adapted to generate at steps **2182** or **2186** other wave modes that may not be subject to a cutoff frequency. For example, FIG. **21L** depicts a block diagram **2141** of an example, non-limiting embodiment of electric fields of a hybrid wave in accordance with various aspects described herein. Waves having an HE mode have linearly polarized e-fields which point away from a direction of propagation of electromagnetic

waves and can be perpendicular (or approximately perpendicular) to a region of obstruction (e.g., water film shown in FIGS. **21H-21J**). Waves with an HE mode can be configured to generate e-fields that extend substantially outside of an outer surface of an insulated conductor so that more of the total accumulated field strength is in air. Accordingly, some electromagnetic waves having an HE mode can exhibit properties of a large wave mode with e-fields orthogonal or approximately orthogonal to a region of obstruction. As described earlier, such properties can reduce propagation losses. Electromagnetic waves having an HE mode also have the unique property that they do not have a cutoff frequency (i.e., they can operate near DC) unlike other wave modes which have non-zero cutoff frequencies.

Turning now to FIG. **21M**, a block diagram **2151** illustrating an example, non-limiting embodiment of electric field characteristics of a hybrid wave versus a Goubau wave in accordance with various aspects described herein is shown. Diagram **2153** shows a distribution of energy between HE11 mode waves and Goubau waves for an insulated conductor. The energy plots of diagram **2153** assume that the amount of power used to generate the Goubau waves is the same as the HE11 waves (i.e., the area under the energy curves is the same). In the illustration of diagram **2153**, Goubau waves have a steep drop in power when Goubau waves extend beyond the outer surface of an insulated conductor, while HE11 waves have a substantially lower drop in power beyond the insulation layer. Consequently, Goubau waves have a higher concentration of energy near the insulation layer than HE11 waves. Diagram **2155** depicts similar Goubau and HE11 energy curves when a water film is present on the outer surface of the insulator. The difference between the energy curves of diagrams **2153** and **2155** is that the drop in power for the Goubau and the HE11 energy curves begins on an outer edge of the insulator for diagram **2153** and on an outer edge of the water film for diagram **2155**. The energy curves diagrams **2153** and **2155**, however, depict the same behavior. That is, the electric fields of Goubau waves are tightly bound to the insulation layer, which when exposed to water results in greater propagation losses than electric fields of HE11 waves having a higher concentration outside the insulation layer and the water film. These properties are depicted in the HE11 and Goubau diagrams **2157** and **2159**, respectively.

By adjusting an operating frequency of HE11 waves, e-fields of HE11 waves can be configured to extend substantially above a thin water film as shown in block diagram **2161** of FIG. **21N** having a greater accumulated field strength in areas in the air when compared to fields in the insulator and a water layer surrounding the outside of the insulator. FIG. **21N** depicts a wire having a radius of 1 cm and an insulation radius of 1.5 cm with a dielectric constant of 2.25. As the operating frequency of HE11 waves is reduced, the e-fields extend outwardly expanding the size of the wave mode. At certain operating frequencies (e.g., 3 GHz) the wave mode expansion can be substantially greater than the diameter of the insulated wire and any obstructions that may be present on the insulated wire.

By having e-fields that are perpendicular to a water film and by placing most of its energy outside the water film, HE11 waves have less propagation loss than Goubau waves when a transmission medium is subjected to water or other obstructions. Although Goubau waves have radial e-fields which are desirable, the waves are tightly coupled to the insulation layer, which results in the e-fields being highly concentrated in the region of an obstruction. Consequently, Goubau waves are still subject to high propagation losses

when an obstruction such as a water film is present on the outer surface of an insulated conductor.

Turning now to FIGS. 22A and 22B, block diagrams illustrating example, non-limiting embodiments of a waveguide system 2200 for launching hybrid waves in accordance with various aspects described herein is shown. The waveguide system 2200 can comprise probes 2202 coupled to a slideable or rotatable mechanism 2204 that enables the probes 2202 to be placed at different positions or orientations relative to an outer surface of an insulated conductor 2208. The mechanism 2204 can comprise a coaxial feed 2206 or other coupling that enables transmission of electromagnetic waves by the probes 2202. The coaxial feed 2206 can be placed at a position on the mechanism 2204 so that the path difference between the probes 2202 is one-half a wavelength or some odd integer multiple thereof. When the probes 2202 generate electromagnetic signals of opposite phase, electromagnetic waves can be induced on the outer surface of the insulated conductor 2208 having a hybrid mode (such as an HE₁₁ mode).

The mechanism 2204 can also be coupled to a motor or other actuator (not shown) for moving the probes 2202 to a desirable position. In one embodiment, for example, the waveguide system 2200 can comprise a controller that directs the motor to rotate the probes 2202 (assuming they are rotatable) to a different position (e.g., east and west) to generate electromagnetic waves that have a horizontally polarized HE₁₁ mode as shown in a block diagram 2300 of FIG. 23. To guide the electromagnetic waves onto the outer surface of the insulated conductor 2208, the waveguide system 2200 can further comprise a tapered horn 2210 shown in FIG. 22B. The tapered horn 2210 can be coaxially aligned with the insulated conductor 2208. To reduce the cross-sectional dimension of the tapered horn 2210, an additional insulation layer (not shown) can be placed on the insulated conductor 2208. The additional insulation layer can be similar to the tapered insulation layer 1879 shown in FIGS. 18Q and 18R. The additional insulation layer can have a tapered end that points away from the tapered horn 2210. The tapered insulation layer 1879 can reduce a size of an initial electromagnetic wave launched according to an HE₁₁ mode. As the electromagnetic waves propagate towards the tapered end of the insulation layer, the HE₁₁ mode expands until it reaches its full size as shown in FIG. 23. In other embodiments, the waveguide system 2200 may not need to use the tapered insulation layer 1879.

FIG. 23 illustrates that HE₁₁ mode waves can be used to mitigate obstructions such as rain water. For example, suppose that rain water has caused a water film to surround an outer surface of the insulated conductor 2208 as shown in FIG. 23. Further assume that water droplets have collected at the bottom of the insulated conductor 2208. As illustrated in FIG. 23, the water film occupies a small fraction of the total HE₁₁ wave. Also, by having horizontally polarized HE₁₁ waves, the water droplets are in a least-intense area of the HE₁₁ waves reducing losses caused by the droplets. Consequently, the HE₁₁ waves experience much lower propagation losses than Goubau waves or waves having a mode that is tightly coupled to the insulated conductor 2208 and thus greater energy in the areas occupied by the water.

It is submitted that the waveguide system 2200 of FIGS. 22A-22B can be replaced with other waveguide systems of the subject disclosure capable of generating electromagnetic waves having an HE mode. For example, the waveguide system 1865' of FIG. 18W can be configured to generate electromagnetic waves having an HE mode. In an embodiment, two or more MMIC's 1870 of the waveguide system

1865' can be configured to generate electromagnetic waves of opposite phase to generate polarized e-fields such as those present in an HE mode. In another embodiment, different pairs of MMIC's 1870 can be selected to generate HE waves that are polarized at different spatial positions (e.g., north and south, west and east, northwest and southeast, northeast and southeast, or other sub-fractional coordinates). Additionally, the waveguide systems of FIGS. 18N-18W can be configured to launch electromagnetic waves having an HE mode onto the core 1852 of one or more embodiments of cable 1850 suitable for propagating HE mode waves.

Although HE waves can have desirable characteristics for mitigating obstructions on a transmission medium, it is submitted that certain wave modes having a cutoff frequency (e.g., TE modes, TM modes, TEM modes or combinations thereof) may also exhibit waves that are sufficiently large and have polarized e-fields that are orthogonal (or approximately orthogonal) to a region of an obstruction enabling their use for mitigating propagation losses caused by the obstruction. Method 2070 can be adapted, for example, to generate such wave modes from a look-up table at step 2086. Wave modes having a cutoff frequency that exhibit, for example, a wave mode larger than the obstruction and polarized e-fields perpendicular (or approximately perpendicular) to the obstruction can be determined by experimentation and/or simulation. Once a combination of parameters (e.g., magnitude, phase, frequency, wave mode(s), spatial positioning, etc.) for generating one or more waves with cutoff frequencies having low propagation loss properties is determined, the parametric results for each wave can be stored in a look-up table in a memory of a waveguide system. Similarly, wave modes with cutoff frequencies exhibiting properties that reduce propagation losses can also be generated iteratively by any of the search algorithms previously described in the process of steps 2082-2084.

While for purposes of simplicity of explanation, the respective processes are shown and described as a series of blocks in FIG. 21G, it is to be understood and appreciated that the claimed subject matter is not limited by the order of the blocks, as some blocks may occur in different orders and/or concurrently with other blocks from what is depicted and described herein. Moreover, not all illustrated blocks may be required to implement the methods described herein.

FIG. 24 illustrates a flow diagram of an example, non-limiting embodiment of a method 2400 for sending and receiving electromagnetic waves. Method 2400 can be adapted for the waveguides 2522 shown in FIGS. 25A through 25C. Method 2400 can begin at step 2402 where a generator generates a first electromagnetic wave. At step 2404 a waveguide guides the first electromagnetic wave to an interface of a transmission medium, which in turn induces at step 2406 a second electromagnetic wave at the interface of the transmission medium. Steps 2402-2406 can be applied to the waveguides 2522 of FIGS. 25A, 25B and 25C. The generator can be an MMIC 1870 or slot 1863 as shown in FIGS. 18N through 18W. For illustration purposes only, the generator is assumed to be an MMIC 2524 positioned within the waveguide 2522 as shown in FIGS. 25A through 25C. Although FIGS. 25A through 25C illustrate in a longitudinal view of cylindrical waveguides 2522, the waveguides 2522 can be adapted to other structural shapes (e.g., square, rectangular, etc.).

Turning to the illustration of FIG. 25A, the waveguide 2522 covers a first region 2506 of a core 2528. Within the first region 2506, waveguide 2522 has an outer surface 2522A and an inner surface 2523. The inner surface 2523 of the waveguide 2522 can be constructed from a metallic

85

material, carbon, or other material that reflects electromagnetic waves and thereby enables the waveguide 2522 to be configured at step 2404 to guide the first electromagnetic wave 2502 towards the core 2528. The core 2528 can comprise a dielectric core (as described in the subject disclosure) that extends to the inner surface 2523 of the waveguide 2522. In other embodiments, the dielectric core can be surrounded by cladding (such as shown in FIG. 18A), whereby the cladding extends to the inner surface 2523 of the waveguide 2522. In yet other embodiments, the core 2528 can comprise an insulated conductor, where the insulation extends to the inner surface 2523 of the waveguide 2522. In this embodiment, the insulated conductor can be a power line, a coaxial cable, or other types of insulated conductors.

In the first region 2506, the core 2528 comprises an interface 2526 for receiving the first electromagnetic wave 2502. In one embodiment, the interface 2526 of the core 2528 can be configured to reduce reflections of the first electromagnetic wave 2502. In one embodiment, the interface 2526 can be a tapered structure to reduce reflections of the first electromagnetic wave 2502 from a surface of the core 2528. Other structures can be used for the interface 2526. For example, the interface 2526 can be partially tapered with a rounded point. Accordingly, any structure, configuration, or adaptation of the interface 2526 that can reduce reflections of the first electromagnetic wave 2502 is contemplated by the subject disclosure. At step 2406, the first electromagnetic wave 2502 induces (or otherwise generates) a second electromagnetic wave 2504 that propagates within the core 2528 in the first region 2506 covered by the waveguide 2522. The inner surface 2523 of the waveguide 2522 confines the second electromagnetic wave 2504 within the core 2528.

A second region 2508 of the core 2528 is not covered by the waveguide 2522, and is thereby exposed to the environment (e.g., air). In the second region 2508, the second electromagnetic wave 2504 expands outwardly beginning from the discontinuity between the edge of the waveguide 2522 and the exposed core 2528. To reduce the radiation into the environment from the second electromagnetic wave 2504, the core 2528 can be configured to have a tapered structure 2520. As the second electromagnetic wave 2504 propagates along the tapered structure 2520, the second electromagnetic wave 2504 remains substantially bound to the tapered structure 2520 thereby reducing radiation losses. The tapered structure 2520 ends at a transition from the second region 2508 to a third region 2510. In the third region, the core has a cylindrical structure 2529 having a diameter equal to the endpoint of the tapered structure 2520 at the juncture between the second region 2508 and the third region 2510. In the third region 2510 of the core 2528, the second electromagnetic wave 2504 experiences a low propagation loss. In one embodiment, this can be accomplished by selecting a diameter of the core 2528 that enables the second electromagnetic wave 2504 to be loosely bound to the outer surface of the core 2528 in the third region 2510. Alternatively, or in combination, propagation losses of the second electromagnetic wave 2504 can be reduced by configuring the MMIC's 2524 to adjust a wave mode, wave length, operating frequency, or other operational parameter of the first electromagnetic wave 2502.

FIG. 25D illustrates a portion of the waveguide 2522 of FIG. 25A depicted as a cylindrical ring (that does not show the MMIC's 2524 or the tapered structure 2526 of FIG. 25A). In the simulations, a first electromagnetic wave is injected at the endpoint of the core 2528 shown in FIG. 25D.

86

The simulation assumes no reflections of the first electromagnetic wave based on an assumption that a tapered structure 2526 (or other suitable structure) is used to reduce such reflections. The simulations are shown as two longitudinal cross-sectional views of the core 2528 covered in part by waveguide section 2522A, and an orthogonal cross-sectional view of the core 2528. In the case of the longitudinal cross-sectional views, one of the illustrations is a blown up view of a portion of the first illustration.

As can be seen from the simulations, electromagnetic wave fields 2532 of the second electromagnetic wave 2504 are confined within the core 2528 by the inner surface 2523 of the waveguide section 2522A. As the second electromagnetic wave 2504 enters the second region 2508 (no longer covered by the waveguide section 2522A), the tapered structure 2520 reduces radiation losses of the electromagnetic wave fields 2532 as it expands over the outer tapered surface of the core 2528. As the second electromagnetic wave 2504 enters the third region 2510, the electromagnetic wave fields 2532 stabilize and thereafter remain loosely coupled to the core 2528 (depicted in the longitudinal and orthogonal cross-sectional views), which reduces propagation losses.

FIG. 25B provides an alternative embodiment to the tapered structure 2520 in the second region 2508. The tapered structure 2520 can be avoided by extending the waveguide 2522 into the second region 2508 with a tapered structure 2522B and maintaining the diameter of the core 2528 throughout the first, second and third regions 2506, 2508 and 2510 of the core 2528 as depicted in FIG. 25B. The horn structure 2522B can be used to reduce radiation losses of the second electromagnetic wave 2504 as the second electromagnetic wave 2504 transitions from the first region 2506 to the second region 2508. In the third region 2510, the core 2528 is exposed to the environment. As noted earlier, the core 2528 is configured in the third region 2510 to reduce propagation losses by the second electromagnetic wave 2504. In one embodiment, this can be accomplished by selecting a diameter of the core 2528 that enables the second electromagnetic wave 2504 to be loosely bound to the outer surface of the core 2528 in the third region 2510. Alternatively, or in combination, propagation losses of the second electromagnetic wave 2504 can be reduced by adjusting a wave mode, wave length, operating frequency, or other performance parameter of the first electromagnetic wave 2502.

The waveguides 2522 of FIGS. 25A and 25B can also be adapted for receiving electromagnetic waves. For example, the waveguide 2522 of FIG. 25A can be adapted to receive an electromagnetic wave at step 2412. This can be represented by an electromagnetic wave 2504 propagating in the third region 2510 from east to west (orientation shown at bottom right of FIGS. 25A-25B) towards the second region 2508. Upon reaching the second region 2508, the electromagnetic wave 2504 gradually becomes more tightly coupled to the tapered structure 2520. When it reaches the boundary between the second region 2508 and the first region 2506 (i.e., the edge of the waveguide 2522), the electromagnetic wave 2504 propagates within the core 2528 confined by the inner surface 2523 of the waveguide 2522. Eventually the electromagnetic wave 2504 reaches an endpoint of the tapered interface 2526 of the core 2528 and radiates as a new electromagnetic wave 2502 which is guided by the inner surface 2523 of the waveguide 2522.

One or more antennas of the MMIC's 2524 can be configured to receive the electromagnetic wave 2502 thereby converting the electromagnetic wave 2502 to an

electrical signal at step 2414 which can be processed by a processing device (e.g., a receiver circuit and microprocessor). To prevent interference between electromagnetic waves transmitted by the MMIC's 2524, a remote waveguide system that transmitted the electromagnetic wave 2504 that is received by the waveguide 2522 of FIG. 25A can be adapted to transmit the electromagnetic wave 2504 at a different operating frequency, different wave mode, different phase, or other adjustable operational parameter to avoid interference. Electromagnetic waves can be received by the waveguide 2522 of FIG. 25B in a similar manner as described above.

Turning now to FIG. 25C, the waveguide 2522 of FIG. 25B can be adapted to support transmission mediums 2528 that have no endpoints such as shown in FIG. 25C. In this illustration, the waveguide 2522 comprises a chamber 2525 in a first region 2506 of the core 2528. The chamber 2525 creates a gap 2527 between an outer surface 2521 of the core 2528 and the inner surface 2523 of the waveguide 2522. The gap 2527 provides sufficient room for placement of the MMIC's 2524 on the inner surface 2523 of the waveguide 2522. To enable the waveguide 2522 to receive electromagnetic waves from either direction, the waveguide 2522 can be configured with symmetrical regions: 2508 and 2508', 2510 and 2510', and 2512, and 2512'. In the first region 2506, the chamber 2525 of the waveguide 2522 has two tapered structures 2522B' and 2522B. These tapered structures 2522B' and 2522B enable an electromagnetic wave to gradually enter or exit the chamber 2525 from either direction of the core 2528. The MMIC's 2524 can be configured with directional antennas to launch a first electromagnetic wave 2502 directed from east-to-west or from west-to-east in relation to the longitudinal view of the core 2528. Similarly, the directional antennas of the MMIC's 2524 can be configured to receive an electromagnetic waves propagating longitudinally on the core 2528 from east-to-west or from west-to-east. The process for transmitting electromagnetic waves is similar to that described for FIG. 25B depending on whether the directional antennas of the MMIC's 2524 are transmitting from east-to-west or from west-to-east.

Although not shown, the waveguide 2522 of FIG. 25C can be configured with a mechanism such as one or more hinges that enable splitting the waveguide 2522 into two parts that can be separated. The mechanism can be used to enable installation of the waveguide 2522 onto a core 2528 without endpoints. Other mechanisms for installation of the waveguide 2522 of FIG. 25C on a core 2528 are contemplated by the subject disclosure. For example, the waveguide 2522 can be configured with a slot opening that spans the entire waveguide structure longitudinally. In a slotted design of the waveguide 2522, the regions 2522C' and 2522C of the waveguide 2522 can be configured so that the inner surface 2523 of the waveguide 2522 is tightly coupled to the outer surface of the core 2528. The tight coupling between the inner surface 2523 of the waveguide 2522 the outer surface of the core 2528 prevents sliding or movement of the waveguide 2522 relative to the core 2528. A tight coupling in the regions 2522C' and 2522C can also be applied to a hinged design of the waveguide 2522.

The waveguides 2522 shown in FIGS. 25A, 25B and 25C can be adapted to perform one or more embodiments described in other figures of the subject disclosure. Accordingly, it is contemplated that such embodiments can be applied to the waveguide 2522 of FIGS. 25A, 25B and 25C.

Additionally, any adaptations in the subject disclosure of a core can be applied to the waveguide 2522 of FIGS. 25A, 25B and 25C.

While for purposes of simplicity of explanation, the respective processes are shown and described as a series of blocks in FIG. 24, it is to be understood and appreciated that the claimed subject matter is not limited by the order of the blocks, as some blocks may occur in different orders and/or concurrently with other blocks from what is depicted and described herein. Moreover, not all illustrated blocks may be required to implement the methods described herein.

Referring now to FIG. 26, there is illustrated a block diagram of a computing environment in accordance with various aspects described herein. In order to provide additional context for various embodiments of the embodiments described herein, FIG. 26 and the following discussion are intended to provide a brief, general description of a suitable computing environment 2600 in which the various embodiments of the subject disclosure can be implemented. While the embodiments have been described above in the general context of computer-executable instructions that can run on one or more computers, those skilled in the art will recognize that the embodiments can be also implemented in combination with other program modules and/or as a combination of hardware and software.

Generally, program modules comprise routines, programs, components, data structures, etc., that perform particular tasks or implement particular abstract data types. Moreover, those skilled in the art will appreciate that the inventive methods can be practiced with other computer system configurations, comprising single-processor or multiprocessor computer systems, minicomputers, mainframe computers, as well as personal computers, hand-held computing devices, microprocessor-based or programmable consumer electronics, and the like, each of which can be operatively coupled to one or more associated devices.

As used herein, a processing circuit includes processor as well as other application specific circuits such as an application specific integrated circuit, digital logic circuit, state machine, programmable gate array or other circuit that processes input signals or data and that produces output signals or data in response thereto. It should be noted that while any functions and features described herein in association with the operation of a processor could likewise be performed by a processing circuit.

The terms "first," "second," "third," and so forth, as used in the claims, unless otherwise clear by context, is for clarity only and doesn't otherwise indicate or imply any order in time. For instance, "a first determination," "a second determination," and "a third determination," does not indicate or imply that the first determination is to be made before the second determination, or vice versa, etc.

The illustrated embodiments of the embodiments herein can be also practiced in distributed computing environments where certain tasks are performed by remote processing devices that are linked through a communications network. In a distributed computing environment, program modules can be located in both local and remote memory storage devices.

Computing devices typically comprise a variety of media, which can comprise computer-readable storage media and/or communications media, which two terms are used herein differently from one another as follows. Computer-readable storage media can be any available storage media that can be accessed by the computer and comprises both volatile and nonvolatile media, removable and non-removable media. By way of example, and not limitation, computer-readable

storage media can be implemented in connection with any method or technology for storage of information such as computer-readable instructions, program modules, structured data or unstructured data.

Computer-readable storage media can comprise, but are not limited to, random access memory (RAM), read only memory (ROM), electrically erasable programmable read only memory (EEPROM), flash memory or other memory technology, compact disk read only memory (CD-ROM), digital versatile disk (DVD) or other optical disk storage, magnetic cassettes, magnetic tape, magnetic disk storage or other magnetic storage devices or other tangible and/or non-transitory media which can be used to store desired information. In this regard, the terms “tangible” or “non-transitory” herein as applied to storage, memory or computer-readable media, are to be understood to exclude only propagating transitory signals per se as modifiers and do not relinquish rights to all standard storage, memory or computer-readable media that are not only propagating transitory signals per se.

Computer-readable storage media can be accessed by one or more local or remote computing devices, e.g., via access requests, queries or other data retrieval protocols, for a variety of operations with respect to the information stored by the medium.

Communications media typically embody computer-readable instructions, data structures, program modules or other structured or unstructured data in a data signal such as a modulated data signal, e.g., a carrier wave or other transport mechanism, and comprises any information delivery or transport media. The term “modulated data signal” or signals refers to a signal that has one or more of its characteristics set or changed in such a manner as to encode information in one or more signals. By way of example, and not limitation, communication media comprise wired media, such as a wired network or direct-wired connection, and wireless media such as acoustic, RF, infrared and other wireless media.

With reference again to FIG. 26, the example environment 2600 for transmitting and receiving signals via or forming at least part of a base station (e.g., base station devices 1504, macrocell site 1502, or base stations 1614) or central office (e.g., central office 1501 or 1611). At least a portion of the example environment 2600 can also be used for transmission devices 101 or 102. The example environment can comprise a computer 2602, the computer 2602 comprising a processing unit 2604, a system memory 2606 and a system bus 2608. The system bus 2608 couple's system components including, but not limited to, the system memory 2606 to the processing unit 2604. The processing unit 2604 can be any of various commercially available processors. Dual microprocessors and other multiprocessor architectures can also be employed as the processing unit 2604.

The system bus 2608 can be any of several types of bus structure that can further interconnect to a memory bus (with or without a memory controller), a peripheral bus, and a local bus using any of a variety of commercially available bus architectures. The system memory 2606 comprises ROM 2610 and RAM 2612. A basic input/output system (BIOS) can be stored in a non-volatile memory such as ROM, erasable programmable read only memory (EPROM), EEPROM, which BIOS contains the basic routines that help to transfer information between elements within the computer 2602, such as during startup. The RAM 2612 can also comprise a high-speed RAM such as static RAM for caching data.

The computer 2602 further comprises an internal hard disk drive (HDD) 2614 (e.g., EIDE, SATA), which internal hard disk drive 2614 can also be configured for external use in a suitable chassis (not shown), a magnetic floppy disk drive (FDD) 2616, (e.g., to read from or write to a removable diskette 2618) and an optical disk drive 2620, (e.g., reading a CD-ROM disk 2622 or, to read from or write to other high capacity optical media such as the DVD). The hard disk drive 2614, magnetic disk drive 2616 and optical disk drive 2620 can be connected to the system bus 2608 by a hard disk drive interface 2624, a magnetic disk drive interface 2626 and an optical drive interface 2628, respectively. The interface 2624 for external drive implementations comprises at least one or both of Universal Serial Bus (USB) and Institute of Electrical and Electronics Engineers (IEEE) 1394 interface technologies. Other external drive connection technologies are within contemplation of the embodiments described herein.

The drives and their associated computer-readable storage media provide nonvolatile storage of data, data structures, computer-executable instructions, and so forth. For the computer 2602, the drives and storage media accommodate the storage of any data in a suitable digital format. Although the description of computer-readable storage media above refers to a hard disk drive (HDD), a removable magnetic diskette, and a removable optical media such as a CD or DVD, it should be appreciated by those skilled in the art that other types of storage media which are readable by a computer, such as zip drives, magnetic cassettes, flash memory cards, cartridges, and the like, can also be used in the example operating environment, and further, that any such storage media can contain computer-executable instructions for performing the methods described herein.

A number of program modules can be stored in the drives and RAM 2612, comprising an operating system 2630, one or more application programs 2632, other program modules 2634 and program data 2636. All or portions of the operating system, applications, modules, and/or data can also be cached in the RAM 2612. The systems and methods described herein can be implemented utilizing various commercially available operating systems or combinations of operating systems. Examples of application programs 2632 that can be implemented and otherwise executed by processing unit 2604 include the diversity selection determining performed by transmission device 101 or 102.

A user can enter commands and information into the computer 2602 through one or more wired/wireless input devices, e.g., a keyboard 2638 and a pointing device, such as a mouse 2640. Other input devices (not shown) can comprise a microphone, an infrared (IR) remote control, a joystick, a game pad, a stylus pen, touch screen or the like. These and other input devices are often connected to the processing unit 2604 through an input device interface 2642 that can be coupled to the system bus 2608, but can be connected by other interfaces, such as a parallel port, an IEEE 1394 serial port, a game port, a universal serial bus (USB) port, an IR interface, etc.

A monitor 2644 or other type of display device can be also connected to the system bus 2608 via an interface, such as a video adapter 2646. It will also be appreciated that in alternative embodiments, a monitor 2644 can also be any display device (e.g., another computer having a display, a smart phone, a tablet computer, etc.) for receiving display information associated with computer 2602 via any communication means, including via the Internet and cloud-based networks. In addition to the monitor 2644, a computer

typically comprises other peripheral output devices (not shown), such as speakers, printers, etc.

The computer **2602** can operate in a networked environment using logical connections via wired and/or wireless communications to one or more remote computers, such as a remote computer(s) **2648**. The remote computer(s) **2648** can be a workstation, a server computer, a router, a personal computer, portable computer, microprocessor-based entertainment appliance, a peer device or other common network node, and typically comprises many or all of the elements described relative to the computer **2602**, although, for purposes of brevity, only a memory/storage device **2650** is illustrated. The logical connections depicted comprise wired/wireless connectivity to a local area network (LAN) **2652** and/or larger networks, e.g., a wide area network (WAN) **2654**. Such LAN and WAN networking environments are commonplace in offices and companies, and facilitate enterprise-wide computer networks, such as intranets, all of which can connect to a global communications network, e.g., the Internet.

When used in a LAN networking environment, the computer **2602** can be connected to the local network **2652** through a wired and/or wireless communication network interface or adapter **2656**. The adapter **2656** can facilitate wired or wireless communication to the LAN **2652**, which can also comprise a wireless AP disposed thereon for communicating with the wireless adapter **2656**.

When used in a WAN networking environment, the computer **2602** can comprise a modem **2658** or can be connected to a communications server on the WAN **2654** or has other means for establishing communications over the WAN **2654**, such as by way of the Internet. The modem **2658**, which can be internal or external and a wired or wireless device, can be connected to the system bus **2608** via the input device interface **2642**. In a networked environment, program modules depicted relative to the computer **2602** or portions thereof, can be stored in the remote memory/storage device **2650**. It will be appreciated that the network connections shown are example and other means of establishing a communications link between the computers can be used.

The computer **2602** can be operable to communicate with any wireless devices or entities operatively disposed in wireless communication, e.g., a printer, scanner, desktop and/or portable computer, portable data assistant, communications satellite, any piece of equipment or location associated with a wirelessly detectable tag (e.g., a kiosk, news stand, restroom), and telephone. This can comprise Wireless Fidelity (Wi-Fi) and BLUETOOTH® wireless technologies. Thus, the communication can be a predefined structure as with a conventional network or simply an ad hoc communication between at least two devices.

Wi-Fi can allow connection to the Internet from a couch at home, a bed in a hotel room or a conference room at work, without wires. Wi-Fi is a wireless technology similar to that used in a cell phone that enables such devices, e.g., computers, to send and receive data indoors and out; anywhere within the range of a base station. Wi-Fi networks use radio technologies called IEEE 802.11 (a, b, g, n, ac, ag etc.) to provide secure, reliable, fast wireless connectivity. A Wi-Fi network can be used to connect computers to each other, to the Internet, and to wired networks (which can use IEEE 802.3 or Ethernet). Wi-Fi networks operate in the unlicensed 2.4 and 5 GHz radio bands for example or with products that contain both bands (dual band), so the networks can provide real-world performance similar to the basic 10BaseT wired Ethernet networks used in many offices.

FIG. **27** presents an example embodiment **2700** of a mobile network platform **2710** that can implement and exploit one or more aspects of the disclosed subject matter described herein. In one or more embodiments, the mobile network platform **2710** can generate and receive signals transmitted and received by base stations (e.g., base station devices **1504**, macrocell site **1502**, or base stations **1614**), central office (e.g., central office **1501** or **1611**), or transmission device **101** or **102** associated with the disclosed subject matter. Generally, wireless network platform **2710** can comprise components, e.g., nodes, gateways, interfaces, servers, or disparate platforms, that facilitate both packet-switched (PS) (e.g., internet protocol (IP), frame relay, asynchronous transfer mode (ATM)) and circuit-switched (CS) traffic (e.g., voice and data), as well as control generation for networked wireless telecommunication. As a non-limiting example, wireless network platform **2710** can be included in telecommunications carrier networks, and can be considered carrier-side components as discussed elsewhere herein. Mobile network platform **2710** comprises CS gateway node(s) **2722** which can interface CS traffic received from legacy networks like telephony network(s) **2740** (e.g., public switched telephone network (PSTN), or public land mobile network (PLMN)) or a signaling system #7 (SS7) network **2770**. Circuit switched gateway node(s) **2722** can authorize and authenticate traffic (e.g., voice) arising from such networks. Additionally, CS gateway node(s) **2722** can access mobility, or roaming, data generated through SS7 network **2770**; for instance, mobility data stored in a visited location register (VLR), which can reside in memory **2730**. Moreover, CS gateway node(s) **2722** interfaces CS-based traffic and signaling and PS gateway node(s) **2718**. As an example, in a 3GPP UMTS network, CS gateway node(s) **2722** can be realized at least in part in gateway GPRS support node(s) (GGSN). It should be appreciated that functionality and specific operation of CS gateway node(s) **2722**, PS gateway node(s) **2718**, and serving node(s) **2716**, is provided and dictated by radio technology(ies) utilized by mobile network platform **2710** for telecommunication.

In addition to receiving and processing CS-switched traffic and signaling, PS gateway node(s) **2718** can authorize and authenticate PS-based data sessions with served mobile devices. Data sessions can comprise traffic, or content(s), exchanged with networks external to the wireless network platform **2710**, like wide area network(s) (WANs) **2750**, enterprise network(s) **2770**, and service network(s) **2780**, which can be embodied in local area network(s) (LANs), can also be interfaced with mobile network platform **2710** through PS gateway node(s) **2718**. It is to be noted that WANs **2750** and enterprise network(s) **2760** can embody, at least in part, a service network(s) like IP multimedia subsystem (IMS). Based on radio technology layer(s) available in technology resource(s) **2717**, packet-switched gateway node(s) **2718** can generate packet data protocol contexts when a data session is established; other data structures that facilitate routing of packetized data also can be generated. To that end, in an aspect, PS gateway node(s) **2718** can comprise a tunnel interface (e.g., tunnel termination gateway (TTG) in 3GPP UMTS network(s) (not shown)) which can facilitate packetized communication with disparate wireless network(s), such as Wi-Fi networks.

In embodiment **2700**, wireless network platform **2710** also comprises serving node(s) **2716** that, based upon available radio technology layer(s) within technology resource(s) **2717**, convey the various packetized flows of data streams received through PS gateway node(s) **2718**. It is to be noted

that for technology resource(s) **2717** that rely primarily on CS communication, server node(s) can deliver traffic without reliance on PS gateway node(s) **2718**; for example, server node(s) can embody at least in part a mobile switching center. As an example, in a 3GPP UMTS network, serving node(s) **2716** can be embodied in serving GPRS support node(s) (SGSN).

For radio technologies that exploit packetized communication, server(s) **2714** in wireless network platform **2710** can execute numerous applications that can generate multiple disparate packetized data streams or flows, and manage (e.g., schedule, queue, format . . .) such flows. Such application(s) can comprise add-on features to standard services (for example, provisioning, billing, customer support . . .) provided by wireless network platform **2710**. Data streams (e.g., content(s) that are part of a voice call or data session) can be conveyed to PS gateway node(s) **2718** for authorization/authentication and initiation of a data session, and to serving node(s) **2716** for communication thereafter. In addition to application server, server(s) **2714** can comprise utility server(s), a utility server can comprise a provisioning server, an operations and maintenance server, a security server that can implement at least in part a certificate authority and firewalls as well as other security mechanisms, and the like. In an aspect, security server(s) secure communication served through wireless network platform **2710** to ensure network's operation and data integrity in addition to authorization and authentication procedures that CS gateway node(s) **2722** and PS gateway node(s) **2718** can enact. Moreover, provisioning server(s) can provision services from external network(s) like networks operated by a disparate service provider; for instance, WAN **2750** or Global Positioning System (GPS) network(s) (not shown). Provisioning server(s) can also provision coverage through networks associated to wireless network platform **2710** (e.g., deployed and operated by the same service provider), such as the distributed antennas networks shown in FIG. 1(s) that enhance wireless service coverage by providing more network coverage. Repeater devices such as those shown in FIGS. 7, 8, and 9 also improve network coverage in order to enhance subscriber service experience by way of UE **2775**.

It is to be noted that server(s) **2714** can comprise one or more processors configured to confer at least in part the functionality of macro network platform **2710**. To that end, the one or more processor can execute code instructions stored in memory **2730**, for example. It is should be appreciated that server(s) **2714** can comprise a content manager **2715**, which operates in substantially the same manner as described hereinbefore.

In example embodiment **2700**, memory **2730** can store information related to operation of wireless network platform **2710**. Other operational information can comprise provisioning information of mobile devices served through wireless platform network **2710**, subscriber databases; application intelligence, pricing schemes, e.g., promotional rates, flat-rate programs, couponing campaigns; technical specification(s) consistent with telecommunication protocols for operation of disparate radio, or wireless, technology layers; and so forth. Memory **2730** can also store information from at least one of telephony network(s) **2740**, WAN **2750**, enterprise network(s) **2770**, or SS7 network **2760**. In an aspect, memory **2730** can be, for example, accessed as part of a data store component or as a remotely connected memory store.

In order to provide a context for the various aspects of the disclosed subject matter, FIG. 27, and the following discussion, are intended to provide a brief, general description of

a suitable environment in which the various aspects of the disclosed subject matter can be implemented. While the subject matter has been described above in the general context of computer-executable instructions of a computer program that runs on a computer and/or computers, those skilled in the art will recognize that the disclosed subject matter also can be implemented in combination with other program modules. Generally, program modules comprise routines, programs, components, data structures, etc. that perform particular tasks and/or implement particular abstract data types.

FIG. 28 depicts an illustrative embodiment of a communication device **2800**. The communication device **2800** can serve as an illustrative embodiment of devices such as mobile devices and in-building devices referred to by the subject disclosure (e.g., in FIGS. 15, 16A and 16B).

The communication device **2800** can comprise a wireline and/or wireless transceiver **2802** (herein transceiver **2802**), a user interface (UI) **2804**, a power supply **2814**, a location receiver **2816**, a motion sensor **2818**, an orientation sensor **2820**, and a controller **2806** for managing operations thereof. The transceiver **2802** can support short-range or long-range wireless access technologies such as Bluetooth®, ZigBee®, WiFi, DECT, or cellular communication technologies, just to mention a few (Bluetooth® and ZigBee® are trademarks registered by the Bluetooth® Special Interest Group and the ZigBee® Alliance, respectively). Cellular technologies can include, for example, CDMA-1X, UMTS/HSDPA, GSM/GPRS, TDMA/EDGE, EV/DO, WiMAX, SDR, LTE, as well as other next generation wireless communication technologies as they arise. The transceiver **2802** can also be adapted to support circuit-switched wireline access technologies (such as PSTN), packet-switched wireline access technologies (such as TCP/IP, VoIP, etc.), and combinations thereof.

The UI **2804** can include a depressible or touch-sensitive keypad **2808** with a navigation mechanism such as a roller ball, a joystick, a mouse, or a navigation disk for manipulating operations of the communication device **2800**. The keypad **2808** can be an integral part of a housing assembly of the communication device **2800** or an independent device operably coupled thereto by a tethered wireline interface (such as a USB cable) or a wireless interface supporting for example Bluetooth®. The keypad **2808** can represent a numeric keypad commonly used by phones, and/or a QWERTY keypad with alphanumeric keys. The UI **2804** can further include a display **2810** such as monochrome or color LCD (Liquid Crystal Display), OLED (Organic Light Emitting Diode) or other suitable display technology for conveying images to an end user of the communication device **2800**. In an embodiment where the display **2810** is touch-sensitive, a portion or all of the keypad **2808** can be presented by way of the display **2810** with navigation features.

The display **2810** can use touch screen technology to also serve as a user interface for detecting user input. As a touch screen display, the communication device **2800** can be adapted to present a user interface having graphical user interface (GUI) elements that can be selected by a user with a touch of a finger. The touch screen display **2810** can be equipped with capacitive, resistive or other forms of sensing technology to detect how much surface area of a user's finger has been placed on a portion of the touch screen display. This sensing information can be used to control the manipulation of the GUI elements or other functions of the user interface. The display **2810** can be an integral part of the housing assembly of the communication device **2800** or an

independent device communicatively coupled thereto by a tethered wireline interface (such as a cable) or a wireless interface.

The UI **2804** can also include an audio system **2812** that utilizes audio technology for conveying low volume audio (such as audio heard in proximity of a human ear) and high volume audio (such as speakerphone for hands free operation). The audio system **2812** can further include a microphone for receiving audible signals of an end user. The audio system **2812** can also be used for voice recognition applications. The UI **2804** can further include an image sensor **2813** such as a charged coupled device (CCD) camera for capturing still or moving images.

The power supply **2814** can utilize common power management technologies such as replaceable and rechargeable batteries, supply regulation technologies, and/or charging system technologies for supplying energy to the components of the communication device **2800** to facilitate long-range or short-range portable communications. Alternatively, or in combination, the charging system can utilize external power sources such as DC power supplied over a physical interface such as a USB port or other suitable tethering technologies.

The location receiver **2816** can utilize location technology such as a global positioning system (GPS) receiver capable of assisted GPS for identifying a location of the communication device **2800** based on signals generated by a constellation of GPS satellites, which can be used for facilitating location services such as navigation. The motion sensor **2818** can utilize motion sensing technology such as an accelerometer, a gyroscope, or other suitable motion sensing technology to detect motion of the communication device **2800** in three-dimensional space. The orientation sensor **2820** can utilize orientation sensing technology such as a magnetometer to detect the orientation of the communication device **2800** (north, south, west, and east, as well as combined orientations in degrees, minutes, or other suitable orientation metrics).

The communication device **2800** can use the transceiver **2802** to also determine a proximity to a cellular, WiFi, Bluetooth®, or other wireless access points by sensing techniques such as utilizing a received signal strength indicator (RSSI) and/or signal time of arrival (TOA) or time of flight (TOF) measurements. The controller **2806** can utilize computing technologies such as a microprocessor, a digital signal processor (DSP), programmable gate arrays, application specific integrated circuits, and/or a video processor with associated storage memory such as Flash, ROM, RAM, SRAM, DRAM or other storage technologies for executing computer instructions, controlling, and processing data supplied by the aforementioned components of the communication device **2800**.

Other components not shown in FIG. **28** can be used in one or more embodiments of the subject disclosure. For instance, the communication device **2800** can include a slot for adding or removing an identity module such as a Subscriber Identity Module (SIM) card or Universal Integrated Circuit Card (UICC). SIM or UICC cards can be used for identifying subscriber services, executing programs, storing subscriber data, and so on.

In the subject specification, terms such as “store,” “storage,” “data store,” “data storage,” “database,” and substantially any other information storage component relevant to operation and functionality of a component, refer to “memory components,” or entities embodied in a “memory” or components comprising the memory. It will be appreciated that the memory components described herein can be either volatile memory or nonvolatile memory, or can com-

prise both volatile and nonvolatile memory, by way of illustration, and not limitation, volatile memory, non-volatile memory, disk storage, and memory storage. Further, non-volatile memory can be included in read only memory (ROM), programmable ROM (PROM), electrically programmable ROM (EPROM), electrically erasable ROM (EEPROM), or flash memory. Volatile memory can comprise random access memory (RAM), which acts as external cache memory. By way of illustration and not limitation, RAM is available in many forms such as synchronous RAM (SRAM), dynamic RAM (DRAM), synchronous DRAM (SDRAM), double data rate SDRAM (DDR SDRAM), enhanced SDRAM (ESDRAM), Synchlink DRAM (SLDRAM), and direct Rambus RAM (DRRAM). Additionally, the disclosed memory components of systems or methods herein are intended to comprise, without being limited to comprising, these and any other suitable types of memory.

Moreover, it will be noted that the disclosed subject matter can be practiced with other computer system configurations, comprising single-processor or multiprocessor computer systems, mini-computing devices, mainframe computers, as well as personal computers, hand-held computing devices (e.g., PDA, phone, smartphone, watch, tablet computers, netbook computers, etc.), microprocessor-based or programmable consumer or industrial electronics, and the like. The illustrated aspects can also be practiced in distributed computing environments where tasks are performed by remote processing devices that are linked through a communications network; however, some if not all aspects of the subject disclosure can be practiced on stand-alone computers. In a distributed computing environment, program modules can be located in both local and remote memory storage devices.

Some of the embodiments described herein can also employ artificial intelligence (AI) to facilitate automating one or more features described herein. For example, artificial intelligence can be used in optional training controller **230** evaluate and select candidate frequencies, modulation schemes, MIMO modes, and/or guided wave modes in order to maximize transfer efficiency. The embodiments (e.g., in connection with automatically identifying acquired cell sites that provide a maximum value/benefit after addition to an existing communication network) can employ various AI-based schemes for carrying out various embodiments thereof. Moreover, the classifier can be employed to determine a ranking or priority of the each cell site of the acquired network. A classifier is a function that maps an input attribute vector, $x=(x_1, x_2, x_3, x_4, \dots, x_n)$, to a confidence that the input belongs to a class, that is, $f(x)=\text{confidence}(\text{class})$. Such classification can employ a probabilistic and/or statistical-based analysis (e.g., factoring into the analysis utilities and costs) to prognose or infer an action that a user desires to be automatically performed. A support vector machine (SVM) is an example of a classifier that can be employed. The SVM operates by finding a hypersurface in the space of possible inputs, which the hypersurface attempts to split the triggering criteria from the non-triggering events. Intuitively, this makes the classification correct for testing data that is near, but not identical to training data. Other directed and undirected model classification approaches comprise, e.g., naïve Bayes, Bayesian networks, decision trees, neural networks, fuzzy logic models, and probabilistic classification models providing different patterns of independence can be employed. Classification as used herein also is inclusive of statistical regression that is utilized to develop models of priority.

As will be readily appreciated, one or more of the embodiments can employ classifiers that are explicitly trained (e.g., via a generic training data) as well as implicitly trained (e.g., via observing UE behavior, operator preferences, historical information, receiving extrinsic information). For example, SVMs can be configured via a learning or training phase within a classifier constructor and feature selection module. Thus, the classifier(s) can be used to automatically learn and perform a number of functions, including but not limited to determining according to a predetermined criteria which of the acquired cell sites will benefit a maximum number of subscribers and/or which of the acquired cell sites will add minimum value to the existing communication network coverage, etc.

As used in some contexts in this application, in some embodiments, the terms “component,” “system” and the like are intended to refer to, or comprise, a computer-related entity or an entity related to an operational apparatus with one or more specific functionalities, wherein the entity can be either hardware, a combination of hardware and software, software, or software in execution. As an example, a component may be, but is not limited to being, a process running on a processor, a processor, an object, an executable, a thread of execution, computer-executable instructions, a program, and/or a computer. By way of illustration and not limitation, both an application running on a server and the server can be a component. One or more components may reside within a process and/or thread of execution and a component may be localized on one computer and/or distributed between two or more computers. In addition, these components can execute from various computer readable media having various data structures stored thereon. The components may communicate via local and/or remote processes such as in accordance with a signal having one or more data packets (e.g., data from one component interacting with another component in a local system, distributed system, and/or across a network such as the Internet with other systems via the signal). As another example, a component can be an apparatus with specific functionality provided by mechanical parts operated by electric or electronic circuitry, which is operated by a software or firmware application executed by a processor, wherein the processor can be internal or external to the apparatus and executes at least a part of the software or firmware application. As yet another example, a component can be an apparatus that provides specific functionality through electronic components without mechanical parts, the electronic components can comprise a processor therein to execute software or firmware that confers at least in part the functionality of the electronic components. While various components have been illustrated as separate components, it will be appreciated that multiple components can be implemented as a single component, or a single component can be implemented as multiple components, without departing from example embodiments.

Further, the various embodiments can be implemented as a method, apparatus or article of manufacture using standard programming and/or engineering techniques to produce software, firmware, hardware or any combination thereof to control a computer to implement the disclosed subject matter. The term “article of manufacture” as used herein is intended to encompass a computer program accessible from any computer-readable device or computer-readable storage/communications media. For example, computer readable storage media can include, but are not limited to, magnetic storage devices (e.g., hard disk, floppy disk, magnetic strips), optical disks (e.g., compact disk (CD), digital ver-

satile disk (DVD)), smart cards, and flash memory devices (e.g., card, stick, key drive). Of course, those skilled in the art will recognize many modifications can be made to this configuration without departing from the scope or spirit of the various embodiments.

In addition, the words “example” and “exemplary” are used herein to mean serving as an instance or illustration. Any embodiment or design described herein as “example” or “exemplary” is not necessarily to be construed as preferred or advantageous over other embodiments or designs. Rather, use of the word example or exemplary is intended to present concepts in a concrete fashion. As used in this application, the term “or” is intended to mean an inclusive “or” rather than an exclusive “or”. That is, unless specified otherwise or clear from context, “X employs A or B” is intended to mean any of the natural inclusive permutations. That is, if X employs A; X employs B; or X employs both A and B, then “X employs A or B” is satisfied under any of the foregoing instances. In addition, the articles “a” and “an” as used in this application and the appended claims should generally be construed to mean “one or more” unless specified otherwise or clear from context to be directed to a singular form.

Moreover, terms such as “user equipment,” “mobile station,” “mobile,” “subscriber station,” “access terminal,” “terminal,” “handset,” “mobile device” (and/or terms representing similar terminology) can refer to a wireless device utilized by a subscriber or user of a wireless communication service to receive or convey data, control, voice, video, sound, gaming or substantially any data-stream or signaling-stream. The foregoing terms are utilized interchangeably herein and with reference to the related drawings.

Furthermore, the terms “user,” “subscriber,” “customer,” “consumer” and the like are employed interchangeably throughout, unless context warrants particular distinctions among the terms. It should be appreciated that such terms can refer to human entities or automated components supported through artificial intelligence (e.g., a capacity to make inference based, at least, on complex mathematical formalisms), which can provide simulated vision, sound recognition and so forth.

As employed herein, the term “processor” can refer to substantially any computing processing unit or device comprising, but not limited to comprising, single-core processors; single-processors with software multithread execution capability; multi-core processors; multi-core processors with software multithread execution capability; multi-core processors with hardware multithread technology; parallel platforms; and parallel platforms with distributed shared memory. Additionally, a processor can refer to an integrated circuit, an application specific integrated circuit (ASIC), a digital signal processor (DSP), a field programmable gate array (FPGA), a programmable logic controller (PLC), a complex programmable logic device (CPLD), a discrete gate or transistor logic, discrete hardware components or any combination thereof designed to perform the functions described herein. Processors can exploit nano-scale architectures such as, but not limited to, molecular and quantum-dot based transistors, switches and gates, in order to optimize space usage or enhance performance of user equipment. A processor can also be implemented as a combination of computing processing units.

As used herein, terms such as “data storage,” “data storage,” “database,” and substantially any other information storage component relevant to operation and functionality of a component, refer to “memory components,” or entities embodied in a “memory” or components comprising

the memory. It will be appreciated that the memory components or computer-readable storage media, described herein can be either volatile memory or nonvolatile memory or can include both volatile and nonvolatile memory.

What has been described above includes mere examples of various embodiments. It is, of course, not possible to describe every conceivable combination of components or methodologies for purposes of describing these examples, but one of ordinary skill in the art can recognize that many further combinations and permutations of the present embodiments are possible. Accordingly, the embodiments disclosed and/or claimed herein are intended to embrace all such alterations, modifications and variations that fall within the spirit and scope of the appended claims. Furthermore, to the extent that the term “includes” is used in either the detailed description or the claims, such term is intended to be inclusive in a manner similar to the term “comprising” as “comprising” is interpreted when employed as a transitional word in a claim.

In addition, a flow diagram may include a “start” and/or “continue” indication. The “start” and “continue” indications reflect that the steps presented can optionally be incorporated in or otherwise used in conjunction with other routines. In this context, “start” indicates the beginning of the first step presented and may be preceded by other activities not specifically shown. Further, the “continue” indication reflects that the steps presented may be performed multiple times and/or may be succeeded by other activities not specifically shown. Further, while a flow diagram indicates a particular ordering of steps, other orderings are likewise possible provided that the principles of causality are maintained.

As may also be used herein, the term(s) “operably coupled to”, “coupled to”, and/or “coupling” includes direct coupling between items and/or indirect coupling between items via one or more intervening items. Such items and intervening items include, but are not limited to, junctions, communication paths, components, circuit elements, circuits, functional blocks, and/or devices. As an example of indirect coupling, a signal conveyed from a first item to a second item may be modified by one or more intervening items by modifying the form, nature or format of information in a signal, while one or more elements of the information in the signal are nevertheless conveyed in a manner than can be recognized by the second item. In a further example of indirect coupling, an action in a first item can cause a reaction on the second item, as a result of actions and/or reactions in one or more intervening items.

Although specific embodiments have been illustrated and described herein, it should be appreciated that any arrangement which achieves the same or similar purpose may be substituted for the embodiments described or shown by the subject disclosure. The subject disclosure is intended to cover any and all adaptations or variations of various embodiments. Combinations of the above embodiments, and other embodiments not specifically described herein, can be used in the subject disclosure. For instance, one or more features from one or more embodiments can be combined with one or more features of one or more other embodiments. In one or more embodiments, features that are positively recited can also be negatively recited and excluded from the embodiment with or without replacement by another structural and/or functional feature. The steps or functions described with respect to the embodiments of the subject disclosure can be performed in any order. The steps or functions described with respect to the embodiments of the subject disclosure can be performed alone or in combi-

nation with other steps or functions of the subject disclosure, as well as from other embodiments or from other steps that have not been described in the subject disclosure. Further, more than or less than all of the features described with respect to an embodiment can also be utilized.

What is claimed is:

1. A device, comprising:

a generator that facilitates generation of a first electromagnetic wave;

a core; and

a waveguide that facilitates guiding the first electromagnetic wave towards the core,

wherein the core comprises a first region and a second region,

wherein the core comprises an interface in the first region, wherein the first electromagnetic wave induces at the interface a second electromagnetic wave,

wherein the waveguide is configured to confine the second electromagnetic wave at least in part within the core in the first region,

wherein the second region of the core is located within the waveguide,

wherein a tapered section of the waveguide covering the second region is configured to reduce a radiation loss of the second electromagnetic wave as the second electromagnetic wave propagates and expands into the second region, and

wherein the core comprises a third region that is not located within the waveguide.

2. The device of claim 1, wherein the second electromagnetic wave propagates along the core in the third region and is directed to another device coupled to the core in the third region.

3. The device of claim 2, wherein the second electromagnetic wave has a first average propagation loss in the second region, wherein the second electromagnetic wave has a second average propagation loss in the third region, and wherein the first average propagation loss exceeds the second average propagation loss.

4. The device of claim 2, wherein the third region of the core is configured with a diameter to reduce a propagation loss of the second electromagnetic wave as the second electromagnetic wave propagates into the third region.

5. The device of claim 2, wherein the first region, the second region, and the third region of the core are configured with a same diameter.

6. The device of claim 1, wherein the interface is configured to reduce a reflection by the first electromagnetic wave at a surface of the interface.

7. The device of claim 1, wherein a surface of the interface comprises a tapered structure to reduce a reflection of the first electromagnetic wave at the surface of the interface.

8. The device of claim 1, wherein the interface comprises an outer surface of the core in the first region.

9. The device of claim 8, wherein the outer surface of the core in the first region is separated from an inner surface of the waveguide.

10. The device of claim 9, wherein a portion of the inner surface of the waveguide comprises a tapered structure to reduce a reflection by the first electromagnetic wave at the outer surface of the core.

11. The device of claim 1, wherein the core is a dielectric core coupled to a dielectric antenna for radiating a wireless signal.

12. The device of claim 1, wherein the generator comprises at least one transmitter located within the waveguide.

101

13. The device of claim 1, wherein the core comprises a non-conducting material or an insulated conductor.

14. A device, comprising:

a core; and

a waveguide that facilitates guiding a first electromagnetic wave towards the core, 5

wherein the core comprises a first region and a second region, the first region and the second region being located within the waveguide,

wherein the core comprises an interface in the first region, 10

wherein the waveguide is configured to confine a second electromagnetic wave induced by the first electromagnetic wave at the interface at least in part within the core in the first region,

wherein a tapered section of the waveguide covering the second region is configured to reduce a radiation loss of the second electromagnetic wave as the second electromagnetic wave propagates and expands into the second region, and 15

wherein the core comprises a third region that is not located within the waveguide. 20

15. The device of claim 14, wherein the waveguide is adapted for guiding electromagnetic waves, and further comprising a generator that facilitates generation of the first electromagnetic wave.

16. The device of claim 14, wherein a propagation loss of the second electromagnetic wave is reduced by adjusting a performance parameter of the first electromagnetic wave. 25

17. The device of claim 16, wherein the performance parameter comprises a wave mode, a wavelength, an operating frequency, or any combination thereof.

102

18. A device, comprising:

a core; and

a waveguide that facilitates guiding and receiving a first electromagnetic wave at an aperture of the waveguide,

wherein the core comprises a first region and a second region, wherein the first region and the second region are located within the waveguide, and wherein the aperture of the waveguide is located in the second region,

wherein the core comprises an interface in the first region,

wherein a tapered section of the waveguide covering the second region is configured to reduce a radiation loss of the first electromagnetic wave as the first electromagnetic wave propagates and expands into the first region,

wherein the waveguide is configured to confine the first electromagnetic wave at least in part within the first region,

wherein the first electromagnetic wave induces a second electromagnetic wave at the interface of the core in the first region, and

wherein the core comprises a third region that is not located within the waveguide.

19. The device of claim 18, further comprising an antenna in the first region and configured to receive the second electromagnetic wave. 25

20. The device of claim 18, wherein the interface of the core comprises a tapered structure.

* * * * *