Morokawa

* Mar. 31, 1981 [45]

[54]	VOLTAGE CONVERSION SYSTEM FOR ELECTRONIC TIMEPIECE			
[75]	Inventor:	Shigeru Morokawa, Higashiyamato, Japan		
[73]	Assignee:	Citizen Watch Co., Ltd., Tokyo, Japan		
[*]	Notice:	The portion of the term of this patent subsequent to Jun. 13, 1995, has been disclaimed.		
[21]	Appl. No.:	912,267		
[22]	Filed:	Jun. 5, 1978		
Related U.S. Application Data				
[62] Division of Ser. No. 726,013, Sep. 22, 1976.				
[30]	Foreign Application Priority Data			
Sep. 27, 1975 [JP] Japan 50-116620				
	U.S. Cl	H02M 7/00 363/60 arch 58/23 A, 23 BA; 363/60, 363/61, 62, 63		

U.S. PATENT DOCUMENTS				
3,708,742	1/1973	Gunn 363/62		
3,868,560	2/1975	Hoffman, Jr		
3,937,002	2/1976	Van Haaften 58/23 BA		
3,942,047	3/1976	Buchanan		
3,999,368	12/1976	Yoshida 58/23 BA		
4,033,110	7/1977	Sagarino 58/23 BA		
4,094,137	6/1978	Morokawa 58/23 BA X		

References Cited


Primary Examiner—William M. Shoop Attorney, Agent, or Firm-Jordan and Hamburg


ABSTRACT [57]

[56]

A voltage conversion system for an electronic timepiece having a power source as a lithium battery, which system generates power at lower voltage level than that of the power source for operating at least one of a frequency standard, a frequency converter, a time counter circuit and a display system. The voltage conversion system comprises an oscillator circuit coupled to the power source to generate output signals, a plurality of capacitors, and a plurality of switching elements responsive to the output signals for alternately setting the capacitors in a parallel connected condition and a series connected condition, whereby an output voltage lower than that of the power source is generated at an output terminal of the system.

28 Claims, 28 Drawing Figures








Fig. 3A




Fig. 3B




Fig. 4A

Mar 31, 1981




Fig. 4B





Fig. 7






Fig. 64




Fig. 6B







Fig. 6C










Fig. 9C







Fig. 9B










Fig. 10E

Mar 31, 1981




Fig. 11A





Fig. 11B



VOLTAGE CONVERSION SYSTEM FOR ELECTRONIC TIMEPIECE

This is a division of application Ser. No. 726,013, filed 5 Sept. 22, 1976.

This invention relates, in general, to electronic timepiece systems, and, more particularly, to electronic timepiece systems with low power consumption.

Until now, there has been an increasing trend 10 towards miniaturization in electronic timepieces, whose size is primarily determined by such elements as a crystal oscillator, pulse motor, display elements, and battery. Together with this trend, it is also true that the parket appeal of such a timepiece is appreciably affected 15 by its operating lifetime, before replacement or recharging of the battery must take place. This is primarily determined by the power required to drive such elements as a frequency divider, pulse motor and crystal oscillator, together with the leakage current of the bat- 20 tery itself. In the case of a mechanically driven display, the improvements which have taken place in the design of gearwheel mechanisms in recent years, together with more efficient designs of motors, have reduced the level of power required for display driving to as low as 1 μ w, 25 as compared with the level of 10 μ w required several years previously. In the case of an electronic timepiece utilizing a liquid crystal type display, the power required to drive the display is less than 0.5 μ w. Thus, if the power required for display driving were the only 30 factor is battery power consumption, it would be possible to use batteries of one tenth the capacity of those used previously or to have an operating lifetime of as long as ten years before battery replacement. However, at the present time, the power consumption in an elec- 35 tronic timepiece other than the power used in display driving is of the order 3 μ w to 1.5 μ w. Of this consumption, two thirds is required by the crystal oscillator circuit and one third for frequency divider circuits and other circuits. Thus, it can be reasonably stated that the 40 main obstacle to the recent trend towards timepieces of thinner shape and longer battery lifetime can be attributed to the various electronic circuits incorporated within the timepiece.

According to the present invention, power supply 45 systems may be incorporated within the timepiece circuitry so that power may be supplied to such circuits as the crystal oscillator and frequency dividers at a lower voltage than that of the battery. Thus, the power dissipated within such circuits is reduced by the reciprocal 50 of the square of the voltage reduction. If the voltage supplied is reduced to one half of the battery voltage, then the power consumption is proportional to a value of V^{-2} , i.e. one fourth of consumption when the full battery voltage is applied, or one twenty-fifth if the 55 voltage applied is reduced to one fifth of the battery voltage. Thus, by the system of the present invention, it becomes possible to design electronic timepieces which are thinner in size and have longer battery lifetime than conventional timepieces, due to having substantially 60 reduced power consumption.

To achieve the maximum degree of timekeeping accuracy in an electronic timepiece, it is necessary that the crystal oscillator which functions as a timekeeping frequency standard has negligible drift in frequency when 65 subjected to changes in temperature, or that such changes are cancelled by some means of compensation. With the present invention, it is also possible to incorpo-

2

rate such compensation means within the voltage conversion circuity, such that, in the case of a wristwatch, temperature changes of the case of the watch caused by contact with the wearer's body or by ambient air temperature fluctuations have virtually no effect upon time-keeping accuracy.

The present invention is highly suitable for application to a multifunction timepiece such as a multi-alarm type wristwatch, a calendar timepiece, etc. It is also suited to any application for which it is desirable to use two or more different voltages for different but related functions. For example, display of the results of a calculation can usually be performed utilizing signals of relatively low frequency, which can be generated efficiently using a low voltage power source. To perform the calculation itself at high speed, however, a source of relatively higher voltage will normally be required because of the higher frequencies involved. Thus, by enabling a high voltage supply to be switched to the circuitry section involved in calculation only when such calculations are actually performed, it is possible using the present invention to combine the advantages of high operational effectiveness with low power consumption.

It is therefore an object of the present invention to provide an improved electronic timepiece of low power consumption, achieved by level conversion of the voltage of the timepiece power source at a high level of efficiency.

It is another object of the present invention to provide an improved electronic timepiece in which compensation is provided for changes in the frequency of the crystal oscillator element used as a frequency standard for timekeeping, due to temperature variations.

It is another object of the present invention to provide an improved electronic timepiece in which the threshold voltages of semiconductor active circuit elements are used as a reference voltage in a power supply circuit such that variations in the threshold voltages of circuits due to processing variations in IC manufacturing process are compensated and current consumption is reduced to a small and desirable value.

It is still another object of the present invention to provide an improved electronic timepiece of thinner shape and longer battery operational lifetime than electronic timepieces of conventional design, which timepiece is simple in construction and low in manufacturing cost.

In the accompanying drawings, in which:

FIG. 1 is a block diagram of an electronic timepiece incorporating a voltage conversion system according to the present invention;

FIG. 2 is a detail circuit diagram of a preferred embodiment of the voltage conversion system shown in FIG. 1 to provide an output voltage which is one half of a battery voltage;

FIG. 3A is a partially detailed circuit diagram of another preferred embodiment of the voltage conversion system adapted to provide an output voltage of one third of the battery voltage;

FIG. 3B is a diagram showing a modification of the circuit of FIG. 3A, whereby the output impedance presented to the load is reduced;

FIG. 4A and 4B are simplified diagrams showing the basic functioning of the voltage conversion system;

FIG. 5 is a partially detailed circuit diagram of an example of a timepiece circuit in which voltage conver-

sion circuit together with a voltage stabilizer circuit are incorporated;

FIG. 6A is a block diagram showing another example of a timepiece circuit in which the voltage conversion system of the present invention is incorporated together 5 with a means of compensating any frequency drift of the crystal oscillator due to temperature changes;

FIG. 6B is a partial circuit diagram of a circuit to generate a signal proportional to the square of an input frequency, for use with the circuit of FIG. 6A;

FIGS. 6C and 6D are waveform diagrams for the circuit of FIG. 6B;

FIG. 7 is a detail circuit diagram of a level shifting circuit whereby signals produced in circuitry operated from a low supply voltage are level shifted for applica- 15 tion to circuitry operated from a higher voltage supply;

FIG. 8 is a partially detailed circuit diagram of a modification of the present invention whereby voltages of one half, one and one half and twice the battery voltage of the timepiece are produced for application to 20 a display driver unit;

FIG. 9A is a simplified diagram illustrating the arrangement of a liquid crystal display matrix;

FIG. 9B is a detail circuit diagram of a portion of a display drive circuit for a liquid crystal display;

FIG. 9C is a waveform diagram for the circuit of FIG. 9B;

FIGS. 10A and 10B are graphs illustrating the effects of voltages applied to electrochromic display elements;

FIG. 10C is a circuit diagram of an example of a 30 driver circuit for electrochromic display elements;

FIG. 10D is a circuit diagram of an example of a driver circuit for electrochromic display elements utilizing the voltage level conversion system of the present invention, and FIG. 10E is a waveform diagram for the 35 circuit of FIG. 9D;

FIG. 11A is a circuit diagram illustrating a method of applying the voltage conversion system of the present invention to a timepiece of an electro-mechanical transducer type; and

FIG. 11B is a waveform diagram for the circuit of FIG. 11A.

Referring now to FIG. 1 in which the thick lines indicate paths of energy flow while the thine lines indicate paths of signal flow, there is shown a block dia-45 gram of an electronic timepiece incorporating a voltage conversion system according to the present invention. As shown, the electronic timepiece generally comprises a power source 10, a voltage conversion system 12 including a signal generator circuit 14 and a voltage 50 converter circuit 16, a frequency standard 18, a frequency converter 20, a timekeeping counter 22, a level shifter circuit 24 and a display system 26. The power source 10 may comprise a silver oxide battery or a combination of a solar cell and rechargeable battery, for 55 example.

The signal generator circuit 14 comprises an auxiliary oscillator circuit adapted to provide an output signal, and a waveform shaping circuit coupled to the output of the oscillator circuit to provide output signals complementary to each other. The auxiliary oscillator circuit may comprise CMOS inverter stages connected as a ring oscillator. The waveform shaping circuit may comprise an inverter stage as will be described in detail hereinafter. The voltage converter circuit 16 contains a 65 number of switching elements which are synchronously driven by output signals from the waveform shaping circuit, to provide a reduced voltage of, for example,

one half of the output voltage of the power source 10 appearing on lead 17 as $V_{ss\frac{1}{2}}$. This voltage is supplied to the frequency standard 18, frequency converter 20 and timekeeping or time counter circuit 22, which are operated at a low voltage level.

The frequency standard 18 may comprise a crystal controlled oscillator circuit which oscillates at a frequency of, for example, 32,768 Hz. This relatively high frequency is supplied to the frequency converter 20 in the form of a divider which devide down the frequency from the standard 18 so that the output from the converter 20 is low frequency of, for example, 1 Hz. This signal is applied to the time counter circuit 22 which produces various output signals including time or calendar information. These output signals of small voltage amplitude are applied to the level shifter circuit 24, which is operated at a high voltage such as a supply voltage level of the power source 10. The level shifter circuit 24 functions to change the voltage level or amplitude of the various output signals from the time counter circuit 22 without changing the information carried thereby. It should be noted that the number of signal paths and the signal frequency applied to the level shifter circuit will vary in accordance with where level shifter circuit 24 is positioned. If it is placed previous to the timekeeping circuits, the power consumption is increased due to the higher frequency. On the other hand, if it is placed after the timekeeping circuits, power consumption is reduced but the number of the level shifter circuits is increased.

Time or other information held in the timekeeping counter 22 is displayed by the display system 26, which incorporates a display drive circuit and a display device.

FIG. 2 shows a preferred embodiment of the voltage conversion system shown in FIG. 1. As shown, the signal generator circuit 14 comprises an oscillator circuit 30 coupled to the battery 10 and operated at a supply voltage of 1.6 V, and a waveform shaping circuit 40 32 coupled to an output of the oscillator circuit 30. The oscillator circuit 30 comprises a plurality of stages of inverter circuits 31, 33 and 35 arranged in a ring configuration, each of which comprises a complementary pair of a P-channel metal oxide semiconductor field effect transistor (hereinafter referred to as a P-channel MOS-FET) 30a and an N-channel metal oxide semiconductor field effect transistor (hereinafter referred to as an Nchannel MOSFET) 30b connected between the positive supply line V_{DD} and the negative supply line V_{ss1} of the battery 10. The gate electrodes of the P-channel MOS-FET 30a and the N-channel MOSFET 30b are coupled together and connected to the output of the inverter circuit 35, i.e., the connected node of the drain electrode of the P-channel MOSFET 30"a and the drain electrode of the N-channel MOSFET 30"b. Likewise, the gate electrodes of the P-channel MOSFET 30'a and the N-channel MOSFET 30'b are coupled together and connected to the output of the inverter circuit 31, i.e., the connected node of the drain electrode of the Pchannel MOSFET 30a and the drain electrode of the N-channel MOSFET 30b. The gate electrodes of the P-channel MOSFET 30"a and the N-channel MOS-FET 30"b are coupled together and connected to the output of the inverter circuit 33, i.e., the connected node of the drain electrode of the P-channel MOSFET 30'a and the drain electrode of the N-channel MOSFET 30'b. As previously noted, the source electrodes of the P-channel MOSFETs 30a, 30'a and 30"a are coupled in

parallel to the positive supply line V_{DD} of the battery 10, while the source electrodes of the N-channel MOS-FETs 30b, 30b and 30b are coupled in parallel to the negative supply line V_{ss1} of the battery 10. The oscillator circuit 30 thus arranged will oscillate at a frequency between 100 and 1000 Hz to provide an output signal φο on lead 34. The current drain of the oscillator circuit 30 is between 0.1 μA and 0.01 μA . Low GM (mutual conductance) FETs are preferably used, for example, the P-channel FETs 30a, in order to reduce the current 10 which flows in each inverter stage during instants when both are turned on simultaneously, i.e. during voltage level transitions. The current drawn by the oscillator circuit may also be reduced by connecting it to the power source via a high value of resistance. The output 15 signal do on lead 34 applied to the waveform shaping circuit 32.

The waveform shaping circuit 32 comprises a plurality of stages of inverter circuits 36, 38 and 40, each of which comprises a complementary pair of a P-channel 20 MOSFET 32a and an N-channel MOSFET 32b. Waveform shaping of the output signal do from the oscillator circuit 30 is performed by the inverter circuit 36, whose output is applied to two series-connected inverter circuits 38 and 40. The outputs from the inverter circuits 25 38 and 40 are indicated as ϕ and $\overline{\phi}$, respectively, these signals being complementry to each other. Signals ϕ and ϕ are applied to the voltage converter circuit 16. It should be noted that it is not necessary to the present invention that signals ϕ and ϕ be precisely complemen- 30 tary. It is possible, for example, to apply an multi-phase signal to the voltage converter circuit, together with its inverse, by applying the outputs of adjacent inverters in the auxiliary oscillator circuit to a decoder circuit such as an exclusive OR circuit. This is because of the fact 35 that the output signals from odd-numbered inverters in the auxiliary oscillator circuit are of the same level but different in phase. For the voltage converter circuit of the embodiment shown in FIG. 2, however, a single phase pair of complementary signals are utilized by way 40 of example.

The voltage converter circuit 16 comprises a plurality of electric energy storage means 41, and a swtiching means 42 for alternately setting the plurality of electric energy storage means into a parallel connection condi- 45 tion and a series connection condition between the positive supply line V_{DD} and the negative supply line V_{ss1} in response to the output signals from the signal generator 14. In FIG. 2, the electric energy storage means 41 is shown as comprising a first capacitor C1 and a second 50 capacitor C2. The switching means 42 is composed of a plurality of switching elements, i.e., a complementary pair of a P-channel MOSFET 44 and an N-channel MOSFET 46, and first and second transmission gates 48 and 50, each composed of a P-channel MOSFET and an 55 N-channel MOSFET. The gate electrodes of the Pchannel MOSFET 44 and the N-channel MOSFET 46 are coupled together and connected to the output of the inverter circuit 38 of the waveform shaping circuit 32, to which control terminals of the transmission gates 48 60 and 50 are also connected. The source electrodes of the P-channel MOSFET 44 and the N-channel MOSFET 46 are coupled to the positive supply line V_{DD} and the negative supply line V_{ss1}, respectively. Th drain electrodes of the P-channel MOSFET 44 and the N-channel 65 MOSFET 46 are coupled together via the second capacitor C2. The first transmission gate 48 has an electrode coupled to the first capacitor C1 and the other

6

electrode coupled to the drain electrode of the P-channel MOSFET 44 and the second capacitor C₂. Similarly, the second transmission gate 50 has an electrode coupled to the first capacitor C₁ and the other electrode coupled to the second capacitor C₂ and the drain electrode of the N-channel MOSFET 46. The control terminals of the transmission gates 48 and 50 are coupled to the output of the inverter circuit 40 of the waveform shaping circuit 32.

With the arrangement mentioned above, when the output signal ϕ goes to a high logic level, the switching elements 46 and 48 are turned on whereas the switching elements 44 and 50 are turned off. Thus, the capacitors C_1 and C_2 become connected in series with each other across the power source 10. In this state capacitor C_1 and C_2 each will become charged and the sum of the charged voltage is equal to that of the power source 10. When, now, the output signal goes to a low logic level, the switching elements 44 and 50 are turned on whereas the switching elements 46 and 48 are turned off. In this condition, the capacitor C_1 and C_2 have thereby become connected in parallel with each other to make the charged voltage equal to each other. Thus, this voltage i.e. V_{ss} appears at the output 17.

It is possible to use capacitors C_1 and C_2 which are not identical in value. However, since in this case the voltage to which each becomes charged when they are connected in the series state will not be identical, Joule losses due to charge transfer for voltage equalization will occur when they are switched into the parallel connection state. This will result in a loss in efficiency. By cyclically switching signals ϕ and $\overline{\phi}$ at a sifficiently high frequency, a constant output voltage of one half the battery voltage is thus obtained at output terminal 17. It is convenient that the output voltage conversion ratio of this circuit is decided by only the circuit connection independenly of the value in capacitances.

It should be noted that for MOSFETs 44,46 and gates 48 and 50, the impedance in the OFF state must be extremely high and the leakage current from source to drain must be very small, in order to prevent losses due to the potential applied between its source and drain in the OFF state.

It is also possible to utilize a system which does not incorporate the type of auxiliary oscillator shown in FIG. 2. Instead, switching signals for the voltage converter circuit 16 may be supplied from the crystal oscillator circuit which functions as the time standard signal source, or from a frequency divider stage connected to the crystal oscillator output. In this case, the battery voltage would be applied directly to the crystal oscillator circuit. It is also possible to utilize an auxiliary oscillator of other configuration than that shown in the example of FIG. 2. The low voltage obtained by level conversion in this case may be used in matrix driving of a liquid crystal display, or for supplying low level bias voltages to various parts of the circuitry.

It should be noted that if a waveform shaping circuit as shown in FIG. 2 is not incorporated, following the auxiliary oscillator circuit, then the drain of inverter stages 38 and 40 will be increased. This is due to the fact that the relatively slow risetimes of the waveform of output \$\phi\$0 of the auxiliary oscillator cause a short circuit current to flow from the battery through the inverters 38 or 40 each time a level transition of signal \$\phi\$0 occurs. Use of waveform shaping circuit 32 ensures that transitions occur sufficiently rapidly that the current drawn by inverters 38 and 40 is extremely low.

FIG. 3A shows another preferred embodiment of the present invention adapted to provide a voltage of one third of the timepiece battery voltage. In FIG. 3A, a battery 10 supplies power to an auxiliary oscillator circuit 30, whose output is applied to a waveform shaping circuit 32 including inverters 36, 38 and 40. When output signal φ from inverter 38 goes to the high logic level, the N-channel MOSFET 54 together with transmission gate 62 and 58 are turned on. Three capacitors C1, C2 and C3 are thereby effectively connected in series with each other and with the power source 10 and are charged therefrom. When the output signal ϕ subsequently goes to the low logic level, then the MOSFET 54 and transmission gates (referred to hereinafter as TGs) 62 and 58 go to the OFF state, while P-channel 15 MOSFETs 52 and 56 and TGs 64 and 60 go to the ON state. Capacitors C1, C2 and C3 are thereby connected in parallel. If these capacitors are each of equal value, then they will each have been charged to one third of the voltage of power source 10. Thus when they are now connected in the parallel condition, a voltage of one third of the battery voltage appears at output terminal 17'. Even if the three capacitors C1, C2 and C3 are of unequal values, one third of the voltage which is the average of the voltage to which each capacitor has been charged will appear at output terminal 17'. However, as stated previously, for optimum efficiency of operation, capacitors of identical value are preferable.

It should be noted that the larger the value of capacitors C1, C2 and C3, the lower will be the output impedance appearing at terminal 17'. On the other hand, from the point of view of minimizing component costs, these capacitors should be as small as possible. In FIG. 3B, a system is shown whereby these conflicting requirements for capacitor size may be reconciled. Within the voltage conversion system 12', capacitors of low value are used. A transmission gate 70 switches the output from voltage conversion system 12' into a comparatively large value buffer capacitor C4. It should be 40 noted that switching element 70 connects the output of the voltage conversion system 12' to capacitor C4 only while the three capacitors within the voltage conversion system 12' (corresponding to C1, C2 and C3 in FIG. 3A) are effectively connected in parallel. Thus, 45 any Joule losses due to charge being transferred to capacitor C4 while the capacitors within the voltage conversion system 12' are being charged from the voltage source, are prevented. With the arrangement shown in FIG. 3B, the output impedance presented to the load 50 is reduced.

FIGS. 4A and 4B illustrate the way in which a voltage equal to n/m times a source voltage may be obtained. Assume that each of the capacitors 72-1 to n-m has the capacity value C_0 , and that the source voltage is 55 V_0 (i.e. the potential difference between Y_{DD} and V_{SS1}), and also that the capacitors have not been charged previously. When connection is now made as shown in FIG. 4A, a charge Q equal to C_0V_0/n is stored in each capacitor, and a voltage of V_0/n appears across the 60 terminals of each.

In FIG. 4A, m columns of capacitors, containing capacitors equally charged as stated above, are connected in parallel. If now, these capacitor connections are rearranged as shown in FIG. 4B, maintaining the 65 same capacitor charge conditions as in FIG. 4A, then a voltage of m/nV₀ will appear across the set of n columns of m capacitors.

8

It should be understood that this example is only provided to enable a clear understanding of the principles of operation of the present invention. In practice, a lower number of capacitors will normally be sufficient. Two ways in which the number of capacitors may be reduced will now be described.

(1) If $n/m > \frac{1}{2}$, then it follows that $(1-n/m) < \frac{1}{2}$. Thus, it is possible to utilize the difference between the output voltage of a voltage conversion system and the power source voltage to provide a voltage $V_0(1-n/m)$. If the capacitors were arranged as described in the previous paragraph, then to obtain this voltage, nm capacitors of equal value would be required. Thus, it is possible to save a total of (m/2-n) capacitors if n is made greater than m.

(2). Where m columns of n series connected capacitors are reconnected to provide n columns of m series connected capacitors, each of the latter columns of series connected capacitors may be replaced by a single capacitor of low value. Thus, if there were n columns of n series connected capacitors, i.e. a total of n² capacitors, these can be replaced by n capacitors each having the value 1/n.

A mode in which the voltage conversion is performed in the circuit shown in FIGS. 2, 3 and 4 will now be summarized.

Firstly, capacitors are connected in series with each other and with the power source and are charged therefrom. A plurality of columns of series connected capacitors may be connected in parallel with the power source or one of the capacitors may be connected in parallel with the other one of the capacitors. The series connected capacitors or the columns of series connected capacitors charged in the above mode are then connected in parallel with one another, and the charged voltages will be equalized. It is required in a no-load steady state that the charged voltages in the capacitors be equal to each other just before the series connected capacitors are rearranged in a parallel connected condition. If this requirement is not met, the efficiency is reduced. The equalizing connections may be sequentially performed in plural states or alternately in various modes combined with the first mode.

As previously noted, it is possible to provide a voltage of n/m V_0 with the use of m capacitors provided each of n and m is integer and n < m. In this case, m capacitors are first connected in series with the power source and charged therefrom. One of m capacitors is then sequentially connected in parallel with each of the remaining capacitors (m-1) to equalize the voltage across the terminals of each, providing a voltage V_0/m . The (m-1) capacitors remain connected in series, and an output voltage will be obtained at terminals of n capacitors connected in series. The output terminal of the n capacitors may be coupled to a circuit shown in FIG. 3B.

In FIG. 5, the voltage conversion system of the present invention is shown as combined with a voltage stabilizer circuit whose operation is based upon the threshold voltages developed by semiconductor active circuit elements. The embodiment shown in FIG. 5 is effective for timepiece utilizing such power sources as lithium batteries, which have high power and long life. However the voltage developed by a lithium type of battery is rather high for use with an electronic timepiece, approximately 3.2 V.

In FIG. 5, a battery 90 is connected to an auxiliary oscillator circuit 91 including inverters 92, 94 and 96,

these inverters being connected as a ring oscillator with extremely low current drain. The output of each inverter is delayed by $2\pi/3$ in phase with respect to the other stages. Waveform shaping of the output from this auxiliary oscillator formed by inverters 92, 94 and 96 is 5 performed by a waveform shaping circuit 98 composed of MOSFETs 100, 102, and 104 and 106. The output from the waveform shaping circuit is sent through inverter stages 108 and 110 to a voltage conversion circuit 112 including a switching circuit 114 and capacitors 116 10 and 118. Down conversion to a level of one half of the battery voltage is thereby accomplished as described above for other embodiments of this invention. The output from the voltage converter circuit 112 is applied to a voltage stabilizer circuit 120. A voltage control 15 reference, with characteristics similar to those of a Zener diode is formed by an inverter gate with dc negative feed-back loop connection indicated by numeral 122. The voltage developed across the inverter 122 is equal to the sum of the absolute values of the threshold 20 voltages of the P-channel and N-channel MOSFETs and can be stated as (|VTP| + VTN). The inverter 122 is connected in series with a P-channel MOSFET 124 connected as a source follower, so that the total voltage developed across the combination is (2|VTP|+VTN). N-channel MOSFET 126 functions as a high value resistor, whereby a small current is drawn through the inverter 122 and MOSFET 124. P-channel MOSFET 128 has a large current carrying capacity, and functions 30 as a source follower circuit, so that the output voltage at the source of MOSFET 128 differs from the voltage at its gate by the amount |VTP|, i.e. the threshold voltage of the MOSFET 128. Since the voltage applied to the gate of MOSFET 128 is the sum of the voltages across 35 the inverter 122 and MOSFET 124, the voltage dropped across MOSFET 124 compensated for the gate-to-source voltage drop in MOSFET 128. Thus, the output voltage at the source of MOSFET 128 is equal to the voltage across the inverter 122, i.e. (VT-40 $P \mid +VTN$). Since any change in the magnitude of this voltage due to variations in the manufacturing process of the CMOS integrated circuit of the timepiece is equal to the change in value of the threshold voltage of CMOS transistors supplied from the source terminal of 45 MOSFET 128, this circut ensures precise regulation of the supply voltage, irrespective of process variations. The output of the voltage stabilizer circuit 120 is applied to a frequency standard 130 such that the current consumption will be reduced to a small and desired 50 value and an output frequency is not affected by variations in the supply voltage from the battery.

The frequency standard 130 is controlled by a quartz crystal 132 to generate an output signal at a relatively high frequency. The output signal from the frequency 55 standard 130, is applied through a waveform shaping circuit 134 to a frequency converter 136 in the form of a divider which divides down the frequency from the standard 130 to a lower frequency signal. Time counter circuit 138 receives a relatively low frequency signal 60 from the frequency converter 136, and is operated at the same relatively low supply voltage as frequency standard 130 with little loss in power efficiency. Frequency converter 136, which presents a high mean impedance to its power source, is also operated from a lower volt- 65 age supply, for maximum efficiency. Level shifter circuit 140 and display system 142 function as previously described.

FIG. 6A shows another example of an electronic timepiece incorporating a temperature compensation circuit associated with a voltage conversion system according to the present invention. The electronic timepiece comprises a power source 150 to which an auxiliary oscillator circuit 152 is coupled.

The auxiliary oscillator circuit 152 functions not only as a temperature sensitive oscillator but also a signal generator for the voltage converter, and includes three inverters 154,156 and 158, of low mutual conductance. The frequency of the oscillator 152 is controlled by a trimming capacitor 160 and a resistor 162. Either capacitor 160 or resistor 162 has a linear type of variation in value with respect to temperature, such that the frequency of oscillator 152 varies in linear fasion with changes in temperature. Alternatively, these elements 160 and 162 may be dispensed with and, in place thereof, the ring oscillator circuit may be arranged such that it generates an output frequency varying in phase in proportion to the variations in ambient temperature. In this case, the ring oscillator may be preferably combined with the stabilizer 120 shown in FIG. 5. Either of both capacitor 160 and resistor 162 may be connected externally to the integrated circuit chip of the oscillator 152, so that, for example, resistor 162 may comprise a thermistor or capacitor may comprise a temperature sensitive capacitor. In this case, adjustment of the frequency of the oscillator 152 may be accomplished by varying such an external component. Alternatively, the resistor 162 may be incorporated within the integrated circuit chip of the oscillator circuit, while the capacitor 160 may be composed of stray capacitance. Such a method will be possible provided that sufficient consistency of reproducibility can be maintained in integrated circuit manufacture.

If a silver oxide type of battery is used for power source 150, and the temperature coefficient of oscillator 152 is large, then the battery voltage may be applied directly to inverters 154, 156 and 158. However, if a manganese type of battery is used (in the case of a timepiece for use in the home, for example), or if temperature sensing is performed by on-chip components as mentioned above, so that the temperature coefficient of oscillator 152 is not large, then it is desirable to supply oscillator circuit 152 from a simple voltage regulator circuit. A suitable type of regulator circuit is that described hereinabove with reference to 120 in FIG. 5, since this regulator provides not only compensation for changes in transistor characteristics caused by variations in manufacturing processing but also compensation for battery supply voltage.

Block 164 in FIG. 6A represents a voltage converter circuit as described hereinabove, being switching by output signals ϕ and $\overline{\phi}$ from the auxiliary oscillator 152. A crystal controlled frequency standard 166 is coupled to the output of the voltage converter circuit 164 and operated at a low supply voltage of $v_{ss1/2}$. The output signal from the frequency standard 166 is applied to a first frequency converter section 168 which is also operated at the supply voltage level of $v_{ss1/2}$.

In the case of an X-cut crystal being utilized in the frequency standard 166, the frequency f of a signal whose component frequencies when summed together provide a temperature compensated frequency may be expressed:

 $f = f_o(1 + (\theta - \theta_o)^2 \cdot a)$ (1)

where f_o is the frequency at a designated referency temperature, θ is temperature and a and θ 0 are constants, such that $a \approx 10^{-4}$, $\theta o = 25$ (°C.).

A relatively low frequency signal from the 1st frequency converter section 168 is applied to a temperature compensation circuit 170 to which an output signal $\overline{\phi}$ is applied from the auxiliary oscillator circuit 152 vid lead 153. The temperature compensation circuit 170 generally comprises a data type flip-flop 172, a frequency squaring circuit 174, a second frequency con- 10 verter section 176, a first frequency summing gate 178, an inverter 179, a data type flip-flop 180 serving as a synchronizing circuit, a third frequency converter section 182, and a second frequency summing gate 184.

within the brackets in the above equation) corresponds to the path in which the output of the frequency standard 166 is applied to one input of the frequency summing gate 178 and hence through another frequency summing gate 184 to final frequency converter section 20 186 and time counter circuit 190. The second term within the brackets of the above frequency equation corresponds to the circuit path through the data type flip-flop 180 and the frequency converter section 182 into the frequency summing gate 184. The term corre- 25 sponding to the square of the temperature component in equation (1) above is represented by the path through the data type flip-flop 172, frequency squaring circuit 174 and the second frequency converter section 176.

The data type flip-flop 172 serves as a frequency 30 sampling circuit to produce a sample output signal whose frequency is proportional to the number of cycles per second by which the frequency of the auxiliary oscillator circuit 152 has varied from a preset referency frequency (such a frequency might be fo/32 that gener- 35 ated at a specific preset temperature which will be referred to as "zero temperature co-efficient" temperature, i.e., 25° C., for example). With oscillator 152 output $\overline{\phi}$ applied to the clock input of the data type flip-flop 172 and the output of frequency converter section 168 40 applied to the data input of flip-flop 172, then if the frequency of the output signal $\overline{\phi}$ is an exact submultiple of the frequency of the output of the frequency converter section 168, the output of the flip-flop 172 will be zero Hz. For example, the output of the first frequency 45 converter section 168 might be 16,384 Hz and that of the auxiliary oscillator circuit 153 might be 1,024 Hz. If now the frequency of the oscillator circuit 152 changes to 1,023 Hz, then a signal of frequency 16,384, $16\times(1,024-1,023)$ Hz, i.e. approximately 16 Hz will be 50 produced by the flip-flop 172. The frequency of this output from the flip-flop 172 is designated x in FIG. 6A.

The frequency squaring circuit 174 produces an output signal of frequency proportional to the square of input signal frequency x. The output of the squaring 55 circuit 174 is applied to the second frequency converter section 176 whose output is applied to the frequency summing gate 178 together with the output of the first frequency converter section 168, to produce a signal whose frequency represents the deviated frequency of 60 a·fo· $(\theta - 74 \text{ o})^2$ term in equation (1) above.

Output ϕ from the auxiliary oscillator circuit 152 is set in synchronism with the output from the frequency standard 166 (but displaced in phase by 180° with respect to the standard 166 output) by applying the $\overline{\phi}$ 65 signal to the data input terminal of the data type flipflop 180 and the standard 166 output signal (inverted by the inverter 179) to the clock terminal of the flip-flop

180. The synchronized output from the flip-flop 180 is divided in frequency by a suitable factor in the third frequency converter section 182, and then is added to the output from the frequency summing gate 178 in the frequency summing gate 184.

Thus, the frequency of the output of the summing gate 184 is the sum of three signal frequencies. One of these is a direct subdivision of the output from the crystal controlled frequency standard (i.e. 166 output), another is a frequency which varies linearly with temperature (i.e. the output from the the third frequency converter section 182) and the third is a frequency which varies with the square of the temperature (i.e. the output from the second frequency converter section 176). Note In FIG. 6A, the first frequency component (i.e. "1" 15 that since in this example exclusive-OR gates are used for frequency summation, the inversion of the clock signal applied to the flip-flop 180 brought about by the inverter 179 is necessary, in order to bring about a correct phase difference relationship with the output from the summing gate 178 for frequency summing to be performed in the frequency summing gate 184.

> The output from the summing gate 184 is applied to the fourth or final frequency converter section 186, whose output phases to the time counter circuit 190. The time counter circuit 190 produces time signals which drive the display system 192, and also in the example of FIG. 6A produces a signal REF which is used in the frequency squaring circuit 174. The operation of a circuit example for block 174 will now be described.

Referring to FIG. 6B and the waveform diagram of FIG. 6C, an input signal x is applied from the flip-flop 172 in FIG. 6A. Input signal REF is a pulse train of low duty cycle as shown in FIG. 6B, which remains at the high and low logic levels for fixed periods of time. Although REF is shown as being generated by the time counter circuit 190 of FIG. 6A, REF may also be produced from any other oscillator or frequency converter circuit capable of providing suitable pulses. REF is inverted and synchronized with the timing of trigger clock pulses ϕ_{cl} in a data type flip-flop 200, providing signal \overline{Q}_{REF} . By applying the data input and the \overline{Q} output of the flip-flop 200 to a NAND gate 202, shaped output signal R is produced, with duration equal to one cycle of clock pulses ϕ_{cl} . The output \overline{R} serves to reset a chain of flip-flops 204 which are connected to form a first counter, which is a binary counter in this example. Output \bar{x}^* from flip-flop 206 is inverted with respect to input x, while each negative-going and positive-going transition of x* is synchronized with a negative-going edge of pulses ϕ_{cl} . Signal x** is of the same frequency as \bar{x}^* , but is inverted and delayed by one cycle of ϕ_{cl} with respect to \overline{x}^* . Thus, since \overline{x}^* and x^{**} are applied to the inhibit inputs of gate 208, a single pulse of duration equal to a cycle of ϕ_{cl} is produced following each negative-going edge of signal x*, i.e. a pulse train of identical frequency to input x but consisting of pulses of relatively narrow width. This pulse train is designated D_x in FIG. 6D. Gate 210 produces pulses identical to those output by the gate 208, but these are output only during each period that signal \overline{Q}_{REF} is at the low logic level. These bursts of pulses are designated Cp in FIGS. 6B and 6C.

Thus, following the leading edge of each REF pulse, the binary counter 204 is reset to the zero state, and from t₁ to t₂ as shown in FIG. 6C a subsequent train of Cp pulses is counted therein, during the low level state of Q_{REF} . The count of the binary counter 204 will thereby increase linearly during this time, reaching a final count of, say N₂ as shown on the lower line of FIG. 6C. This count value is clearly directly proportional to the frequency of the Cp pulses during the REF pulse in which the count to value N₂ is performed, i.e. 5 proportional to the frequency of input x during this REF pulse. Due to the low duty cycle of signal REF, (for example suitable values are one second for the high level periods of REF and 15 to 300 seconds for the low level periods), the count values stored in the binary 10 counter 204 are affected very little by any noise or jitter on input signal x. The time constant for heat conduction of step changes in temperature, in the case of a timepiece enclosed in a metal casing, is of the order 8 to 15 seconds, while the minimum time for variations in tem- 15 perature due to the timepiece being worn on the human body is of the order of several minutes. In addition, it requires another 20 to 30 hours for changes in temperature to result in visible variations in the operation of the timepiece. Thus, it would be possible to set the low level period of the REF signal to as long as one hour or more, provided that errors in timekeeping accuracy of 0.5 seconds or slightly less can be neglected.

Clock pulses D_x from the gate 208 are applied to a $_{25}$ second binary counter 212 composed of seven flip-flops, with outputs Q_{01} , \overline{Q}_{01} to Q_{07} , \overline{Q}_{07} . The waveforms for these outputs are shown in the upper set of lines in FIG. 6D. With the AND gate matrix 214 shown, then for example if the count in the counter 204 is such that only output Q₁₆ of counter 204 is at the high level, then output signal Q₀₁ of counter **212** will be selected for input to a frequency summing gate 216. Since output Q₁₆ is ANDed together with signal D_x before being ANDed with output Q_{01} in AND gate matrix 214, the signal $_{35}$ actually applied to the summing gate 216 in this case will be the pulse train shown in FIG. 6D with the designation $D_x \cdot Q_{01}$. Similarly, if only output Q_{15} of the counter 204 is in the high state, then a signal $\overline{Q}_{01}\cdot Q_{0-1}$ $2 \cdot D_x$ will be applied to the summing gate 216.

Thus, depending upon the count state of the counter 204, pulse trains of various frequencies are selected by matrix 214 from the outputs of the counter 212. The signals selected by the matrix is designated as follows:

$$\begin{split} &C_1 \!=\! Q_{01} \\ &C_2 \!=\! \overline{Q}_{01} \!\cdot\! Q_{02} \\ &C_3 \!=\! \overline{Q}_{01} \!\cdot\! \overline{Q}_{02} \!\cdot\! Q_{03} \\ &C_4 \!=\! \overline{Q}_{01} \!\cdot\! \overline{Q}_{02} \!\cdot\! \overline{Q}_{03} \!\cdot\! Q_{04} \\ &C_5 \!=\! \overline{Q}_{01} \!\cdot\! \overline{Q}_{02} \!\cdot\! \overline{Q}_{03} \!\cdot\! \overline{Q}_{04} \!\cdot\! Q_{05} \\ &C_6 \!=\! \overline{Q}_{01} \!\cdot\! \overline{Q}_{02} \!\cdot\! \overline{Q}_{03} \!\cdot\! \overline{Q}_{04} \!\cdot\! \overline{Q}_{05} \!\cdot\! Q_{06} \\ &C_7 \!=\! \overline{Q}_{01} \!\cdot\! \overline{Q}_{02} \!\cdot\! \overline{Q}_{03} \!\cdot\! \overline{Q}_{04} \!\cdot\! \overline{Q}_{05} \!\cdot\! \overline{Q}_{06} \!\cdot\! Q_{07} \end{split}$$

Thus, the general equation for the signal which will be output from the summing gate 216 may be written:

$$y = D_x \cdot C_1 \cdot Q_{16}$$

$$+ D_x \cdot C_2 \cdot Q_{15}$$

$$+ D_x \cdot C_3 \cdot Q_{14}$$

$$+ D_x \cdot C_4 \cdot Q_{13}$$

$$+D_{x}\cdot C_{5}\cdot Q_{12}$$
 $+D_{x}\cdot C_{6}\cdot Q_{11}$
 $+D_{x}\cdot C_{7}\cdot Q_{10}$

where y represents the output from the summing gate 216. As shown in FIG. 6D, the pulse trains represented by the terms of the above equation are interlaced in such a way that frequency summing can be performed merely by utilizing a logic OR gate. Alternatively, an AND gate could be used similarly, if negative-logic pulses were applied. In either case, any combination of pulse trains corresponding to any combination of outputs from the counter 204 may be added correctly in frequency without mutual interference between the pulses. If an exclusive OR gate is used for frequency summing, it is only necessary to ensure that the edges of pulses within the various pulse trains do not coincide.

As explained hereinabove, the count value stored in the counter 204 while frequency summing is taking place, i.e. during time interval t₂ to t₃ in FIG. 6C, is directly proportional to the frequency of input signal x, which may be designated f(x). Thus, the value stored in the counter 204 may be designated as $k_1 \cdot f(x)$. And obviously the frequency of any summed combination of pulse trains selected in the matrix 214 will be directly proportional to that of the input signal to the counter 30 212, i.e. to input D_x . Therefore, the frequency of any of the pulse trains may be designated as $k_2 \cdot f(x)$. Thus, due to the operation of the matrix 214, the selected combination of pulse trains has a frequency which is the product of two quantities which vary linearly with f(x), and thus is proportional to the square of f(x), i.e. the frequency of the output signal from the summing gate 216 in FIG. 6B may be written

$$f(y) = k_3 \cdot f(x)^2$$

where k_3 is a constant, which for the circuit shown in FIG. 6B has a value of 2^{-7} .

The frequencies of the various pulse trains applied to the summing gate 214 may be expressed as follows, with for example, $f(C_1 \cdot D_x)$ having the meaning of the frequency of the pulse train designated $C_1 \cdot D_x$ in FIG. 6D:

$$f(C_{1}\cdot D_{x})=2^{-1}\cdot f(D_{x})=2^{6}\cdot f(C_{7}\cdot D_{x})$$

$$f(C_{2}\cdot D_{x})=2^{-2}\cdot f(D_{x})=2^{5}\cdot f(C_{7}\cdot D_{x})$$

$$f(C_{3}\cdot D_{x})=2^{-3}\cdot f(D_{x})=2^{4}\cdot f(C_{7}\cdot D_{x})$$

$$f(C_{4}\cdot D_{x})=2^{-4}\cdot f(D_{x})=2^{-3}\cdot f(C_{7}\cdot D_{x})$$

$$f(C_{5}\cdot D_{x})=2^{-5}\cdot f(D_{x})=2^{-2}\cdot f(C_{7}\cdot D_{x})$$

$$f(C_{6}\cdot D_{x})=2^{-6}\cdot f(D_{x})=2^{-1}\cdot f(C_{7}\cdot D_{x})$$

$$f(C_{7}\cdot D_{x})=2^{-7}\cdot f(D_{x})=2^{0}\cdot f(C_{7}\cdot D_{x})$$

It should be noted that for the waveform diagram of FIG. 6D, negative edge-triggered logic is assumed, i.e. each transition of a flip-flop output takes place in response to the negative-going edge of a clock pulse applies thereto. Also, although in FIG. 6A the temperature compensation signal frequency components are shown as being derived from the φ output of the auxiliary oscillator 152, it is equally possible to use some

other source of signals with suitable frequency and

temperature/frequency characterstic.

In FIG. 7, an example of a level shifter circuit for use with the voltage conversion system of the present invention is shown. Input signal A is level shifted to be- 5 come output signal A'. Inverter stage 220 is operated at a low voltage and input signal A and output 222 of the inverter stage 220 are complementary to each other. NAND gates are formed by the pairs of MOSFETs 224 and 226, 228 and 230, 232 and 234, and 236 and 238. 10 These are connected to form a bistable flip-flop, such that P-channel MOSFET 224 is turned on when signal A is at the low level, with N-channel MOSFET 234 being simultaneously turned off. Since in this condition turned off and N-channel MOSFET 238 is turned on. Due to positive feedback action, output signal A' goes rapidly to the V_{DD} level. P-channel MOSFET 226 is turned on and P-channel MOSFET 228 turned off. while N-channel MOSFET 232 turnes off and N-chan-20 nel MOSFET 236 turns on. The circuit is now in a stable state.

The output signal A' shown is an antiphase to the input signal A. If an output signal in the same phase as input signal A is required, this may be taken from the 25 drain terminals of MOSFETs 228 and 230.

In the design of the level shifter circuit of FIG. 7, it must be ensured that the mutual conductance of the P-channel MOSFETs is made relatively high and that of the N-channel MOSFETs is made relatively low. 30 Thus, the N-channel MOSFETs 234 and 238 will present a higher impedance when a voltage $(V_{SS1}-V_{SS2})$ is applied to their gates than the impedance presented by the P-channel MOSFETs 224 and 230 when a voltage of $(V_{DD}-V_{SS1})$ is applied to their gates. This ensures 35 that the setting of the flip-flop is determined by the MOSFET 224 and MOSFET 230. This condition can be met by making the channel widths of MOSFETs 224 and 230 relatively wide and those of MOSFETs 234 and 238 relatively long, at the time of integrated circuit 40 manufacture.

FIG. 8 shows an example of an electronic timepiece circuit incorporating a further preferred embodiment of the voltage conversion system embodying the present invention. In this case, both voltage down conversion 45 and voltage up conversion are incorporated. The electronic timepiece comprises a power source 250 and a voltage conversion system 251 composed of an auxiliary oscillator circuit 252 coupled to the power source 250. The oscillator circuit 252 may be of the ring oscilla- 50 tor type previously described. An output signal from the auxiliary oscillator circuit 252 is applied to a waveform shaping circuit 254 which is composed of inverters 256, 258, 260 and 262. The inverters 262 and 258 perform waveform shaping and also provide complemen- 55 tary boost switching signals ϕ and ϕ . The switching signal ϕ is also produced by the inverter 260 and applied to a voltage down converter circuit 263 including capacitors 263a and 263b. The voltage down converter circuit 263 is similar in construction with that described 60 with reference to FIG. 2 and, therefore, a detailed description of the same is herein omitted. The switching signals ϕ and $\overline{\phi}$ are also applied to a voltage up converter circuit 264 including switching elements composed of P-channels MOSFETs 266 and 268 and N- 65 channel MOSFETs 270 and 272, capacitors 274 and 276, and diodes 278 and 280. The diode 278 is a clamping diode and capacitor 274 a clamping capacitor in the

voltage up converter circuit 264. When the switching signal ϕ goes to the high level, the diode 278 becomes forward biased. Simultaneously, the electrode of capacitor 274 connected to the output of the inverter 258 becomes charged positively, and the opposite electrode charged negatively. When the switching signal ϕ goes to the low level, the diode 278 is cut off by being reverse biased, and the previously positively charged electrode of the capacitor 274 is set to the low level, i.e. to V_{SS1} . The potential of the previously negatively charged electrode of capacitor 274 thereby becomes more negative than V_{SS1} by the amount $(V_{DD}-V_{SS1})$ where V_{DD} is the forward voltage drop across the diode 278. Thus, a combination of the diode 278 and capacitor 274 prosignal A' is at the high level, P-channel MOSFET 230 is 15 duces a voltage from the output of the inverter 258 which is clamped to potential V_{SS1} as its high level. The substrate and source of the N-channel MOSFET 270 are connected together and coupled to V_{DD} through capacitor 282. Functionally speaking, MOSFET 270 may be considered to act as ideal diode, the forward direction of the diode being the direction of current flow from drain to source. Thus, the output obtained by clamping signal ϕ at potential V_{SS1} as its high level, by means of the diode 278 and capacitor 274, is further rectified by the diode 270 causing charge to be stored in the capacitor 282. If the output impedance of the inverter 258 is such that it is significantly lower than the impedance presented by the MOSFETs 266 and 270 when they turn on, then the high level of the clamped output 275 is almost equal to 2V_{SS1}. It will not be precisely equal to $2V_{SS1}$, since the forward voltage drop of the diode will cause the clamping level to be somewhat more positive than V_{SS1} . If the potential at the output terminal 277 is close to $2V_{SS1}$, then the MOSFETs 272 and 268 have source-voltage levels of V_{SS1} and 2V_{SS1}, respectively. Thus, when voltage level 253 becomes 2V_{SS1}, since voltage level 273 is V_{SS1}, MOSFET 270 is turned on. Due to the low impedance of MOSFET 270 in the on state, the forward voltage drop of MOSFET 270 existing when it functioned as a diode is eliminated.

With this embodiment of the present invention therefore, the forward voltage in a diode clamping circuit can be effectively eliminated and thus a high efficiency voltage up conversion circuit can be produced. The circuit may be modified such that when the capacitor 276 and diode 280 are used, the capacitor 282 is eliminated. Alternatively, if the diode 282 is utilized, then the capacitor 276 and diode 280 may be omitted. Diode 280 may be replaced by an N-channel MOSFET, whose gate, source and backgate are all connected to lead 273 and the drain is connected to V_{ss1} . The same principle may be applied to the other diode 278.

A second voltage up converter circuit 284 operates in the same way as the circuit 264 just described. However, in this case, instead of clamping to the level V_{SS1} , clamping is performed to the level 0.5V_{SS1}, which is output 265 from the voltage down converter circuit 263. Thus a potential of $3/2V_{SS1}$ is obtained, by addition of V_{SS1} to $\frac{1}{2}V_{SS1}$.

As shown, therefore, by combining the circuits shown above, three or more power supplies of potentials such as $\frac{1}{2}$, 3/2 and 2V_{SSI} can be produced. In addition, potentials differing from the source voltage V_{SS1} as a reference by amounts such as $\frac{1}{2}V_{SS1}$ or $2V_{SS1}$ can be produced both positive or negative with respect to V_{SS1} potential. A liquid crystal display panel may thus be driven using a dynamic matrix drive system with a \frac{1}{3} voltage application arrangement. With this, the volt-

ages applied to selected and non-selected portions of the matrix are in the ratio of 3:1.

In FIG. 8, the electronic timepiece further comprises a crystal controlled frequency standard 286, which generates an output signal of the order 2¹⁵ to 2²² Hz. 5 The output signal from standard 286 is applied to a frequency converter 288 in the form of a frequency divider which produces a relatively low frequency signal. This relatively low frequency signal is applied through a level shifter circuit 290 to a time counter 10 circuit 292, which produces a time or calendar information 35 signals. These signals are applied to a driver circuit 294 which drives a dispay device 296 to cause display of time or calendar information.

A way in which the voltage conversion system of the 15 present invention may be applied to a liquid crystal display matrix corresponding to block 296 in FIG. 8, will now be described, in order to illustrate the advantages to be gained therefrom. These advantages are obtained from the fact that it becomes possible to utilize 20 fractional or integral multiples of the timpiece battery voltage in producing drive signals for the liquid crystal display matrix, i.e the optimum required voltages may be utilized and so efficiency may be maximized.

Referring now to FIG. 9A, the basic outlines of a 25 matrix for a liquid crystal display unit are shown. S_{11} to S_{mn} represent display elements, driven by n columns and m lines of electrode drive conductors. The n columns of conductors may be formed upon an upper glass substrate while the m rows of conductors may be 30 formed upon a lower glass substrate, these substrates being separated by suitable insulating spacers within which a layer of field-effect liquid crystal material is sandwiched. To address a typical element, $S_{ii(300)}$, the applied rout mean square (r.m.s.) voltages by the i-th 35 row and the j-th column which are common to display element 300 must be larger than the threshold voltage of the liquid crystal. The liquid crystal element should have the characteristic of rapid response, such that the element may be turned on by a drive pulse of short 40 duration, and also should have a long decay time, such that the "ON" condition is memorized during each cycle of drive pulses and also the ratio of the threshold voltage to the saturation voltage is larger than 0.5 to 1.

Referring to the waveform diagram of FIG. 9B, each 45 line of the matrix of FIG. 9A is selected by one of the signals ϕ_{di} to ϕ_{dm} , i.e. corresponding to the upper electrodes of the matrix, for example. Selection of columns, i.e. the lower electrodes, is performed by application of either signal ϕ_s or signal ϕ_s , depending upon whether 50 the ON or OFF state is required for the element selected.

An example of a circuit for display driving which is suitable for use with the voltage conversion system of the present invention is shown in FIG. 9C. Signal ϕ_{sj} 55 represents either ϕ_s or $\overline{\phi_s}$ (in FIG. 9B) depending upon the polarity of signal S_j and S_j . Signal ϕ_{sj} thus determines whether the selected element is to be turned to the ON state or the OFF state. For example, to turn element S_{ij} in FIG. 9A to the ON state, then ϕ_{sj} is selected to be low 60 level as $\overline{\phi_s}$ during the time in which signal ϕ_{di} is at the high level of ϕ . When signal ϕ_{di} is at the low level as ϕ , then signal ϕ_{sj} becomes as high level as $\overline{\phi_s}$. Again, for example, if segment S_{ij+1} is required to be turned to the OFF state, then signal ϕ_{sj+1} is selected to become ϕ_s 65 while ϕ_{di} is at the level of ϕ .

Due to the capacity of the liquid crystal elements, a discharge current flows from the segments being driven

18

each time the polarity of the alternating voltage of the drive pulses changes. In conventional designs of liquid crystal drive systems, this current flows through the battery of the timepiece in such a way as to cause increased power consumption. To save such power consumption, the signals ϕ^* and $\overline{\phi}^*$, which are slightly different only in phase, are replaced with ϕ and $\overline{\phi}$ signals which are applied to the gate of the circuit to produce output ϕ_{di} . In other case, for modulating the display mode, signals E and \overline{E} are applied as shown in FIG. 9B and 9C, such that a short circuit path is provided to reduce the OFF state r.m.s. voltage applied to the segment to a value lower than the threshold voltage of the liquid crystal cell.

Referring to FIG. 9B, since the voltage applied to a segment required to be in the OFF state can be expressed by $(\phi_{di} - \overline{\phi}_s)$ whereas the voltage to be applied to a segment which is to be turned to the ON state is expressed by $(\phi_{di} - \overline{\phi_s})$, it can be seen that a voltage three times that in the OFF state is applied to turn the segment to the ON state, although this high voltage is applied only for a short period. For signal ϕ_{si} in FIG. **9C**, the respective potential levels are $V_{ss1/2}$ for the high level V_{ss1} for the intermediate level, and $V_{ss3/2}$ for the low level. While E is at the high level, ϕ_{si} is at the intermediate level, and when E is at the low level, ϕ_{sj} varies between $V_{ss1/2}$ and $V_{ss3/2}$. When S_i is at the high level, ϕ_{si} becomes in the same phase as ϕ , when ϕ_{si} is at the low level, ϕ_{si} becomes in the same phase as $\overline{\phi}$. Signal ϕ_{di} varies between a high level of V_{DD} and a low level of V_{ss2} , with an intermediate level of $V_{ss1} \cdot \phi_{di}$ goes to the intermediate level when either E or \overline{D}_1 is at the high level, and is in the same phase as ϕ when D_i is at the low level. The high and low logic levels of ϕ , ϕ , E, E, D_i and D_i in FIG. 9C may be considered to be V_{DD} and V_{ss2} , respectively. In the case when E is at low level, the relationship between liquid crystal threshold voltage and signals shown in FIG. 9C may be expressed:

$$(((m-1)(V_{ss1/2}-V_{ss1})^2+(V_{DD}-V_{ss1/2})^2)\div m)^{1/2}$$

$$< V_{TLC}$$

 $((((m-1)(V_{ss1/2}-V_{ss1})^2+(V_{DD}+V_{ss1/2})^2)\div m^{1/2}-V_{TLC})^2+(V_{DD}+V_{ss1/2})^2)$

Thus, depending upon V_{TLC} , various voltages such as $\frac{1}{3}$, $\frac{2}{3}$, $\frac{2}{3}$, $\frac{2}{3}$, $\frac{2}{3}$, and $\frac{4}{3}$ of the source voltage may be provided for use in such a display drive application, using a voltage conversion system of the present invention (the $\frac{3}{3}$ ratio would simply be the source voltage directly applied).

With presently available liquid crystal materials, matrix configurated elements may be driven by a voltage V_{LC} of 1.1 V. These can be driven in a matrix composed of from 8 columns by 2 lines to 8 columns by 8 lines, for example. In such a system, it is rational to perform information processing at low voltage, and to provide display drive signals such as ϕ by level shifting to a higher voltage.

FIGS. 10A and 10B show the relationship between the voltages applied to PLZT or electrochromic display elements and the resultant state of the element. The drive system for an element with the characteristic shown in FIG. 10A will depend upon whether the element is switched on at point B' and off at point 0 (Q=0) or whether the element is switched on at point B' and off at point E'. In the case of a PLZT element, where Q represents the degree of polarization of the element, the

ON state will occur at point B' and the OFF state between points H' and D'. Thus, the element may be switched on by applying a voltage greater than the range 0 to A', and may be turned off by applying a reverse voltage of between H' to D'. In the case of an electrochromic display element, a similar driving method may be used. In this case, Q denotes the amount of electrochemically separated material (positive for separation on the front face of the element and negative for separation on the rear face).

Where a PLZT, electrochromic or elastomeric display element having the characteristic shown in FIG. 10B is used, it is necessary to limit the amount of electrical charge accumulated in the element to that corresponding to position D when turning off the element (or 15 position A, depending upon the element configuration). The OFF voltage applied may also be set to point 0, thereby forming a minor loop. If a clearly visible distinction can be made between the states of the element at points B and E, then the element is turned on by 20 application of a voltage bringing the element to state B, and is turned off by a voltage sufficient to bring it to state E.

FIG. 10C shows an example of a driver circuit 302 for a PLZT or electrochromic display element with the 25 characteristic shown in FIG. 10A. Following the rising edge of display signal S_k , a signal S_k on is generated in synchronism with signal ϕ , as a single pulse. Following the trailing edge of S_k , a signal S_k off is generated in synchronism with ϕ , also as a single pulse. Signal S_k on 30 serves to turn the selected display element to the visible state, while S_k off turns the selected element to the OFF or non-visible state.

FIG. 10D shows an example of a driver circuit 304 incorporating the circuit 302 of FIG. 10C which is 35 suitable for application of the voltage conversion system of the present invention. P-channel MOSFET 306 is turned on when signal S_k on goes to the high level, and so output signal ϕ_{sk} goes to level V_{DD} . When signal S_k off goes to the high level, then P-channel MOSFET 40 308 is turned on and signal ϕ_{sk} goes to the level $V_{SS1/4}$. Note that signals S_k on and S_k off cannot both go to the high level simultaneously. With both S_k on and S_k off at the low level, MOSFETs 306 and 308 are completely cut off. Thus, the voltage applied to display element 312 45 falls to zero with a time constant determined by the leakage resistance and capacitance of the display element, or remains at the level which has been established. Output ϕ_{com} , is synchronism with $\overline{\phi}$ but of different voltage level, is produced from inverter 310. This 50 signal is applied to display element 312 to provide a common electrode voltage. As a result, the total potential applied to the selected element 312, designated V_{ec-k} , has the waveform shown in FIG. 10E. The waveforms for ϕ_{sk} , ϕ_{com} , S_k , S_k on and S_k off are also 55 shown in FIG. 10E.

A method whereby the voltage conversion system of the present invention may be used to increase the efficiency of an electronic timepiece with a pulse motor will now be described with reference to FIG. 11A, and 60 the corresponding waveform diagrams in FIG. 11B. A part of timepiece circuit section 322 in FIG. 11A incorporates a crystal controlled frequency standard, frequency divider and waveform shaping circuits, operated from the low voltage V_{SS1/4}. Level shifter circuit 65 324 is capable of producing output signals of lower potential than the negative level of the battery voltage, V_{SS1}, by utilizing supply V_{SS2} produced by a voltage

converter circuit. The voltage V_{ss2} has a magnitude twice that of V_{ss1} , and $V_{ss1/4}$ is one quarter the value of V_{ss1} . A pulse motor M is driven by FET inverters 325 and 327, which have large current carrying capacity. When a low potential signal of amplitude twice V_{ss1} is applied to the gates of P-channel MOSFETs 326 and 330, these FETs are turned to the ON state. The circuit shown has the advantage that the impedance of MOSFETs 326 and 330 in the ON state is $\frac{1}{4}$ that of MOSFETs used in a conventional circuit in which voltage supply V_{ss2} is not provided. This is because a low potential signal of amplitude $2V_{ss1}$ is applied to the gates of MOSFETs 326 and 330 to turn them ON. The area on the timpiece integrated circuit chip required to accomodate the motor drive inverters can therefore be reduced.

With the circuit as shown in FIG. 11A, such a reduction in impedance (compared to a conventional circuit) does not occur when N-channel MOSFETs 328 and 332 are turned ON. However, since the gate signals 329 and 331 have a potential more negative than V_{ss1}, in the low level state of these signals, MOSFETs 328 and 332 are completely cut off. Thus, the leakage current flowing in MOSFETs 328 and 332 in the OFF state is extremely low.

If it is desired to further decrease the impedance of MOSFETs 328 and 332 in the ON state, this may be achieved by inserting capacitors between their gates and inputs 329 and 333, and 331 and 339, respectively, to provide DC blocking. The gates may then be connected by diodes to V_{ss1} , to be clamped to this potential. Input 334 should still be connected directly to the gate of MOSFET 326, while input 339 is still applied directly to the gate of MOSFET 330. Alternatively, an additional supply voltage of $2V_{DD}$, i.e. positive with respect to V_{DD} may be provided. In this case, inverters 325 and 327 may be driven by signals whose logic level range is from V_{ss2} to V_{DD2} .

It will now be appreciated from the foregoing description that in accordance with the present invention an electronic timepiece of extremely low power consumption can be provided to increase lifetime of a power source of the timepiece. It should also be understood that in accordance with the present invention the combination of "voltage-down conversion" and the "level conversion" of the signals in an electronic timepiece can be achieved at a high level of efficiency.

While the present invention has been shown and described with reference to particular embodiments by way of example, it should be noted that various other changes or modifications may be made without departing from the scope of the present invention.

What is claimed is:

- 1. A voltage convertion system coupled to a power source having high and low potentials, to provide a lower output voltage than that of the power source, comprising:
 - a plurality of capacitors; and
 - a plurality of different types of fieled effect transistors for switching connections of said plurality of capacitors relative to the power source for thereby providing said lower output voltage, one type of said plurality of field effect transistors having a source electrode connected to the high potential of said power source, and another type of said plurality of field effect transistors having a source electrode connected to the low potential of said power source.

2. A voltage convertion system according to claim 1, in which said one type and said another type of said plurality of field effect transistors comprise a P-channel field effect transistor and a N-channel field effect transistor, respectively.

3. A voltage convertion system according to claim 2, further comprising a signal generator circuit coupled to the power source to generate an output signal, and in which said P-channel field effect transistor and said N-channel field effect transistor responsive to said out- 10 put signal, respectively, for setting said plurality of capacitors into a parallel connected condition and a series connected condition.

4. A voltage conversion system according to claim 3, cillator circuit coupled to the power source to provide said output signal.

5. A voltage conversion system according to claim 4, in which said oscillator circuit comprises a plurality of inverters coupled in a ring configuration.

6. A voltage conversion system according to claim 5, in which each of said inverters comprises complementary metal oxide semiconductor field effect transistors.

7. A voltage conversion system according to claim 6, in which said signal generator circuit further comprises 25 a waveform shaping circuit coupled to said oscillator circuit to perform waveshaping of said output signal from said oscillator circuit.

8. A voltage conversion system according to claim 7, in which said waveform shaping circuit comprises a 30 plurality of inverters connected in series.

9. A voltage conversion system according to claim 5, in which said oscillator circuit further comprises temperature sensing means coupled to said inverters for causing said oscillator circuit to serve as a temperature 35 sensitive oscillator to generate an output signal at a frequency varying in dependence on ambient temperature.

10. A voltage conversion system according to claim 9, further comprising temperature compensation means 40 coupled to a frequency standard and said oscillator circuit for automatically compensating changes in an output signal frequency of said frequency standard caused by said changes in temperature in dependence on a frequency of the output signal of said oscillator 45 circuit.

11. A voltage conversion system according to claim 10, in which said temperature compensation means comprises means for generating an output signal of a frequency deviation proportional to a power of the 50 value of any change in said ambient temperatue, and frequency summing means for generating an output signal of a frequency equal to the sum of frequencies of the output signals of said oscillator circuit, frequency standard and output signal generating means.

12. A voltage conversion system according to claim 11, in which said output signal generating means comprises a frequency squaring circuit which generates an output signal of a frequency proportional to the square of changes in the value of said ambient temperature 60 above and below a preset specific temperature.

13. A voltage conversion system according to claim 12, in which said output signal generating means further comprises a frequency sampling circuit coupled to said frequency standard and said oscillator circuit and re- 65 sponsive to the output pulse signals from said frequency standard and the output signal from said oscillator circuit for thereby generating a sample output signal

whose frequency is zero at said specific temperature and increases in proportion to the absolute value of any changes in said ambient temperature relative to said specific temperature value.

14. A voltage conversion system according to claim 13, in which said frequency squaring circuit comprises means for generating a plurality of pulse trains of different frequencies relative to one another, each having a frequency proportional to said sample output signal, frequency selecting means for selecting various combinations of said pulse trains, and frequency summing means for summing said selected combinations of pulse trains.

15. A voltage enversion system according to claim in which said signal generator circuit comprises an os- 15 14, in which said frequency selecting means comprises means for generating various control signals in proportion to changes in frequency of said sample output signal.

> 16. A voltage conversion system according to claim 20 15, in which said control signal generating means comprises a counter circuit coupled to said sampling circuit and responsive to said sample output signal for generating said control signals.

17. A voltage conversion system according to claim 14, in which said means for generating said plurality of pulse trains comprises a counter circuit which counts continuously in response to an input signal of frequency proportional to that of said sample output signal.

18. A voltage conversion system according to claim 11, in which said temperature compensating means further comprises means for intermittently detecting said ambient temperature to provide a temperature information signal, and memory means for storing said temperature information signal.

19. A voltage conversion system according to claim 15, in which said frequency selecting means further comprises a matrix of logic AND gates coupled to said control signal generating means and said means for generating said plurality of pulse trains, said matrix selecting said various combinations of said pulse trains in response to said control signals.

20. A voltage conversion system according to claim 1, in which said power source comprises a lithium battery.

21. A voltage conversion system according to claim 1, in which said power source comprises a silver oxide battery.

22. A voltage conversion system according to claim 1, further comprising voltage stabilizing means coupled to said power source to stabilize the level of said lower output voltage, said voltage stabilizing means including first transistors as a reference voltage generator, and a second power controlling transistor coupled between said voltage conversion system and an output of said reference voltage generator.

23. A voltage conversion system according to claim 22, in which a threshold voltage of said first transistors is utilized as a reference voltage.

24. A voltage convertion system coupled to a power source to provide a lower output voltage than that of the power source, comprising:

a plurality of capacitors;

means for switching connections of said plurality of electric energy storage means relative to the power source for thereby providing said lower output voltage;

a buffer capacitor coupled to a terminal of the power source; and

- a switching device coupled between said buffer capacitor and one of the output terminal of said switching means, said switching device coupling the output terminal of said switching means to said buffer capacitor only while said plurality of electric energy storage means are in a specific, present connected condition.
- 25. A voltage convertion system coupled to a power source to provide a lower output voltage than that of the power source, comprising:

a plurality of capacitors;

means for switching connections of said plurality of electric energy storage means relative to the power source for thereby providing said lower output voltage;

a signal generator circuit coupled to the power source to generate an output signal;

- said switching means responsive to said output signal for setting said plurality of electric energy storage means into a parallel connected condition and a 20 series connected condition;
- a voltage up converter circuit coupled to the power source to generate a higher output voltage than that of the power source, said voltage up converter circuit including a plurality of metal oxide field 25 effect semiconductor transistors, a first capacitor coupled to a source terminal of one of said field effect transistors and coupled to a drain terminal of another of said field effect transistors, a source of boost switching signals, and a reservoir capacitor 30 coupled to a terminal of the power source and to an output terminal of said voltage up converter circuit, wherein charge stored in said first capacitor by a first polarity of transitions of said boost switching signals is transferred to said reservoir 35 capacitor by the action of a second polarity of

transitions of said boost switching signal, causing one or more of said field effect transistors to pass from a high resistance state between drain and source terminals to a low resistance state.

26. A voltage convertion system according to claim 25, in which said boost switching signals are provided from said signal generator.

27. A voltage convertion system coupled to a lithium battery having high and low potentials, to provide a lower output voltage than that of the lithium battery, comprising:

a plurality of capacitors: and

- a plurality of field effect transistors for switching connections of said plurality of capacitors relative to the lithium battery for thereby providing said lower output voltage, said plurality of field effect transistors including a P-channel field effect transistor having a source electrode connected to the high potential of said lithium battery and a drain electrode connected to said plurality of capacitors, and a N-channel field effect transistor having a source electrode connected to the low potential of said lithium battery and a drain electrode connected to said plurality of capacitors.
- 28. A voltage convertion system according to claim 27, further comprising a signal generator circuit coupled to the lithium battery to generate an output signal, and in which said P-channel field effect transistor and said N-channel field effect transistor have gate electrodes connected to said signal generator, said P-channel field effect transistor and said N-channel field effect transistor being responsive to the output signal for setting said plurality of capacitors into a parallel connected condition and a series connected condition.

40

45

50

55

60

With the second second

·