

US006960607B2

(12) **United States Patent**
Malamas et al.

(10) **Patent No.:** **US 6,960,607 B2**
(45) **Date of Patent:** **Nov. 1, 2005**

(54) **NAPHTHYL BENZOXAZOLES AND
BENZISOXAZOLES AS ESTROGENIC
AGENTS**

(75) Inventors: **Michael S. Malamas**, Jamison, PA (US); **Iwan Gunawan**, Somerset, NJ (US); **Heather A. Harris**, Phoenixville, PA (US); **James C. Keith, Jr.**, Andover, MA (US); **Leo M. Albert**, Burlington, MA (US)

(73) Assignee: **Wyeth**, Madison, NJ (US)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 38 days.

(21) Appl. No.: **10/316,641**

(22) Filed: **Dec. 11, 2002**

(65) **Prior Publication Data**

US 2003/0171412 A1 Sep. 11, 2003

Related U.S. Application Data

(60) Provisional application No. 60/341,125, filed on Dec. 13, 2001.

(51) **Int. Cl.**⁷ **C07D 263/54**; A61K 31/42

(52) **U.S. Cl.** **514/375**; 514/367; 548/152;
548/224

(58) **Field of Search** 548/224; 514/375

(56) **References Cited**

PUBLICATIONS

Mendelsohn and Karas, "The protective effects of estrogen on the cardiovascular system," *New Engl. J. Med.* (1999) 340:1801-1811.

Epperson, et al., "Gonadal steroids treatment of mood disorders," *Psychosomatic Med.* (1999) 61:678-697.

Crandall, J. "Estrogen replacement therapy and colon cancer: a clinical review," *Women's Health Gender-Based Med.* (1999) 8:1155-1166.

Monk and Brodaty, "Use of estrogens for the prevention and treatment of Alzheimer's disease," *Dementia & Geriatric Cognitive Disorders* (2000) 11:1-10.

Hum and Macrae, "Estrogen as a neuroprotectant in stroke," *J. Cerebral Blood Flow & Metab.* (2000) 20:631-652.

Calvin, "Oestrogens and wound healing," *Maturitas* (2000) 34:195-200.

Finking, et al., "The effects of estrogen in the cardiovascular system," *Zeitschrift fur Kardiologie* (2000) 89:442-453.

Brincat, "Hormone replacement therapy and the skin," *Maturitas* (2000) 35:107-117.

Al-Azzawi, "The menopause and its treatment in perspective," *Postgrad. Med. J.* (2001) 77:292-304.

Moggs and Orphanides, "Estrogen receptors: orchestrators of pituitary cellular response," *EMBO Reports* (2001) 2:775-7781.

Hall, et al., "The multifaceted mechanisms of estradiol and estrogen receptor signaling," *J. Biol. Chem.* (2001) 276:36869-36872.

McConnell, *Principles of Molecular Regulation*, (2000) pp. 351-361.

McKenna, et al., "Nuclear receptor coregulators: cellular and molecular biology," *Endocrine Rev.* (1999) 20:321-344.

Quaedackers, et al., "4-Hydroxytamoxifen trans-represses nuclear factor kappa-B activity in human osteoblastic U2-OS cells through estrogen receptor (ER)alpha and not through ERbeta," *Endocrinol.* (2001) 142:1156-1166.

Bhat, et al., "A novel estrogen receptor beta: identification and functional analysis of additional N-terminal amino acids," *J. Steroid Biochem. Mol. Biol.* (1998) 67:233-240.

Pelzer, et al., "Estrogen effects in the myocardium: inhibition of NF-kappaB DNA binding by estrogen receptor-alpha and -beta," *Biochem. Biophys. Res. Comm.* (2001) 286:1153-1157.

Levin, "Cell localization, physiology, and non-genomic actions of estrogen receptors," *J. Appl. Physiol.* (2001) 91:1860-1867.

Levin, "Cellular functions of the plasma membrane estrogen receptor," *Trends Endocrinol. Metab.* (1999) 10:374-377.

Green, et al., "Human oestrogen receptor cDNA: sequence, expression and homology to v-erb-A," *Nature* (1986) 320:134-139.


(Continued)

Primary Examiner—Kamal A. Saeed


(74) *Attorney, Agent, or Firm*—Michael P. Straher; Arnold S. Milowsky; Zozen O'Connor

(57) **ABSTRACT**


This invention provides estrogen receptor modulators of formula I, having the structure



wherein,



or



wherein

R¹, R², R³, and R⁴, and X as defined in the specification, or a pharmaceutically acceptable salt thereof.

7 Claims, No Drawings

OTHER PUBLICATIONS

Kuiper, et al., "Cloning of a novel estrogen receptor expressed in rat prostate and ovary," *Proc. Natl. Acad. Sci. USA* (1996) 93:5925–5930.

Couse, et al., "Tissue distribution and quantitative analysis of estrogen receptor- α (ER α) and estrogen receptor- β (ER β) messenger ribonucleic acid in the wild-type and ER α -knockout mouse," *Endocrinol.* (1997) 138:4613–4621.

Kuiper et al., "Comparison of the ligand binding specificity and transcript tissue distribution of estrogen receptors α and β ," *Endocrinol.* (1997) 138:863–870.

Sar and Welsch, "Differential expression of estrogen receptor- β and estrogen receptor- α in the rat ovary," *Endocrinol.* (1999) 140:963–971.

Fitzpatrick, et al., "Expression of estrogen receptor- β protein in rodent ovary," *Endocrinol.* (1999) 140:2581–2591.

Cowley, et al., "Estrogen receptors α and β form heterodimers on DNA," *J. Biol. Chem.* (1997) 272:19858–19862.

McDonnell, J., "Selective estrogen receptor modulators (SERMs): a first step in the development of perfect hormone replacement therapy regimen," *Soc. Gynecolog. Invest.* (2000) 7:S10–S15.

Goldstein, "A pharmacological review of selective oestrogen receptor modulators," *Human Reproduction Update* (2000) 6:212–224.

Pike, et al., "Structure of the ligand-binding domain of oestrogen receptor β presence of a partial agonist and a full antagonist," *EMBO J.* (1999) 18:4608–4618.

Shiau, et al., "The structural basis of estrogen receptor/coactivator recognition and the antagonism of this interaction by tamoxifen," *Cell* (1998) 95:927–937.

Ogawa, et al., "The complete primary structure of human estrogen receptor β (hER- β) and its heterodimerization with ER α in vivo and in vitro," *Biochem. Biophys. Res. Comm.* (1998) 243:122–126.

Sun, et al., "Novel ligands that function as selective estrogens or antiestrogens for estrogen receptor- α or estrogen receptor- β ," *Endocrinol.* (1999) 140:800–804.

Shugrue, et al., "Regulation of progesterone receptor messenger ribonucleic acid in the rat medial preoptic nucleus by estrogenic and antiestrogenic compounds: an in situ hybridization study," *Endocrinol.* (1997) 138:5476–5484.

Dubai, et al., "Estrogen receptor α , not β , is a critical link in estradiol-mediated protection against brain injury," *Proc. Natl. Acad. Sci. USA* (2001) 98:1952–1957.

Lundeen, et al., "Rat urine complement C3 expression as a model for progesterone receptor modulators," *J. Steroid. Mol. Biol.* (2001) 78:137–143.

Dubal, et al., "Estradiol modulates bcl-2 in cerebral ischemia: a potential role for estrogen receptors," *J. Neurosci.* (1999) 19:6385–6393.

NAPHTHYL BENZOXAZOLES AND BENZISOXAZOLES AS ESTROGENIC AGENTS

This application claims priority from now abandoned provisional application Ser. No. 60/341,125, filed Dec. 13, 2001, the entire disclosure of which is hereby incorporated by reference.

BACKGROUND OF THE INVENTION

This invention relates to naphthyl benzoxazoles and benzisoxazoles, which are useful as estrogenic agents.

The pleiotropic effects of estrogens in mammalian tissues have been well documented, and it is now appreciated that estrogens affect many organ systems [Mendelsohn and Karas, *New England Journal of Medicine* 340: 1801–1811 (1999), Epperson, et al., *Psychosomatic Medicine* 61: 676–697 (1999), Crandall, *Journal of Womens Health & Gender Based Medicine* 8: 1155–1166 (1999), Monk and Brodaty, *Dementia & Geriatric Cognitive Disorders* 11: 1–10 (2000), Hum and Macrae, *Journal of Cerebral Blood Flow & Metabolism* 20: 631–652 (2000), Calvin, *Maturitas* 34: 195–210 (2000), Finking, et al., *Zeitschrift fur Kardiologie* 89: 442–453 (2000), Brincat, *Maturitas* 35: 107–117 (2000), Al-Azzawi, *Postgraduate Medical Journal* 77: 292–304 (2001)]. Estrogens can exert effects on tissues in several ways, and the most well characterized mechanism of action is their interaction with estrogen receptors leading to alterations in gene transcription. Estrogen receptors are ligand-activated transcription factors and belong to the nuclear hormone receptor superfamily. Other members of this family include the progesterone, androgen, glucocorticoid and mineralocorticoid receptors. Upon binding ligand, these receptors dimerize and can activate gene transcription either by directly binding to specific sequences on DNA (known as response elements) or by interacting with other transcription factors (such as AP1), which in turn bind directly to specific DNA sequences [Moggs and Orphamides, *EMBO Reports* 2: 775–781 (2001), Hall, et al., *Journal of Biological Chemistry* 276: 36869–36872 (2001), McDonnell, *Principles Of Molecular Regulation*. p351–361 (2000)]. A class of “coregulatory” proteins can also interact with the ligand-bound receptor and further modulate its transcriptional activity [McKenna, et al., *Endocrine Reviews* 20: 321–344 (1999)]. It has also been shown that estrogen receptors can suppress NF κ B-mediated transcription in both a ligand-dependent and independent manner [Quaedackers, et al., *Endocrinology* 142: 1156–1166 (2001), Bhat, et al., *Journal of Steroid Biochemistry & Molecular Biology* 67: 233–240 (1998), Peizer, et al., *Biochemical & Biophysical Research Communications* 286:1153–7 (2001)].

Estrogen receptors can also be activated by phosphorylation. This phosphorylation is mediated by growth factors such as EGF and causes changes in gene transcription in the absence of ligand [Moggs and Orphamides, *EMBO Reports* 2: 775–781 (2001), Hall, et al., *Journal of Biological Chemistry* 276: 36869–36872 (2001)].

A less well-characterized means by which estrogens can affect cells is through a so-called membrane receptor. The existence of such a receptor is controversial, but it has been well documented that estrogens can elicit very rapid non-genomic responses from cells. The molecular entity responsible for transducing these effects has not been definitively isolated, but there is evidence to suggest it is at least related to the nuclear forms of the estrogen receptors [Levin, *Journal of Applied Physiology* 91: 1860–1867 (2001), Levin, *Trends in Endocrinology & Metabolism* 10: 374–377 (1999)].

Two estrogen receptors have been discovered to date. The first estrogen receptor was cloned about 15 years ago and is now referred to as ER α [Green, et al., *Nature* 320: 134–9 (1986)]. The second form of the estrogen receptor was found comparatively recently and is called ER β [Kuiper, et al., *Proceedings of the National Academy of Sciences of the United States of America* 93: 5925–5930 (1996)]. Early work on ER β focused on defining its affinity for a variety of ligands and indeed, some differences with ER α were seen. The tissue distribution of ER β has been well mapped in the rodent and it is not coincident with ER α . Tissues such as the mouse and rat uterus express predominantly ER α , whereas the mouse and rat lung express predominantly ER β [Couse, et al., *Endocrinology* 138: 4613–4621 (1997), Kuiper, et al., *Endocrinology* 138: 863–870 (1997)]. Even within the same organ, the distribution of ER α and ER β can be compartmentalized. For example, in the mouse ovary, ER β is highly expressed in the granulosa cells and ER α is restricted to the thecal and stromal cells [Sar and Welsch, *Endocrinology* 140: 963–971 (1999), Fitzpatrick, et al., *Endocrinology* 140: 2581–2591 (1999)]. However, there are examples where the receptors are coexpressed and there is evidence from in vitro studies that ER α and ER β can form heterodimers [Cowley, et al., *Journal of Biological Chemistry* 272: 19858–19862 (1997)].

A large number of compounds have been described that either mimic or block the activity of 17 β -estradiol. Compounds having roughly the same biological effects as 17 β -estradiol, the most potent endogenous estrogen, are referred to as “estrogen receptor agonists”. Those which, when given in combination with 17 β -estradiol, block its effects are called “estrogen receptor antagonists”. In reality there is a continuum between estrogen receptor agonist and estrogen receptor antagonist activity and indeed some compounds behave as estrogen receptor agonists in some tissues and estrogen receptor antagonists in others. These compounds with mixed activity are called selective estrogen receptor modulators (SERMS) and are therapeutically useful agents (e.g. EVISTA) [McDonnell, *Journal of the Society for Gynecologic Investigation* 7: S10–S15 (2000), Goldstein, et al., *Human Reproduction Update* 6: 212–224 (2000)]. The precise reason why the same compound can have cell-specific effects has not been elucidated, but the differences in receptor conformation and/or in the milieu of coregulatory proteins have been suggested.


It has been known for some time that estrogen receptors adopt different conformations when binding ligands. However, the consequence and subtlety of these changes has been only recently revealed. The three dimensional structures of ER α and ER β have been solved by co-crystallization with various ligands and clearly show the repositioning of helix 12 in the presence of an estrogen receptor antagonist which sterically hinders the protein sequences required for receptor-coregulatory protein interaction [Pike, et al., *Embo* 18: 4608–4618 (1999), Shiau, et al., *Cell* 95: 927–937 (1998)]. In addition, the technique of phage display has been used to identify peptides that interact with estrogen receptors in the presence of different ligands [Paige, et al., *Proceedings of the National Academy of Sciences of the United States of America* 96: 3999–4004 (1999)]. For example, a peptide was identified that distinguished between ER α bound to the full estrogen receptor agonists 17 β -estradiol and diethylstilbesterol. A different peptide was shown to distinguish between clomiphene bound to ER α and ER β . These data indicate that each ligand potentially places the receptor in a unique and unpredictable conformation that is likely to have distinct biological activities.

3

As mentioned above, estrogens affect a panoply of biological processes. In addition, where gender differences have been described (e.g. disease frequencies, responses to challenge, etc), it is possible that the explanation involves the difference in estrogen levels between males and females.

DESCRIPTION OF THE INVENTION

This invention provides estrogenic compound of formula I having the structure,



R^1 , R^3 , and R^4 are each, independently, hydrogen, hydroxyl, halogen, alkyl of 1–6 carbon atoms, cycloalkyl of 3–8 carbon atoms, alkoxy of 1–4 carbon atoms, alkenyl of 2–7 carbon atoms, or alkynyl of 2–7 carbon atoms, trifluoroalkyl of 1–6 carbon atoms, or trifluoroalkoxy of 1–6 carbon atoms; wherein the alkyl or alkenyl moieties are optionally substituted with hydroxyl, —CN, halogen, trifluoroalkyl of 1–6 carbon atoms, trifluoroalkoxy of 1–6 carbon atoms, —COR⁵, —CO₂R⁵, —NO₂, CONR⁵R⁶, NR⁵R⁶ or N(R⁵)COR⁶;

R^2 is hydrogen, hydroxyl, halogen, alkyl of 1–6 carbon atoms, trifluoroalkyl of 1–6 carbon atoms, cycloalkyl of 3–8 carbon atoms, alkoxy of 1–6 carbon atoms, trifluoroalkoxy of 1–6 carbon atoms, thioalkyl of 1–6 carbon atoms, sulfoxoalkyl of 1–6 carbon atoms, sulfonoalkyl of 1–6 carbon atoms, aryl of 6–10 carbon atoms, a 5 or 6-membered heterocyclic ring having 1 to 4 heteroatoms selected from O, N or S, —NO₂, —NR₅R₆, —N(R₅)COR₆, —CN, —CHF₂CN, —CF₂CN, alkynyl of 2–7 carbon atoms, or alkenyl of 2–7 carbon atoms; wherein the alkyl or alkenyl moieties are optionally substituted with hydroxyl, —CN, halogen, trifluoroalkyl, trifluoroalkoxy, —COR₅, —CO₂R₅, —NO₂, CONR₅R₆, NR₅R₆ or N(R₅)COR₆;

R^5 and R^6 are each, independently, hydrogen, alkyl of 1–6 carbon atoms, alkenyl of 2–7 carbon atoms, aryl of 6–10 carbon atoms, —CN, —CHF₂CN, or —CF₂CN; wherein the alkyl or alkenyl moieties are optionally substituted with hydroxyl, —CN, halogen, trifluoroalkyl of 1–6 carbon atoms, trifluoroalkoxy of 1–6 carbon atoms, —COR⁷, —CO₂R⁷, —NO₂, CONR⁷R⁸, NR⁷R⁸ or N(R⁷)COR⁸;

4

R^7 and R^8 are each, independently, hydrogen, alkyl of 1–6 carbon atoms, or aryl of 6–10 carbon atoms;

X is O, S, or NR⁹;

R^9 is hydrogen, alkyl of 1–6 carbon atoms, aryl of 6–10 carbon atoms, COR⁵, CO₂R⁵, or SO₂R⁵;

or a pharmaceutically acceptable salt thereof.

Pharmaceutically acceptable salts can be formed from organic and inorganic acids, for example, acetic, propionic, lactic, citric, tartaric, succinic, fumaric, maleic, malonic, mandelic, malic, phthalic, hydrochloric, hydrobromic, phosphoric, nitric, sulfuric, methanesulfonic, naphthalenesulfonic, benzenesulfonic, toluenesulfonic, camphorsulfonic, and similarly known acceptable aids when a compound of this invention contains a basic moiety. Salts may also be formed from organic and inorganic bases, such as alkali metal salts (for example, sodium, lithium, or potassium) alkaline earth metal salts, ammonium salts, alkylammonium salts containing 1–6 carbon atoms or dialkylammonium salts containing 1–6 carbon atoms in each alkyl group, and trialkylammonium salts containing 1–6 carbon atoms in each alkyl group, when a compound of this invention contains an acidic moiety.

The terms alkyl, alkenyl, and alkynyl include both branched and straight chain moieties. Examples include methyl, ethyl, propyl, butyl, isopropyl, sec-butyl, tert-butyl, vinyl, allyl, acetylene, 1-methyl vinyl, and the like. When alkyl or alkenyl moieties are substituted, they may typically be mono-, di-, tri- or persubstituted. Examples for a halogen substituent include 1-bromo vinyl, 1-fluoro vinyl, 1,2-difluoro vinyl, 2,2-difluorovinyl, 1,2,2-trifluorovinyl, 1,2-dibromo ethane, 1,2 difluoro ethane, 1-fluoro-2-bromo ethane, CF₂CF₃, CF₂CF₂CF₃, and the like. The term halogen includes bromine, chlorine, fluorine, and iodine. The term aryl means phenyl, 1-naphthyl, or 2-naphthyl. Preferred 5–6 membered heterocyclic rings include furan, thiophene, pyrrole, isopyrrole, pyrazole, imidazole, triazole, dithiole, oxathiole, isoxazole, oxazole, thiazole, isothiazole, oxadiazole, furazan, oxatriazole, dioxazole, oxathiazole, tetrazole, pyran, pyridine, pyridazine, pyrimidine, pyrazine, triazine, oxazine, oxathiazine, or oxadiazine. It is more preferred that the heterocyclic ring is furan, thiophene, and thiazole.


As used in accordance with this invention, the term “providing,” with respect to providing a compound or substance covered by this invention, means either directly administering such a compound or substance, or administering a prodrug, derivative, or analog which will form the effective amount of the compound or substance within the body.

Of the compounds of this invention, it is preferred that X is O or NR⁹. More preferred compounds include those in which X is O or NR⁹; R^1 is hydrogen; R^4 is hydrogen; R^2 is hydrogen, hydroxyl, halogen, alkyl of 1–6 carbon atoms, cycloalkyl of 3–8 carbon atoms, alkoxy of 1–6 carbon atoms, phenyl, trifluoroalkyl of 1–6 carbon atoms, furyl, thienyl, thiazolyl, thioalkyl of 1–6 carbon atoms, —CN, —CH₂CN, —COR⁵, CO₂R⁵, CONHR⁵R⁶, alkynyl of 2–7 carbon atoms, or alkenyl of 2–7 carbon atoms; R^3 is hydrogen, alkyl of 1–6 carbon atoms, halogen, alkoxy of 1–6 carbon atoms, or trifluoroalkyl of 1–6 carbon atoms; R^5 and R^6 are each, independently, hydrogen or alkyl of 1–6 carbon atoms; and R^9 is alkyl of 1–6 carbon atoms. Still more preferred compounds include those in which X is O or NR⁹; R^1 is hydrogen; R^2 is hydrogen or halogen; R^3 is hydrogen; R^4 is hydrogen; and R^9 is alkyl of 1–6 carbon atoms.

The reagents used in the preparation of the compounds of this invention can be either commercially obtained or can be prepared by standard procedures described in the literature.


5

The compounds of the present invention can be prepared according to the following synthetic Schemes (I-V)





6

In Scheme I, commercially available naphthoic acid 1, (or can be prepared according to known procedures), was treated with thionyl chloride to produce naphthoyl chloride 2. Coupling of chloride 2 with aniline 3 (commercially available or can be prepared according to known procedures) in the presence of triethylamine afforded amide 4. Cyclization of 4 to benzoxazole was accomplished with pyridine hydrochloride at high temperatures (200° C.).




In Scheme II, bromination of naphthol 6 with bromine in acetic acid at low temperatures (5° C.) produced bromo-naphthalene 7.






In Scheme III, commercially available bromo-naphthalene 8 (commercially available or can be prepared according to known procedures) was treated with *n*-butyllithium at low temperature (-40°C .) followed by reaction with benzaldehyde 9 (commercially available or can be prepared according to known procedures) to produce alcohol 10. Oxidation of 10 with $\text{CrO}_3/\text{H}_2\text{SO}_4$ in acetone at low temperature (10°C .) produced ketone 11. Acetone oxime was first treated with potassium tert-butoxide and then ketone 11 was added into this mixture to produce oxime 12. Cyclization of 12, under acidic conditions (i.e. 5% HCl) afforded benzisoxazole 13. Demethylation of 13 with hydriotic acid/acetic anhydride/acetic acid at high temperature (140°C .) produced naphthol 14.




In Scheme II, bromination of naphthol 15 with bromine in acetic acid at low temperature (5°C .) produced bromo-naphthalene 16.



In Scheme V, ketone 11 was treated with hydrazine 15 to produce indazole 16. Demethylation of 16 with hydriotic acid/acetic anhydride/acetic acid at high temperature (140°C .) produced naphthol 17.

Compounds having the general structure IV are useful as intermediates in the preparation of compounds of formula I, as shown above:



wherein

R^1 , R^2 , R^3 , R^4 , and X are as defined hereinbefore, and R^{10} and R^{11} are alkyl of 1–6 carbon atoms.

Standard pharmacological test procedures are readily available to determine the activity profile of a given test compound. The following briefly summarizes several representative test procedures and may include data for representative compounds of the invention. All assays, except the radioligand binding assay, can be used to detect estrogen receptor agonist or antagonist activity of compounds. In general, estrogen receptor agonist activity is measured by comparing the activity of the compound to a reference estrogen (e.g. 17β -estradiol, 17α -ethinyl, 17β -estradiol, estrone, diethylstilbesterol etc). Estrogen receptor antagonist activity is generally measured by co-treating the test compound with the reference estrogen and comparing the result to that obtained with the reference estrogen alone. Standard pharmacological test procedures for SERMs are also provided in U.S. Pat. Nos. 4,418,068 and 5,998,402 which are hereby incorporated by reference.

Evaluation of Binding Affinities to ER α and ER β

Representative examples of the invention were evaluated for their ability to compete with 17β -estradiol for both ER α and ER β in a conventional radioligand binding assay. This test procedure provides the methodology for one to determine the relative binding affinities for the ER α or ER β receptors. The procedure used is briefly described below.

Preparation of receptor extracts for characterization of binding selectivity. The ligand binding domains, conveniently defined here as all sequence downstream of the DNA binding domain, were obtained by PCR using full length cDNA as templates and primers that contained appropriate restriction sites for subcloning while maintaining the appropriate reading frame for expression. These templates contained amino acids $M_{250}V_{595}$ of human ER α [Green, et al., Nature 320: 134–9 (1986)] and $M_{214}Q_{530}$ of human ER β [Ogawa, et al., Biochemical & Biophysical Research Communications 243: 122–6 (1998)]. Human ER β was cloned into pET15b (Novagen, Madison Wis.) as a Nco1-BamH1 fragment bearing a C-terminal Flag tag. Human ER α was cloned as for human ER β except that an N-terminal His tag was added. The sequences of all constructs used were verified by complete sequencing of both strands.

BL21(DE3) cells were used to express the human proteins. Typically a 10 mL overnight culture was used to

- IV inoculate a 1 L culture of LB medium containing 100 $\mu\text{g}/\text{mL}$ of ampicillin. After incubation overnight at 37° C., IPTG was added to a final concentration of 1 mM and incubation proceeded at 25° C. for 2 hours. Cells were harvested by centrifugation (1500 \times g), and the pellets washed with and resuspended in 100 mL of 50 mM Tris-Cl (pH 7.4), 150 mM NaCl. Cells were lysed by passing twice through a French press at 12000 psi. The lysate was clarified by centrifugation at 12,000 \times g for 30 minutes at 4° C. and stored at -70° C.
- V Evaluation of extracts for specific [^3H]-estradiol binding. Dulbecco's phosphate buffered saline (Gibco, 1 \times final concentration) supplemented with 1 mM EDTA was used as the assay buffer. To optimize the amount of receptor to use in the assay, [^3H]- 17β -estradiol (New England Nuclear; final concentration=2 nM) \pm 0.6 μM diethylstilbesterol and 100 μL of various dilutions of the *E. coli* lysate were added to each well of a high binding masked microtiter plate (EG&G Wallac). The final assay volume was 120 μL and the concentration of DMSO was \leq 1%. After incubation at room temperature for 5–18 hours, unbound material was aspirated and the plate washed three times with approximately 300 μL of assay buffer. After washing, 135 μL of scintillation cocktail (Optiphase Supermix, EG&G Wallac) was added to the wells, and the plate was sealed and agitated for at least 5 minutes to mix scintillant with residual wash buffer. Bound radioactivity was evaluated by liquid scintillation counting (EG&G Wallac Microbeta Plus).
- VI

After determining the dilution of each receptor preparation that provided maximum specific binding, the assay was further optimized by estimating the IC_{50} of unlabelled 17β -estradiol using various dilutions of the receptor preparation. A final working dilution for each receptor preparation was chosen for which the IC_{50} of unlabelled 17β -estradiol was 2–4 nM.

Ligand binding competition test procedure. Test compounds were initially solubilized in DMSO and the final concentration of DMSO in the binding assay was \leq 1%. Eight dilutions of each test compound were used as an unlabelled competitor for [^3H]- 17β -estradiol. Typically, a set of compound dilutions would be tested simultaneously on human ER α and ER β . The results were plotted as measured DPM vs. concentration of test compound. For dose-response curve fitting, a four parameter logistic model on the transformed, weighted data was fit and the IC_{50} was defined as the concentration of compound decreasing maximum [^3H]-estradiol binding by 50%.

Binding affinities for ER α and ER β (as measured by IC_{50}) for representative examples of the invention are shown in Table (1).

TABLE 1

Estrogen receptor binding affinities of compounds of the invention		
Example	ER- β IC_{50} (nM)	ER- α IC_{50} (nM)
1	15	153
2	3	35
3	521	3800
4	533	780
5	5	117
6	230	581
7	1530	1900
8	1050	1880
9	134	373
10	1	8
11	112	463
12	20	24
13	2	6

TABLE 1-continued

Estrogen receptor binding affinities of compounds of the invention		
Example	ER- β IC ₅₀ (nM)	ER- α IC ₅₀ (nM)
14	17	49
15	879	1727
16	87	360
17	1510	>5000
18	>5000	3170

The results obtained in the standard pharmacologic test procedure described above demonstrate that the compounds of this invention bind both subtypes of the estrogen receptor. The IC₅₀s are generally lower for ER β , indicating these compounds are preferentially ER β selective ligands, but are still considered active at ER α . Compounds of this invention will exhibit a range of activity based, at least partially, on their receptor affinity selectivity profiles. Since the compounds of the invention bind ER- β with higher affinity than ER- α , they will be useful in treating or inhibiting diseases that can be modulated via ER- β . Additionally, since each receptor ligand complex is unique and thus its interaction with various coregulatory proteins is unique, compounds of this invention will display different and unpredictable activities depending on cellular context. For example, in some cell-types, it is possible for a compound to behave as an estrogen receptor agonist while in other tissues, an estrogen receptor antagonist. Compounds with such activity have sometimes been referred to as SERMs (Selective Estrogen Receptor Modulators). Unlike many estrogens, however, many of the SERMs do not cause increases in uterine wet weight. These compounds are antiestrogenic in the uterus and can completely antagonize the trophic effects of estrogen receptor agonists in uterine tissue. These compounds, however, act as estrogen receptor agonists in the bone, cardiovascular, and central nervous systems. Due to this tissue selective nature of these compounds, they are useful in treating or inhibiting in a mammal disease states or syndromes which are caused or associated with an estrogen deficiency (in certain tissues such as bone or cardiovascular) or an excess of estrogen (in the uterus or mammary glands). In addition, compounds of this invention also have the potential to behave as estrogen receptor agonists on one receptor type while behaving as estrogen receptor antagonists on the other. For example, it has been demonstrated that compounds can be antagonize the action of 17 β -estradiol via ER β while exhibiting estrogen receptor agonist activity with ER α [Sun, et al., *Endocrinology* 140: 800–804 (1999)]. Such ERSAA (Estrogen Receptor Selective Agonist Antagonist) activity provides for pharmacologically distinct estrogenic activity within this series of compounds

Regulation of Metallothionein II mRNA

Estrogens acting through ER β , but not ER α can upregulate metallothionein II mRNA levels in Saos-2 cells as described by Harris [*Endocrinology* 142: 645–652 (2001)]. Results from this test procedure can be combined with results from the test procedure described below (ERE reporter test procedure) to generate a selectivity profile for compounds of this invention (see also WO 00/37681). Data for representative compounds of the invention are shown in Table (2).

TABLE 2

Upregulation of metallothionein-II mRNA in Saos-2 cells by selected compounds of the invention		
Example	Fold upregulation	
1	11.6	
2	7.1	
5	6.3	

Evaluation of Test Compound using an ERE-Reporter Test Procedure in MCF-7 Breast Cancer Cells

Stock solutions of test compounds (usually 0.1 M) are prepared in DMSO and then diluted 10 to 100-fold with DMSO to make working solutions of 1 or 10 mM. The DMSO stocks are stored at either 4° C. (0.1 M) or -20° C. (<0.1M). MCF-7 cells are passaged twice a week with growth medium [D-MEM/F-12 medium containing 10% (v/v) heat-inactivated fetal bovine serum, 1% (v/v) Penicillin-Streptomycin, and 2 mM glutaMax-1]. The cells are maintained in vented flasks at 37° C. inside a 5% CO₂/95% humidified air incubator. One day prior to treatment, the cells are plated with growth medium at 25,000 cells/well into 96 well plates and incubated at 37° C. overnight.

The cells are infected for 2 hr at 37° C. with 50 μ l/well of a 1:10 dilution of adenovirus 5-ERE-tk-luciferase in experimental medium [phenol red-free D-MEM/F-12 medium containing 10% (v/v) heat-inactivated charcoal-stripped fetal bovine serum, 1% (v/v) Penicillin-Streptomycin, 2 mM glutaMax-1, 1 mM sodium pyruvate]. The wells are then washed once with 150 μ l of experimental medium. Finally, the cells are treated for 24 hr at 37° C. in replicates of 8 wells/treatment with 150 μ l/well of vehicle (<0.1% v/v DMSO) or compound that is diluted >1000-fold into experimental medium.

Initial screening of test compounds is done at a single dose of 1 μ M that is tested alone (estrogen receptor agonist mode) or in combination with 0.1 nM 17 β -estradiol (EC₈₀; estrogen receptor antagonist mode). Each 96 well plate also includes a vehicle control group (0.1% v/v DMSO) and an estrogen receptor agonist control group (either 0.1 or 1 nM 17 β -estradiol). Dose-response experiments are performed in either the estrogen receptor agonist and/or estrogen receptor antagonist modes on active compounds in log increases from 10⁻¹⁴ to 10⁻⁵ M. From these dose-response curves, EC₅₀ and IC₅₀ values, respectively, are generated. The final well in each treatment group contains 5 μ l of 3 \times 10⁻⁵ M ICI-182,780 (10⁻⁶ M final concentration) as an estrogen receptor antagonist control.

After treatment, the cells are lysed on a shaker for 15 min with 25 μ l/well of 1 \times cell culture lysis reagent (Promega Corporation). The cell lysates (20 μ l) are transferred to a 96 well luminometer plate, and luciferase activity is measured in a MicroLumat LB 96 P luminometer (EG & G Berthold) using 100 μ l/well of luciferase substrate (Promega Corporation). Prior to the injection of substrate, a 1 second background measurement is made for each well. Following the injection of substrate, luciferase activity is measured for 10 seconds after a 1 second delay. The data are transferred from the luminometer to a Macintosh personal computer and analyzed using the JMP software (SAS Institute); this program subtracts the background reading from the luciferase measurement for each well and then determines the mean and standard deviation of each treatment.

The luciferase data are transformed by logarithms, and the Huber M-estimator is used to down-weight the outlying

transformed observations. The JMP software is used to analyze the transformed and weighted data for one-way ANOVA (Dunnett's test). The compound treatments are compared to the vehicle control results in the estrogen receptor agonist mode, or the positive estrogen receptor agonist control results (0.1 nM 17 β -estradiol) in the estrogen receptor antagonist mode. For the initial single dose experiment, if the compound treatment results are significantly different from the appropriate control ($p < 0.05$), then the results are reported as the percent relative to the 17 β -estradiol control [i.e., ((compound-vehicle control)/(17 β -estradiol control-vehicle control)) $\times 100$]. The JMP software is also used to determine the EC₅₀ and/or IC₅₀ values from the non-linear dose-response curves.

Evaluation of Uterotrophic Activity

Uterotrophic activity of a test compound can be measured according to the following standard pharmacological test procedures.

Procedure 1: Sexually immature (18 days of age) Sprague-Dawley rats are obtained from Taconic and provided unrestricted access to a casein-based diet (Purina Mills 5K96C) and water. On day 19, 20 and 21 the rats are dosed subcutaneously with 17 α -ethinyl-17 β -estradiol (0.06 μ g/rat/day), test compound or vehicle (50% DMSO/50% Dulbecco's PBS). To assess estrogen receptor antagonist, compounds are coadministered with 17 α -ethinyl-17 β -estradiol (0.06 μ g/rat/day). There are six rats/group and they are euthanized approximately 24 hours after the last injection by CO₂ asphyxiation and pneumothorax. Uteri are removed and weighed after trimming associated fat and expressing any internal fluid. A tissue sample can also be snap frozen for analysis of gene expression (e.g. complement factor 3 mRNA).

Procedure 2: Sexually immature (18 days of age) 129 SvE mice are obtained from Taconic and provided unrestricted access to a casein-based diet (Purina Mills 5K96C) and water. On day 22, 23, 24 and 25 the mice are dosed subcutaneously with compound or vehicle (corn oil). There are six mice/group and they are euthanized approximately 6 hours after the last injection by CO₂ asphyxiation and pneumothorax. Uteri are removed and weighed after trimming associated fat and expressing any internal fluid.

Evaluation of Osteoporosis and Lipid Modulation (Cardioprotection)

Female Sprague-Dawley rats, ovariectomized or sham operated, are obtained 1 day after surgery from Taconic Farms (weight range 240–275 g). They are housed 3 or 4 rats/cage in a room on a 12/12 (light/dark) schedule and provided with food (Purina 5K96C rat chow) and water ad libitum. Treatment for all studies begin 1 day after arrival and rats are dosed 7 days per week as indicated for 6 weeks. A group of age matched sham operated rats not receiving any treatment serve as an intact, estrogen replete control group for each study.

All test compounds are prepared in a vehicle of 50% DMSO (JT Baker, Phillipsburg, N.J.)/1 \times Dulbecco's phosphate saline (GibcoBRL, Grand Island, N.Y.) at defined concentrations so that the treatment volume is 0.1 mL/100 g body weight. 17 β -estradiol is dissolved in corn oil (20 μ g/mL) and delivered subcutaneously, 0.1 mL/rat. All dosages are adjusted at three week intervals according to group mean body weight measurements, and given subcutaneously.

Five weeks after the initiation of treatment and one week prior to the termination of the study, each rat is evaluated for bone mineral density (BMD). The total and trabecular density of the proximal tibia are evaluated in anesthetized

rats using an XCT-960M (pQCT; Stratec Medizintechnik, Pforzheim, Germany). The measurements are performed as follows: Fifteen minutes prior to scanning, each rat is anesthetized with an intraperitoneal injection of 45 mg/kg ketamine, 8.5 mg/kg xylazine, and 1.5 mg/kg acepromazine.

The right hind limb is passed through a polycarbonate tube with a diameter of 25 mm and taped to an acrylic frame with the ankle joint at a 90° angle and the knee joint at 180°. The polycarbonate tube is affixed to a sliding platform that maintains it perpendicular to the aperture of the pQCT. The platform is adjusted so that the distal end of the femur and the proximal end of the tibia is in the scanning field. A two dimensional scout view is run for a length of 10 mm and a line resolution of 0.2 mm. After the scout view is displayed on the monitor, the proximal end of the tibia is located. The pQCT scan is initiated 3.4 mm distal from this point. The pQCT scan is 1 mm thick, has a voxel (three dimensional pixel) size of 0.140 mm, and consists of 145 projections through the slice.

After the pQCT scan is completed, the image is displayed on the monitor. A region of interest including the tibia but excluding the fibula is outlined. The soft tissue is mathematically removed using an iterative algorithm. The density of the remaining bone (total density) is reported in mg/cm³. The outer 55% of the bone is mathematically peeled away in a concentric spiral. The density of the remaining bone (Trabecular density) is reported in mg/cm³.

One week after BMD evaluation the rats are euthanized by CO₂ asphyxiation and pneumothorax, and blood is collected for cholesterol determination. The uteri are also removed and the weighed after trimming associated fat and expressing any luminal fluid. Total cholesterol is determined using a Boehringer-Mannheim Hitachi 911 clinical analyzer using the Cholesterol/HP kit. Statistics were compared using one-way analysis of variance with Dunnett's test.

Evaluation of Antioxidant Activity

Porcine aortas are obtained from an abattoir, washed, transported in chilled PBS, and aortic endothelial cells are harvested. To harvest the cells, the intercostal vessels of the aorta are tied off and one end of the aorta clamped. Fresh, sterile filtered, 0.2% collagenase (Sigma Type I) is placed in the vessel and the other end of the vessel then clamped to form a closed system. The aorta is incubated at 37° C. for 15–20 minutes, after which the collagenase solution is collected and centrifuged for 5 minutes at 2000 \times g. Each pellet is suspended in 7 mL of endothelial cell culture medium consisting of phenol red free DMEM/Ham's F12 media supplemented with charcoal stripped FBS (5%), NuSerum (5%), L-glutamine (4 mM), penicillin-streptomycin (1000 U/ml, 1000 μ g/ml) and gentamycin (75 μ g/ml), seeded in 100 mm petri dish and incubated at 37° C. in 5% CO₂. After 20 minutes, the cells are rinsed with PBS and fresh medium added, this was repeated again at 24 hours. The cells are confluent after approximately 1 week. The endothelial cells are routinely fed twice a week and, when confluent, trypsinized and seeded at a 1:7 ratio. Cell mediated oxidation of 12.5 μ g/mL LDL is allowed to proceed in the presence of the compound to be evaluated (5 μ M) for 4 hours at 37° C. Results are expressed as the percent inhibition of the oxidative process as measured by the TBARS (thiobarbituric acid reactive substances) method for analysis of free aldehydes [Yagi, Biochemical Medicine 15: 212–6 (1976)].

Progesterone Receptor mRNA Regulation Standard Pharmacological Test Procedure

This test procedure can be used to evaluate the estrogenic or antiestrogenic activity of compounds from this invention [Shughrue, et al., Endocrinology 138: 5476–5484 (1997)].

Rat Hot Flush Test Procedure

The effect of test compounds on hot flushes can be evaluated in a standard pharmacological test procedure which measures the ability of a test compound to blunt the increase in tail skin temperature which occurs as morphine-addicted rats are acutely withdrawn from the drug using naloxone [Merchenthaler, et al., *Maturitas* 30: 307–16 (1998)]. It can also be used to detect estrogen receptor antagonist activity by co-dosing test compound with the reference estrogen.

Evaluation of Vasomotor Function in Isolated Rat Aortic Rings

Sprague-Dawley rats (240–260 grams) are divided into 4 groups:

1. Normal non-ovariectomized (intact)
2. Ovariectomized (ovex) vehicle treated
3. Ovariectomized 17 β -estradiol treated (1 mg/kg/day)
4. Ovariectomized animals treated with test compound (various doses)

Animals are ovariectomized approximately 3 weeks prior to treatment. Each animal receives either 17- β estradiol sulfate (1 mg/kg/day) or test compound suspended in distilled, deionized water with 1% tween-80 by gastric gavage. Vehicle treated animals received an appropriate volume of the vehicle used in the drug treated groups.

Animals are euthanized by CO₂ inhalation and exsanguination. Thoracic aortae are rapidly removed and placed in 37° C. physiological solution with the following composition (mM): NaCl (54.7), KCl (5.0), NaHCO₃ (25.0), MgCl₂ 2H₂O (2.5), D-glucose (11.8) and CaCl₂ (0.2) gassed with CO₂-O₂, 95%/5% for a final pH of 7.4. The adventitia is removed from the outer surface and the vessel is cut into 2–3 mm wide rings. Rings are suspended in a 10 mL tissue bath with one end attached to the bottom of the bath and the other to a force transducer. A resting tension of 1 gram is placed on the rings. Rings are equilibrated for 1 hour, signals are acquired and analyzed.

After equilibration, the rings are exposed to increasing concentrations of phenylephrine (10⁻⁸ to 10⁻⁴ M) and the tension recorded. Baths are then rinsed 3 times with fresh buffer. After washout, 200 mM L-NAME is added to the tissue bath and equilibrated for 30 minutes. The phenylephrine concentration response curve is then repeated.

Evaluation of Cardioprotective Activity

Apolipoprotein E-deficient C57/B1J (apo E KO) mice are obtained from Taconic Farms. All animal procedures are performed under strict compliance to IACUC guidelines. Ovariectomized female apo E KO mice, 4–7 weeks of age, are housed in shoe-box cages and were allowed free access to food and water. The animals are randomized by weight into groups (n=12–15 mice per group). The animals are dosed with test compounds or estrogen (17 β -estradiol sulfate at 1 mg/kg/day) in the diet using a Precise-dosing Protocol, where the amount of diet consumed is measured weekly, and the dose adjusted accordingly, based on animal weight. The diet used is a Western-style diet (57U5) that is prepared by Purina and contains 0.50% cholesterol, 20% lard and 25 IU/KG Vitamin E. The animals are dosed/fed using this paradigm for a period of 12 weeks. Control animals are fed the Western-style diet and receive no compound. At the end of the study period, the animals are euthanized and plasma samples obtained. The hearts are perfused in situ, first with saline and then with neutral buffered 10% formalin solution.

For the determination of plasma lipids and lipoproteins, total cholesterol and triglycerides are determined using enzymatic methods with commercially available kits from

Boehringer Mannheim and Wako Biochemicals, respectively and analyzed using the Boehringer Mannheim Hitachi 911 Analyzer. Separation and quantification of plasma lipoproteins were performed using FPLC size fractionation. Briefly, 50–100 mL of serum is filtered and injected into Superose 12 and Superose 6 columns connected in series and eluted at a constant flow rate with 1 mM sodium EDTA and 0.15 M NaCl. Areas of each curve representing VLDL, LDL and HDL are integrated using Waters Millennium™ software, and each lipoprotein fraction is quantified by multiplying the Total Cholesterol value by the relative percent area of each respective chromatogram peak.

For the quantification of aortic atherosclerosis, the aortas are carefully isolated and placed in formalin fixative for 48–72 hours before handling. Atherosclerotic lesions are identified using Oil Red O staining. The vessels are briefly destained, and then imaged using a Nikon SMU800 microscope fitted with a Sony 3CCD video camera system in concert with IMAQ Configuration Utility (National Instrument) as the image capturing software. The lesions are quantified en face along the aortic arch using a custom threshold utility software package (Coleman Technologies). Automated lesion assessment is performed on the vessels using the threshold function of the program, specifically on the region contained within the aortic arch from the proximal edge of the brachio-cephalic trunk to the distal edge of the left subclavian artery. Aortic atherosclerosis data are expressed as percent lesion involvement strictly within this defined luminal area.

Evaluation of Cognition Enhancement

Ovariectomized rats (n=50) are habituated to an 8-arm radial arm maze for 10-min periods on each of 5 consecutive days. Animals are water-deprived prior to habituation and testing. A 100 μ L aliquot of water placed at the ends of each arm serves as reinforcement. Acquisition of a win-shift task in the radial arm maze is accomplished by allowing the animal to have access to one baited arm. After drinking, the animal exits the arm and re-enters the central compartment, where it now has access to the previously visited arm or to a novel arm. A correct response is recorded when the animal chooses to enter a novel arm. Each animal is given 5 trials per day for 3 days. After the last acquisition trial, the animals are assigned to one of the following 4 groups:

1. Negative controls: injected with 10% DMSO/ sesame oil vehicle once daily for 6 days (1 μ g/kg, SC)
 2. Positive controls: injected with 17 β -estradiol benzoate for 2 days and tested 4 days after the second injection (17 β -estradiol benzoate at 10 μ g/0.1 mL per rat)
 3. Estradiol: 17 β -estradiol will be injected daily for 6 days (20 μ g/kg, SC)
 4. Test compound: injected daily for 6 days (doses vary).
- All injections will begin after testing on the last day of acquisition. The last injection for groups 1, 3, and 4 will take place 2 hours before testing for working memory.

The test for working memory is a delayed non-matching-to-sample task (DNMS) utilizing delays of 15, 30, or 60 seconds. This task is a variation of the acquisition task in which the rat is placed in the central arena and allowed to enter one arm as before. A second arm is opened once the rat traverses halfway down the first arm, and again the rat is required to choose this arm. When it has traveled halfway down this second arm, both doors are closed and the delay is instituted. Once the delay has expired, both of the original two doors, and a third novel door, are opened simultaneously. A correct response is recorded when the animal travels halfway down the third, novel arm. An incorrect

response is recorded when the animal travels halfway down either the first or second arms. Each animal will receive 5 trials at each of the three delay intervals for a total of 15 trials per subject.

Evaluation of Effect on Pleurisy

The ability to reduce the symptoms of experimentally-induced pleurisy in rats can be evaluated according to the procedure of Cuzzocrea [Endocrinology 141: 1455–63 (2000)].

Evaluation of Protection Against Glutamate-induced Cytotoxicity (Neuroprotection)

The neuroprotective activity of compounds of this invention can be evaluated in an in vitro standard pharmacological test procedure using glutamate challenge [Zaulyanov, et al., Cellular & Molecular Neurobiology 19: 705–18 (1999); Prokai, et al., Journal of Medicinal Chemistry 44: 110–4 (2001)].

Evaluation in the Mammary End Bud Test Procedure

Estrogens are required for full ductal elongation and branching of the mammary ducts, and the subsequent development of lobulo-alveolar end buds under the influence of progesterone. In this test procedure, the mammatrophic activity of selected compounds of the invention can be evaluated according to the following standard pharmacological test procedure. Twenty-eight day old Sprague-Dawley rats (Taconic Farms, Germantown, N.Y.) are ovariectomized and rested for nine days. Animals are housed under a 12-hour light/dark cycle, fed a casein-based Purina Laboratory Rodent Diet 5K96 (Purina, Richmond, Ind.) and allowed free access to water. Rats were then dosed subcutaneously for six days with vehicle (50% DMSO (JT Baker, Phillipsburg, N.J.)/50% 1×Dulbecco's Phosphate buffered saline (GibcoBRL, Grand Island, N.Y.), 17β-estradiol (0.1 mg/kg) or test compound (20 mg/kg). For the final three days, rats are also dosed subcutaneously with progesterone (30 mg/kg). On the seventh day, rats are euthanized and a mammary fat pad excised. This fat pad is analyzed for casein kinase II mRNA as a marker of end bud proliferation. Casein kinase II mRNA is analyzed by real-time RT-PCR. Briefly, RNA is isolated following Trizol (GibcoBRL, Grand Island, N.Y.) according to the manufacturer's directions. Samples are treated with DNase I using DNA-free kit (Ambion), and casein kinase II mRNA levels are measured by real-time RT-PCR using the Taqman Gold procedure (PE Applied Biosystems). A total of 50 ng of RNA is analyzed in triplicate using casein kinase II specific primer pair (5' primer, CACACGGATGGCGCATACT; 3' primer, CTCGGGATGCACCATGAAG) and customized probe (TAMRA-CGGCACTGGTTTCCCTCACATGCT-FAM). Casein kinase II mRNA levels are normalized to 18s ribosomal RNA contained within each sample reaction using primers and probe supplied by PE Applied Biosystems.

Evaluation in the HLA Rat Standard Pharmacological Test Procedure for Inflammatory Bowel Disease

Representative compounds can be evaluated in the HLA rat standard pharmacological test procedure which emulates inflammatory bowel disease in humans. The following briefly describes the procedure used and results obtained. Male HLA-B27 rats are obtained from Taconic and provided unrestricted access to food (PMI Lab diet 5001) and water. Stool quality is observed daily and graded according to the following scale: Diarrhea=3; soft stool=2; normal stool=1. At the end of the study, serum is collected and stored at -70° C. A section of colon is prepared for histological analysis and an additional segment is analyzed for myeloperoxidase activity.

Histological analysis. Colonic tissue is immersed in 10% neutral buffered formalin. Each specimen of colon is sepa-

rated into four samples for evaluation. The formalin-fixed tissues are processed in a Tissue Tek vacuum infiltration processor (Miles, Inc; West Haven, Conn.) for paraffin embedding. The samples are sectioned at 5 μm and then stained with hematoxylin and eosin (H&E) for blinded histologic evaluations using a scale modified after Boughton-Smith. After the scores are completed the samples are unblinded, and data are tabulated and analyzed by ANOVA linear modeling with multiple mean comparisons. Sections of colonic tissue are evaluated for several disease indicators and given relative scores.

Evaluation in Two Models of Arthritis

Lewis rat assay of adjuvant-induced arthritis. Sixty, female, 12 weeks old, Lewis rats are housed according to standard facility operating procedures. They receive a standard regimen of food and water ad libitum. Each animal is identified by a cage card indicating the project group and animal number. Each rat number is marked by indelible ink marker on the tail. At least 10–21 days before study they are anesthetized and ovariectomized by standard aseptic surgical techniques.

Freund's Adjuvant-Complete (Sigma Immuno Chemicals, St. Louis, Mo.) is used to induce arthritis, each mL containing 1 mg *Mycobacterium tuberculosis* heat killed and dried, 0.85 mL mineral oil and 0.15 mL mannide monooleate Lot No. 084H8800.

The following are examples of two test procedures. Inhibition test procedure: Thirty rats are injected intradermally with 0.1 mL of Freund's Adjuvant-Complete at the base of the tail. The animals are randomized to four groups, each group containing six rats. Each day, the groups receive vehicle (50% DMSO (JT Baker, Phillipsburg, N.J.)/1× Dulbecco's phosphate saline (GibcoBRL, Grand Island, N.Y.)) or test compound (administered subcutaneously). All rats begin treatment on Day 1.

Treatment test procedure: Thirty rats are injected intradermally with 0.1 mL of Freund's Adjuvant-Complete at the base of the tail. The animals are randomized to four groups, each group containing six rats. Each day, the groups receive vehicle (50% DMSO (JT Baker, Phillipsburg, N.J.)/1× Dulbecco's phosphate saline (GibcoBRL, Grand Island, N.Y.)) or test compound (administered subcutaneously). All rats begin treatment on Day 8 after adjuvant injection.

Statistical analysis is performed using Abacus Concepts Super ANOVA. (Abacus Concepts, Inc., Berkeley, Calif.). All of the parameters of interest are subjected to Analysis of Variance with Duncan's new multiple range post hoc testing between groups. Data are expressed throughout as mean±standard deviation (SD), and differences are deemed significant if p<0.05.

The degree of arthritis severity is monitored daily in terms of the following disease indices: Hindpaw erythema, hindpaw swelling, tenderness of the joints, and movements and posture. An integer scale of 0 to 3 is used to quantify the level of erythema (0=normal paw, 1=mild erythema, 2=moderate erythema, 3=severe erythema) and swelling (0=normal paw, 1=mild swelling, 2=moderate swelling, 3=severe swelling of the hind paw). The maximal score per day is 12.

At the end of the study the rats are euthanized with CO₂, hindlimbs removed at necropsy and fixed in 10% buffered formalin, and the tarsal joints decalcified and embedded in paraffin. Histologic sections are stained with Hematoxylin and Eosin or Saffranin O—Fast Green stain.

Slides are coded so that the examiner is blinded to the treatment groups. Synovial tissue from tarsal joints is evaluated based on synovial hyperplasia, inflammatory cell

infiltration, and pannus formation [Poole and Coombs, International Archives of Allergy & Applied Immunology 54: 97–113 (1977)] as outlined below.

Category	Grade
<u>1. Synovial lining cells</u>	
a. No change	0
b. Cells enlarged, slightly thickened	1
c. Cells enlarged, increase in numbers, moderately thickened. No villus present	2
d. Cells enlarged, thickened. Villus present	3
<u>2. Fibroplasia</u>	
a. No change	0
b. Fibroplasia present under lining cells	1
c. Small areas of areolar tissue replaced by fibrous tissue	2
d. Replacement of areolar tissue by fibrous tissue	3
<u>3. Inflammatory cells</u>	
a. Occasionally seen, scattered throughout selection	0
b. Cells present in small numbers in, or just under lining cell layer and/or around blood vessels.	1
c. Small focal collection of cells may be present	2
d. Large numbers of cells present in capsule and in or under lining cell layers. Large foci often seen.	3
<u>4. Pannus</u>	
a. Not detectable	0
b. Detectable	1

In addition, articular cartilage and bone is evaluated using Mankin's histological grading system [Mankin, et al., Journal of Bone & Joint Surgery—American Volume 53: 523–37 (1971)] as shown below.

Category	Grade
<u>1. Structure</u>	
a. Normal	0
b. Surface irregularity	1
c. Pannus and surface irregularity	2
d. Clefts to transitional zone	3
e. Clefts to radial zone	4
f. Clefts to calcified zone	5
g. Complete disorganization	6
<u>2. Cells</u>	
a. Normal	0
b. Diffuse hypercellularit	1
c. Cloning	2
d. Hypocellularity	3
<u>3. Safranin-O staining</u>	
a. Normal	0
b. Slight reduction	1
c. Modest reduction	2
d. Severe reduction	3
e. No dye noted	4
<u>4. Tidemark integrity</u>	
a. Intact	0
b. Crossed by blood vessels	1

Evaluation in the HLA-B27 Rat model of arthritis. Representative compounds are evaluated in the HLA-B27 rat standard pharmacological test procedure which emulates arthritis in humans. The following briefly describes the procedure used. Male HLA-B27 rats are obtained from Taconic and provided unrestricted access to a food (PMI Lab diet 5001) and water. Joint scores and histology are evaluated as described above for the Lewis rat model of adjuvant-induced arthritis.

Evaluation in in vivo Models of Carcinogenesis

The ability of compounds of this invention to treat and inhibit various malignancies or hyperproliferic disorders can be evaluated in standard pharmacological test procedures that are readily available in the literature, and include the following two procedures.

5 Breast cancer. Athymic nu/nu (nude) mice are obtained ovariectomized from Charles River Laboratories (Wilmington, Mass.). One day prior to tumor cell injection, 10 animals are implanted with time-release pellets containing 0.36–1.7 mg 17 β -estradiol (60 or 90 day release, Innovative Research of America, Sarasota, Fla.) or a placebo. The pellet is introduced subcutaneously into the intrascapular region using a 10-gauge precision trochar. Subsequently, mice are 15 injected subcutaneously into the breast tissue with either 1 \times 10⁷ MCF-7 cells or 1 \times 10⁷ BG-1 cells. The cells are mixed with an equal volume of matrigel, a basement membrane matrix preparation to enhance tumor establishment. Test compounds can be evaluated either by dosing one day after 20 tumor cell implantation (inhibition regimen) or after tumors have reached a certain size (treatment regimen). Compounds are administered either intraperitoneally or orally in a vehicle of 1% tween-80 in saline each day. Tumor size is evaluated every three or seven days.

25 Colon cancer. The ability to treat or inhibit colon cancer can be evaluated in the test procedure of Smirnoff [Oncology Research 11: 255–64 (1999)].

Evaluation of Neuroprotection in Two in vivo Test Procedures

30 Transient global ischemia in the Mongolian gerbil. The effect of test compounds on preventing or treating brain injury in response to oxygen deprivation/reperfusion can be measured using the following test procedure.

35 Female Mongolian gerbils (60–80 g; Charles River Laboratories, Kingston, N.Y.) are housed in the Wyeth-Ayerst animal care facility (AAALAC certified) with a 12-hour light, 12-hour dark photoperiod and free access to tap water and a low-estrogen casein diet (Purina; Richmond, Ind.). After acclimation (3–5 days), gerbils are anesthetized 40 with isoflurane (2–3% mixture with O₂), ovariectomized (Day 0). Beginning the following morning (Day 1), gerbils are treated subcutaneously each day with either vehicle (10% ETOH/corn oil), 17 β -estradiol (1 mg/kg, sc) or an experimental compound. On Day 6, gerbils (n=4–5/group) 45 are anesthetized with isoflurane, the common carotid arteries visualized via a mid-line neck incision and both arteries simultaneously occluded for 5 minutes with non-traumatic micro aneurysm clips. After occlusion, the clips are removed to allow cerebral reperfusion and the neck incision closed 50 with wound clips. All animals are fasted overnight prior to the global ischemia surgery, a step that facilitates consistent ischemic injury. On Day 12, gerbils are exposed to a lethal dose of CO₂, and the brains frozen on dry ice and stored at –80° C.

55 The degree of neuronal protection is evaluated by in situ hybridization analysis of neurogranin mRNA. Briefly, 20 μ m coronal cryostat sections are collected on gelatin-coated slides, dried and stored at –80° C. At the time of processing, the desiccated slide boxes are warmed to room temperature, 60 the slides postfixed in 4% paraformaldehyde, treated with acetic anhydride and then delipidated and dehydrated with chloroform and ethanol. Processed section-mounted slides are then hybridized with 200 μ l (6 \times 10⁶ DPM/slide) of an antisense or sense (control) riboprobe for Neurogranin (³⁵S-UTP-labeled NG-241; bases 99–340). in a 50% formamide 65 hybridization mix and incubated overnight at 55° C. in a humidified slide chamber without coverslipping. The fol-

lowing morning, the slides are collected in racks, immersed in 2×SSC (0.3 M NaCl, 0.03 M sodium citrate; pH 7.0)/10 mM DTT, treated with RNase A (20 μg/ml) and washed (2×30 min) at 67° C. in 0.1×SSC to remove nonspecific label. After dehydration, the slides are opposed to BioMax (BMR-1; Kodak) X-ray film overnight.

The level of neurogranin hybridization signal is used to quantitatively assess the degree of neuronal loss in the CA1 region after injury and to evaluate the efficacy of 17β-estradiol and experimental compounds. Neurogranin mRNA is selected for these studies because it is highly expressed in the hippocampal neurons including CA1, but absent in glia and other cell types present in this brain region. Therefore, measurement of the amount of neurogranin mRNA present represents surviving neurons. Relative optical density measurements of neurogranin hybridization signal are obtained from film autoradiograms with a computer based image analysis system (C-Imaging Inc., Pittsburgh, Pa.). The results from 6 sections (40 μm apart) per animal are averaged and statistically evaluated. Numerical values are reported as the mean±SEM. One-way analysis of variance is used to test for differences in the level of neurogranin mRNA and all statements of non-difference in the results section imply that p>0.05.

Middle cerebral artery occlusion in mice. Neuroprotection can be evaluated according to the test procedures described by Dubal [see, Dubal, et al., Proceedings of the National Academy of Sciences of the United States of America 98: 1952–1957 (2001), Dubal, et al., Journal of Neuroscience 19: 6385–6393 (1999)].

Ovulation Inhibition Standard Pharmacological Test Procedure

The test procedure is used to determine whether test compounds can inhibit or change the timing of ovulation. It can also be used to determine the number of oocytes ovulated [Lundeen, et al., J Steroid Biochem Mol Biol 78: 137–143 (2001)].

Based on the results obtained in the standard pharmacological test procedures, the compounds of this invention are estrogen receptor modulators useful in the treatment or inhibition of conditions, disorders, or disease states that are at least partially mediated by an estrogen deficiency or excess, or which may be treated or inhibited through the use of an estrogenic agent. The compounds of this invention are particularly useful in treating a peri-menopausal, menopausal, or postmenopausal patient in which the levels of endogenous estrogens produced are greatly diminished. Menopause is generally defined as the last natural menstrual period and is characterized by the cessation of ovarian function, leading to the substantial diminution of circulating estrogen in the bloodstream. As used herein, menopause also includes conditions of decreased estrogen production that may be surgically, chemically, or be caused by a disease state which leads to premature diminution or cessation of ovarian function.

The compounds of this invention are also useful in inhibiting or treating other effects of estrogen deprivation including, hot flushes, vaginal or vulvar atrophy, atrophic vaginitis, vaginal dryness, pruritus, dyspareunia, dysuria, frequent urination, urinary incontinence, urinary tract infections. Other reproductive tract uses include the treatment or inhibition of dysfunctional uterine bleeding. The compounds are also useful in treating or inhibiting endometriosis.

The compounds of this invention are also active in the brain and are therefore useful for inhibiting or treating Alzheimer's disease, cognitive decline, decreased libido, senile dementia, neurodegenerative disorders, depression,

anxiety, insomnia, schizophrenia, and infertility. The compounds of this invention are also useful in treating or inhibiting benign or malignant abnormal tissue growth including, glomerulosclerosis, prostatic hypertrophy, uterine leiomyomas, breast cancer, scleroderma, fibromatosis, endometrial cancer, polycystic ovary syndrome, endometrial polyps, benign breast disease, adenomyosis, ovarian cancer, melanoma, prostate cancer, cancers of the colon, CNS cancers, such as glioma or astioblastoma.

The compounds of this invention are cardioprotective and are antioxidants, and are useful in lowering cholesterol, triglycerides, Lp(a), and LDL levels; inhibiting or treating hypercholesteremia, hyperlipidemia, cardiovascular disease, atherosclerosis, peripheral vascular disease, restenosis, and vasospasm, and inhibiting vascular wall damage from cellular events leading toward immune mediated vascular damage. The compounds of this invention are also useful in treating disorders associated with inflammation or autoimmune diseases, including inflammatory bowel disease (Crohn's disease, ulcerative colitis, indeterminate colitis), arthritis (rheumatoid arthritis, spondyloarthropathies, osteoarthritis), pleurisy, ischemia/reperfusion injury (e.g. stroke, transplant rejection, myocardial infarction, etc.), asthma, giant cell arteritis, prostatitis interstitial cystitis, uveitis, psoriasis, multiple sclerosis, systemic lupus erythematosus and sepsis.

The compounds of this invention are also useful in treating or inhibiting ocular disorders including cataracts, uveitis, and macular degeneration and in treating skin conditions such as aging, alopecia, and acne.

The compounds of this invention are also useful in treating or inhibiting metabolic disorders such as type-II diabetes, of lipid metabolism, appetite (e.g. anorexia nervosa and bulimia).

Compounds in this invention are also useful in treating or inhibiting bleeding disorders such as hereditary hemorrhagic telangiectasia, dysfunctional uterine bleeding, and combating hemorrhagic shock.

The compounds of this invention are useful in disease states where amenorrhea is advantageous, such as leukemia, endometrial ablations, chronic renal or hepatic disease or coagulation diseases or disorders.

The compounds of this invention can be used as a contraceptive agent, particularly when combined with a progestin.

When administered for the treatment or inhibition of a particular disease state or disorder, it is understood that the effective dosage may vary depending upon the particular compound utilized, the mode of administration, the condition, and severity thereof, of the condition being treated, as well as the various physical factors related to the individual being treated. Effective administration of the compounds of this invention may be given at an oral dose of from about 0.1 mg/day to about 1,000 mg/day. Preferably, administration will be from about 10 mg/day to about 600 mg/day, more preferably from about 50 mg/day to about 600 mg/day, in a single dose or in two or more divided doses. The projected daily dosages are expected to vary with route of administration.

Such doses may be administered in any manner useful in directing the active compounds herein to the recipient's bloodstream, including orally, via implants, parentally (including intravenous, intraperitoneal, intraarticularly and subcutaneous injections), rectally, intranasally, topically, ocularly (via eye drops), vaginally, and transdermally.

Oral formulations containing the active compounds of this invention may comprise any conventionally used oral forms,

including tablets, capsules, buccal forms, troches, lozenges and oral liquids, suspensions or solutions. Capsules may contain mixtures of the active compound(s) with inert fillers and/or diluents such as the pharmaceutically acceptable starches (e.g. corn, potato or tapioca starch), sugars, artificial sweetening agents, powdered celluloses, such as crystalline and microcrystalline celluloses, flours, gelatins, gums, etc. Useful tablet formulations may be made by conventional compression, wet granulation or dry granulation methods and utilize pharmaceutically acceptable diluents, binding agents, lubricants, disintegrants, surface modifying agents (including surfactants), suspending or stabilizing agents, including, but not limited to, magnesium stearate, stearic acid, talc, sodium lauryl sulfate, microcrystalline cellulose, carboxymethylcellulose calcium, polyvinylpyrrolidone, gelatin, alginic acid, acacia gum, xanthan gum, sodium citrate, complex silicates, calcium carbonate, glycine, dextrin, sucrose, sorbitol, dicalcium phosphate, calcium sulfate, lactose, kaolin, mannitol, sodium chloride, talc, dry starches and powdered sugar. Preferred surface modifying agents include nonionic and anionic surface modifying agents. Representative examples of surface modifying agents include, but are not limited to, poloxamer 188, benzalkonium chloride, calcium stearate, cetostearyl alcohol, cetomacrogol emulsifying wax, sorbitan esters, colloidal silicon dioxide, phosphates, sodium dodecylsulfate, magnesium aluminum silicate, and triethanolamine. Oral formulations herein may utilize standard delay or time release formulations to alter the absorption of the active compound(s). The oral formulation may also consist of administering the active ingredient in water or a fruit juice, containing appropriate solubilizers or emulsifiers as needed.

In some cases it may be desirable to administer the compounds directly to the airways in the form of an aerosol.

The compounds of this invention may also be administered parenterally or intraperitoneally. Solutions or suspensions of these active compounds as a free base or pharmaceutically acceptable salt can be prepared in water suitably mixed with a surfactant such as hydroxy-propylcellulose. Dispersions can also be prepared in glycerol, liquid polyethylene glycols and mixtures thereof in oils. Under ordinary conditions of storage and use, these preparations contain a preservative to inhibit the growth of microorganisms.

The pharmaceutical forms suitable for injectable use include sterile aqueous solutions or dispersions and sterile powders for the extemporaneous preparation of sterile injectable solutions or dispersions. In all cases, the form must be sterile and must be fluid to the extent that easy syringability exists. It must be stable under the conditions of manufacture and storage and must be preserved against the contaminating action of microorganisms such as bacteria and fungi. The carrier can be a solvent or dispersion medium containing, for example, water, ethanol, polyol (e.g., glycerol, propylene glycol and liquid polyethylene glycol), suitable mixtures thereof, and vegetable oils.

For the purposes of this disclosure, transdermal administrations are understood to include all administrations across the surface of the body and the inner linings of bodily passages including epithelial and mucosal tissues. Such administrations may be carried out using the present compounds, or pharmaceutically acceptable salts thereof, in lotions, creams, foams, patches, suspensions, solutions, and suppositories (rectal and vaginal).

Transdermal administration may be accomplished through the use of a transdermal patch containing the active compound and a carrier that is inert to the active compound, is non toxic to the skin, and allows delivery of the agent for

systemic absorption into the blood stream via the skin. The carrier may take any number of forms such as creams and ointments, pastes, gels, and occlusive devices. The creams and ointments may be viscous liquid or semisolid emulsions of either the oil-in-water or water-in-oil type. Pastes comprised of absorptive powders dispersed in petroleum or hydrophilic petroleum containing the active ingredient may also be suitable. A variety of occlusive devices may be used to release the active ingredient into the blood stream such as a semi-permeable membrane covering a reservoir containing the active ingredient with or without a carrier, or a matrix containing the active ingredient. Other occlusive devices are known in the literature.

Suppository formulations may be made from traditional materials, including cocoa butter, with or without the addition of waxes to alter the suppository's melting point, and glycerin. Water soluble suppository bases, such as polyethylene glycols of various molecular weights, may also be used.

The preparation of representative examples of this invention is described below.

EXAMPLE 1

2-(6-Hydroxy-1-naphthyl)-1,3-benzoxazol-5-ol

Step a) N-(2,5-Dimethoxyphenyl)-6-hydroxy-1-naphthamide.

A mixture of 6-hydroxy-1-naphthoic acid (5.0 g, 26.6 mmol) and thionyl chloride (20 mL) was refluxed for 1 h. The volatiles were then removed under vacuum. The residue was dissolved in THF (20 mL) and added into a cold (0° C.) solution of 2,5-dimethoxyaniline (4.06 g, 26.6 mmol), triethylamine (10 mL, 71.8 mmol) and THF (100 mL). The mixture was stirred for 30 min, poured into water, acidified with HCl (2N) and extracted with EtOAc. The organic extracts were dried over MgSO₄. Evaporation and purification by flash chromatography (hexanes/EtOAc 1/1) gave a tan solid (8.2 g, 95% yield, m.p. 165–166° C.); MS m/e 324 (M+H)⁺.

Analysis for: C₁₉H₁₇NO₄

Calc'd: C, 70.58; H, 5.30; N, 4.33

Found: C, 70.44; H, 5.03; N, 4.32

Step b) 2-(6-Hydroxy-1-naphthyl)-1,3-benzoxazol-5-ol

A mixture of N-(2,5-dimethoxyphenyl)-6-hydroxy-1-naphthamide (2.0 g, 6.2 mmol), and pyridine hydrochloride (4.0 g, 34.6 mmol) was heated at 200° C. for 1 h. The reaction mixture was cooled to room temperature, acidified with HCl (2N) and extracted with EtOAc. The organic extracts were dried over MgSO₄. Evaporation and purification by flash chromatography (hexanes/EtOAc 1/1) gave a tan solid (1.45 g, 85% yield, m.p. 232–234° C.); MS m/e 278 (M+H)⁺.

Analysis for: C₁₇H₁₁NO₃

Calc'd: C, 73.64; H, 4.00; N, 5.05

Found: C, 73.31; H, 3.64; N, 4.93

EXAMPLE 2

2-(6-Hydroxy-1-naphthyl)-1,3-benzoxazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 1, from 2,4-dimethoxyaniline and 6-hydroxy-1-naphthoic acid. The product was obtained as a tan solid, m.p. 273–275° C.; MS m/e 278 (M+H)⁺

Analysis for: C₁₇H₁₁NO₃

Calc'd: C, 73.64; H, 4.00; N, 5.05

Found: C, 73.17; H, 3.61; N, 4.94

25

EXAMPLE 3

2-(6-Hydroxy-2-naphthyl)-1,3-benzoxazol-5-ol

The title compound was prepared in substantially the same manner as described in Example 1, from 2,5-dimethoxyaniline and 6-methoxy-2-naphthoic acid. The product was obtained as a yellow solid, m.p. 288–290° C.; MS m/e 276 (M–H)⁺

Analysis for: C₁₇H₁₁NO₃

Calc'd: C, 73.64; H, 4.00; N, 5.05

Found: C, 72.89; H, 3.89; N, 4.59

EXAMPLE 4

2-(6-Hydroxy-2-naphthyl)-1,3-benzoxazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 1, from 2,4-dimethoxyaniline and 6-methoxy-2-naphthoic acid. The product was obtained as a tan solid, m.p. 288–290° C.; MS m/e 278 (M+H)⁺

Analysis for: C₁₇H₁₁NO₃

Calc'd: C, 73.64; H, 4.00; N, 5.05

Found: C, 73.19; H, 3.81; N, 4.87

EXAMPLE 5

2-(5-Hydroxy-1-naphthyl)-1,3-benzoxazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 1, from 2,4-dimethoxyaniline and 5-methoxy-1-naphthoic acid. The product was obtained as a yellow solid, m.p. 240–242° C.; MS m/e 278 (M+H)⁺

Analysis for: C₁₇H₁₁NO₃

Calc'd: C, 73.64; H, 4.00; N, 5.05

Found: C, 73.90; H, 3.79; N, 5.11

EXAMPLE 6

2-(4-Hydroxy-1-naphthyl)-1,3-benzoxazol-5-ol

The title compound was prepared in substantially the same manner as described in Example 1, from 2,5-dimethoxyaniline and 4-methoxy-1-naphthoic acid. The product was obtained as an off-white solid, m.p. 182–184° C.; MS m/e 278 (M+H)⁺

Analysis for: C₁₇H₁₁NO₃×0.4H₂O

Calc'd: C, 70.01; H, 4.35; N, 4.80

Found: C, 70.17; H, 4.33; N, 4.52

EXAMPLE 7

2-(4-Hydroxy-1-naphthyl)-1,3-benzoxazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 1, from 2,4-dimethoxyaniline and 4-methoxy-1-naphthoic acid. The product was obtained as an off-white solid, m.p. 194–196° C.; MS m/e 278 (M+H)⁺

Analysis for: C₁₇H₁₁NO₃×0.15H₂O

Calc'd: C, 72.23; H, 4.13; N, 4.95

Found: C, 72.01; H, 4.09; N, 4.76

EXAMPLE 8

2-(1-Naphthyl)-1,3-benzoxazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 1, from 2,4-dimethoxyaniline and 1-naphthoic acid. The product was obtained as a white solid, m.p. 185–187° C.; MS m/e 262 (M+H)⁺

Analysis for: C₁₇H₁₁NO₂

Calc'd: C, 78.15; H, 4.24; N, 5.36

Found: C, 77.56; H, 3.85; N, 5.28

26

EXAMPLE 9

2-(5-Bromo-6-hydroxy-1-naphthyl)-1,3-benzoxazol-6-ol

Bromine (86 mg, 0.54 mmol) in acetic acid (2 mL) was added dropwise into solution of 2-(6-hydroxy-1-naphthyl)-1,3-benzoxazol-6-ol (0.15 g, 0.54 mmol) and acetic acid (9 mL). The reaction mixture was stirred for 2 h, poured into water and the precipitated solid filtered and dried. The product was recrystallized from acetone/EtOAc to give a yellow solid, m.p. 221–223° C.; MS m/e 354 (M–H)⁺

Analysis for: C₁₇H₁₀BrNO₃×1.4H₂O

Calc'd: C, 50.21; H, 3.86; N, 3.44

Found: C, 49.32; H, 3.33; N, 2.85

EXAMPLE 10

3-(6-Hydroxy-2-naphthyl)-1,2-benzisoxazol-6-ol

Step a) (2-Fluoro-4-methoxyphenyl)(6-methoxy-2-naphthyl)methanol.

n-Butyllithium (2.5 M, 16.9 mL) was added dropwise into a cold (–78° C.) solution of 2-bromo-6-methoxynaphthalene (10.0 g, 42.2 mmol), and THF (200 mL). The reaction mixture was stirred at –78° C. for 2 h, and then 2-fluoro-4-methoxybenzaldehyde (6.5 g, 42.2 mmol) in THF (10 mL) was added. The mixture was allowed to warm up to 0° C. stirred for 10 min, and then quenched with aqueous ammonium chloride. The mixture was poured into water, acidified with HCl (2N) and extracted with EtOAc. The organic extracts were dried over MgSO₄. Evaporation and purification by flash chromatography (hexanes/EtOAc 3/1) gave a brown solid (12.2 g, 93% yield, m.p. 68–69° C.); MS m/e 312 (M⁺).

Analysis for: C₁₉H₁₇FO₃

Calc'd: C, 73.06; H, 5.49

Found: C, 72.25; H, 5.55

Step b) (2-Fluoro-4-methoxyphenyl)(6-methoxy-2-naphthyl)methanone.

Jones Reagent (38.5 mL) was added dropwise into a cold (10° C.) solution of (2-fluoro-4-methoxyphenyl)(6-methoxy-2-naphthyl)methanol (12.0 g, 38.46 mmol), and acetone (200 mL). The mixture was stirred for 30 min, poured into water and the precipitated solid filtered off and dried to give a brown solid (11.6 g, 97% yield, m.p. 120–122° C.); MS m/e 311 (M+H)⁺.

Analysis for: C₁₉H₁₅FO₃

Calc'd: C, 73.54; H, 4.87

Found: C, 73.08; H, 4.46

Step c) Acetone O-[5-methoxy-2-(6-methoxy-2-naphthoyl)phenyl]oxime.

Potassium tert-butoxide (1.2 g, 10.6 mmol) was added into a solution of acetone oxime (0.78 g, 10.6 mmol) and THF (15 mL). After stirring for 1 h, (2-fluoro-4-methoxyphenyl)(6-methoxy-2-naphthyl)methanone (3.0 g, 9.7 mmol) in THF (3 mL) was added. The reaction mixture was refluxed for 3 h, then cooled to room temperature, poured into aqueous ammonium chloride, and extracted with EtOAc. The organic extracts were dried over MgSO₄. Evaporation and purification by flash chromatography (hexanes/EtOAc 3/1) gave a brown solid (3.35 g, 95% yield, m.p. 117–118° C.); MS m/e 364 (M⁺).

Analysis for: C₂₂H₂₁NO₄

Calc'd: C, 72.71; H, 5.82; N, 3.85

Found: C, 72.51; H, 5.54; N, 3.74

Step d) 6-Methoxy-3-(6-methoxy-2-naphthyl)-1,2-benzisoxazole.

A mixture of acetone O[5-methoxy-2-(6-methoxy-2-naphthoyl)phenyl]oxime (3.0 g, 8.26 mmol), 5% HCl (30 mL) and EtOH (30 mL) was refluxed for 2 h. The mixture was poured into water and extracted with EtOAc. The organic extracts were dried over MgSO₄. Evaporation and

27

purification by flash chromatography (hexanes/EtOAc 2/1) gave a yellow solid (2.2 g, 87% yield, m.p. 141–143° C.); MS m/e 306 (M+H)⁺.

Analysis for: C₁₉H₁₅NO₃

Calc'd: C, 74.74; H, 4.95; N, 4.59

Found: C, 74.49; H, 4.55; N, 4.48

Step e) 3-(6-Hydroxy-2-naphthyl)-1,2-benzisoxazol-6-ol.

Hydriotic acid (57% w/w aq., 10 mL) was added into a mixture of 6-methoxy-3-(6-methoxy-2-naphthyl)-1,2-benzisoxazole (1.0 g, 3.3 mmol), acetic acid (10 mL) and acetic anhydride (5 mL). The reaction mixture was stirred at 160° C. for 2 h, and then cooled to room temperature and poured into water. The precipitated solid was filtered off and dried to give a yellow solid (0.89 g, 91% yield, m.p. 280–282° C.); MS m/e 278 (M+H)⁺.

Analysis for: C₁₇H₁₁NO₃

Calc'd: C, 73.64; H, 4.00; N, 5.05

Found: C, 72.81; H, 3.70; N, 4.85

EXAMPLE 11

3-(6-Hydroxy-2-naphthyl)-1,2-benzisoxazol-5-ol

The title compound was prepared in substantially the same manner as described in Example 10, from 2-fluoro-5-methoxybenzaldehyde and 2-bromo-6-methoxynaphthalene. The product was obtained as a yellow solid, m.p. 250–252° C.; MS m/e 278 (M+H)⁺

Analysis for: C₁₇H₁₁NO₃

Calc'd: C, 73.64; H, 4.00; N, 5.05

Found: C, 73.14; H, 3.67; N, 4.73

EXAMPLE 12

3-(5-Hydroxy-2-naphthyl)-1,2-benzisoxazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 10, from 2-fluoro-4-methoxybenzaldehyde and 2-bromo-5-methoxynaphthalene. The product was obtained as a yellow solid, m.p. 275–277° C.; MS m/e 278 (M+H)⁺

Analysis for: C₁₇H₁₁NO₃

Calc'd: C, 73.64; H, 4.00; N, 5.05

Found: C, 72.98; H, 3.79; N, 4.65

EXAMPLE 13

3-(5-Hydroxy-1-naphthyl)-1,2-benzisoxazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 10, from 2-fluoro-4-methoxybenzaldehyde and 1-bromo-5-methoxynaphthalene. The product was obtained as a yellow solid, m.p. 258–259° C.; MS m/e 278 (M+H)⁺

Analysis for: C₁₇H₁₁NO₃×0.3 HCl

Calc'd: C, 70.80; H, 3.95; N, 4.86

Found: C, 70.94; H, 3.79; N, 4.75

EXAMPLE 14

3-(6-Hydroxy-1-naphthyl)-1,2-benzisoxazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 10, from 2-fluoro-4-methoxybenzaldehyde and 1-bromo-6-methoxynaphthalene. The product was obtained as a yellow solid, m.p. 268–288° C.; MS m/e 278 (M+H)⁺

Analysis for: C₁₇H₁₁NO₃

Calc'd: C, 73.64; H, 4.00; N, 5.05

Found: C, 73.20; H, 3.77; N, 4.84

EXAMPLE 15

3-(7-Hydroxy-1-naphthyl)-1,2-benzisoxazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 10, from 2-fluoro-4-methoxybenzaldehyde and 1-bromo-7-

28

methoxynaphthalene. The product was obtained as an off-white solid, m.p. 262–264° C.; MS m/e 278 (M+H)⁺

Analysis for: C₁₇H₁₁NO₃

Calc'd: C, 73.64; H, 4.00; N, 5.05

Found: C, 72.84; H, 4.34; N, 4.71

EXAMPLE 16

3-(5-Bromo-6-hydroxy-2-naphthyl)-1,2-benzisoxazol-6-ol

Bromine (0.11 mL, 2.17 mmol) in acetic acid (3 mL) was added dropwise into cold (5° C.) mixture of 3-(6-hydroxy-2-naphthyl)-1,2-benzisoxazol-6-ol (0.6 g, 2.17 mmol) and acetic acid (10 mL). The mixture was stirred for 30 min, poured into water and extracted with EtOAc. The organic extracts were dried over MgSO₄. Evaporation and purification by flash chromatography (hexanes/EtOAc 1/1) gave an off-white solid (0.41 g, 53% yield, m.p. 275–277° C.); MS m/e 354 (M–H)⁺.

Analysis for: C₁₇H₁₀BrNO₃

Calc'd: C, 57.33; H, 2.83; N, 3.93

Found: C, 57.03; H, 2.59; N, 3.76

EXAMPLE 17

3-(6-Hydroxy-2-naphthyl)-1-methyl-1H-indazol-6-ol

Step a) 6-Methoxy-3-(6-methoxy-2-naphthyl)-1-methyl-1H-indazole.

A mixture of (2-fluoro-4-methoxyphenyl)(6-methoxy-2-naphthyl)methanone (1.0 g, 3.22 mmol), 1-methylhydrazine (0.74 g, 16.1 mmol), pyridine (10 mL), and 4-dimethylaminopyridine (0.39 g, 3.22 mmol) was stirred at 100° C. for 12 h. The mixture poured in the water, extracted with ethyl ether, washed with HCl (2N), and dried over MgSO₄. Evaporation and crystallization from ethyl ether/hexanes gave an off-white solid (0.82 g, 80% yield, m.p. 166–168° C.); MS m/e 319 (M+H)⁺.

Analysis for: C₂₀H₁₈N₂O₂

Calc'd: C, 75.45; H, 5.70; N, 8.80

Found: C, 75.11; H, 5.62; N, 8.66

Step b) 3-(6-Hydroxy-2-naphthyl)-1-methyl-1H-indazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 10, Step e, from 6-methoxy-3-(6-methoxy-2-naphthyl)-1-methyl-1H-indazole. The product was obtained as a white solid, m.p. 290–292° C.; MS m/e 290 (M)⁺

Analysis for: C₁₈H₁₄N₂O₂×0.2H₂O

Calc'd: C, 72.57; H, 5.02; N, 9.40

Found: C, 72.74; H, 5.07; N, 9.12

EXAMPLE 18

1-Ethyl-3-(6-hydroxy-2-naphthyl)-1H-indazol-6-ol

The title compound was prepared in substantially the same manner as described in Example 17, from (2-fluoro-4-methoxyphenyl)(6-methoxy-2-naphthyl)methanone and 1-ethylhydrazine. The product was obtained as a white solid, m.p. 146–148° C.; MS m/e 304 (M)⁺

Analysis for: C₁₉H₁₆N₂O₂×0.1H₂O


Calc'd: C, 74.10; H, 5.37; N, 9.10

Found: C, 74.04; H, 5.45; N, 9.09


29

What is claimed is:

1. A compound of formula I having the structure,



wherein,



R^1 , R^3 , and R^4 are each, independently, hydrogen, hydroxyl, halogen, alkyl of 1–6 carbon atoms, cycloalkyl of 3–8 carbon atoms, alkoxy of 1–4 carbon atoms, alkenyl of 2–7 carbon atoms, or alkynyl of 2–7 carbon atoms, trifluoroalkyl of 1–6 carbon atoms, or trifluoroalkoxy of 1–6 carbon atoms; wherein the alkyl or alkenyl moieties are optionally substituted with hydroxyl, —CN, halogen, trifluoroalkyl of 1–6 carbon atoms, trifluoroalkoxy of 1–6 carbon atoms, —COR⁵, —CO₂R⁵, —NO₂, CONR⁵R⁶, NR⁵R⁶ or N(R⁵)COR⁶;

R^2 is hydrogen, hydroxyl, halogen, alkyl of 1–6 carbon atoms, trifluoroalkyl of 1–6 carbon atoms, cycloalkyl of 3–8 carbon atoms, alkoxy of 1–6 carbon atoms, trifluoroalkoxy of 1–6 carbon atoms, thioalkyl of 1–6 carbon atoms, sulfoxoalkyl of 1–6 carbon atoms, sulfonoalkyl of 1–6 carbon atoms, aryl of 6–10 carbon atoms, furanyl, thienyl, —NO₂, —NR₅R₆, —N(R₅)COR₆, —CN, —CHFCN, —CF₂CN, alkynyl of 2–7 carbon atoms, or alkenyl of 2–7 carbon atoms; wherein the alkyl or alkenyl moieties are optionally substituted with hydroxyl, —CN, halogen, trifluoroalkyl, trifluoroalkoxy, —COR₅, —CO₂R₅, —NO₂, CONR₅R₆, NR₅R₆ or N(R₅)COR₆;

R^5 and R^6 are each, independently, hydrogen, alkyl of 1–6 carbon atoms, alkenyl of 2–7 carbon atoms, aryl of 6–10 carbon atoms, —CN, —CHFCN, or —CF₂CN; wherein the alkyl or alkenyl moieties are optionally substituted with hydroxyl, —CN, halogen, trifluoroalkyl of 1–6 carbon atoms, trifluoroalkoxy of 1–6 carbon atoms, —COR⁷, —CO₂R⁷, —NO₂, CONR⁷R⁸, NR⁷R⁸ or N(R⁷)COR⁸;

R^7 and R^8 are each, independently, hydrogen, alkyl of 1–6 carbon atoms, or aryl of 6–10 carbon atoms;

X is O, S;

or a pharmaceutically acceptable salt thereof.

2. The compound according to claim 1, wherein X is O or a pharmaceutically acceptable salt thereof.

3. The compound according to claim 2, wherein

R^1 is hydrogen;

R^4 is hydrogen;

R^2 is hydrogen, hydroxyl, halogen, alkyl of 1–6 carbon atoms, cycloalkyl of 3–8 carbon atoms, alkoxy of 1–6 carbon atoms, phenyl, trifluoroalkyl of 1–6 carbon atoms, furyl, thienyl, thioalkyl of 1–6 carbon atoms, —CN, —CH₂CN, —COR⁵, C₂R⁵, CONHR⁵R⁶, alkynyl of 2–7 carbon atoms, or alkenyl of 2–7 carbon atoms;

R^3 is hydrogen, alkyl of 1–6 carbon atoms, halogen, alkoxy of 1–6 carbon atoms, or trifluoroalkyl of 1–6 carbon atoms;

30

R^5 and R^6 are each, independently, hydrogen or alkyl of 1–6 carbon atoms;

or a pharmaceutically acceptable salt thereof.

4. The compound according to claim 3, wherein

X is O;

R^1 is hydrogen;

R^2 is hydrogen or halogen;

R^3 is hydrogen;

R^4 is hydrogen;

or a pharmaceutically acceptable salt thereof.

5. The compound according to claim 1, which is

a) 2-(6-Hydroxy-1-naphthyl)-1,3-benzoxazol-5-ol;

b) 2-(6-Hydroxy-1-naphthyl)-1,3-benzoxazol-6-ol;

c) 2-(6-Hydroxy-2-naphthyl)-1,3-benzoxazol-5-ol;

d) 2-(6-Hydroxy-2-naphthyl)-1,3-benzoxazol-6-ol;

e) 2-(5-Hydroxy-1-naphthyl)-1,3-benzoxazol-6-ol;

f) 2-(4-Hydroxy-1-naphthyl)-1,3-benzoxazol-5-ol;


g) 2-(4-Hydroxy-1-naphthyl)-1,3-benzoxazol-6-ol;

h) 2-(5-Bromo-6-hydroxy-1-naphthyl)-1,3-benzoxazol-6-ol;


or a pharmaceutically acceptable salt thereof.

6. A compound which is 2-(1-naphthyl)-1,3-benzoxazol-6-ol or a pharmaceutically acceptable salt thereof.

7. A compound of formula IV having the structure



wherein,



wherein

R^1 , R^3 , and R^4 are each independently, hydrogen, hydroxyl, halogen, alkyl of 1–6 carbon atoms, cycloalkyl of 3–8 carbon atoms, alkoxy of 1–4 carbon atoms, alkenyl of 2–7 carbon atoms, or alkynyl of 2–7 carbon atoms, trifluoroalkyl of 1–6 carbon atoms, or trifluoroalkoxy of 1–6 carbon atoms; wherein the alkyl or alkenyl moieties are optionally substituted with hydroxyl, —CN, halogen, trifluoroalkyl of 1–6 carbon atoms, trifluoroalkoxy of 1–6 carbon atoms, —COR⁵, —CO₂R⁵, —NO₂, CONR⁵R⁶, NR⁵R⁶ or N(R⁵)COR⁶;

R^2 is hydrogen, hydroxyl, halogen, alkyl of 1–6 carbon atoms, trifluoroalkyl of 1–6 carbon atoms, cycloalkyl of 3–8 carbon atoms, alkoxy of 1–6 carbon atoms, trifluoroalkoxy of 1–6 carbon atoms, thioalkyl of 1–6 carbon atoms, sulfoxoalkyl of 1–6 carbon atoms, sulfonoalkyl of 1–6 carbon atoms, aryl of 6–10 carbon atoms, furanyl, thienyl, —NO₂, —NR₅R₆, —N(R₅)COR₆, —CN, —CHFCN, —CF₂CN, alkynyl of 2–7 carbon atoms, or alkenyl of 2–7 carbon atoms; wherein the alkyl or alkenyl moieties are optionally substituted with hydroxyl, —CN, halogen, trifluoroalkyl, trifluoroalkoxy, —COR₅, —CO₂R₅, —NO₂, CONR₅R₆, NR₅R₆ or N(R₅)COR₆;

31

R⁵ and R⁶ are each, independently, hydrogen, alkyl of 1–6 carbon atoms, alkenyl of 2–7 carbon atoms, aryl of 6–10 carbon atoms, —CN, —CHFCN, or —CF₂CN; wherein the alkyl or alkenyl moieties are optionally substituted with hydroxyl, —CN, halogen, trifluoroalkyl of 1–6 carbon atoms, trifluoroalkoxy of 1–6 carbon atoms, —COR⁷, —CO₂R⁷, —NO₂, CONR⁷R⁸, NR⁷R⁸ or N(R⁷)COR⁸;

32

R⁷ and R⁸ are each, independently, hydrogen, alkyl of 1–6 carbon atoms, or aryl of 6–10 carbon atoms;

X is O, S; and

R¹⁰ and R¹¹ are alkyl of 1–6 carbon atoms.

* * * * *