

US009509415B1

(12) **United States Patent**
Henry et al.

(10) **Patent No.:** **US 9,509,415 B1**
(45) **Date of Patent:** **Nov. 29, 2016**

(54) **METHODS AND APPARATUS FOR INDUCING A FUNDAMENTAL WAVE MODE ON A TRANSMISSION MEDIUM**

(56) **References Cited**

U.S. PATENT DOCUMENTS

(71) Applicant: **AT&T INTELLECTUAL PROPERTY I, LP**, Atlanta, GA (US)

529,290 A	11/1894	Harry et al.
1,721,785 A	7/1929	Meyer
1,860,123 A	5/1932	Yagi
2,129,711 A	9/1938	Southworth
2,147,717 A	2/1939	Schelkunoff
2,187,908 A	1/1940	McCreary
2,199,083 A	4/1940	Schelkunoff
2,232,179 A	2/1941	King
2,283,935 A	5/1942	King
2,398,095 A	4/1946	Katzin
2,402,622 A	6/1946	Hansen
2,407,068 A	9/1946	Fiske et al.
2,407,069 A	9/1946	Fiske

(72) Inventors: **Paul Shala Henry**, Holmdel, NJ (US); **Robert Bennett**, Southold, NY (US); **Farhad Barzegar**, Branchburg, NJ (US); **Irwin Gerszberg**, Kendall Park, NJ (US); **Donald J Barnickel**, Flemington, NJ (US); **Thomas M. Willis, III**, Tinton Falls, NJ (US)

(Continued)

(73) Assignee: **AT&T Intellectual Property I, L.P.**, Atlanta, GA (US)

FOREIGN PATENT DOCUMENTS

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 0 days.

AU	565039 B2	9/1987
AU	7261000 A	4/2001

(Continued)

(21) Appl. No.: **14/750,866**

OTHER PUBLICATIONS

(22) Filed: **Jun. 25, 2015**

“Cband & L/Sband Telemetry Horn Antennas,” mWAVE, mwavelc.com, <http://www.mwavelc.com/custom-Band-LS-BandTelemetryHornAntennas.php>, Jul. 7, 2012.

(51) **Int. Cl.**
H04B 10/90 (2013.01)
H01P 3/16 (2006.01)

(Continued)

(52) **U.S. Cl.**
CPC **H04B 10/90** (2013.01); **H01P 3/16** (2013.01)

Primary Examiner — Siu Lee


(74) *Attorney, Agent, or Firm* — Guntin & Gust, PLC; Ed Guntin

(58) **Field of Classification Search**
CPC H01P 1/16; H01P 1/161; H01P 1/20; H01P 3/00; H01P 3/06; H01P 3/02; H01P 3/04; H01P 3/08; H01P 3/10; H04B 3/50; H04B 3/52
USPC 375/256, 288, 295; 333/109, 113, 114, 333/122, 134, 136, 137, 156, 157, 202, 209
See application file for complete search history.

(57) **ABSTRACT**

Aspects of the subject disclosure may include, for example, a system for generating electromagnetic waves having a fundamental wave mode, and directing the electromagnetic waves to an interface of a transmission medium for guiding propagation of the electromagnetic waves. Other embodiments are disclosed.

26 Claims, 42 Drawing Sheets



(56)

References Cited

U.S. PATENT DOCUMENTS

2,411,338 A	11/1946	Roberts	3,623,114 A	11/1971	Seaton
2,415,807 A	2/1947	Barrow et al.	3,668,459 A	6/1972	Symons et al.
2,420,007 A	5/1947	Olden	3,668,574 A	6/1972	Barlow
2,422,058 A	6/1947	Whinnery	3,672,202 A	6/1972	Barber et al.
2,432,134 A	12/1947	Bagnall	3,686,596 A	8/1972	Albee
2,461,005 A	2/1949	Southworth	3,699,574 A	10/1972	Plunk et al.
2,471,021 A	5/1949	Bradley	3,725,937 A	4/1973	Schreiber
2,488,400 A	11/1949	Harder	3,772,528 A	11/1973	Anderson et al.
2,514,679 A	7/1950	Southworth	3,806,931 A	4/1974	Wright
2,519,603 A	8/1950	Reber	3,833,909 A	9/1974	Schaufelberger
2,540,839 A	2/1951	Southworth	3,835,407 A	9/1974	Yariv et al.
2,542,980 A	2/1951	Barrow	3,896,380 A	7/1975	Martin
2,557,110 A	6/1951	Jaynes	3,935,577 A	1/1976	Hansen et al.
2,562,281 A	7/1951	Mumford	3,936,838 A	2/1976	Foldes et al.
2,596,190 A	5/1952	Wiley	3,959,794 A *	5/1976	Chrepta H01Q 13/20 257/428
2,677,055 A	4/1954	Allen	4,010,799 A	3/1977	Kern et al.
2,685,068 A	7/1954	Goubau	4,020,431 A	4/1977	Saunders et al.
2,688,732 A	9/1954	Kock	4,026,632 A	5/1977	Hill et al.
2,691,766 A	10/1954	Clapp	4,030,048 A	6/1977	Foldes et al.
2,706,279 A	4/1955	Aron	4,035,054 A	7/1977	Lattanzi et al.
2,711,514 A	6/1955	Rines	4,080,600 A	3/1978	Toman et al.
2,723,378 A	11/1955	Clavier et al.	4,123,759 A	10/1978	Hines et al.
2,727,232 A	12/1955	Pryga	4,149,170 A	4/1979	Campbell et al.
2,740,826 A	4/1956	Bondon	4,156,241 A	5/1979	Mobley et al.
2,745,101 A	5/1956	Marie	4,188,595 A	2/1980	Cronson et al.
2,749,545 A	6/1956	Kostriza	4,190,137 A	2/1980	Shimada et al.
2,754,513 A	7/1956	Goubau	4,210,357 A	7/1980	Adachi et al.
2,761,137 A	8/1956	Atta et al.	4,216,449 A	8/1980	Kach
2,769,147 A	10/1956	Black et al.	4,234,753 A	11/1980	Clutter
2,794,959 A	6/1957	Fox	4,238,974 A	12/1980	Fawcett et al.
2,805,415 A	9/1957	Berkowitz	4,246,584 A	1/1981	Noerpel et al.
2,806,972 A	9/1957	Sensiper	4,274,097 A	6/1981	Krall et al.
2,810,111 A	10/1957	Cohn	4,278,955 A	7/1981	Lunden et al.
2,820,083 A	1/1958	Hendrix	4,293,833 A	10/1981	Popa et al.
2,835,871 A	5/1958	Raabe	4,316,646 A	2/1982	Siebens et al.
2,867,776 A	1/1959	Wilkinson, Jr.	4,319,074 A	3/1982	Yaste et al.
2,912,695 A	11/1959	Cutler	4,329,690 A	5/1982	Parker et al.
2,914,741 A	11/1959	Unger	4,333,082 A	6/1982	Susman et al.
2,921,277 A	1/1960	Goubau	4,336,719 A	6/1982	Lynnworth
2,949,589 A	8/1960	Hafner	4,345,256 A	8/1982	Rainwater et al.
2,972,148 A	2/1961	Rupp et al.	4,366,565 A	12/1982	Herskowitz
2,974,297 A	3/1961	Ros	4,378,143 A	3/1983	Winzer et al.
3,040,278 A	6/1962	Griemsmann et al.	4,398,058 A	8/1983	Gerth et al.
3,072,870 A	1/1963	Walker	4,398,121 A	8/1983	Chodorow et al.
3,101,472 A	8/1963	Goubau	4,482,899 A	11/1984	Dragone et al.
3,109,175 A	10/1963	Lloyd	4,491,386 A	1/1985	Negishi et al.
3,129,356 A	4/1964	Phillips	4,525,432 A	6/1985	Saito et al.
3,134,951 A	5/1964	Huber et al.	4,533,875 A	8/1985	Lau et al.
3,146,297 A	8/1964	Hahne	4,541,303 A	9/1985	Kuzunishi et al.
3,146,453 A	8/1964	Hagaman	4,550,271 A	10/1985	Lau et al.
3,201,724 A	8/1965	Hafner	4,556,271 A	12/1985	Hubbard
3,218,384 A	11/1965	Shaw	4,558,325 A	12/1985	Stroem et al.
3,234,559 A	2/1966	Bartholoma et al.	4,566,012 A	1/1986	Choung et al.
3,255,454 A	6/1966	Walter et al.	4,567,401 A	1/1986	Barnett et al.
3,296,364 A	1/1967	Jefferson et al.	4,573,215 A	2/1986	Oates et al.
3,316,344 A	4/1967	Toms et al.	4,598,262 A	7/1986	Chen et al.
3,316,345 A	4/1967	Toms et al.	4,604,627 A	8/1986	Saad et al.
3,321,763 A	5/1967	Ikrath et al.	4,636,753 A	1/1987	Geller et al.
3,389,394 A	6/1968	Lewis et al.	4,641,916 A	2/1987	Oestreich et al.
3,392,395 A	7/1968	Hannan	4,660,050 A	4/1987	Phillips et al.
3,411,112 A	11/1968	Honig et al.	4,665,660 A	5/1987	Krall et al.
3,413,642 A	11/1968	Cook	4,680,558 A	7/1987	Ghosh et al.
3,414,903 A	12/1968	Bartlett et al.	4,704,611 A	11/1987	Edwards et al.
3,427,573 A	2/1969	White et al.	4,715,695 A	12/1987	Nishimura et al.
3,459,873 A	8/1969	Harris et al.	4,730,172 A	3/1988	Bengeult
3,487,158 A	12/1969	Killian	4,730,888 A	3/1988	Darcie et al.
3,500,422 A	3/1970	Grady et al.	4,731,810 A	3/1988	Watkins
3,509,463 A	4/1970	Woodward et al.	4,743,916 A	5/1988	Bengeult
3,522,560 A	8/1970	Hayany	4,745,377 A	5/1988	Stern et al.
3,524,192 A	8/1970	Sakiotis et al.	4,749,244 A	6/1988	Luh
3,530,481 A	9/1970	Tanaka et al.	4,758,962 A	7/1988	Fernandes
3,531,803 A	9/1970	Hudspeth et al.	4,764,738 A	8/1988	Fried et al.
3,557,341 A	1/1971	Sochilin et al.	4,772,891 A	9/1988	Svy
3,589,121 A	6/1971	Mulvey	4,786,913 A	11/1988	Barendregt et al.
3,609,247 A	9/1971	Halstead	4,792,812 A	12/1988	Rinehart et al.
			4,799,031 A	1/1989	Lang et al.
			4,818,963 A	4/1989	Green et al.
			4,818,990 A	4/1989	Fernandes

(56)

References Cited

U.S. PATENT DOCUMENTS

4,829,310 A	5/1989	Losee et al.	5,630,223 A	5/1997	Bahu et al.
4,831,346 A	5/1989	Brooker et al.	5,637,521 A	6/1997	Rhodes et al.
4,835,517 A	5/1989	van der Gracht et al.	5,640,168 A	6/1997	Heger et al.
4,845,508 A	7/1989	Krall et al.	5,650,788 A	7/1997	Jha
4,849,611 A	7/1989	Whitney et al.	5,652,554 A	7/1997	Krieg et al.
4,851,788 A	7/1989	Ives et al.	5,671,304 A	9/1997	Duguay
4,873,534 A	10/1989	Wohlleben et al.	5,677,909 A	10/1997	Heide
4,886,980 A	12/1989	Fernandes et al.	5,684,495 A	11/1997	Dyott et al.
4,897,663 A	1/1990	Kusano et al.	5,724,168 A	3/1998	Oschmann et al.
4,904,996 A	2/1990	Fernandes	5,784,683 A	7/1998	Sistanizadeh et al.
4,915,468 A	4/1990	Kim et al.	5,793,334 A	8/1998	Harrison et al.
4,929,962 A	5/1990	Begout et al.	5,818,396 A	10/1998	Harrison et al.
4,931,808 A	6/1990	Munson et al.	5,818,512 A	10/1998	Fuller
4,946,202 A	8/1990	Perricone et al.	5,850,199 A	12/1998	Wan et al.
4,977,618 A	12/1990	Allen	5,854,608 A	12/1998	Leisten
5,006,846 A	4/1991	Granville et al.	5,861,843 A	1/1999	Sorace et al.
5,015,914 A	5/1991	Ives et al.	5,870,060 A	2/1999	Chen et al.
5,017,936 A	5/1991	Massey et al.	5,873,324 A	2/1999	Kaddas et al.
5,017,937 A	5/1991	Newham et al.	5,890,055 A	3/1999	Chu et al.
5,019,832 A	5/1991	Ekdahl et al.	5,898,133 A	4/1999	Bleich et al.
5,042,903 A	8/1991	Jakubowski et al.	5,898,830 A	4/1999	Wesinger, Jr. et al.
5,043,538 A	8/1991	Hughey et al.	5,900,847 A	5/1999	Ishikawa et al.
5,043,629 A	8/1991	Doane et al.	5,903,373 A	5/1999	Welch et al.
5,044,722 A	9/1991	Voser et al.	5,905,949 A	5/1999	Hawkes et al.
5,082,349 A	1/1992	Cordova-Plaza et al.	5,917,977 A	6/1999	Barrett et al.
5,086,467 A	2/1992	Malek	5,926,128 A	7/1999	Brash et al.
5,107,231 A	4/1992	Knox et al.	5,936,589 A	8/1999	Kawahata
5,109,232 A	4/1992	Monte et al.	5,948,044 A	9/1999	Varley et al.
5,117,237 A	5/1992	Legg	5,952,964 A	9/1999	Chan et al.
5,132,968 A	7/1992	Cephus	5,952,972 A	9/1999	Ittipiboon et al.
5,134,251 A	7/1992	Martin et al.	5,977,650 A	11/1999	Rickard et al.
5,134,965 A	8/1992	Tokuda et al.	5,982,276 A	11/1999	Stewart
5,142,767 A	9/1992	Adams et al.	5,986,331 A	11/1999	Letavic et al.
5,148,509 A	9/1992	Kannabiran et al.	5,994,984 A	11/1999	Stancil et al.
5,153,676 A	10/1992	Bergh et al.	5,994,998 A	11/1999	Fisher et al.
5,174,164 A	12/1992	Wilheim et al.	6,005,758 A	12/1999	Spencer et al.
5,182,427 A	1/1993	McGaffigan et al.	6,011,520 A	1/2000	Howell et al.
5,187,409 A	2/1993	Ito et al.	6,014,110 A	1/2000	Bridges et al.
5,198,823 A	3/1993	Litchford et al.	6,023,619 A	2/2000	Kaminsky
5,212,755 A	5/1993	Holmberg et al.	6,026,208 A	2/2000	Will et al.
5,214,394 A	5/1993	Wong et al.	6,026,331 A	2/2000	Feldberg et al.
5,235,662 A	8/1993	Prince et al.	6,037,894 A	3/2000	Pfizenmaier et al.
5,248,876 A	9/1993	Kerstens et al.	6,049,647 A	4/2000	Register et al.
5,254,809 A	10/1993	Martin	6,063,234 A	5/2000	Chen et al.
5,265,266 A	11/1993	Trinh	6,078,297 A	6/2000	Kormanyos et al.
5,266,961 A	11/1993	Milroy et al.	6,088,001 A	7/2000	Burger et al.
5,278,687 A	1/1994	Jannson et al.	6,100,846 A	8/2000	Li et al.
5,291,211 A	3/1994	Tropper et al.	6,103,031 A	8/2000	Aeschbacher et al.
5,311,596 A	5/1994	Scott et al.	6,114,998 A	9/2000	Schefte et al.
5,329,285 A	7/1994	McCandless et al.	6,140,911 A	10/2000	Fisher et al.
5,341,088 A	8/1994	David	6,150,612 A	11/2000	Grandy et al.
5,345,522 A	9/1994	Vali et al.	6,151,145 A	11/2000	Srivastava et al.
5,371,623 A	12/1994	Eastmond et al.	6,154,488 A	11/2000	Hunt
5,380,224 A	1/1995	DiCicco	6,158,383 A	12/2000	Watanabe et al.
5,389,442 A	2/1995	Kathiresan et al.	6,166,694 A	12/2000	Ying et al.
5,410,318 A	4/1995	Wong et al.	6,184,828 B1	2/2001	Shoki et al.
5,412,654 A	5/1995	Perkins	6,195,395 B1	2/2001	Frodsham et al.
5,428,818 A	6/1995	Meidan et al.	6,208,161 B1	3/2001	Suda et al.
5,434,575 A	7/1995	Jelinek et al.	6,211,837 B1	4/2001	Crouch et al.
5,440,660 A	8/1995	Dombrowski et al.	6,222,503 B1	4/2001	Gietema et al.
5,479,176 A	12/1995	Zavrel et al.	6,225,960 B1	5/2001	Collins et al.
5,481,268 A	1/1996	Higgins	6,229,327 B1	5/2001	Boll et al.
5,482,525 A	1/1996	Kajitoka et al.	6,239,379 B1	5/2001	Cotter et al.
5,486,839 A	1/1996	Rodeffer et al.	6,246,821 B1	6/2001	Hemken et al.
5,495,546 A	2/1996	Bottoms et al.	6,259,337 B1	7/2001	Wen et al.
5,499,311 A	3/1996	DeCusatis et al.	6,266,016 B1	7/2001	Bergstedt et al.
5,512,906 A	4/1996	Speciale et al.	6,266,025 B1	7/2001	Popa et al.
5,515,059 A	5/1996	How et al.	6,271,790 B2	8/2001	Smith et al.
5,528,208 A	6/1996	Kobayashi et al.	6,271,952 B1	8/2001	Epworth et al.
5,543,000 A	8/1996	Lique	6,278,357 B1	8/2001	Croushore et al.
5,559,359 A	9/1996	Reyes	6,282,354 B1	8/2001	Jones et al.
5,566,022 A	10/1996	Segev	6,292,143 B1	9/2001	Romanofsky et al.
5,566,196 A	10/1996	Scifres	6,301,420 B1	10/2001	Greenaway et al.
5,592,183 A	1/1997	Henf	6,323,819 B1	11/2001	Ergene et al.
5,619,015 A	4/1997	Kirma	6,329,959 B1	12/2001	Varadan et al.
			6,351,247 B1	2/2002	Linstrom et al.
			6,362,789 B1	3/2002	Trumbull et al.
			6,366,238 B1	4/2002	DeMore et al.
			6,404,773 B1	6/2002	Williams et al.

(56)

References Cited

U.S. PATENT DOCUMENTS

6,421,021 B1	7/2002	Rupp et al.	6,909,893 B2	6/2005	Aoki et al.
6,433,736 B1	8/2002	Timothy et al.	6,917,974 B1	7/2005	Stytz et al.
6,433,741 B2	8/2002	Tanizaki et al.	6,920,289 B2	7/2005	Zimmerman et al.
6,436,536 B2	8/2002	Peruzzotti et al.	6,922,135 B2	7/2005	Abraham et al.
6,445,774 B1	9/2002	Kidder et al.	6,934,655 B2	8/2005	Jones et al.
6,452,467 B1	9/2002	McEwan	6,937,595 B2	8/2005	Barzegar et al.
6,455,769 B1	9/2002	Belli et al.	6,944,555 B2	9/2005	Blackett et al.
6,456,251 B1	9/2002	Rao et al.	6,947,635 B2	9/2005	Kohns et al.
6,462,700 B1	10/2002	Schmidt et al.	6,950,567 B2	9/2005	Kline et al.
6,469,676 B1	10/2002	Fehrenbach et al.	6,958,729 B1	10/2005	Metz et al.
6,483,470 B1	11/2002	Hohnstein et al.	6,965,302 B2	11/2005	Mollenkopf et al.
6,489,928 B2	12/2002	Sakurada	6,965,355 B1	11/2005	Durham et al.
6,501,433 B2	12/2002	Popa et al.	6,972,729 B2	12/2005	Wang et al.
6,515,635 B2	2/2003	Chiang et al.	6,980,091 B2	12/2005	White, II et al.
6,522,305 B2	2/2003	Sharman et al.	6,982,611 B2	1/2006	Cope et al.
6,531,991 B2	3/2003	Adachi et al.	6,982,679 B2	1/2006	Kralovec et al.
6,542,739 B1	4/2003	Garner	6,992,639 B1	1/2006	Lier et al.
6,549,106 B2	4/2003	Martin et al.	6,999,667 B2	2/2006	Jang et al.
6,549,173 B1	4/2003	King et al.	7,008,120 B2	3/2006	Zaborsky et al.
6,552,693 B1	4/2003	Leisten et al.	7,009,471 B2	3/2006	Elmore
6,563,981 B2	5/2003	Weisberg et al.	7,012,572 B1	3/2006	Schaffner et al.
6,567,573 B1	5/2003	Domash et al.	7,016,585 B2	3/2006	Diggle, III et al.
6,573,813 B1	6/2003	Joannopoulos et al.	7,023,400 B2	4/2006	Hill et al.
6,580,295 B2	6/2003	Takekuma et al.	7,032,016 B2	4/2006	Cerami et al.
6,584,084 B1	6/2003	Barany et al.	7,039,048 B1	5/2006	Monta et al.
6,584,252 B1	6/2003	Schier et al.	7,042,403 B2	5/2006	Sievenpiper et al.
6,596,944 B1	7/2003	Clark et al.	7,042,416 B2	5/2006	Kingsley et al.
6,606,066 B1	8/2003	Fawcett et al.	7,042,420 B2	5/2006	Ebling et al.
6,606,077 B2	8/2003	Ebling et al.	7,054,286 B2	5/2006	Ertel et al.
6,631,229 B1	10/2003	Norris et al.	7,054,513 B2	5/2006	Herz et al.
6,639,566 B2	10/2003	Knop et al.	7,055,148 B2	5/2006	Marsh et al.
6,650,296 B2	11/2003	Wong et al.	7,068,998 B2	6/2006	Zavidniak et al.
6,653,598 B2	11/2003	Sullivan et al.	7,098,405 B2	8/2006	Glew et al.
6,659,655 B2	12/2003	Dair et al.	7,098,773 B2	8/2006	Berkman et al.
6,671,824 B1	12/2003	Hyland et al.	7,102,581 B1	9/2006	West et al.
6,677,899 B1	1/2004	Lee et al.	7,106,265 B2	9/2006	Robertson et al.
6,683,580 B2	1/2004	Kuramoto	7,113,002 B2	9/2006	Otsuka et al.
6,686,832 B2	2/2004	Abraham et al.	7,113,134 B1	9/2006	Berkman et al.
6,686,873 B2	2/2004	Patel et al.	7,119,755 B2	10/2006	Harvey et al.
6,686,875 B1	2/2004	Wolfson et al.	7,120,345 B2	10/2006	Naitou et al.
6,697,030 B2	2/2004	Gleener	7,123,801 B2	10/2006	Fitz et al.
6,703,981 B2	3/2004	Meitzler et al.	7,126,711 B2	10/2006	Fruth
6,714,165 B2	3/2004	Verstraeten	7,130,516 B2	10/2006	Wu et al.
6,725,035 B2	4/2004	Jochim et al.	7,132,950 B2	11/2006	Stewart et al.
6,727,470 B2	4/2004	Reichle et al.	7,133,930 B2	11/2006	Sabio et al.
6,731,649 B1	5/2004	Silverman	7,134,012 B2	11/2006	Doyle et al.
6,741,705 B1	5/2004	Nelson et al.	7,134,135 B2	11/2006	Cerami et al.
6,750,827 B2	6/2004	Manasson et al.	7,137,605 B1	11/2006	Guertler et al.
6,765,479 B2	7/2004	Stewart et al.	7,145,440 B2	11/2006	Gerszberg et al.
6,768,456 B1	7/2004	Lalezari et al.	7,151,497 B2	12/2006	Crystal et al.
6,768,471 B2	7/2004	Bostwick et al.	7,161,934 B2	1/2007	Buchsbaum et al.
6,768,474 B2	7/2004	Hunt et al.	7,167,139 B2	1/2007	Kim et al.
6,771,216 B2	8/2004	Patel et al.	7,171,087 B2	1/2007	Takahashi et al.
6,771,225 B2	8/2004	Tits et al.	7,176,589 B2	2/2007	Rouquette et al.
6,771,739 B1	8/2004	Beamon et al.	7,180,459 B2	2/2007	Damini et al.
6,788,865 B2	9/2004	Kawanishi et al.	7,180,467 B2	2/2007	Fabrega-Sanchez
6,788,951 B2	9/2004	Aoki et al.	7,194,528 B1	3/2007	Davidow et al.
6,789,119 B1	9/2004	Zhu et al.	7,200,658 B2	4/2007	Goeller et al.
6,812,895 B2	11/2004	Anderson et al.	7,205,950 B2	4/2007	Imai et al.
6,822,615 B2	11/2004	Quan et al.	7,212,163 B2	5/2007	Huang et al.
6,839,846 B2	1/2005	Mangold et al.	7,215,220 B1	5/2007	Jia et al.
6,842,157 B2	1/2005	Phelan et al.	7,215,928 B2	5/2007	Gage et al.
6,842,430 B1	1/2005	Melnik et al.	7,218,285 B2	5/2007	Davis et al.
6,850,128 B2	2/2005	Park	7,224,243 B2	5/2007	Cope et al.
6,859,185 B2	2/2005	Royalty et al.	7,224,320 B2	5/2007	Cook et al.
6,859,590 B1	2/2005	Zacccone	7,228,123 B2	6/2007	Moursund et al.
6,867,744 B2	3/2005	Toncich et al.	7,234,413 B2	6/2007	Suzuki et al.
6,868,258 B2	3/2005	Hayata et al.	7,234,895 B2	6/2007	Richardson et al.
6,870,465 B1	3/2005	Song et al.	7,239,284 B1	7/2007	Staal et al.
6,885,674 B2	4/2005	Hunt et al.	7,243,610 B2	7/2007	Ishii et al.
6,886,065 B2	4/2005	Sides et al.	7,248,148 B2	7/2007	Kline et al.
6,888,623 B2	5/2005	Clements	7,260,424 B2	8/2007	Schmidt et al.
6,901,064 B2	5/2005	Billhartz et al.	7,266,154 B2	9/2007	Gundrum et al.
6,904,218 B2	6/2005	Sun et al.	7,266,275 B2	9/2007	Hansen et al.
6,906,676 B2	6/2005	Killen et al.	7,272,281 B2	9/2007	Stahulak et al.
			7,274,305 B1	9/2007	Luttrell
			7,276,990 B2	10/2007	Sievenpiper et al.
			7,280,033 B2	10/2007	Berkman et al.
			7,289,704 B1	10/2007	Wagman et al.

(56)

References Cited

U.S. PATENT DOCUMENTS

7,297,869 B2	11/2007	Hiller et al.	7,596,222 B2	9/2009	Jonas et al.
7,307,596 B1	12/2007	West et al.	7,598,844 B2	10/2009	Corcoran et al.
7,308,370 B2	12/2007	Mason, Jr. et al.	7,602,333 B2	10/2009	Hiramatsu et al.
7,310,335 B1	12/2007	Garcia-Luna-Aceves et al.	7,602,815 B2	10/2009	Houghton et al.
7,311,605 B2	12/2007	Moser	7,620,370 B2	11/2009	Barak et al.
7,313,312 B2	12/2007	Kimball et al.	7,625,131 B2	12/2009	Zienkewicz et al.
7,315,678 B2	1/2008	Siegel	7,626,489 B2	12/2009	Berkman et al.
7,319,717 B2	1/2008	Zitting et al.	7,634,250 B1	12/2009	Prasad et al.
7,321,291 B2	1/2008	Gidge et al.	7,640,562 B2	12/2009	Bouilloux-Lafont et al.
7,324,046 B1	1/2008	Wu et al.	7,640,581 B1	12/2009	Brenton et al.
7,329,815 B2	2/2008	Johnston et al.	7,653,363 B2	1/2010	Karr et al.
7,333,064 B1	2/2008	Timothy et al.	RE41,147 E	2/2010	Pang et al.
7,333,593 B2	2/2008	Beamon et al.	7,656,167 B1	2/2010	McLean et al.
7,339,466 B2	3/2008	Mansfield et al.	7,660,252 B1	2/2010	Huang et al.
7,339,897 B2	3/2008	Larsson et al.	7,660,328 B1	2/2010	Oz et al.
7,340,768 B2	3/2008	Rosenberger et al.	7,664,117 B2	2/2010	Lou et al.
7,345,623 B2	3/2008	McEwan et al.	7,669,049 B2	2/2010	Wang et al.
7,346,244 B2	3/2008	Gowan et al.	7,671,701 B2	3/2010	Radtke
7,346,359 B2	3/2008	Damarla et al.	7,671,820 B2	3/2010	Tokoro et al.
7,355,560 B2	4/2008	Nagai et al.	7,676,679 B2	3/2010	Weis et al.
7,358,808 B2	4/2008	Berkman et al.	7,680,478 B2	3/2010	Willars et al.
7,369,085 B1	5/2008	Jacomb-Hood et al.	7,680,516 B2	3/2010	Lovberg et al.
7,380,272 B2	5/2008	Sharp et al.	7,680,561 B2	3/2010	Rodgers et al.
7,381,089 B2	6/2008	Hosler, Sr.	7,683,848 B2	3/2010	Musch et al.
7,383,577 B2	6/2008	Hrstar et al.	7,684,383 B1	3/2010	Thompson et al.
7,397,422 B2	7/2008	Tekawy et al.	7,693,079 B2	4/2010	Cerami et al.
7,398,946 B1	7/2008	Marshall	7,693,162 B2	4/2010	McKenna et al.
7,408,426 B2	8/2008	Broyde et al.	7,693,939 B2	4/2010	Wu et al.
7,417,587 B2	8/2008	Iskander et al.	7,701,931 B2	4/2010	Kajiwara
7,418,178 B2	8/2008	Kudou et al.	7,705,747 B2	4/2010	Twitchell, Jr.
7,420,474 B1	9/2008	Elks et al.	7,715,672 B2	5/2010	Dong et al.
7,426,554 B2	9/2008	Kennedy et al.	7,716,660 B2	5/2010	Mackay et al.
7,430,932 B2	10/2008	Mekhanoshin et al.	7,724,782 B2	5/2010	Wang et al.
7,443,334 B2	10/2008	Rees et al.	7,728,772 B2	6/2010	Mortazawi et al.
7,444,404 B2	10/2008	Wetherall et al.	7,734,717 B2	6/2010	Saarimäki et al.
7,450,001 B2	11/2008	Berkman	7,743,403 B2	6/2010	McCarty et al.
7,453,352 B2	11/2008	Kline et al.	7,747,356 B2	6/2010	Andarawis et al.
7,453,393 B2	11/2008	Duivenvoorden et al.	7,747,774 B2	6/2010	Aaron et al.
7,456,650 B2	11/2008	Lee et al.	7,750,244 B1	7/2010	Melding et al.
7,459,834 B2	12/2008	Knowles et al.	7,750,763 B2	7/2010	Praßmayer et al.
7,463,877 B2	12/2008	Iwamura	7,760,978 B2	7/2010	Fishteyn et al.
7,465,879 B2	12/2008	Glew et al.	7,761,079 B2	7/2010	Mollenkopf et al.
7,466,225 B2	12/2008	White, II et al.	7,764,943 B2	7/2010	Radtke et al.
7,468,657 B2	12/2008	Yaney	7,773,664 B2	8/2010	Myers et al.
7,492,317 B2	2/2009	Tinsley et al.	7,782,156 B2	8/2010	Woods et al.
7,496,674 B2	2/2009	Jorgensen et al.	7,783,195 B2	8/2010	Riggsby et al.
7,509,009 B2	3/2009	Suzuki et al.	7,786,894 B2	8/2010	Polk et al.
7,509,675 B2	3/2009	Aaron et al.	7,786,945 B2	8/2010	Baldauf et al.
7,512,090 B2	3/2009	Benitez Pelaez et al.	7,786,946 B2	8/2010	Diaz et al.
7,516,487 B1	4/2009	Szeto et al.	7,791,549 B2	9/2010	Clymer et al.
7,518,952 B1	4/2009	Padden et al.	7,795,877 B2	9/2010	Radtke et al.
7,519,323 B2	4/2009	Mohebbi et al.	7,795,994 B2	9/2010	Radtke et al.
7,522,115 B2	4/2009	Waltman et al.	7,796,025 B2	9/2010	Berkman et al.
7,522,812 B2	4/2009	Zitting	7,796,890 B1	9/2010	Johnson
7,525,501 B2	4/2009	Black et al.	7,805,029 B2	9/2010	Bayindir et al.
7,531,803 B2	5/2009	Mittleman et al.	7,808,441 B2	10/2010	Parsche et al.
7,532,792 B2	5/2009	Skovgaard et al.	7,809,223 B2	10/2010	Miyabe et al.
7,539,381 B2	5/2009	Li et al.	7,812,778 B2	10/2010	Hasegawa et al.
7,545,818 B2	6/2009	Chen et al.	7,813,344 B2	10/2010	Cheswick
7,546,214 B2	6/2009	Rivers, Jr. et al.	7,825,793 B1	11/2010	Spillman et al.
7,554,998 B2	6/2009	Simonsson et al.	7,826,602 B1	11/2010	Hunyady et al.
7,555,182 B2	6/2009	Martin et al.	7,827,610 B2	11/2010	Wang et al.
7,555,186 B2	6/2009	De Montmorillon et al.	7,830,228 B2	11/2010	Evans et al.
7,555,187 B2	6/2009	Bickham et al.	7,835,600 B1	11/2010	Yap et al.
7,561,025 B2	7/2009	Gerszberg et al.	7,848,517 B2	12/2010	Britz et al.
7,567,154 B2	7/2009	Elmore	7,852,837 B1	12/2010	Au et al.
7,567,740 B2	7/2009	Bayindir et al.	7,869,391 B2	1/2011	Lee et al.
7,570,137 B2	8/2009	Kintis et al.	7,872,610 B2	1/2011	Motzer et al.
7,570,470 B2	8/2009	Holley	7,873,249 B2	1/2011	Kachmar et al.
7,580,643 B2	8/2009	Moore et al.	7,876,174 B2	1/2011	Radtke et al.
7,583,074 B1	9/2009	Lynch et al.	7,884,285 B2	2/2011	Spencer
7,584,470 B2	9/2009	Barker et al.	7,884,648 B2	2/2011	Broyde et al.
7,589,686 B2	9/2009	Balzovsky et al.	7,885,542 B2	2/2011	Riggsby et al.
7,590,404 B1	9/2009	Johnson	7,889,148 B2	2/2011	Diaz et al.
7,591,020 B2	9/2009	Kammer et al.	7,889,149 B2	2/2011	Peebles et al.
			7,890,053 B2	2/2011	Washiro
			7,893,789 B2 *	2/2011	Paynter B22D 17/007 333/21 R
			7,894,770 B2	2/2011	Washiro et al.

(56)

References Cited

U.S. PATENT DOCUMENTS

7,903,918 B1	3/2011	Bickham et al.	8,255,952 B2	8/2012	Boylan, III et al.
7,903,972 B2	3/2011	Riggsby et al.	8,258,743 B2	9/2012	Tyler et al.
7,929,940 B1	4/2011	Dianda et al.	8,264,417 B2	9/2012	Snow et al.
7,930,750 B1	4/2011	Gauvin et al.	8,269,583 B2	9/2012	Miller, II et al.
7,937,699 B2	5/2011	Schneider et al.	8,295,301 B2	10/2012	Yonge, III et al.
7,958,120 B2	6/2011	Muntz et al.	8,300,538 B2	10/2012	Kim et al.
7,962,957 B2	6/2011	Keohane et al.	8,300,640 B2	10/2012	Al-Banna et al.
7,965,842 B2	6/2011	Whelan et al.	8,316,228 B2	11/2012	Winslow et al.
7,970,937 B2	6/2011	Shuster et al.	8,316,364 B2	11/2012	Stein et al.
7,971,053 B2	6/2011	Gibson, Sr. et al.	8,343,145 B2	1/2013	Brannan et al.
7,974,387 B2	7/2011	Lutz et al.	8,344,829 B2	1/2013	Miller, II et al.
7,983,740 B2	7/2011	Culver et al.	8,363,313 B2	1/2013	Nakaguma et al.
7,986,711 B2	7/2011	Horvath et al.	8,369,667 B2	2/2013	Rose et al.
7,990,329 B2	8/2011	Deng et al.	8,374,821 B2	2/2013	Rousselle et al.
7,991,877 B2	8/2011	Keohane et al.	8,384,600 B2	2/2013	Huang et al.
7,992,014 B2	8/2011	Langgood et al.	8,385,978 B2	2/2013	Leung et al.
8,013,694 B2	9/2011	Sagala et al.	8,386,198 B2	2/2013	Lancaster
8,022,885 B2	9/2011	Smoyer et al.	8,390,402 B2	3/2013	Kunes et al.
8,022,887 B1	9/2011	Zarnaghi et al.	8,406,239 B2	3/2013	Hurwitz et al.
8,027,391 B2	9/2011	Matsubara et al.	8,406,593 B2	3/2013	Molin et al.
8,036,207 B2	10/2011	Chen et al.	8,407,687 B2	3/2013	Moshir et al.
8,049,576 B2	11/2011	Broyde et al.	8,412,130 B2	4/2013	Suematsu et al.
8,065,099 B2	11/2011	Gibala et al.	8,414,326 B2	4/2013	Bowman
8,069,483 B1	11/2011	Matlock et al.	8,415,884 B2	4/2013	Chen et al.
8,072,323 B2	12/2011	Kodama et al.	8,433,168 B2	4/2013	Filippov et al.
8,073,810 B2	12/2011	Maes	8,434,103 B2	4/2013	Tsuchida et al.
8,077,049 B2	12/2011	Yaney et al.	8,458,453 B1	6/2013	Mahalingaiah et al.
8,081,854 B2	12/2011	Yoon et al.	8,462,063 B2	6/2013	Gummalla et al.
8,089,404 B2	1/2012	Nichols et al.	8,467,363 B2	6/2013	Lea et al.
8,089,952 B2	1/2012	Spade et al.	8,468,244 B2	6/2013	Redlich et al.
8,090,379 B2	1/2012	Lambert et al.	8,484,511 B2	7/2013	Tidwell et al.
8,094,081 B1	1/2012	Boone et al.	8,495,718 B2	7/2013	Han et al.
8,094,985 B2	1/2012	Imamura et al.	8,497,749 B2	7/2013	Elmore
8,098,198 B2	1/2012	Thiesen et al.	8,503,845 B2	8/2013	Winzer et al.
8,102,779 B2	1/2012	Kim et al.	8,505,057 B2	8/2013	Rogers
RE43,163 E	2/2012	Anderson	8,509,114 B1	8/2013	Szajdecki
8,111,148 B2	2/2012	Parker et al.	8,514,980 B2	8/2013	Kuhtz
8,120,488 B2	2/2012	Bloy et al.	8,515,383 B2	8/2013	Prince et al.
8,121,624 B2	2/2012	Cai et al.	8,516,470 B1	8/2013	Joshi et al.
8,129,817 B2	3/2012	Jou et al.	8,516,474 B2	8/2013	Lamba et al.
8,131,125 B2	3/2012	Molin et al.	8,520,636 B2	8/2013	Xu
8,131,266 B2	3/2012	Cai et al.	8,528,059 B1	9/2013	Saluzzo et al.
8,132,239 B2	3/2012	Wahl	8,532,023 B2	9/2013	Buddhikot et al.
8,134,424 B2	3/2012	Kato et al.	8,532,046 B2	9/2013	Hu et al.
8,134,458 B2	3/2012	Lund	8,537,068 B2	9/2013	Call et al.
8,140,113 B2	3/2012	Rofougaran et al.	8,537,705 B2	9/2013	Afkhamie et al.
8,151,306 B2	4/2012	Rakib	8,539,540 B2	9/2013	Zenoni
8,156,520 B2	4/2012	Casagrande et al.	8,539,569 B2	9/2013	Mansour
8,159,385 B2	4/2012	Farneth et al.	8,542,968 B2	9/2013	Dong et al.
8,159,394 B2	4/2012	Hayes et al.	8,548,294 B2	10/2013	Toge et al.
8,159,742 B2	4/2012	McKay et al.	8,553,646 B2	10/2013	Kumar
8,159,933 B2	4/2012	Henry	8,561,104 B1	10/2013	Dow et al.
8,160,064 B2	4/2012	Kokernak et al.	8,561,181 B1	10/2013	Sobel et al.
8,160,530 B2	4/2012	Corman et al.	8,565,568 B2	10/2013	Bigot-Astruc et al.
8,160,825 B1	4/2012	Roe, Jr. et al.	8,572,247 B2	10/2013	Larson et al.
8,171,146 B2	5/2012	Chen et al.	8,572,639 B2	10/2013	Ficco
8,180,917 B1	5/2012	Yan et al.	8,572,661 B2	10/2013	Strong et al.
8,184,015 B2	5/2012	Lilien et al.	8,578,076 B2	11/2013	van der Linden et al.
8,184,059 B2	5/2012	Bunch et al.	8,578,486 B2	11/2013	Lifliand et al.
8,184,311 B2	5/2012	Sakai et al.	8,584,195 B2	11/2013	Sherlock et al.
8,188,855 B2	5/2012	Sharma	8,587,490 B2	11/2013	Niver et al.
8,199,762 B2	6/2012	Michelson et al.	8,587,492 B2	11/2013	Runyon et al.
8,203,501 B2	6/2012	Kim et al.	8,588,567 B2	11/2013	Kamps et al.
8,212,635 B2	7/2012	Miller, II et al.	8,588,991 B1	11/2013	Forbes, Jr.
8,213,758 B2	7/2012	Dong et al.	8,593,238 B2	11/2013	Miller, II et al.
8,218,929 B2	7/2012	Bickham et al.	8,604,982 B2	12/2013	Gummalla et al.
8,222,919 B2	7/2012	Broyde et al.	8,604,999 B2	12/2013	Abumrad et al.
8,222,977 B2	7/2012	Oyama et al.	8,605,579 B2	12/2013	Abraham et al.
8,225,379 B2	7/2012	van de Groenendaal	8,612,550 B2	12/2013	Yoo et al.
8,237,617 B1	8/2012	Johnson	8,613,020 B2	12/2013	Knudson et al.
8,238,824 B2	8/2012	Washiro	8,625,547 B1	1/2014	Miller et al.
8,242,358 B2	8/2012	Park et al.	8,629,811 B2	1/2014	Gaynor et al.
8,243,603 B2	8/2012	Gossain et al.	8,639,934 B2	1/2014	Kruglick
8,249,028 B2	8/2012	Porras et al.	8,653,906 B2	2/2014	Mahon et al.
8,253,516 B2	8/2012	Miller, II et al.	8,656,458 B2	2/2014	Heffez et al.
			8,660,526 B1	2/2014	Heiderscheit et al.
			8,660,698 B2	2/2014	Phillips et al.
			8,665,102 B2	3/2014	Salewske et al.
			8,666,553 B2	3/2014	Phillips et al.

(56)

References Cited

U.S. PATENT DOCUMENTS

8,674,630 B1	3/2014	Cornelius et al.	8,970,438 B2	3/2015	Hager et al.
8,681,463 B2	3/2014	Franks et al.	8,984,113 B2	3/2015	Li et al.
8,687,650 B2	4/2014	King	8,994,474 B2	3/2015	Mahon et al.
8,688,153 B2	4/2014	Komori et al.	8,996,188 B2	3/2015	Frader-Thompson et al.
8,699,454 B2	4/2014	Hapsari et al.	8,996,728 B2	3/2015	Cochinwala et al.
8,699,461 B2	4/2014	Qian et al.	9,000,353 B2	4/2015	Seo et al.
8,705,925 B2	4/2014	Terada et al.	9,001,689 B1	4/2015	Ponnampalam et al.
8,707,432 B1	4/2014	Rathi et al.	9,003,492 B2	4/2015	Katar
8,711,732 B2	4/2014	Johnson et al.	9,008,513 B2	4/2015	Kim et al.
8,711,806 B2	4/2014	Lim et al.	9,009,460 B2	4/2015	Chen
8,711,857 B2	4/2014	Jackson et al.	9,014,621 B2	4/2015	Mohebbi
8,712,200 B1	4/2014	Abernathy et al.	9,015,467 B2	4/2015	Buer
8,719,938 B2	5/2014	Demeter et al.	9,019,595 B2	4/2015	Jain et al.
8,731,358 B2	5/2014	Pare et al.	9,021,251 B2	4/2015	Chawla
8,732,476 B1	5/2014	Van et al.	9,021,575 B2	4/2015	Martini
8,737,793 B2	5/2014	Imamura et al.	9,037,516 B2	5/2015	Abhyanker
8,738,318 B2	5/2014	Spillane et al.	9,042,812 B1	5/2015	Bennett et al.
8,743,004 B2	6/2014	Haziza	9,082,307 B2	7/2015	Sharawi
8,749,449 B2	6/2014	Caldwell et al.	9,094,407 B1	7/2015	Matthieu
8,750,664 B2	6/2014	Huang et al.	9,098,325 B2	8/2015	Reddin
8,755,659 B2	6/2014	Imamura et al.	9,103,864 B2	8/2015	Ali
8,760,354 B2	6/2014	Flannery et al.	9,106,617 B2	8/2015	Kshirsagar et al.
8,761,792 B2	6/2014	Sennett et al.	9,113,347 B2	8/2015	Henry
8,763,097 B2	6/2014	Bhatnagar et al.	9,119,127 B1	8/2015	Henry
8,769,622 B2	7/2014	Chang et al.	9,128,941 B2	9/2015	Shulman
8,780,012 B2	7/2014	Llombart Juan et al.	9,130,641 B2	9/2015	Mohebbi
8,782,195 B2	7/2014	Foti	9,134,945 B2	9/2015	Husain
8,786,284 B2	7/2014	Sirigiri et al.	2001/0030789 A1	10/2001	Jiang et al.
8,786,514 B2	7/2014	Dickie et al.	2002/0002040 A1	1/2002	Kline et al.
8,789,091 B2	7/2014	Eldering et al.	2002/0024424 A1	2/2002	Burns et al.
8,792,760 B2	7/2014	Choi et al.	2002/0040439 A1	4/2002	Kellum et al.
8,793,363 B2	7/2014	Sater et al.	2002/0069417 A1	6/2002	Kliger et al.
8,793,742 B2	7/2014	Macrae et al.	2002/0099949 A1	7/2002	Fries et al.
8,804,667 B2	8/2014	Wang	2002/0111997 A1	8/2002	Herlihy et al.
8,806,202 B2	8/2014	Shoemake et al.	2002/0156917 A1	10/2002	Nye et al.
8,810,404 B2	8/2014	Bertoncini et al.	2002/0186694 A1	12/2002	Mahajan et al.
8,810,421 B2	8/2014	Deaver, Sr. et al.	2003/0002476 A1	1/2003	Chung et al.
8,811,278 B2	8/2014	Hori et al.	2003/0010528 A1	1/2003	Niles
8,817,741 B2	8/2014	Shaheen	2003/0049003 A1	3/2003	Ahmad et al.
8,830,112 B1	9/2014	Buehler et al.	2003/0054793 A1	3/2003	Manis et al.
8,836,607 B2	9/2014	Cook et al.	2003/0095208 A1	5/2003	Chouraqui et al.
8,839,350 B1	9/2014	Shapcott et al.	2003/0152331 A1	8/2003	Dair et al.
8,847,840 B1	9/2014	Diaz	2003/0188308 A1	10/2003	Kizuka
8,856,239 B1	10/2014	Oliver et al.	2003/0190110 A1	10/2003	Kline et al.
8,856,530 B2	10/2014	Lamberg et al.	2003/0202756 A1	10/2003	Hurley et al.
8,863,245 B1	10/2014	Abhyanker	2003/0210197 A1	11/2003	Cencich et al.
8,867,226 B2	10/2014	Colomb et al.	2004/0015725 A1	1/2004	Boneh et al.
8,872,032 B2	10/2014	Su et al.	2004/0023640 A1	2/2004	Ballai et al.
8,875,224 B2	10/2014	Gross et al.	2004/0048596 A1	3/2004	Wyrzykowska et al.
8,878,740 B2	11/2014	Coupland et al.	2004/0054425 A1	3/2004	Elmore
8,881,588 B2	11/2014	Baer et al.	2004/0100343 A1	5/2004	Tsu et al.
8,885,689 B2	11/2014	Blasco Claret et al.	2004/0104410 A1	6/2004	Gilbert et al.
8,887,212 B2	11/2014	Dua	2004/0113757 A1	6/2004	White, II et al.
8,890,759 B2	11/2014	Pantea et al.	2004/0119564 A1	6/2004	Itoh et al.
8,893,246 B2	11/2014	El-Moussa et al.	2004/0131310 A1	7/2004	Walker et al.
8,897,697 B1	11/2014	Willis, III et al.	2004/0163135 A1	8/2004	Giaccherini et al.
8,901,916 B2	12/2014	Rodriguez et al.	2004/0165669 A1	8/2004	Otsuka et al.
8,903,214 B2	12/2014	Alkeskjold	2004/0169572 A1	9/2004	Elmore et al.
8,907,222 B2	12/2014	Stransky	2004/0196784 A1	10/2004	Larsson et al.
8,913,862 B1	12/2014	Emmerich et al.	2004/0212481 A1	10/2004	Abraham et al.
8,917,215 B2	12/2014	Pohl	2004/0213147 A1	10/2004	Wiese et al.
8,917,964 B2	12/2014	Blew et al.	2004/0213189 A1	10/2004	Alsbaugh et al.
8,918,108 B2	12/2014	van Heeswyk et al.	2004/0213294 A1	10/2004	Hughes et al.
8,925,079 B2	12/2014	Miyake et al.	2004/0250069 A1	12/2004	Kosamo et al.
8,934,747 B2	1/2015	Smith et al.	2005/0005854 A1	1/2005	Suzuki et al.
8,937,577 B2	1/2015	Gerini et al.	2005/0017825 A1	1/2005	Hansen et al.
8,938,144 B2	1/2015	Hennink et al.	2005/0068223 A1	3/2005	Vavik et al.
8,941,912 B2	1/2015	Ichii et al.	2005/0069321 A1	3/2005	Sullivan et al.
8,955,051 B2	2/2015	Marzii	2005/0097396 A1	5/2005	Wood
8,955,075 B2	2/2015	Smith et al.	2005/0102185 A1	5/2005	Barker et al.
8,957,818 B2	2/2015	Chen et al.	2005/0111533 A1	5/2005	Berkman et al.
8,958,665 B2	2/2015	Ziari et al.	2005/0143868 A1	6/2005	Whelan et al.
8,963,790 B2	2/2015	Brown et al.	2005/0169056 A1	8/2005	Berkman et al.
8,964,433 B2	2/2015	Hai-Maharsi	2005/0169401 A1	8/2005	Abraham et al.
8,966,609 B2	2/2015	Lee et al.	2005/0177463 A1	8/2005	Crutchfield et al.
			2005/0212626 A1	9/2005	Takamatsu et al.
			2005/0219135 A1	10/2005	Lee et al.
			2005/0226353 A1	10/2005	Gebara et al.
			2005/0258920 A1	11/2005	Elmore

(56)

References Cited

U.S. PATENT DOCUMENTS

2006/0034724 A1	2/2006	Hamano et al.	2010/0169937 A1	7/2010	Atwal et al.
2006/0053486 A1	3/2006	Wesinger et al.	2010/0175080 A1	7/2010	Yuen et al.
2006/0082516 A1	4/2006	Strickland et al.	2010/0176894 A1	7/2010	Tahara et al.
2006/0111047 A1	5/2006	Louberg et al.	2010/0177894 A1	7/2010	Yasuma et al.
2006/0114925 A1	6/2006	Gerszberg et al.	2010/0185614 A1	7/2010	O'Brien et al.
2006/0120399 A1	6/2006	Claret et al.	2010/0201313 A1	8/2010	Vorenkamp et al.
2006/0128322 A1	6/2006	Igarashi et al.	2010/0214183 A1	8/2010	Stoneback et al.
2006/0153878 A1	7/2006	Savarino et al.	2010/0214185 A1	8/2010	Sammoura et al.
2006/0172781 A1	8/2006	Mohebbi et al.	2010/0225426 A1	9/2010	Unger et al.
2006/0181394 A1	8/2006	Clarke et al.	2010/0243633 A1	9/2010	Huynh et al.
2006/0187023 A1	8/2006	Iwamura et al.	2010/0253450 A1	10/2010	Kim et al.
2006/0192672 A1	8/2006	Gidge et al.	2010/0265877 A1	10/2010	Foxworthy et al.
2006/0220833 A1	10/2006	Berkman et al.	2010/0283693 A1	11/2010	Xie et al.
2006/0239501 A1	10/2006	Petrovic et al.	2010/0284446 A1	11/2010	Mu et al.
2006/0255930 A1	11/2006	Berkman et al.	2010/0319068 A1	12/2010	Abbadessa et al.
2006/0286927 A1	12/2006	Berkman et al.	2010/0327880 A1	12/2010	Stein et al.
2007/0022475 A1	1/2007	Rossi et al.	2011/0018704 A1	1/2011	Burrows et al.
2007/0025386 A1	2/2007	Riedel et al.	2011/0040861 A1	2/2011	Van der Merwe et al.
2007/0041554 A1	2/2007	Newman	2011/0042120 A1	2/2011	Otsuka et al.
2007/0054622 A1	3/2007	Berkman	2011/0053498 A1	3/2011	Nogueira-Nine
2007/0090185 A1	4/2007	Lewkowitz et al.	2011/0068893 A1	3/2011	Lahiri et al.
2007/0105508 A1	5/2007	Tong et al.	2011/0068988 A1	3/2011	Monte et al.
2007/0135044 A1	6/2007	Rhodes et al.	2011/0107364 A1	5/2011	Lajoie et al.
2007/0144779 A1	6/2007	Vicente et al.	2011/0109936 A1	5/2011	Coffee et al.
2007/0211689 A1	9/2007	Campero et al.	2011/0110404 A1	5/2011	Washiro
2007/0211786 A1	9/2007	Shattil et al.	2011/0118888 A1	5/2011	White et al.
2007/0252998 A1	11/2007	Berthold et al.	2011/0132658 A1	6/2011	Miller, II et al.
2007/0268124 A1	11/2007	Berkman et al.	2011/0133865 A1	6/2011	Miller, II et al.
2007/0300280 A1	12/2007	Turner et al.	2011/0133867 A1	6/2011	Miller, II et al.
2008/0002652 A1	1/2008	Gupta et al.	2011/0136432 A1	6/2011	Miller, II et al.
2008/0003872 A1	1/2008	Chen et al.	2011/0140911 A1	6/2011	Pant et al.
2008/0007416 A1	1/2008	Cern et al.	2011/0140911 A1	6/2011	Pant et al.
2008/0060832 A1	3/2008	Razavi et al.	2011/0141555 A1	6/2011	Fermann et al.
2008/0064331 A1	3/2008	Washiro et al.	2011/0148578 A1	6/2011	Aloi et al.
2008/0120667 A1	5/2008	Zaltsman	2011/0164514 A1	7/2011	Afkhamie et al.
2008/0130639 A1	6/2008	Costa-Requena et al.	2011/0165847 A1*	7/2011	Kawasaki H04B 3/52 455/73
2008/0143491 A1	6/2008	Deaver et al.	2011/0169336 A1	7/2011	Yerazunis et al.
2008/0153416 A1	6/2008	Washiro et al.	2011/0172000 A1	7/2011	Quigley et al.
2008/0211727 A1	9/2008	Elmore et al.	2011/0187578 A1	8/2011	Farneth et al.
2008/0247716 A1	10/2008	Thomas et al.	2011/0208450 A1	8/2011	Salka et al.
2008/0253723 A1	10/2008	Stokes et al.	2011/0219402 A1	9/2011	Candelore et al.
2008/0255782 A1	10/2008	Bilac et al.	2011/0225046 A1	9/2011	Eldering et al.
2008/0266060 A1	10/2008	Takei et al.	2011/0228814 A1	9/2011	Washiro et al.
2008/0267076 A1	10/2008	Laperi et al.	2011/0268085 A1	11/2011	Barany et al.
2008/0279199 A1	11/2008	Park et al.	2011/0274396 A1	11/2011	Nakajima et al.
2008/0313691 A1	12/2008	Cholas	2011/0294509 A1	12/2011	Kim et al.
2009/0002137 A1	1/2009	Radtke et al.	2012/0039366 A1	2/2012	Wood et al.
2009/0007190 A1	1/2009	Weber et al.	2012/0046891 A1	2/2012	Yaney et al.
2009/0015239 A1	1/2009	Georgiou et al.	2012/0068903 A1	3/2012	Thevenard et al.
2009/0067441 A1	3/2009	Ansari et al.	2012/0077485 A1	3/2012	Shin et al.
2009/0079660 A1	3/2009	Elmore	2012/0078452 A1	3/2012	Daum et al.
2009/0085726 A1	4/2009	Radtke et al.	2012/0084807 A1	4/2012	Thompson et al.
2009/0109981 A1	4/2009	Keselman	2012/0091820 A1	4/2012	Campanella et al.
2009/0129301 A1	5/2009	Belimpasakis et al.	2012/0092161 A1	4/2012	West et al.
2009/0138931 A1	5/2009	Lin et al.	2012/0102568 A1	4/2012	Tarbotton et al.
2009/0144417 A1	6/2009	Kisel et al.	2012/0105246 A1	5/2012	Sexton et al.
2009/0171780 A1	7/2009	Aldrey et al.	2012/0117584 A1	5/2012	Gordon
2009/0201133 A1	8/2009	Bruns et al.	2012/0133373 A1	5/2012	Ali et al.
2009/0210901 A1	8/2009	Hawkins et al.	2012/0144420 A1	6/2012	Del Sordo et al.
2009/0250449 A1	10/2009	Petrenko et al.	2012/0154239 A1	6/2012	Bar-Sade et al.
2009/0254971 A1	10/2009	Herz et al.	2012/0161543 A1	6/2012	Reuven et al.
2009/0258652 A1	10/2009	Lambert et al.	2012/0181258 A1	7/2012	Shan et al.
2009/0311960 A1	12/2009	Farahani et al.	2012/0197558 A1	8/2012	Henig et al.
2009/0315668 A1	12/2009	Leete, III et al.	2012/0250534 A1	10/2012	Langer et al.
2010/0026607 A1	2/2010	Imai et al.	2012/0263152 A1	10/2012	Fischer et al.
2010/0045447 A1	2/2010	Mollenkopf et al.	2012/0272741 A1	11/2012	Xiao et al.
2010/0057894 A1	3/2010	Glasser	2012/0287922 A1	11/2012	Heck et al.
2010/0085036 A1	4/2010	Banting et al.	2012/0304294 A1	11/2012	Fujiwara et al.
2010/0090887 A1	4/2010	Cooper et al.	2012/0306708 A1	12/2012	Henderson et al.
2010/0100918 A1	4/2010	Egan, Jr. et al.	2012/0324018 A1	12/2012	Metcalf et al.
2010/0111521 A1	5/2010	Kim et al.	2012/0327908 A1	12/2012	Gupta et al.
2010/0119234 A1	5/2010	Suematsu et al.	2012/0329523 A1	12/2012	Stewart et al.
2010/0121945 A1	5/2010	Gerber et al.	2012/0330756 A1	12/2012	Morris et al.
2010/0150215 A1	6/2010	Black et al.	2013/0002409 A1	1/2013	Molina et al.
2010/0153990 A1	6/2010	Ress et al.	2013/0003876 A1	1/2013	Bennett
			2013/0039624 A1	2/2013	Scherer et al.
			2013/0064178 A1	3/2013	Cs et al.
			2013/0064311 A1	3/2013	Turner et al.
			2013/0077664 A1	3/2013	Lee et al.

(56)

References Cited

OTHER PUBLICATIONS

- “Exacter Outage-Avoidance System”, <http://www.epri.com/abstracts/Pages/ProductAbstract.aspx?ProductId=00000000001020393>, Nov. 30, 2009.
- “GM-12 Gimbal Mount”, Newmark System, Inc, newmarksystems.com, 2015.
- “HiveManager Network Management System”, Aerohive® Networks, aerohive.com, Sep. 2015.
- “Home”, Darktrace, darktrace.com, Jul. 10, 2014.
- “How to Use STUF”, STUF Page Link Info, crossdevices.com, http://www.crossdevices.com/cross_devices_010.htm, 2015, 1 page.
- “IEEE Standard for Information technology—Local and metropolitan area networks—Specific requirements”, Part 15.4: Wireless Medium Access Control (MAC) and Physical Layer (PHY) Specifications for Low Rate Wireless Personal Area Networks (WPANs), in IEEE Std 802.15.4, (Revision of IEEE Std 802.15.4-2003), Sep. 7, 2006, 1-320.
- “Installing Satellite Accessories”, ACE®, acehardware.com, May 8, 2006.
- “Ipitek All-Optical Sensors”, <http://www.ipitek.com/solutions-by-industry/all-optical-sensors>, Jun. 2, 2014.
- “mmWave Axial Choke Horn Antenna with Lens”, Feko, Sep. 24, 2013.
- “Network technology”, nbn™, nbco.com.au, Jun. 27, 2014.
- “Norse Appliance™: Block attacks before they target your network, and dramatically improve the ROI on your entire security infrastructure”, norsecorp.com, 2015.
- “Out-of-Band Mgmt”, Cradle Point, cradlepoint.com, Sep. 2015.
- “Out-of-Band Security Solution”, Gigamon®, gigamon.com, Aug. 3, 2014.
- “Powerline—Juice Up Your Network With Powerline”, Netgear®, <http://www.netgear.com/home/products/networking/powerline/>, Apr. 21, 2015, 3 pages.
- “PRO 600 Sirius XM Radio Amplified Outdoor Antenna”, Pixel Technologies, Oct. 3, 2014.
- “Product Overview: Introducing SilentDefense”, Security Matters, secmatters.com, Nov. 9, 2013.
- “Quickly identify malicious traffics: Detect”, Lancopé®, lancopé.com, Mar. 15, 2015.
- “radar at st Andrews”, [mmwaves.epr, st-andrews.ac.uk](http://mmwaves.epr.st-andrews.ac.uk), Feb. 4, 2011.
- “Resilience to Smart Meter Disconnect Attacks”, ADSC Illinois at Singapore PTE, Ltd., [publish.illinois.edu http://publish.illinois.edu/integrativesecurityassessment/resiliencetosmartmeterdisconnectattacks/](http://publish.illinois.edu/integrativesecurityassessment/resiliencetosmartmeterdisconnectattacks/), 2015.
- “RF Sensor Node Development Platform for 6LoWPAN and 2.4 GHz Applications”, <http://www.ti.com/tool/TIDM-RF-SENSORNODE>, Jun. 2, 2014.
- “Smart Out-Of-Band Management”, Open Gear, opengear.com, Sep. 2015.
- “Tapered waveguide”, Lumerical Solutions, Inc., docs.lumerical.com, 2010.
- “Tapered Waveguides Improve Fiber Light Coupling Efficiency”, Tech Briefs, techbriefs.com, Molex Inc., Downers Grove, Illinois and KiloLambda Technologies Ltd., Tel Aviv, Israel., Jan. 1, 2006.
- “Wireless powerline sensor”, [wikipedia.org, http://en.wikipedia.org/wiki/Wireless_powerline_sensor](http://en.wikipedia.org/wiki/Wireless_powerline_sensor), 2014, 3 pages.
- Akiba, Shigeyuki et al., “Photonic Architecture for Beam Forming of RF Phased Array Antenna”, Optical Fiber Communication Conference. Optical Society of America., Abstract Only, 2014.
- Alam, M N et al., “Novel surface wave exciters for power line fault detection and communications”, Antennas and Propagation (APSURSI), IEEE International Symposium on, IEEE, pp. 1139-1142, Jul. 3, 2011.
- Alam, MD N. et al., “Design and Application of Surface Wave Sensors for nonintrusive Power Line Fault Detection,” IEEE Sensors Journal, IEEE Service Center, New York, NY, US, vol. 13, No. 1, pp. 339-347, Jan. 1, 2013.
- Ali, Muhammad Q. et al., “Randomizing AMI configuration for proactive defense in smart grid”, Smart Grid Communications (SmartGridComm), IEEE International Conference on. IEEE, Abstract Only, <http://ieeexplore.ieee.org/xpl/login.jsp?tp=&arnumber=6688027>, 2013.
- Angove, Alex , “Direct Bury Duct Assemblies, MPB 302 3+—Ribbon Microducts”, Ericsson, archive.ericsson.net, Jul. 30, 2014.
- Angove, Alex , “How the NBN Differs from ADSL2+, Cable and Wireless”, Whistle Out, whistleout.com.au, Jul. 30, 2014.
- Arage, Alebel et al., “Measurement of wet antenna effects on millimetre wave propagation”, Radar, IEEE Conference on IEEE., Abstract Only, 2006.
- Arthur, Joseph Kweku , “Improving QoS in UMTS Network in ACCRA Business District Using Tower-Less Towers”, IPASJ International Journal of Electrical Engineering (IJEE), vol. 2, Issue 11., Nov. 2014.
- Asadallahi, Sina et al., “Performance comparison of CSMA/CA Advanced Infrared (AIr) and a new pointtomultipoint optical MAC protocol.” Wireless Communications and Mobile Computing Conference (IWCMC), 2012 8th International. IEEE., Abstract Only, 2012.
- Atwater, Harry A. , “The promise of plasmonics.” Scientific American 296.4: 56-62., 2007.
- Bach, Christian , “Current Sensor—Power Line Monitoring for Energy Demand Control”, Application Note 308, http://www.enocean.com/fileadmin/redaktion/pdf/app_notes/AN308_CURRENT_SENSOR_Jan09.pdf, Jan. 2009, 4 pages.
- Barron, Ashleigh L. , “Integrated Multicore Fibre Devices for Optical Trapping”, Diss. Heriot-Watt University, 2014, 11-15.
- Beal, J.C. et al., “Coaxial-slot surface-wave launcher”, Electronics Letters 4.25: 557559, Abstract Only, 1968.
- Bhushan, Naga , “Network densification: the dominant theme for wireless evolution into 5G”, Communications Magazine, IEEE 52.2: 82-89, 2014.
- Bing, Benny , “Ubiquitous Broadband Access Networks with Peer-to-Peer Application Support”, Evolving the Access Network: 27-36, 2006.
- Bock, James et al., “Optical coupling.” Journal of Physics: Conference Series. vol. 155. No. 1. IOP Publishing., 2009.
- Bowen, Leland H. et al., “A Solid Dielectric Lens Impulse Radiating Antenna with High Dielectric Constant Surrounded by a Cylindrical Shroud,” Sensor and Simulation Note 498., Introduction, Apr. 2005, 3 pages.
- Bridges, Greg E. et al., “Plane wave coupling to multiple conductor transmission lines above a lossy earth”, Compatibility, IEEE Transactions on 31.1, Abstract Only, 1989, 21-33.
- Brooke, Gary H. , Properties of surface waveguides with discontinuities and perturbations in cross-section. Diss. University of British Columbia, 1977., 1977.
- Brown, J. et al., “The launching of radial cylindrical surface waves by a circumferential slot”, Proceedings of the IEE Part B: Radio and Electronic Engineering 106.26: 123128., Abstract Only, 1959.
- Bruno, Joseph , “Interference Reduction in Wireless Networks”, Computing Research Topics, Computing Sciences Department, Villanova University, Nov. 14, 2007, 8 pages.
- Burkhart, Martin et al., “Does Topology Control Reduce Interference?”, Department of Computer Science, ETH Zurich, Proceedings of the 5th ACM international symposium on Mobile ad hoc networking and computing, ACM, 2004, 11 pages.
- Callis, et al., “An In-Line Power Monitor for HE11 Low Loss Transmission Lines”, Proceedings of the 29th International Conference on Infrared and Millimeter Waves (IRMMW), Karlsruhe, Germany, 2004.
- Carroll, John M. et al., “Developing the Blacksburg electronic village”, Communications of the ACM 39.12: 69-74, 1996.
- Chen, Dong et al., “A trust management model based on fuzzy reputation for internet of things”, Computer Science and Information Systems 8.4: 12071228, Abstract Only, 2011.
- Chen, Yingying , “Detecting and Localizing Wireless Spoofing Attacks”, Sensor, Mesh and Ad Hoc Communications and Networks, SECON’07. 4th Annual IEEE Communications Society Conference on IEEE, 2007, 10 pages.

(56)

References Cited

OTHER PUBLICATIONS

- Chiba, Jiro , "Experimental Studies of the Losses and Radiations Due to Bends in the Goubau Line", IEEE Transactions on Microwave Theory and Techniques, Feb. 1977, 94-100.
- Chiba, Jiro , "On the Equivalent Circuit for the G-Line Above Ground", International Wroclaw Symposium on Electromagnetic Compatibility, 1998, 78-82.
- Cimini, Carlos Alberto et al., "Temperature profile of progressive damaged overhead electrical conductors", Journal of Electrical Power & Energy Systems 49: 280-286., 2013.
- Costantine, Joseph et al., "The analysis of a reconfigurable antenna with a rotating feed using graph models", Antennas and Wireless Propagation Letters 8: 943-946, 2009.
- Covington, Michael J. et al., "Threat implications of the internet of things", Cyber Conflict (CyCon), 2013 5th International Conference on. IEEE., Abstract Only, 2013.
- Crane, Robert K. , "Analysis of the effects of water on the ACTS propagation terminal antenna", Antennas and Propagation, IEEE Transactions on 50.7: 954965, Abstract Only, 2002.
- De Sabata, Aldo et al., "Universitatea Politehnica", din Timișoara Facultatea de Electronică și Telecomunicații, 2012.
- Dini, Gianluca et al., "MADAM: A Multilevel Anomaly Detector for Android Malware", MMMACNS. vol. 12, 2012.
- Doane, J.L. et al., "Oversized rectangular waveguides with modefree bends and twists for broadband applications", Microwave Journal 32(3), Abstract Only, 1989, 153-160.
- Doelitzscher, et al., "ViteraaS: Virtual cluster as a service." Cloud Computing Technology and Science (CloudCom), 2011 IEEE Third International Conference on. IEEE., 2011.
- Dooley, Kevin , "Out-of-Band Management", auvik, auvik.com., Apr. 12, 2014.
- Dostert, Klaus , "Frequency-hopping spread-spectrum modulation for digital communications over electrical power lines." Selected Areas in Communications, IEEE Journal on 8.4: 700-710., Abstract Only, 1990.
- Dragoo, R.E. et al., "Fiber Optic Data Bus for the AN/GYQ21(V)." Harris Corp, U.S. Communications Syst. Div. Chart, Microcopy Resolution Test, 1980.
- Dutton, Harry Jr. , "Understanding Optical Communications", International Technical Support Organization, SG24-5230-00., Sep. 1998.
- Ehyaie, Danial , "Novel Approaches to the Design of Phased Array Antennas," Diss. The University of Michigan., 2011.
- Elmore, Glenn , "Introduction to the Propagating Wave on a Single Conductor", www.corridor.biz, Jul. 27, 2009, 30 pages.
- Erickson, Katherine , "Conductive cylindrical surface waveguides." https://www.ideals.illinois.edu/bitstream/handle/2142/30914/Erickson_Katherine.pdf?sequence=1, 2012.
- Eskelinen, Harri , "DFM (A)-aspects for a horn antenna design," Lappeenranta University of Technology., 2004.
- Eskelinen, P. , "A low-cost microwave rotary joint," International Radar Conference, 13-17, p. 1-4., Abstract Only, Oct. 2014, 1 page.
- Feng, Taiming et al., "Design of a survivable hybrid wireless-optical broadband-access network", Journal of Optical Communications and Networking 3.5, 2011, 458-464.
- Fenye, Bao et al., "Dynamic trust management for internet of things applications", Proceedings of the 2012 international workshop on Selfaware internet of things. ACM, Abstract Only, 2012, 1 page.
- Freyer, Dan , "Combating the Challenges of Ka-Band Signal Degradation", SatMagazine, satmagazine.com., Sep. 2014.
- Friedman, M et al., "Low-loss RF transport over long distances," IEEE Transactions on Microwave Theory and Techniques, Jan. 1, 2001, pp. 341-348.
- Friedman, M. et al., "Low-Loss RF Transport Over Long Distances", IEEE Transactions on Microwave Theory and Techniques, vol. 49, No. 2, Feb. 2001, 341-348.
- Fromm, W. et al., "A new microwave rotary joint," 1958 IRE International Convention Record, 21-25, 6:78-82., Abstract Only, Mar. 1966, 2 pages.
- Garcia-Etxarri, Aitzol et al., "A combination of concave/convex surfaces for fieldenhancement optimization: the indented nanocone", Optics express 20.23, 2012, 2520125212.
- Ghazisaidi, Navid et al., "Survivability analysis of next-generation passive optical networks and fiber-wireless access networks", Reliability, IEEE Transactions on 60.2, 2011, 479-492.
- Goldsmith, P.F. , "Quasi-optical techniques", Proceedings of the IEEE., vol. 80, No. 11, Nov. 1, 1992.
- Golrezaei, Negin et al., "FemtoCaching: Wireless Video Content Delivery through Distributed Caching Helpers", INFOCOM, Proceedings IEEE, 2012.
- Gomes, Nathan J. et al., "Radio-over-fiber transport for the support of wireless broadband services", Journal of Optical Networking 8.2: 156-178., 2009.
- Gonthier, François et al., "Mode coupling in nonuniform fibers: comparison between coupled-mode theory and finite-difference beam-propagation method simulations", JOSA B 8.2: 416421, Abstract Only, 1991, 3 pages.
- Gritzalis, Dimitris et al., "The Sphinx enigma in critical VoIP infrastructures: Human or botnet?." Information, Intelligence, Systems and Applications (IISA), 2013 Fourth International Conference, IEEE., 2013.
- Han, Chong et al., "crosslayer communication module for the Internet of Things", Computer Networks 57.3: 622633, Abstract Only, 2013, 1 page.
- Haroun, Ibrahim et al., "WLANs meet fiber optics—Evaluating 802.11 a WLANs over fiber optics links", RF Des. Mag: 36-39., 2003.
- Hassan, Karim , "Fabrication and characterization of thermo-plasmonic routers for telecom applications", Diss. Univ. de Bourgogne., 2014.
- Hassan, Maaly A. , "Interference reduction in mobile ad hoc and sensor networks", Journal of Engineering and Computer Innovations vol. 2(7), Sep. 2011, 138-154.
- Hassani, Alireza et al., "Porous polymer fibers for low-loss Terahertz guiding." Optics express 16.9: 6340-6351., 2008.
- Hautakorpi, Jani et al., "Requirements from Session Initiation Protocol (SIP) Session Border Control (SBC) Deployments." RFC5853, IETF (2010)., 2010.
- Hawrylyshen, A. et al., "SIPPING Working Group J. Hautakorpi, Ed. Internet-Draft G. Camarillo Intended status: Informational Ericsson Expires: Dec. 18, 2008 R. Penfield Acme Packet.", 2008.
- Hoss, R.J. et al., "Manufacturing Methods and Technology Program for Ruggedized Tactical Fiber Optic Cable", No. ITT-80-03-078. ITT Electrooptical Products Div Roanoke VA., 1980.
- Ippolito, Louis J. , "Propagation effects handbook for satellite systems design. A summary of propagation impairments on 10 to 100 GHz satellite links with techniques for system design", 1989, Abstract Only, 1989, 1 page.
- Izumiyama, Hidetaka et al., "Multicast over satellite", Applications and the Internet, (SAINT 2002). Proceedings. Symposium on. IEEE, 2002.
- Jackson, Mark , "Timico CTO Hit by Slow FTTC Broadband Speeds After Copper Corrosion", ISP review, ispreview.co.uk, Mar. 5, 2013.
- Jaeger, Raymond et al., "Radiation Performance of Germanium Phosphosilicate Optical Fibers." RADC-TR-81-69: Final Technical Report, Galileo Electro-Optical Corp., May 1981.
- James, J.R. et al., "Investigations and Comparisons of New Types of Millimetre-Wave Planar Arrays Using Microstrip and Dielectric Structures", Royal Military Coll of Science Shrivenham (England)., 1985.
- Jang, Hung-Chin , "Applications of Geometric Algorithms to Reduce Interference in Wireless Mesh Network", Journal on Applications of Graph Theory in Wireless Ad hoc Networks and Sensor Networks (JGRAPH-HOC) vol. 2, No. 1, Abstract Only, Mar. 2010, 1 page.
- Jawhar, Imad et al., "A hierarchical and topological classification of linear sensor networks", Wireless Telecommunications Symposium, WTS, IEEE, http://faculty.uaeu.ac.ae/Nader_M/papers/WTS2009.pdf, 2009, 8 pages.
- Jee, George et al., "Demonstration of the Technical Viability of PLC Systems on Medium- and Low-Voltage Lines in the United States",

(56)

References Cited

OTHER PUBLICATIONS

- net”, Innovations in NGN: Future Network and Services, 2008. K-INGN 2008. First ITU-T Kaleidoscope Academic Conference, 2008.
- Perkons, Alfred R. et al., “TM surface-wave power combining by a planar active-lens amplifier”, *Microwave Theory and Techniques, IEEE Transactions on* 46.6: 775783, 1998.
- Péter, Zsolt et al., “Assessment of the current intensity for preventing ice accretion on overhead conductors”, *Power Delivery, IEEE Transactions on* 22.1: 565-574., 2007.
- Petrovsky, Oleg , “The Internet of Things: A Security Overview”, w.druva.com, Mar. 31, 2015.
- Pham, Tien-Thang et al., “A WDM-PON-compatible system for simultaneous distribution of gigabit baseband and wireless ultrawideband services with flexible bandwidth allocation”, *Photonics Journal, IEEE* 3.1, 2011, 13-19.
- Piksa, Petr et al., “Elliptic and hyperbolic dielectric lens antennas in mmwaves”, *Radioengineering* 20.1, 2011, 271.
- Plagemann, Thomas et al., “Infrastructures for community networks”, *Content Delivery Networks*. Springer Berlin Heidelberg, 367-388, 2008.
- “A dielectric lens-based antenna concept for high-precision industrial radar measurements at 24GHz,” *Radar Conference (EuRAD)*, 2012 9th European, IEEE., 2012.
- Pranonsatit, S. et al., “Sectorised horn antenna array using an RF MEMS rotary switch”, *Asia-Pacific Microwave Conf., APMC.*, 2010.
- Pranonsatit, Suneat et al., “Single-pole eight-throw RF MEMS rotary switch”, *Microelectromechanical Systems, Journal of* 15.6: 1735-1744, 2006.
- Prashant, R.R. et al., “Detecting and Identifying the Location of Multiple Spoofing Adversaries in Wireless Network”, *International Journal of Computer Science and Mobile Applications*, vol. 2 Issue. 5, May 2014, 1-6.
- Rahim, S. K. A. et al., “Measurement of wet antenna losses on 26 GHz terrestrial microwave link in Malaysia”, *Wireless Personal Communications* 64.2: 225231, 2012.
- Rambabu, K. et al., “Compact single-channel rotary joint using ridged waveguide sections for phase adjustment,” *IEEE Transactions on Microwave Theory and Techniques (Aug. 2003)* 51(8):1982-1986., Abstract Only, Aug. 2003, 2 pages.
- Rappaport, Theodore S. et al., “Mobile’s Millimeter-Wave Make-over”, *Spectrum.IEEE.Org*, Sep. 2014.
- Raychaudhuri, Dipankar et al., “Emerging Wireless Technologies and the Future Mobile Internet”, Cambridge University Press, Abstract Only, Mar. 2011, 1 page.
- Raychem, “Wire and Cable”, *Dimensions* 2:1., 1996.
- Reynet, Olivier et al., “Effect of the magnetic properties of the inclusions on the high-frequency dielectric response of diluted composites.” *Physical Review B* 66.9: 094412., 2002.
- Rouse, Margaret , “Transport Layer Security (TLS)”, *TechTarget, searchsecurity.techtarget.com*, Jul. 2006.
- Roze, Mathieu et al., “Suspended core subwavelength fibers: towards practical designs for low-loss terahertz guidance.” *Optics express* 19.10 (2011): 9127-9138., 2011.
- Sagar, Nishant , “Powerline Communications Systems: Overview and Analysis”, Thesis, May 2011, 80 pages.
- Sagues, Mikel et al., “Multi-tap complex-coefficient incoherent microwave photonic filters based on optical single-sideband modulation and narrow band optical filtering.” *Optics express* 16.1: 295-303., 2008.
- Saied, Yosra Ben et al., “Trust management system design for the internet of things: a contextaware and multiservice approach”, *Computers & Security* 39: 351365, Abstract Only, 2013, 2 pages.
- Salema, Carlos et al., “Solid dielectric horn antennas,” *Artech House Publishers*, 1998.
- Salema, Carlos et al., “Solid dielectric horn antennas,” *Artech House Publishers*, 1998, Amazon., Book—description only, 1998.
- Sarafi, A. et al., “Hybrid wireless-broadband over power lines: A promising broadband solution in rural areas.” *Communications Magazine, IEEE* 47.11 (2009): 140-147., 2009.
- Sarafi, Angeliki M. et al., “Hybrid Wireless-Broadband over Power Lines: A Promising Broadband Solution in Rural Areas”, *IEEE Communications Magazine*, Nov. 2009, 8 pages.
- Sarnecki, Joseph et al., “Microcell design principles”, *Communications Magazine, IEEE* 31.4: 76-82, 1993.
- Saruhan, Ibrahim Halil , “Detecting and Preventing Rogue Devices on the Network”, *SANS Institute InfoSec Reading Room, sans.org*, Aug. 8, 2007, 1 page.
- Scarfone, Karen et al., “Technical Guide to Information Security Testing and Assessment”, National Institute of Standards and Technology, csrc.nist.gov, Special Publication, Sep. 2008, 800-115.
- Shafai, Lotfollah , “Dielectric Loaded Antennas”, John Wiley & Sons, Inc., http://www.researchgate.net/publication/227998803_Dielectric_Loaded_Antennas, Apr. 15, 2005.
- Shafi, Mansoor et al., “Advances in Propagation Modeling for Wireless Systems”, *EURASIP Journal on Wireless Communications and Networking*. Hindawi Publishing Corp, 2009, p. 5.
- Shimabukuko, F.I. et al., “Attenuation measurement of very low-loss dielectric waveguides by the cavity resonator method in the millimeter/submillimeter wavelength range.” No. TR-0086A(2925-06)-1. Aerospace Corp El Segundo CA Electronics Research Lab, 1989., 1989.
- Shindo, Shuichi et al., “Attenuation measurement of cylindrical dielectric-rod waveguide.” *Electronics Letters* 12.5, 117-118., 1976.
- Shumate, Paul W. et al., “Evolution of fiber in the residential loop plant.” *IEEE Communications Magazine* 29.3: 68-74., 1991.
- Sievenpiper, D.F. et al., “Two-dimensional beam steering using an electrically tunable impedance surface,” in *Antennas and Propagation, IEEE Transactions on* , vol. 51, No. 10, pp. 2713-2722., Oct. 2003.
- Sommerfeld, A. , “On the propagation of electrodynamic waves along a wire”, *Annals of Physics and Chemistry New Edition*, vol. 67, No. 2, 1899, 72 pages.
- Strahler, Olivier , “Network Based VPNs”, *SANS Institute InfoSec Reading Room, sans.org.*, Aug. 2002.
- Strieby, M.E. et al., “Television transmission over wire lines.” *American Institute of Electrical Engineers, Transactions of the* 60.12: 1090-1096., Abstract Only, 1941, 2 pages.
- Szabó, Csaba A. , “European Broadband Initiatives with Public Participation”, *Broadband Services*: 255, 2005.
- Taboada, John M. et al., “Thermo-optically tuned cascaded polymer waveguide taps.” *Applied physics letters* 75.2: 163-165., 1999.
- Templeton, Steven J. et al., “Detecting Spoofed Packets”, *DARPA Information Survivability Conference and Exposition*, vol. 1, IEEE, 2003.
- Theoleyr, Fabrice , “Internet of Things and M2M Communications”, books.google.com, ISBN13: 9788792982483, Book—description only, Apr. 17, 2013, 1 page.
- Thornton, John et al., “Modern lens antennas for communications engineering”, vol. 39, 2013.
- Valladares, Cindy , “20 Critical Security Controls: Control 7—Wireless Device Control”, *Tripwire—The State of Security*, tripwire.com, Mar. 21, 2013.
- Vogelgesang, Ralf et al., “Plasmonic nanostructures in aperture-less scanning near-field optical microscopy (aSNOM)”, *physica status solidi (b)* 245.10: 22552260, 2008.
- Volat, C. et al., “De-icing/anti-icing techniques for power lines: current methods and future direction”, *Proceedings of the 11th International Workshop on Atmospheric Icing of Structures*, Montreal, Canada., 2005.
- Wagter, Herman , “Fiber-to-the-X: the economics of last-mile fiber”, *ARS Technica, arstechnica.com.*, Mar. 31, 2010.
- Wake, David et al., “Radio over fiber link design for next generation wireless systems”, *Lightwave Technology, Journal of* 28.16: 2456-2464., 2010.
- Wang, Jing et al., “The influence of optical fiber bundle parameters on the transmission of laser speckle patterns”, *Optics express* 22.8, 2014, 8908-8918.
- Wilkins, George A. , “Fiber Optic Telemetry in Ocean Cable Systems”, Chapter in new edition of *Handbook of Oceanographic*

(56)

References Cited

OTHER PUBLICATIONS

Winch, Wire and Cable Technology, Alan H. Driscoll, Ed., (to be published by University of Rhode Island), 1986.

Wolff, Christian , “Phased Array Antenna” Radar Tutorial, web.archive.org, radartutorial.eu, Oct. 21, 2014.

Wu, Xidong et al., “Design and characterization of singleand multiplebeam mmwave circularly polarized substrate lens antennas for wireless communications”, Microwave Theory and Techniques, IEEE Transactions on 49.3, 2001, 431-441.

Xi, Liu Xiao , “Security services in SoftLayer”, Sep. 21, 2015.

Xia, Cen et al., “Supermodes for optical transmission”, Optics express 19.17, 2011, 16653-16664.

Yang, , “Power Line Sensor Networks for Enhancing Power Line Reliability and Utilization”, Georgia Institute of Technology, https://smartech.gatech.edu/bitstream/handle/1853/41087/Yang_Yi_201108_phd.pdf, Apr. 26, 2011, 264 pages.

Yang, et al., “Power line sensornet—a new concept for power grid monitoring”, IEEE Power Engineering Society General Meeting, Abstract Only, 2006, pp. 8.

Yeh, C. et al., “Ceramic Waveguides.” Interplanetary Network Progress Report141.26: 1., 2000.

Yu, Shui et al., “Predicted packet padding for anonymous web browsing against traffic analysis attacks”, Information Forensics and Security, IEEE Transactions on 7.4, <http://nsp.org.au/syu/papers/tifs12.pdf>, 2012, 1381-1393.

Zelby, Leon W. , “Propagation Modes on a Dielectric Coated Wire”, J. The Franklin Institute, vol. 274(2), pp. 85-97, 1962.

Zhao, et al., “Energy harvesting for a wireless-monitoring system of overhead high-voltage power lines”, IET Generation, Transmission & Distribution 7, IEEE Xplore Abstract, 2013, 2 pages.

Zheng, Zhu et al., “Efficient coupling of propagating broadband terahertz radial beams to metal wires”, Optics express 21.9: 1064210650, 2013.

Zucker, , “Surface-wave antennas”, Antenna engineering handbook 4, 2007.

“International Search Report & Written Opinion”, PCT/US16/28207, 2016.

“International Preliminary Report on Patentability”, PCT/US2014/039746, Dec. 10, 2015.

“International Preliminary Report on Patentability”, PCT/US2014/060841, May 19, 2016, 8 pages.

“International Search Report & Written Opinion”, PCT/US2015/034827, Sep. 30, 2015.

“International Search Report & Written Opinion”, PCT/US2015/056316, Jan. 21, 2016.

“International Search Report & Written Opinion”, PCT/US2015/056320, Jan. 29, 2016.

“International Search Report & Written Opinion”, PCT/US2015/056365, Jan. 22, 2016.

“International Search Report & Written Opinion”, PCT/US2015/056368, Jan. 25, 2016.

“International Search Report & Written Opinion”, PCT/US2015/056598, Jan. 28, 2016.

“International Search Report & Written Opinion”, PCT/US2015/056615, Jan. 21, 2016.

“International Search Report & Written Opinion”, PCT/US2015/056626, Jan. 21, 2016.

“International Search Report & Written Opinion”, PCT/US2015/056632, Jan. 26, 2016.

“International Search Report & Written Opinion”, PCT/US2016/013988, Apr. 8, 2016.

“International Search Report & Written Opinion”, PCT/US2016/020001, May 23, 2016.

“International Search Report & Written Opinion”, PCT/US2016/026860, Jun. 1, 2016.

“International Search Report & Written Opinion”, PCT/US2016/026318, Jun. 15, 2016.

“International Search Report & Written Opinion”, PCT/US2014/039746, Jan. 12, 2015.

“International Search Report & Written Opinion”, PCT/US2014/060841, Jan. 7, 2015.

“International Search Report & Written Opinion”, PCT/US2015/039848, Oct. 20, 2015.

“International Search Report & Written Opinion”, PCT/US2015/047315, Oct. 30, 2015.

“International Search Report & Written Opinion”, PCT/US2015/048454, Nov. 11, 2015.

“International Search Report & Written Opinion”, PCT/US2015/049928, Nov. 16, 2015.

“International Search Report & Written Opinion”, PCT/US2015/049932, Nov. 16, 2015.

“International Search Report & Written Opinion”, PCT/US2015/049927, Nov. 24, 2015.

“International Search Report & Written Opinion”, PCT/US2015/051193, Nov. 27, 2015.

“International Search Report & Written Opinion”, PCT/US2015/051146, Dec. 15, 2015.

“International Search Report & Written Opinion”, PCT/US2015/051183, Dec. 15, 2015.

“International Search Report & Written Opinion”, PCT/US2015/051194, Dec. 15, 2015.

“International Search Report & Written Opinion”, PCT/US2015/051578, Dec. 17, 2015.

“International Search Report & Written Opinion”, PCT/US2015/051583, Dec. 21, 2015.

“International Search Report & Written Opinion”, PCT/US2015/048458, Dec. 23, 2015.

“International Search Report & Written Opinion”, PCT/US2015/051213, Dec. 4, 2015.

“International Search Report & Written Opinion”, PCT/US2015/051163, Dec. 7, 2015.

“International Search Report & Written Opinion”, PCT/US2014/061445, Feb. 10, 2015.

“International Search Report & Written Opinion”, PCT/US2016/015501, Apr. 29, 2016, 11 pages.

“International Search Report & Written Opinion”, PCT/US2015/047225, mailed Nov. 6, 2015, Nov. 6, 2015.

“PCT International Search Report & Written Opinion”, PCT/US2016/026193, Jun. 1, 2016.

“Transducer”, IEEE Std 100-2000, Sep. 21, 2015, 1154.

Alam, M.N. et al., “Novel surface wave exciters for power line fault detection and communications.” Antennas and Propagation (APSURSI), 2011 IEEE International Symposium on. IEEE, 2011.

Bing, Benny , “Ubiquitous Broadband Access Networks with Peer-to-Peer Application Support”, Evolving the Access Network, 2006, 27-36.

Erickson, Katherine , “Conductive cylindrical surface waveguides”, 2012.

Laforte, J.L. et al., “State-of-the-art on power line de-icing”, Atmospheric Research 46, 143-158, 1998.

Ponchak, George E. et al., “A New Model for Broadband Waveguide to Microstrip Transition Design”, NASA TM-88905, Dec. 1, 1986, 18 pgs.

* cited by examiner




FIG. 1






FIG. 2




300

FIG. 3




400


FIG. 4



500
FIG. 5A




550
FIG. 5B




600


FIG. 6




700
FIG. 7



800
FIG. 8




900
FIG. 9A



950
FIG. 9B

1000
FIG. 10A










FIG. 10B







1300
FIG. 13



1400
FIG. 14



1500
FIG. 15



1600
FIG. 16A






FIG. 16B



1700

FIG. 17A



1750

FIG. 17B




FIG. 18A




FIG. 18B




FIG. 18C




FIG. 18D




FIG. 18E




FIG. 18F




FIG. 18G




FIG. 18H




FIG. 18I




FIG. 18J




FIG. 18K




FIG. 18L




FIG. 18M




FIG. 18N




FIG. 18O




FIG. 18P




FIG. 18Q






FIG. 18R






FIG. 18U




FIG. 18V




FIG. 18W




FIG. 19A




FIG. 19B








FIG. 19C






2030

FIG. 20C




2040

FIG. 20D



2050

FIG. 20E



2060

FIG. 20F




FIG. 21





FIG. 22



2300
FIG. 23

**METHODS AND APPARATUS FOR
INDUCING A FUNDAMENTAL WAVE MODE
ON A TRANSMISSION MEDIUM**

FIELD OF THE DISCLOSURE

The subject disclosure relates to communications via microwave transmission in a communication network.

BACKGROUND

As smart phones and other portable devices increasingly become ubiquitous, and data usage increases, macrocell base station devices and existing wireless infrastructure in turn require higher bandwidth capability in order to address the increased demand. To provide additional mobile bandwidth, small cell deployment is being pursued, with microcells and picocells providing coverage for much smaller areas than traditional macrocells.

In addition, most homes and businesses have grown to rely on broadband data access for services such as voice, video and Internet browsing, etc. Broadband access networks include satellite, 4G or 5G wireless, power line communication, fiber, cable, and telephone networks.

BRIEF DESCRIPTION OF THE DRAWINGS

Reference will now be made to the accompanying drawings, which are not necessarily drawn to scale, and wherein:

FIG. 1 is a block diagram illustrating an example, non-limiting embodiment of a guided-wave communications system in accordance with various aspects described herein.

FIG. 2 is a block diagram illustrating an example, non-limiting embodiment of a transmission device in accordance with various aspects described herein.

FIG. 3 is a graphical diagram illustrating an example, non-limiting embodiment of an electromagnetic field distribution in accordance with various aspects described herein.

FIG. 4 is a graphical diagram illustrating an example, non-limiting embodiment of an electromagnetic field distribution in accordance with various aspects described herein.

FIG. 5A is a graphical diagram illustrating an example, non-limiting embodiment of a frequency response in accordance with various aspects described herein.

FIG. 5B is a graphical diagram illustrating example, non-limiting embodiments of a longitudinal cross-section of an insulated wire depicting fields of guided electromagnetic waves at various operating frequencies in accordance with various aspects described herein.

FIG. 6 is a graphical diagram illustrating an example, non-limiting embodiment of an electromagnetic field distribution in accordance with various aspects described herein.

FIG. 7 is a block diagram illustrating an example, non-limiting embodiment of an arc coupler in accordance with various aspects described herein.

FIG. 8 is a block diagram illustrating an example, non-limiting embodiment of an arc coupler in accordance with various aspects described herein.

FIG. 9A is a block diagram illustrating an example, non-limiting embodiment of a stub coupler in accordance with various aspects described herein.

FIG. 9B is a diagram illustrating an example, non-limiting embodiment of an electromagnetic distribution in accordance with various aspects described herein.

FIGS. 10A and 10B are block diagrams illustrating example, non-limiting embodiments of couplers and transceivers in accordance with various aspects described herein.

FIG. 11 is a block diagram illustrating an example, non-limiting embodiment of a dual stub coupler in accordance with various aspects described herein.

FIG. 12 is a block diagram illustrating an example, non-limiting embodiment of a repeater system in accordance with various aspects described herein.

FIG. 13 illustrates a block diagram illustrating an example, non-limiting embodiment of a bidirectional repeater in accordance with various aspects described herein.

FIG. 14 is a block diagram illustrating an example, non-limiting embodiment of a waveguide system in accordance with various aspects described herein.

FIG. 15 is a block diagram illustrating an example, non-limiting embodiment of a guided-wave communications system in accordance with various aspects described herein.

FIGS. 16A & 16B are block diagrams illustrating an example, non-limiting embodiment of a system for managing a power grid communication system in accordance with various aspects described herein.

FIG. 17A illustrates a flow diagram of an example, non-limiting embodiment of a method for detecting and mitigating disturbances occurring in a communication network of the system of FIGS. 16A and 16B.

FIG. 17B illustrates a flow diagram of an example, non-limiting embodiment of a method for detecting and mitigating disturbances occurring in a communication network of the system of FIGS. 16A and 16B.

FIGS. 18A, 18B, and 18C are block diagrams illustrating example, non-limiting embodiment of a transmission medium for propagating guided electromagnetic waves.

FIG. 18D is a block diagram illustrating an example, non-limiting embodiment of bundled transmission media in accordance with various aspects described herein.

FIG. 18E is a block diagram illustrating an example, non-limiting embodiment of a plot depicting cross-talk between first and second transmission mediums of the bundled transmission media of FIG. 18D in accordance with various aspects described herein.

FIG. 18F is a block diagram illustrating an example, non-limiting embodiment of bundled transmission media to mitigate cross-talk in accordance with various aspects described herein.

FIGS. 18G and 18H are block diagrams illustrating example, non-limiting embodiments of a transmission medium with an inner waveguide in accordance with various aspects described herein.

FIGS. 18I and 18J are block diagrams illustrating example, non-limiting embodiments of connector configurations that can be used with the transmission medium of FIG. 18A, 18B, or 18C.

FIG. 18K is a block diagram illustrating example, non-limiting embodiments of transmission mediums for propagating guided electromagnetic waves.

FIG. 18L is a block diagram illustrating example, non-limiting embodiments of bundled transmission media to mitigate cross-talk in accordance with various aspects described herein.

FIG. 18M is a block diagram illustrating an example, non-limiting embodiment of exposed stubs from the bundled transmission media for use as antennas in accordance with various aspects described herein.

FIGS. 18N, 18O, 18P, 18Q, 18R, 18S, 18T, 18U, 18V and 18W are block diagrams illustrating example, non-limiting

embodiments of a waveguide device for transmitting or receiving electromagnetic waves in accordance with various aspects described herein.

FIGS. 19A and 19B are block diagrams illustrating example, non-limiting embodiments of the transmission medium of FIG. 18A used for inducing guided electromagnetic waves on power lines supported by utility poles.

FIG. 19C is a block diagram of an example, non-limiting embodiment of a communication network in accordance with various aspects described herein.

FIG. 20A illustrates a flow diagram of an example, non-limiting embodiment of a method for transmitting downlink signals.

FIG. 20B illustrates a flow diagram of an example, non-limiting embodiment of a method for transmitting uplink signals.

FIG. 20C illustrates a flow diagram of an example, non-limiting embodiment of a method for inducing electromagnetic waves on a transmission medium.

FIG. 20D illustrates a flow diagram of an example, non-limiting embodiment of a method for receiving electromagnetic waves from a transmission medium.

FIG. 20E illustrates a flow diagram of an example, non-limiting embodiment of a method for inducing electromagnetic waves on a transmission medium.

FIG. 20F illustrates a flow diagram of an example, non-limiting embodiment of a method for receiving electromagnetic waves from a transmission medium.

FIG. 21 is a block diagram of an example, non-limiting embodiment of a computing environment in accordance with various aspects described herein.

FIG. 22 is a block diagram of an example, non-limiting embodiment of a mobile network platform in accordance with various aspects described herein.

FIG. 23 is a block diagram of an example, non-limiting embodiment of a communication device in accordance with various aspects described herein.

DETAILED DESCRIPTION

One or more embodiments are now described with reference to the drawings, wherein like reference numerals are used to refer to like elements throughout. In the following description, for purposes of explanation, numerous details are set forth in order to provide a thorough understanding of the various embodiments. It is evident, however, that the various embodiments can be practiced without these details (and without applying to any particular networked environment or standard).

In an embodiment, a guided wave communication system is presented for sending and receiving communication signals such as data or other signaling via guided electromagnetic waves. The guided electromagnetic waves include, for example, surface waves or other electromagnetic waves that are bound to or guided by a transmission medium. It will be appreciated that a variety of transmission media can be utilized with guided wave communications without departing from example embodiments. Examples of such transmission media can include one or more of the following, either alone or in one or more combinations: wires, whether insulated or not, and whether single-stranded or multi-stranded; conductors of other shapes or configurations including wire bundles, cables, rods, rails, pipes; non-conductors such as dielectric pipes, rods, rails, or other dielectric members; combinations of conductors and dielectric materials; or other guided wave transmission media.

The inducement of guided electromagnetic waves on a transmission medium can be independent of any electrical potential, charge or current that is injected or otherwise transmitted through the transmission medium as part of an electrical circuit. For example, in the case where the transmission medium is a wire, it is to be appreciated that while a small current in the wire may be formed in response to the propagation of the guided waves along the wire, this can be due to the propagation of the electromagnetic wave along the wire surface, and is not formed in response to electrical potential, charge or current that is injected into the wire as part of an electrical circuit. The electromagnetic waves traveling on the wire therefore do not require a circuit to propagate along the wire surface. The wire therefore is a single wire transmission line that is not part of a circuit. Also, in some embodiments, a wire is not necessary, and the electromagnetic waves can propagate along a single line transmission medium that is not a wire.

More generally, “guided electromagnetic waves” or “guided waves” as described by the subject disclosure are affected by the presence of a physical object that is at least a part of the transmission medium (e.g., a bare wire or other conductor, a dielectric, an insulated wire, a conduit or other hollow element, a bundle of insulated wires that is coated, covered or surrounded by a dielectric or insulator or other wire bundle, or another form of solid, liquid or otherwise non-gaseous transmission medium) so as to be at least partially bound to or guided by the physical object and so as to propagate along a transmission path of the physical object. Such a physical object can operate as at least a part of a transmission medium that guides, by way of an interface of the transmission medium (e.g., an outer surface, inner surface, an interior portion between the outer and the inner surfaces or other boundary between elements of the transmission medium), the propagation of guided electromagnetic waves, which in turn can carry energy, data and/or other signals along the transmission path from a sending device to a receiving device.

Unlike free space propagation of wireless signals such as unguided (or unbounded) electromagnetic waves that decrease in intensity inversely by the square of the distance traveled by the unguided electromagnetic waves, guided electromagnetic waves can propagate along a transmission medium with less loss in magnitude per unit distance than experienced by unguided electromagnetic waves.

Unlike electrical signals, guided electromagnetic waves can propagate from a sending device to a receiving device without requiring a separate electrical return path between the sending device and the receiving device. As a consequence, guided electromagnetic waves can propagate from a sending device to a receiving device along a transmission medium having no conductive components (e.g., a dielectric strip), or via a transmission medium having no more than a single conductor (e.g., a single bare wire or insulated wire). Even if a transmission medium includes one or more conductive components and the guided electromagnetic waves propagating along the transmission medium generate currents that flow in the one or more conductive components in a direction of the guided electromagnetic waves, such guided electromagnetic waves can propagate along the transmission medium from a sending device to a receiving device without requiring a flow of opposing currents on an electrical return path between the sending device and the receiving device.

In a non-limiting illustration, consider electrical systems that transmit and receive electrical signals between sending and receiving devices by way of conductive media. Such

5

systems generally rely on electrically separate forward and return paths. For instance, consider a coaxial cable having a center conductor and a ground shield that are separated by an insulator. Typically, in an electrical system a first terminal of a sending (or receiving) device can be connected to the center conductor, and a second terminal of the sending (or receiving) device can be connected to the ground shield. If the sending device injects an electrical signal in the center conductor via the first terminal, the electrical signal will propagate along the center conductor causing forward currents in the center conductor, and return currents in the ground shield. The same conditions apply for a two terminal receiving device.

In contrast, consider a guided wave communication system such as described in the subject disclosure, which can utilize different embodiments of a transmission medium (including among others a coaxial cable) for transmitting and receiving guided electromagnetic waves without an electrical return path. In one embodiment, for example, the guided wave communication system of the subject disclosure can be configured to induce guided electromagnetic waves that propagate along an outer surface of a coaxial cable. Although the guided electromagnetic waves will cause forward currents on the ground shield, the guided electromagnetic waves do not require return currents to enable the guided electromagnetic waves to propagate along the outer surface of the coaxial cable. The same can be said of other transmission media used by a guided wave communication system for the transmission and reception of guided electromagnetic waves. For example, guided electromagnetic waves induced by the guided wave communication system on an outer surface of a bare wire, or an insulated wire can propagate along the bare wire or the insulated bare wire without an electrical return path.

Consequently, electrical systems that require two or more conductors for carrying forward and reverse currents on separate conductors to enable the propagation of electrical signals injected by a sending device are distinct from guided wave systems that induce guided electromagnetic waves on an interface of a transmission medium without the need of an electrical return path to enable the propagation of the guided electromagnetic waves along the interface of the transmission medium.

It is further noted that guided electromagnetic waves as described in the subject disclosure can have an electromagnetic field structure that lies primarily or substantially outside of a transmission medium so as to be bound to or guided by the transmission medium and so as to propagate non-trivial distances on or along an outer surface of the transmission medium. In other embodiments, guided electromagnetic waves can have an electromagnetic field structure that lies primarily or substantially inside a transmission medium so as to be bound to or guided by the transmission medium and so as to propagate non-trivial distances within the transmission medium. In other embodiments, guided electromagnetic waves can have an electromagnetic field structure that lies partially inside and partially outside a transmission medium so as to be bound to or guided by the transmission medium and so as to propagate non-trivial distances along the transmission medium. The desired electronic field structure in an embodiment may vary based upon a variety of factors, including the desired transmission distance, the characteristics of the transmission medium itself, and environmental conditions/characteristics outside of the transmission medium (e.g., presence of rain, fog, atmospheric conditions, etc.).

6

Various embodiments described herein relate to coupling devices, that can be referred to as “waveguide coupling devices”, “waveguide couplers” or more simply as “couplers”, “coupling devices” or “launchers” for launching and/or extracting guided electromagnetic waves to and from a transmission medium at millimeter-wave frequencies (e.g., 30 to 300 GHz), wherein the wavelength can be small compared to one or more dimensions of the coupling device and/or the transmission medium such as the circumference of a wire or other cross sectional dimension, or lower microwave frequencies such as 300 MHz to 30 GHz. Transmissions can be generated to propagate as waves guided by a coupling device, such as: a strip, arc or other length of dielectric material; a horn, monopole, rod, slot or other antenna; an array of antennas; a magnetic resonant cavity, or other resonant coupler; a coil, a strip line, a waveguide or other coupling device. In operation, the coupling device receives an electromagnetic wave from a transmitter or transmission medium. The electromagnetic field structure of the electromagnetic wave can be carried inside the coupling device, outside the coupling device or some combination thereof. When the coupling device is in close proximity to a transmission medium, at least a portion of an electromagnetic wave couples to or is bound to the transmission medium, and continues to propagate as guided electromagnetic waves. In a reciprocal fashion, a coupling device can extract guided waves from a transmission medium and transfer these electromagnetic waves to a receiver.

According to an example embodiment, a surface wave is a type of guided wave that is guided by a surface of a transmission medium, such as an exterior or outer surface of the wire, or another surface of the wire that is adjacent to or exposed to another type of medium having different properties (e.g., dielectric properties). Indeed, in an example embodiment, a surface of the wire that guides a surface wave can represent a transitional surface between two different types of media. For example, in the case of a bare or uninsulated wire, the surface of the wire can be the outer or exterior conductive surface of the bare or uninsulated wire that is exposed to air or free space. As another example, in the case of insulated wire, the surface of the wire can be the conductive portion of the wire that meets the insulator portion of the wire, or can otherwise be the insulator surface of the wire that is exposed to air or free space, or can otherwise be any material region between the insulator surface of the wire and the conductive portion of the wire that meets the insulator portion of the wire, depending upon the relative differences in the properties (e.g., dielectric properties) of the insulator, air, and/or the conductor and further dependent on the frequency and propagation mode or modes of the guided wave.

According to an example embodiment, the term “about” a wire or other transmission medium used in conjunction with a guided wave can include fundamental guided wave propagation modes such as a guided waves having a circular or substantially circular field distribution, a symmetrical electromagnetic field distribution (e.g., electric field, magnetic field, electromagnetic field, etc.) or other fundamental mode pattern at least partially around a wire or other transmission medium. In addition, when a guided wave propagates “about” a wire or other transmission medium, it can do so according to a guided wave propagation mode that includes not only the fundamental wave propagation modes (e.g., zero order modes), but additionally or alternatively non-fundamental wave propagation modes such as higher-order guided wave modes (e.g., 1st order modes, 2nd order modes, etc.), asymmetrical modes and/or other guided (e.g.,

surface) waves that have non-circular field distributions around a wire or other transmission medium. As used herein, the term “guided wave mode” refers to a guided wave propagation mode of a transmission medium, coupling device or other system component of a guided wave communication system.

For example, such non-circular field distributions can be unilateral or multi-lateral with one or more axial lobes characterized by relatively higher field strength and/or one or more nulls or null regions characterized by relatively low-field strength, zero-field strength or substantially zero-field strength. Further, the field distribution can otherwise vary as a function of azimuthal orientation around the wire such that one or more angular regions around the wire have an electric or magnetic field strength (or combination thereof) that is higher than one or more other angular regions of azimuthal orientation, according to an example embodiment. It will be appreciated that the relative orientations or positions of the guided wave higher order modes or asymmetrical modes can vary as the guided wave travels along the wire.

As used herein, the term “millimeter-wave” can refer to electromagnetic waves/signals that fall within the “millimeter-wave frequency band” of 30 GHz to 300 GHz. The term “microwave” can refer to electromagnetic waves/signals that fall within a “microwave frequency band” of 300 MHz to 300 GHz. The term “radio frequency” or “RF” can refer to electromagnetic waves/signals that fall within the “radio frequency band” of 10 kHz to 1 THz. It is appreciated that wireless signals, electrical signals, and guided electromagnetic waves as described in the subject disclosure can be configured to operate at any desirable frequency range, such as, for example, at frequencies within, above or below millimeter-wave and/or microwave frequency bands. In particular, when a coupling device or transmission medium includes a conductive element, the frequency of the guided electromagnetic waves that are carried by the coupling device and/or propagate along the transmission medium can be below the mean collision frequency of the electrons in the conductive element. Further, the frequency of the guided electromagnetic waves that are carried by the coupling device and/or propagate along the transmission medium can be a non-optical frequency, e.g. a radio frequency below the range of optical frequencies that begins at 1 THz.

As used herein, the term “antenna” can refer to a device that is part of a transmitting or receiving system to transmit/radiate or receive wireless signals.

In accordance with one or more embodiments, a method includes generating, by a waveguide system, instances of first electromagnetic waves that combine to form combined electromagnetic waves having a fundamental wave mode and a non-optical operating frequency, and directing, by the waveguide system, the combined electromagnetic waves to an interface of a transmission medium for guiding propagation of the combined electromagnetic wave without utilizing an electrical return path.

In accordance with one or more embodiments, a system can include a plurality of transmitters for launching instances of first electromagnetic waves that combine to generate combined electromagnetic waves having a substantially fundamental wave mode and a non-optical operating frequency, and a waveguide for directing the combined electromagnetic waves to an interface of a transmission medium for guiding propagation of the combined electromagnetic waves without utilizing an electrical return path.

In accordance with one or more embodiments, a machine-readable storage medium includes executable instructions

that, when executed by a processor of a waveguide system, facilitate performance of operations, comprising obtaining operational parameters for configuring a plurality of launchers of the waveguide system, and configuring the plurality of launchers according to the operational parameters to generate instances of electromagnetic waves that combined to produce combined electromagnetic waves having a substantially fundamental wave mode and a non-optical operating frequency, wherein the waveguide system comprises a waveguide structure to direct the combined electromagnetic waves to an interface of a transmission medium for guiding propagation of the combined electromagnetic waves without utilizing an electrical return path.

Referring now to FIG. 1, a block diagram **100** illustrating an example, non-limiting embodiment of a guided wave communications system is shown. In operation, a transmission device **101** receives one or more communication signals **110** from a communication network or other communications device that includes data and generates guided waves **120** to convey the data via the transmission medium **125** to the transmission device **102**. The transmission device **102** receives the guided waves **120** and converts them to communication signals **112** that include the data for transmission to a communications network or other communications device. The guided waves **120** can be modulated to convey data via a modulation technique such as phase shift keying, frequency shift keying, quadrature amplitude modulation, amplitude modulation, multi-carrier modulation such as orthogonal frequency division multiplexing and via multiple access techniques such as frequency division multiplexing, time division multiplexing, code division multiplexing, multiplexing via differing wave propagation modes and via other modulation and access strategies.

The communication network or networks can include a wireless communication network such as a mobile data network, a cellular voice and data network, a wireless local area network (e.g., WiFi or an 802.xx network), a satellite communications network, a personal area network or other wireless network. The communication network or networks can also include a wired communication network such as a telephone network, an Ethernet network, a local area network, a wide area network such as the Internet, a broadband access network, a cable network, a fiber optic network, or other wired network. The communication devices can include a network edge device, bridge device or home gateway, a set-top box, broadband modem, telephone adapter, access point, base station, or other fixed communication device, a mobile communication device such as an automotive gateway or automobile, laptop computer, tablet, smartphone, cellular telephone, or other communication device.

In an example embodiment, the guided wave communication system **100** can operate in a bi-directional fashion where transmission device **102** receives one or more communication signals **112** from a communication network or device that includes other data and generates guided waves **122** to convey the other data via the transmission medium **125** to the transmission device **101**. In this mode of operation, the transmission device **101** receives the guided waves **122** and converts them to communication signals **110** that include the other data for transmission to a communications network or device. The guided waves **122** can be modulated to convey data via a modulation technique such as phase shift keying, frequency shift keying, quadrature amplitude modulation, amplitude modulation, multi-carrier modulation such as orthogonal frequency division multiplexing and via multiple access techniques such as frequency division

multiplexing, time division multiplexing, code division multiplexing, multiplexing via differing wave propagation modes and via other modulation and access strategies.

The transmission medium **125** can include a cable having at least one inner portion surrounded by a dielectric material such as an insulator or other dielectric cover, coating or other dielectric material, the dielectric material having an outer surface and a corresponding circumference. In an example embodiment, the transmission medium **125** operates as a single-wire transmission line to guide the transmission of an electromagnetic wave. When the transmission medium **125** is implemented as a single wire transmission system, it can include a wire. The wire can be insulated or uninsulated, and single-stranded or multi-stranded (e.g., braided). In other embodiments, the transmission medium **125** can contain conductors of other shapes or configurations including wire bundles, cables, rods, rails, pipes. In addition, the transmission medium **125** can include non-conductors such as dielectric pipes, rods, rails, or other dielectric members; combinations of conductors and dielectric materials, conductors without dielectric materials or other guided wave transmission media. It should be noted that the transmission medium **125** can otherwise include any of the transmission media previously discussed.

Further, as previously discussed, the guided waves **120** and **122** can be contrasted with radio transmissions over free space/air or conventional propagation of electrical power or signals through the conductor of a wire via an electrical circuit. In addition to the propagation of guided waves **120** and **122**, the transmission medium **125** may optionally contain one or more wires that propagate electrical power or other communication signals in a conventional manner as a part of one or more electrical circuits.

Referring now to FIG. 2, a block diagram **200** illustrating an example, non-limiting embodiment of a transmission device is shown. The transmission device **101** or **102** includes a communications interface (I/F) **205**, a transceiver **210** and a coupler **220**.

In an example of operation, the communications interface **205** receives a communication signal **110** or **112** that includes data. In various embodiments, the communications interface **205** can include a wireless interface for receiving a wireless communication signal in accordance with a wireless standard protocol such as LTE or other cellular voice and data protocol, WiFi or an 802.11 protocol, WIMAX protocol, Ultra Wideband protocol, Bluetooth protocol, Zigbee protocol, a direct broadcast satellite (DBS) or other satellite communication protocol or other wireless protocol. In addition or in the alternative, the communications interface **205** includes a wired interface that operates in accordance with an Ethernet protocol, universal serial bus (USB) protocol, a data over cable service interface specification (DOCSIS) protocol, a digital subscriber line (DSL) protocol, a Firewire (IEEE 1394) protocol, or other wired protocol. In addition to standards-based protocols, the communications interface **205** can operate in conjunction with other wired or wireless protocol. In addition, the communications interface **205** can optionally operate in conjunction with a protocol stack that includes multiple protocol layers including a MAC protocol, transport protocol, application protocol, etc.

In an example of operation, the transceiver **210** generates an electromagnetic wave based on the communication signal **110** or **112** to convey the data. The electromagnetic wave has at least one carrier frequency and at least one corresponding wavelength. The carrier frequency can be within a millimeter-wave frequency band of 30 GHz-300 GHz, such as 60

GHz or a carrier frequency in the range of 30-40 GHz or a lower frequency band of 300 MHz-30 GHz in the microwave frequency range such as 26-30 GHz, 11 GHz, 6 GHz or 3 GHz, but it will be appreciated that other carrier frequencies are possible in other embodiments. In one mode of operation, the transceiver **210** merely upconverts the communications signal or signals **110** or **112** for transmission of the electromagnetic signal in the microwave or millimeter-wave band as a guided electromagnetic wave that is guided by or bound to the transmission medium **125**. In another mode of operation, the communications interface **205** either converts the communication signal **110** or **112** to a baseband or near baseband signal or extracts the data from the communication signal **110** or **112** and the transceiver **210** modulates a high-frequency carrier with the data, the baseband or near baseband signal for transmission. It should be appreciated that the transceiver **210** can modulate the data received via the communication signal **110** or **112** to preserve one or more data communication protocols of the communication signal **110** or **112** either by encapsulation in the payload of a different protocol or by simple frequency shifting. In the alternative, the transceiver **210** can otherwise translate the data received via the communication signal **110** or **112** to a protocol that is different from the data communication protocol or protocols of the communication signal **110** or **112**.

In an example of operation, the coupler **220** couples the electromagnetic wave to the transmission medium **125** as a guided electromagnetic wave to convey the communications signal or signals **110** or **112**. While the prior description has focused on the operation of the transceiver **210** as a transmitter, the transceiver **210** can also operate to receive electromagnetic waves that convey other data from the single wire transmission medium via the coupler **220** and to generate communications signals **110** or **112**, via communications interface **205** that includes the other data. Consider embodiments where an additional guided electromagnetic wave conveys other data that also propagates along the transmission medium **125**. The coupler **220** can also couple this additional electromagnetic wave from the transmission medium **125** to the transceiver **210** for reception.

The transmission device **101** or **102** includes an optional training controller **230**. In an example embodiment, the training controller **230** is implemented by a standalone processor or a processor that is shared with one or more other components of the transmission device **101** or **102**. The training controller **230** selects the carrier frequencies, modulation schemes and/or guided wave modes for the guided electromagnetic waves based on feedback data received by the transceiver **210** from at least one remote transmission device coupled to receive the guided electromagnetic wave.

In an example embodiment, a guided electromagnetic wave transmitted by a remote transmission device **101** or **102** conveys data that also propagates along the transmission medium **125**. The data from the remote transmission device **101** or **102** can be generated to include the feedback data. In operation, the coupler **220** also couples the guided electromagnetic wave from the transmission medium **125** and the transceiver receives the electromagnetic wave and processes the electromagnetic wave to extract the feedback data.

In an example embodiment, the training controller **230** operates based on the feedback data to evaluate a plurality of candidate frequencies, modulation schemes and/or transmission modes to select a carrier frequency, modulation

scheme and/or transmission mode to enhance performance, such as throughput, signal strength, reduce propagation loss, etc.

Consider the following example: a transmission device **101** begins operation under control of the training controller **230** by sending a plurality of guided waves as test signals such as pilot waves or other test signals at a corresponding plurality of candidate frequencies and/or candidate modes directed to a remote transmission device **102** coupled to the transmission medium **125**. The guided waves can include, in addition or in the alternative, test data. The test data can indicate the particular candidate frequency and/or guided-wave mode of the signal. In an embodiment, the training controller **230** at the remote transmission device **102** receives the test signals and/or test data from any of the guided waves that were properly received and determines the best candidate frequency and/or guided wave mode, a set of acceptable candidate frequencies and/or guided wave modes, or a rank ordering of candidate frequencies and/or guided wave modes. This selection of candidate frequenc(ies) or/and guided-mode(s) are generated by the training controller **230** based on one or more optimizing criteria such as received signal strength, bit error rate, packet error rate, signal to noise ratio, propagation loss, etc. The training controller **230** generates feedback data that indicates the selection of candidate frequenc(ies) or/and guided wave mode(s) and sends the feedback data to the transceiver **210** for transmission to the transmission device **101**. The transmission device **101** and **102** can then communicate data with one another based on the selection of candidate frequenc(ies) or/and guided wave mode(s).

In other embodiments, the guided electromagnetic waves that contain the test signals and/or test data are reflected back, repeated back or otherwise looped back by the remote transmission device **102** to the transmission device **101** for reception and analysis by the training controller **230** of the transmission device **101** that initiated these waves. For example, the transmission device **101** can send a signal to the remote transmission device **102** to initiate a test mode where a physical reflector is switched on the line, a termination impedance is changed to cause reflections, a loop back mode is switched on to couple electromagnetic waves back to the source transmission device **102**, and/or a repeater mode is enabled to amplify and retransmit the electromagnetic waves back to the source transmission device **102**. The training controller **230** at the source transmission device **102** receives the test signals and/or test data from any of the guided waves that were properly received and determines selection of candidate frequenc(ies) or/and guided wave mode(s).

While the procedure above has been described in a start-up or initialization mode of operation, each transmission device **101** or **102** can send test signals, evaluate candidate frequencies or guided wave modes via non-test such as normal transmissions or otherwise evaluate candidate frequencies or guided wave modes at other times or continuously as well. In an example embodiment, the communication protocol between the transmission devices **101** and **102** can include an on-request or periodic test mode where either full testing or more limited testing of a subset of candidate frequencies and guided wave modes are tested and evaluated. In other modes of operation, the re-entry into such a test mode can be triggered by a degradation of performance due to a disturbance, weather conditions, etc. In an example embodiment, the receiver bandwidth of the transceiver **210** is either sufficiently wide or swept to receive all candidate frequencies or can be selectively adjusted by

the training controller **230** to a training mode where the receiver bandwidth of the transceiver **210** is sufficiently wide or swept to receive all candidate frequencies.

Referring now to FIG. 3, a graphical diagram **300** illustrating an example, non-limiting embodiment of an electromagnetic field distribution is shown. In this embodiment, a transmission medium **125** in air includes an inner conductor **301** and an insulating jacket **302** of dielectric material, as shown in cross section. The diagram **300** includes different gray-scales that represent differing electromagnetic field strengths generated by the propagation of the guided wave having an asymmetrical and non-fundamental guided wave mode.

In particular, the electromagnetic field distribution corresponds to a modal “sweet spot” that enhances guided electromagnetic wave propagation along an insulated transmission medium and reduces end-to-end transmission loss. In this particular mode, electromagnetic waves are guided by the transmission medium **125** to propagate along an outer surface of the transmission medium—in this case, the outer surface of the insulating jacket **302**. Electromagnetic waves are partially embedded in the insulator and partially radiating on the outer surface of the insulator. In this fashion, electromagnetic waves are “lightly” coupled to the insulator so as to enable electromagnetic wave propagation at long distances with low propagation loss.

As shown, the guided wave has a field structure that lies primarily or substantially outside of the transmission medium **125** that serves to guide the electromagnetic waves. The regions inside the conductor **301** have little or no field. Likewise regions inside the insulating jacket **302** have low field strength. The majority of the electromagnetic field strength is distributed in the lobes **304** at the outer surface of the insulating jacket **302** and in close proximity thereof. The presence of an asymmetric guided wave mode is shown by the high electromagnetic field strengths at the top and bottom of the outer surface of the insulating jacket **302** (in the orientation of the diagram)—as opposed to very small field strengths on the other sides of the insulating jacket **302**.

The example shown corresponds to a 38 GHz electromagnetic wave guided by a wire with a diameter of 1.1 cm and a dielectric insulation of thickness of 0.36 cm. Because the electromagnetic wave is guided by the transmission medium **125** and the majority of the field strength is concentrated in the air outside of the insulating jacket **302** within a limited distance of the outer surface, the guided wave can propagate longitudinally down the transmission medium **125** with very low loss. In the example shown, this “limited distance” corresponds to a distance from the outer surface that is less than half the largest cross sectional dimension of the transmission medium **125**. In this case, the largest cross sectional dimension of the wire corresponds to the overall diameter of 1.82 cm, however, this value can vary with the size and shape of the transmission medium **125**. For example, should the transmission medium **125** be of a rectangular shape with a height of 0.3 cm and a width of 0.4 cm, the largest cross sectional dimension would be the diagonal of 0.5 cm and the corresponding limited distance would be 0.25 cm. The dimensions of the area containing the majority of the field strength also vary with the frequency, and in general, increase as carrier frequencies decrease.

It should also be noted that the components of a guided wave communication system, such as couplers and transmission media can have their own cut-off frequencies for each guided wave mode. The cut-off frequency generally sets forth the lowest frequency that a particular guided wave mode is designed to be supported by that particular com-

ponent. In an example embodiment, the particular asymmetric mode of propagation shown is induced on the transmission medium **125** by an electromagnetic wave having a frequency that falls within a limited range (such as f_c to $2f_c$) of the lower cut-off frequency f_c for this particular asymmetric mode. The lower cut-off frequency f_c is particular to the characteristics of transmission medium **125**. For embodiments as shown that include an inner conductor **301** surrounded by an insulating jacket **302**, this cutoff frequency can vary based on the dimensions and properties of the insulating jacket **302** and potentially the dimensions and properties of the inner conductor **301** and can be determined experimentally to have a desired mode pattern. It should be noted however, that similar effects can be found for a hollow dielectric or insulator without an inner conductor. In this case, the cutoff frequency can vary based on the dimensions and properties of the hollow dielectric or insulator.

At frequencies lower than the lower cut-off frequency, the asymmetric mode is difficult to induce in the transmission medium **125** and fails to propagate for all but trivial distances. As the frequency increases above the limited range of frequencies about the cut-off frequency, the asymmetric mode shifts more and more inward of the insulating jacket **302**. At frequencies much larger than the cut-off frequency, the field strength is no longer concentrated outside of the insulating jacket, but primarily inside of the insulating jacket **302**. While the transmission medium **125** provides strong guidance to the electromagnetic wave and propagation is still possible, ranges are more limited by increased losses due to propagation within the insulating jacket **302**—as opposed to the surrounding air.

Referring now to FIG. 4, a graphical diagram **400** illustrating an example, non-limiting embodiment of an electromagnetic field distribution is shown. In particular, a cross section diagram **400**, similar to FIG. 3 is shown with common reference numerals used to refer to similar elements. The example shown corresponds to a 60 GHz wave guided by a wire with a diameter of 1.1 cm and a dielectric insulation of thickness of 0.36 cm. Because the frequency of the guided wave is above the limited range of the cut-off frequency of this particular asymmetric mode, much of the field strength has shifted inward of the insulating jacket **302**. In particular, the field strength is concentrated primarily inside of the insulating jacket **302**. While the transmission medium **125** provides strong guidance to the electromagnetic wave and propagation is still possible, ranges are more limited when compared with the embodiment of FIG. 3, by increased losses due to propagation within the insulating jacket **302**.

Referring now to FIG. 5A, a graphical diagram illustrating an example, non-limiting embodiment of a frequency response is shown. In particular, diagram **500** presents a graph of end-to-end loss (in dB) as a function of frequency, overlaid with electromagnetic field distributions **510**, **520** and **530** at three points for a 200 cm insulated medium voltage wire. The boundary between the insulator and the surrounding air is represented by reference numeral **525** in each electromagnetic field distribution.

As discussed in conjunction with FIG. 3, an example of a desired asymmetric mode of propagation shown is induced on the transmission medium **125** by an electromagnetic wave having a frequency that falls within a limited range (such as f_c to $2f_c$) of the lower cut-off frequency f_c of the transmission medium for this particular asymmetric mode. In particular, the electromagnetic field distribution **520** at 6 GHz falls within this modal “sweet spot” that enhances

electromagnetic wave propagation along an insulated transmission medium and reduces end-to-end transmission loss. In this particular mode, guided waves are partially embedded in the insulator and partially radiating on the outer surface of the insulator. In this fashion, the electromagnetic waves are “lightly” coupled to the insulator so as to enable guided electromagnetic wave propagation at long distances with low propagation loss.

At lower frequencies represented by the electromagnetic field distribution **510** at 3 GHz, the asymmetric mode radiates more heavily generating higher propagation losses. At higher frequencies represented by the electromagnetic field distribution **530** at 9 GHz, the asymmetric mode shifts more and more inward of the insulating jacket providing too much absorption, again generating higher propagation losses.

Referring now to FIG. 5B, a graphical diagram **550** illustrating example, non-limiting embodiments of a longitudinal cross-section of a transmission medium **125**, such as an insulated wire, depicting fields of guided electromagnetic waves at various operating frequencies is shown. As shown in diagram **556**, when the guided electromagnetic waves are at approximately the cutoff frequency (f_c) corresponding to the modal “sweet spot”, the guided electromagnetic waves are loosely coupled to the insulated wire so that absorption is reduced, and the fields of the guided electromagnetic waves are bound sufficiently to reduce the amount radiated into the environment (e.g., air). Because absorption and radiation of the fields of the guided electromagnetic waves is low, propagation losses are consequently low, enabling the guided electromagnetic waves to propagate for longer distances.

As shown in diagram **554**, propagation losses increase when an operating frequency of the guide electromagnetic waves increases above about two-times the cutoff frequency (f_c)—or as referred to, above the range of the “sweet spot”. More of the field strength of the electromagnetic wave is driven inside the insulating layer, increasing propagation losses. At frequencies much higher than the cutoff frequency (f_c) the guided electromagnetic waves are strongly bound to the insulated wire as a result of the fields emitted by the guided electromagnetic waves being concentrated in the insulation layer of the wire, as shown in diagram **552**. This in turn raises propagation losses further due to absorption of the guided electromagnetic waves by the insulation layer. Similarly, propagation losses increase when the operating frequency of the guided electromagnetic waves is substantially below the cutoff frequency (f_c), as shown in diagram **558**. At frequencies much lower than the cutoff frequency (f_c) the guided electromagnetic waves are weakly (or nominally) bound to the insulated wire and thereby tend to radiate into the environment (e.g., air), which in turn, raises propagation losses due to radiation of the guided electromagnetic waves.

Referring now to FIG. 6, a graphical diagram **600** illustrating an example, non-limiting embodiment of an electromagnetic field distribution is shown. In this embodiment, a transmission medium **602** is a bare wire, as shown in cross section. The diagram **300** includes different gray-scales that represent differing electromagnetic field strengths generated by the propagation of a guided wave having a symmetrical and fundamental guided wave mode at a single carrier frequency.

In this particular mode, electromagnetic waves are guided by the transmission medium **602** to propagate along an outer surface of the transmission medium—in this case, the outer surface of the bare wire. Electromagnetic waves are

“lightly” coupled to the wire so as to enable electromagnetic wave propagation at long distances with low propagation loss. As shown, the guided wave has a field structure that lies substantially outside of the transmission medium **602** that serves to guide the electromagnetic waves. The regions inside the conductor **602** have little or no field.

Referring now to FIG. 7, a block diagram **700** illustrating an example, non-limiting embodiment of an arc coupler is shown. In particular a coupling device is presented for use in a transmission device, such as transmission device **101** or **102** presented in conjunction with FIG. 1. The coupling device includes an arc coupler **704** coupled to a transmitter circuit **712** and termination or damper **714**. The arc coupler **704** can be made of a dielectric material, or other low-loss insulator (e.g., Teflon, polyethylene, etc.), or made of a conducting (e.g., metallic, non-metallic, etc.) material, or any combination of the foregoing materials. As shown, the arc coupler **704** operates as a waveguide and has a wave **706** propagating as a guided wave about a waveguide surface of the arc coupler **704**. In the embodiment shown, at least a portion of the arc coupler **704** can be placed near a wire **702** or other transmission medium, (such as transmission medium **125**), in order to facilitate coupling between the arc coupler **704** and the wire **702** or other transmission medium, as described herein to launch the guided wave **708** on the wire. The arc coupler **704** can be placed such that a portion of the curved arc coupler **704** is tangential to, and parallel or substantially parallel to the wire **702**. The portion of the arc coupler **704** that is parallel to the wire can be an apex of the curve, or any point where a tangent of the curve is parallel to the wire **702**. When the arc coupler **704** is positioned or placed thusly, the wave **706** travelling along the arc coupler **704** couples, at least in part, to the wire **702**, and propagates as guided wave **708** around or about the wire surface of the wire **702** and longitudinally along the wire **702**. The guided wave **708** can be characterized as a surface wave or other electromagnetic wave that is guided by or bound to the wire **702** or other transmission medium.

A portion of the wave **706** that does not couple to the wire **702** propagates as a wave **710** along the arc coupler **704**. It will be appreciated that the arc coupler **704** can be configured and arranged in a variety of positions in relation to the wire **702** to achieve a desired level of coupling or non-coupling of the wave **706** to the wire **702**. For example, the curvature and/or length of the arc coupler **704** that is parallel or substantially parallel, as well as its separation distance (which can include zero separation distance in an embodiment), to the wire **702** can be varied without departing from example embodiments. Likewise, the arrangement of arc coupler **704** in relation to the wire **702** may be varied based upon considerations of the respective intrinsic characteristics (e.g., thickness, composition, electromagnetic properties, etc.) of the wire **702** and the arc coupler **704**, as well as the characteristics (e.g., frequency, energy level, etc.) of the waves **706** and **708**.

The guided wave **708** stays parallel or substantially parallel to the wire **702**, even as the wire **702** bends and flexes. Bends in the wire **702** can increase transmission losses, which are also dependent on wire diameters, frequency, and materials. If the dimensions of the arc coupler **704** are chosen for efficient power transfer, most of the power in the wave **706** is transferred to the wire **702**, with little power remaining in wave **710**. It will be appreciated that the guided wave **708** can still be multi-modal in nature (discussed herein), including having modes that are non-fundamental or asymmetric, while traveling along a path that is parallel or substantially parallel to the wire **702**, with or without a

fundamental transmission mode. In an embodiment, non-fundamental or asymmetric modes can be utilized to minimize transmission losses and/or obtain increased propagation distances.

It is noted that the term parallel is generally a geometric construct which often is not exactly achievable in real systems. Accordingly, the term parallel as utilized in the subject disclosure represents an approximation rather than an exact configuration when used to describe embodiments disclosed in the subject disclosure. In an embodiment, substantially parallel can include approximations that are within 30 degrees of true parallel in all dimensions.

In an embodiment, the wave **706** can exhibit one or more wave propagation modes. The arc coupler modes can be dependent on the shape and/or design of the coupler **704**. The one or more arc coupler modes of wave **706** can generate, influence, or impact one or more wave propagation modes of the guided wave **708** propagating along wire **702**. It should be particularly noted however that the guided wave modes present in the guided wave **706** may be the same or different from the guided wave modes of the guided wave **708**. In this fashion, one or more guided wave modes of the guided wave **706** may not be transferred to the guided wave **708**, and further one or more guided wave modes of guided wave **708** may not have been present in guided wave **706**. It should also be noted that the cut-off frequency of the arc coupler **704** for a particular guided wave mode may be different than the cutoff frequency of the wire **702** or other transmission medium for that same mode. For example, while the wire **702** or other transmission medium may be operated slightly above its cutoff frequency for a particular guided wave mode, the arc coupler **704** may be operated well above its cut-off frequency for that same mode for low loss, slightly below its cut-off frequency for that same mode to, for example, induce greater coupling and power transfer, or some other point in relation to the arc coupler's cutoff frequency for that mode.

In an embodiment, the wave propagation modes on the wire **702** can be similar to the arc coupler modes since both waves **706** and **708** propagate about the outside of the arc coupler **704** and wire **702** respectively. In some embodiments, as the wave **706** couples to the wire **702**, the modes can change form, or new modes can be created or generated, due to the coupling between the arc coupler **704** and the wire **702**. For example, differences in size, material, and/or impedances of the arc coupler **704** and wire **702** may create additional modes not present in the arc coupler modes and/or suppress some of the arc coupler modes. The wave propagation modes can comprise the fundamental transverse electromagnetic mode (Quasi-TEM₀₀), where only small electric and/or magnetic fields extend in the direction of propagation, and the electric and magnetic fields extend radially outwards while the guided wave propagates along the wire. This guided wave mode can be donut shaped, where few of the electromagnetic fields exist within the arc coupler **704** or wire **702**.

Waves **706** and **708** can comprise a fundamental TEM mode where the fields extend radially outwards, and also comprise other, non-fundamental (e.g., asymmetric, higher-level, etc.) modes. While particular wave propagation modes are discussed above, other wave propagation modes are likewise possible such as transverse electric (TE) and transverse magnetic (TM) modes, based on the frequencies employed, the design of the arc coupler **704**, the dimensions and composition of the wire **702**, as well as its surface characteristics, its insulation if present, the electromagnetic properties of the surrounding environment, etc. It should be

noted that, depending on the frequency, the electrical and physical characteristics of the wire 702 and the particular wave propagation modes that are generated, guided wave 708 can travel along the conductive surface of an oxidized 5
uninsulated wire, an unoxidized uninsulated wire, an insulated wire and/or along the insulating surface of an insulated wire.

In an embodiment, a diameter of the arc coupler 704 is smaller than the diameter of the wire 702. For the millimeter-band wavelength being used, the arc coupler 704 supports a single waveguide mode that makes up wave 706. This single waveguide mode can change as it couples to the wire 702 as guided wave 708. If the arc coupler 704 were larger, more than one waveguide mode can be supported, but these additional waveguide modes may not couple to the wire 702 as efficiently, and higher coupling losses can result. However, in some alternative embodiments, the diameter of the arc coupler 704 can be equal to or larger than the diameter of the wire 702, for example, where higher coupling losses are desirable or when used in conjunction with other techniques to otherwise reduce coupling losses (e.g., impedance matching with tapering, etc.).

In an embodiment, the wavelength of the waves 706 and 708 are comparable in size, or smaller than a circumference of the arc coupler 704 and the wire 702. In an example, if the wire 702 has a diameter of 0.5 cm, and a corresponding circumference of around 1.5 cm, the wavelength of the transmission is around 1.5 cm or less, corresponding to a frequency of 70 GHz or greater. In another embodiment, a suitable frequency of the transmission and the carrier-wave signal is in the range of 30-100 GHz, perhaps around 30-60 GHz, and around 38 GHz in one example. In an embodiment, when the circumference of the arc coupler 704 and wire 702 is comparable in size to, or greater, than a wavelength of the transmission, the waves 706 and 708 can exhibit multiple wave propagation modes including fundamental and/or non-fundamental (symmetric and/or asymmetric) modes that propagate over sufficient distances to support various communication systems described herein. The waves 706 and 708 can therefore comprise more than one type of electric and magnetic field configuration. In an embodiment, as the guided wave 708 propagates down the wire 702, the electrical and magnetic field configurations will remain the same from end to end of the wire 702. In other embodiments, as the guided wave 708 encounters interference (distortion or obstructions) or loses energy due to transmission losses or scattering, the electric and magnetic field configurations can change as the guided wave 708 propagates down wire 702.

In an embodiment, the arc coupler 704 can be composed of nylon, Teflon, polyethylene, a polyamide, or other plastics. In other embodiments, other dielectric materials are possible. The wire surface of wire 702 can be metallic with either a bare metallic surface, or can be insulated using plastic, dielectric, insulator or other coating, jacket or sheathing. In an embodiment, a dielectric or otherwise non-conducting/insulated waveguide can be paired with either a bare/metallic wire or insulated wire. In other embodiments, a metallic and/or conductive waveguide can be paired with a bare/metallic wire or insulated wire. In an embodiment, an oxidation layer on the bare metallic surface of the wire 702 (e.g., resulting from exposure of the bare metallic surface to oxygen/air) can also provide insulating or dielectric properties similar to those provided by some insulators or sheathings.

It is noted that the graphical representations of waves 706, 708 and 710 are presented merely to illustrate the principles

that wave 706 induces or otherwise launches a guided wave 708 on a wire 702 that operates, for example, as a single wire transmission line. Wave 710 represents the portion of wave 706 that remains on the arc coupler 704 after the generation of guided wave 708. The actual electric and magnetic fields generated as a result of such wave propagation may vary depending on the frequencies employed, the particular wave propagation mode or modes, the design of the arc coupler 704, the dimensions and composition of the wire 702, as well as its surface characteristics, its optional insulation, the electromagnetic properties of the surrounding environment, etc.

It is noted that arc coupler 704 can include a termination circuit or damper 714 at the end of the arc coupler 704 that can absorb leftover radiation or energy from wave 710. The termination circuit or damper 714 can prevent and/or minimize the leftover radiation or energy from wave 710 reflecting back toward transmitter circuit 712. In an embodiment, the termination circuit or damper 714 can include termination resistors, and/or other components that perform impedance matching to attenuate reflection. In some embodiments, if the coupling efficiencies are high enough, and/or wave 710 is sufficiently small, it may not be necessary to use a termination circuit or damper 714. For the sake of simplicity, these transmitter 712 and termination circuits or dampers 714 may not be depicted in the other figures, but in those embodiments, transmitter and termination circuits or dampers may possibly be used.

Further, while a single arc coupler 704 is presented that generates a single guided wave 708, multiple arc couplers 704 placed at different points along the wire 702 and/or at different azimuthal orientations about the wire can be employed to generate and receive multiple guided waves 708 at the same or different frequencies, at the same or different phases, at the same or different wave propagation modes.

FIG. 8, a block diagram 800 illustrating an example, non-limiting embodiment of an arc coupler is shown. In the embodiment shown, at least a portion of the coupler 704 can be placed near a wire 702 or other transmission medium, (such as transmission medium 125), in order to facilitate coupling between the arc coupler 704 and the wire 702 or other transmission medium, to extract a portion of the guided wave 806 as a guided wave 808 as described herein. The arc coupler 704 can be placed such that a portion of the curved arc coupler 704 is tangential to, and parallel or substantially parallel to the wire 702. The portion of the arc coupler 704 that is parallel to the wire can be an apex of the curve, or any point where a tangent of the curve is parallel to the wire 702. When the arc coupler 704 is positioned or placed thusly, the wave 806 travelling along the wire 702 couples, at least in part, to the arc coupler 704, and propagates as guided wave 808 along the arc coupler 704 to a receiving device (not expressly shown). A portion of the wave 806 that does not couple to the arc coupler propagates as wave 810 along the wire 702 or other transmission medium.

In an embodiment, the wave 806 can exhibit one or more wave propagation modes. The arc coupler modes can be dependent on the shape and/or design of the coupler 704. The one or more modes of guided wave 806 can generate, influence, or impact one or more guide-wave modes of the guided wave 808 propagating along the arc coupler 704. It should be particularly noted however that the guided wave modes present in the guided wave 806 may be the same or different from the guided wave modes of the guided wave 808. In this fashion, one or more guided wave modes of the

guided wave **806** may not be transferred to the guided wave **808**, and further one or more guided wave modes of guided wave **808** may not have been present in guided wave **806**.

Referring now to FIG. 9A, a block diagram **900** illustrating an example, non-limiting embodiment of a stub coupler is shown. In particular a coupling device that includes stub coupler **904** is presented for use in a transmission device, such as transmission device **101** or **102** presented in conjunction with FIG. 1. The stub coupler **904** can be made of a dielectric material, or other low-loss insulator (e.g., Teflon, polyethylene and etc.), or made of a conducting (e.g., metallic, non-metallic, etc.) material, or any combination of the foregoing materials. As shown, the stub coupler **904** operates as a waveguide and has a wave **906** propagating as a guided wave about a waveguide surface of the stub coupler **904**. In the embodiment shown, at least a portion of the stub coupler **904** can be placed near a wire **702** or other transmission medium, (such as transmission medium **125**), in order to facilitate coupling between the stub coupler **904** and the wire **702** or other transmission medium, as described herein to launch the guided wave **908** on the wire.

In an embodiment, the stub coupler **904** is curved, and an end of the stub coupler **904** can be tied, fastened, or otherwise mechanically coupled to a wire **702**. When the end of the stub coupler **904** is fastened to the wire **702**, the end of the stub coupler **904** is parallel or substantially parallel to the wire **702**. Alternatively, another portion of the dielectric waveguide beyond an end can be fastened or coupled to wire **702** such that the fastened or coupled portion is parallel or substantially parallel to the wire **702**. The fastener **910** can be a nylon cable tie or other type of non-conducting/dielectric material that is either separate from the stub coupler **904** or constructed as an integrated component of the stub coupler **904**. The stub coupler **904** can be adjacent to the wire **702** without surrounding the wire **702**.

Like the arc coupler **704** described in conjunction with FIG. 7, when the stub coupler **904** is placed with the end parallel to the wire **702**, the guided wave **906** travelling along the stub coupler **904** couples to the wire **702**, and propagates as guided wave **908** about the wire surface of the wire **702**. In an example embodiment, the guided wave **908** can be characterized as a surface wave or other electromagnetic wave.

It is noted that the graphical representations of waves **906** and **908** are presented merely to illustrate the principles that wave **906** induces or otherwise launches a guided wave **908** on a wire **702** that operates, for example, as a single wire transmission line. The actual electric and magnetic fields generated as a result of such wave propagation may vary depending on one or more of the shape and/or design of the coupler, the relative position of the dielectric waveguide to the wire, the frequencies employed, the design of the stub coupler **904**, the dimensions and composition of the wire **702**, as well as its surface characteristics, its optional insulation, the electromagnetic properties of the surrounding environment, etc.

In an embodiment, an end of stub coupler **904** can taper towards the wire **702** in order to increase coupling efficiencies. Indeed, the tapering of the end of the stub coupler **904** can provide impedance matching to the wire **702** and reduce reflections, according to an example embodiment of the subject disclosure. For example, an end of the stub coupler **904** can be gradually tapered in order to obtain a desired level of coupling between waves **906** and **908** as illustrated in FIG. 9A.

In an embodiment, the fastener **910** can be placed such that there is a short length of the stub coupler **904** between

the fastener **910** and an end of the stub coupler **904**. Maximum coupling efficiencies are realized in this embodiment when the length of the end of the stub coupler **904** that is beyond the fastener **910** is at least several wavelengths long for whatever frequency is being transmitted.

Turning now to FIG. 9B, a diagram **950** illustrating an example, non-limiting embodiment of an electromagnetic distribution in accordance with various aspects described herein is shown. In particular, an electromagnetic distribution is presented in two dimensions for a transmission device that includes coupler **952**, shown in an example stub coupler constructed of a dielectric material. The coupler **952** couples an electromagnetic wave for propagation as a guided wave along an outer surface of a wire **702** or other transmission medium.

The coupler **952** guides the electromagnetic wave to a junction at x_0 via a symmetrical guided wave mode. While some of the energy of the electromagnetic wave that propagates along the coupler **952** is outside of the coupler **952**, the majority of the energy of this electromagnetic wave is contained within the coupler **952**. The junction at x_0 couples the electromagnetic wave to the wire **702** or other transmission medium at an azimuthal angle corresponding to the bottom of the transmission medium. This coupling induces an electromagnetic wave that is guided to propagate along the outer surface of the wire **702** or other transmission medium via at least one guided wave mode in direction **956**. The majority of the energy of the guided electromagnetic wave is outside or, but in close proximity to the outer surface of the wire **702** or other transmission medium. In the example shown, the junction at x_0 forms an electromagnetic wave that propagates via both a symmetrical mode and at least one asymmetrical surface mode, such as the first order mode presented in conjunction with FIG. 3, that skims the surface of the wire **702** or other transmission medium.

It is noted that the graphical representations of guided waves are presented merely to illustrate an example of guided wave coupling and propagation. The actual electric and magnetic fields generated as a result of such wave propagation may vary depending on the frequencies employed, the design and/or configuration of the coupler **952**, the dimensions and composition of the wire **702** or other transmission medium, as well as its surface characteristics, its insulation if present, the electromagnetic properties of the surrounding environment, etc.

Turning now to FIG. 10A, illustrated is a block diagram **1000** of an example, non-limiting embodiment of a coupler and transceiver system in accordance with various aspects described herein. The system is an example of transmission device **101** or **102**. In particular, the communication interface **1008** is an example of communications interface **205**, the stub coupler **1002** is an example of coupler **220**, and the transmitter/receiver device **1006**, diplexer **1016**, power amplifier **1014**, low noise amplifier **1018**, frequency mixers **1010** and **1020** and local oscillator **1012** collectively form an example of transceiver **210**.

In operation, the transmitter/receiver device **1006** launches and receives waves (e.g., guided wave **1004** onto stub coupler **1002**). The guided waves **1004** can be used to transport signals received from and sent to a host device, base station, mobile devices, a building or other device by way of a communications interface **1008**. The communications interface **1008** can be an integral part of system **1000**. Alternatively, the communications interface **1008** can be tethered to system **1000**. The communications interface **1008** can comprise a wireless interface for interfacing to the host device, base station, mobile devices, a building or other

device utilizing any of various wireless signaling protocols (e.g., LTE, WiFi, WiMAX, IEEE 802.xx, etc.) including an infrared protocol such as an infrared data association (IrDA) protocol or other line of sight optical protocol. The communications interface **1008** can also comprise a wired interface such as a fiber optic line, coaxial cable, twisted pair, category 5 (CAT-5) cable or other suitable wired or optical mediums for communicating with the host device, base station, mobile devices, a building or other device via a protocol such as an Ethernet protocol, universal serial bus (USB) protocol, a data over cable service interface specification (DOCSIS) protocol, a digital subscriber line (DSL) protocol, a Firewire (IEEE 1394) protocol, or other wired or optical protocol. For embodiments where system **1000** functions as a repeater, the communications interface **1008** may not be necessary.

The output signals (e.g., Tx) of the communications interface **1008** can be combined with a carrier wave (e.g., millimeter-wave carrier wave) generated by a local oscillator **1012** at frequency mixer **1010**. Frequency mixer **1010** can use heterodyning techniques or other frequency shifting techniques to frequency shift the output signals from communications interface **1008**. For example, signals sent to and from the communications interface **1008** can be modulated signals such as orthogonal frequency division multiplexed (OFDM) signals formatted in accordance with a Long-Term Evolution (LTE) wireless protocol or other wireless 3G, 4G, 5G or higher voice and data protocol, a Zigbee, WiMAX, UltraWideband or IEEE 802.11 wireless protocol; a wired protocol such as an Ethernet protocol, universal serial bus (USB) protocol, a data over cable service interface specification (DOCSIS) protocol, a digital subscriber line (DSL) protocol, a Firewire (IEEE 1394) protocol or other wired or wireless protocol. In an example embodiment, this frequency conversion can be done in the analog domain, and as a result, the frequency shifting can be done without regard to the type of communications protocol used by a base station, mobile devices, or in-building devices. As new communications technologies are developed, the communications interface **1008** can be upgraded (e.g., updated with software, firmware, and/or hardware) or replaced and the frequency shifting and transmission apparatus can remain, simplifying upgrades. The carrier wave can then be sent to a power amplifier (“PA”) **1014** and can be transmitted via the transmitter receiver device **1006** via the diplexer **1016**.

Signals received from the transmitter/receiver device **1006** that are directed towards the communications interface **1008** can be separated from other signals via diplexer **1016**. The received signal can then be sent to low noise amplifier (“LNA”) **1018** for amplification. A frequency mixer **1020**, with help from local oscillator **1012** can downshift the received signal (which is in the millimeter-wave band or around 38 GHz in some embodiments) to the native frequency. The communications interface **1008** can then receive the transmission at an input port (Rx).

In an embodiment, transmitter/receiver device **1006** can include a cylindrical or non-cylindrical metal (which, for example, can be hollow in an embodiment, but not necessarily drawn to scale) or other conducting or non-conducting waveguide and an end of the stub coupler **1002** can be placed in or in proximity to the waveguide or the transmitter/receiver device **1006** such that when the transmitter/receiver device **1006** generates a transmission, the guided wave couples to stub coupler **1002** and propagates as a guided wave **1004** about the waveguide surface of the stub coupler **1002**. In some embodiments, the guided wave **1004** can propagate in part on the outer surface of the stub coupler

1002 and in part inside the stub coupler **1002**. In other embodiments, the guided wave **1004** can propagate substantially or completely on the outer surface of the stub coupler **1002**. In yet other embodiments, the guided wave **1004** can propagate substantially or completely inside the stub coupler **1002**. In this latter embodiment, the guided wave **1004** can radiate at an end of the stub coupler **1002** (such as the tapered end shown in FIG. 4) for coupling to a transmission medium such as a wire **702** of FIG. 7. Similarly, if guided wave **1004** is incoming (coupled to the stub coupler **1002** from a wire **702**), guided wave **1004** then enters the transmitter/receiver device **1006** and couples to the cylindrical waveguide or conducting waveguide. While transmitter/receiver device **1006** is shown to include a separate waveguide—an antenna, cavity resonator, klystron, magnetron, travelling wave tube, or other radiating element can be employed to induce a guided wave on the coupler **1002**, with or without the separate waveguide.

In an embodiment, stub coupler **1002** can be wholly constructed of a dielectric material (or another suitable insulating material), without any metallic or otherwise conducting materials therein. Stub coupler **1002** can be composed of nylon, Teflon, polyethylene, a polyamide, other plastics, or other materials that are non-conducting and suitable for facilitating transmission of electromagnetic waves at least in part on an outer surface of such materials. In another embodiment, stub coupler **1002** can include a core that is conducting/metallic, and have an exterior dielectric surface. Similarly, a transmission medium that couples to the stub coupler **1002** for propagating electromagnetic waves induced by the stub coupler **1002** or for supplying electromagnetic waves to the stub coupler **1002** can, in addition to being a bare or insulated wire, be wholly constructed of a dielectric material (or another suitable insulating material), without any metallic or otherwise conducting materials therein.

It is noted that although FIG. 10A shows that the opening of transmitter receiver device **1006** is much wider than the stub coupler **1002**, this is not to scale, and that in other embodiments the width of the stub coupler **1002** is comparable or slightly smaller than the opening of the hollow waveguide. It is also not shown, but in an embodiment, an end of the coupler **1002** that is inserted into the transmitter/receiver device **1006** tapers down in order to reduce reflection and increase coupling efficiencies.

Before coupling to the stub coupler **1002**, the one or more waveguide modes of the guided wave generated by the transmitter/receiver device **1006** can couple to the stub coupler **1002** to induce one or more wave propagation modes of the guided wave **1004**. The wave propagation modes of the guided wave **1004** can be different than the hollow metal waveguide modes due to the different characteristics of the hollow metal waveguide and the dielectric waveguide. For instance, wave propagation modes of the guided wave **1004** can comprise the fundamental transverse electromagnetic mode (Quasi-TEM₀₀), where only small electrical and/or magnetic fields extend in the direction of propagation, and the electric and magnetic fields extend radially outwards from the stub coupler **1002** while the guided waves propagate along the stub coupler **1002**. The fundamental transverse electromagnetic mode wave propagation mode may or may not exist inside a waveguide that is hollow. Therefore, the hollow metal waveguide modes that are used by transmitter/receiver device **1006** are waveguide modes that can couple effectively and efficiently to wave propagation modes of stub coupler **1002**.

It will be appreciated that other constructs or combinations of the transmitter/receiver device **1006** and stub coupler **1002** are possible. For example, a stub coupler **1002'** can be placed tangentially or in parallel (with or without a gap) with respect to an outer surface of the hollow metal waveguide of the transmitter/receiver device **1006'** (corresponding circuitry not shown) as depicted by reference **1000'** of FIG. **10B**. In another embodiment, not shown by reference **1000'**, the stub coupler **1002'** can be placed inside the hollow metal waveguide of the transmitter/receiver device **1006'** without an axis of the stub coupler **1002'** being coaxially aligned with an axis of the hollow metal waveguide of the transmitter/receiver device **1006'**. In either of these embodiments, the guided wave generated by the transmitter/receiver device **1006'** can couple to a surface of the stub coupler **1002'** to induce one or more wave propagation modes of the guided wave **1004'** on the stub coupler **1002'** including a fundamental mode (e.g., a symmetric mode) and/or a non-fundamental mode (e.g., asymmetric mode).

In one embodiment, the guided wave **1004'** can propagate in part on the outer surface of the stub coupler **1002'** and in part inside the stub coupler **1002'**. In another embodiment, the guided wave **1004'** can propagate substantially or completely on the outer surface of the stub coupler **1002'**. In yet other embodiments, the guided wave **1004'** can propagate substantially or completely inside the stub coupler **1002'**. In this latter embodiment, the guided wave **1004'** can radiate at an end of the stub coupler **1002'** (such as the tapered end shown in FIG. **9**) for coupling to a transmission medium such as a wire **702** of FIG. **9**.

It will be further appreciated that other constructs the transmitter/receiver device **1006** are possible. For example, a hollow metal waveguide of a transmitter/receiver device **1006''** (corresponding circuitry not shown), depicted in FIG. **10B** as reference **1000''**, can be placed tangentially or in parallel (with or without a gap) with respect to an outer surface of a transmission medium such as the wire **702** of FIG. **4** without the use of the stub coupler **1002**. In this embodiment, the guided wave generated by the transmitter/receiver device **1006''** can couple to a surface of the wire **702** to induce one or more wave propagation modes of a guided wave **908** on the wire **702** including a fundamental mode (e.g., a symmetric mode) and/or a non-fundamental mode (e.g., asymmetric mode). In another embodiment, the wire **702** can be positioned inside a hollow metal waveguide of a transmitter/receiver device **1006'''** (corresponding circuitry not shown) so that an axis of the wire **702** is coaxially (or not coaxially) aligned with an axis of the hollow metal waveguide without the use of the stub coupler **1002**—see FIG. **10B** reference **1000'''**. In this embodiment, the guided wave generated by the transmitter/receiver device **1006'''** can couple to a surface of the wire **702** to induce one or more wave propagation modes of a guided wave **908** on the wire including a fundamental mode (e.g., a symmetric mode) and/or a non-fundamental mode (e.g., asymmetric mode).

In the embodiments of **1000''** and **1000'''**, for a wire **702** having an insulated outer surface, the guided wave **908** can propagate in part on the outer surface of the insulator and in part inside the insulator. In embodiments, the guided wave **908** can propagate substantially or completely on the outer surface of the insulator, or substantially or completely inside the insulator. In the embodiments of **1000''** and **1000'''**, for a wire **702** that is a bare conductor, the guided wave **908** can propagate in part on the outer surface of the conductor and in part inside the conductor. In another embodiment, the guided wave **908** can propagate substantially or completely on the outer surface of the conductor.

Referring now to FIG. **11**, a block diagram **1100** illustrating an example, non-limiting embodiment of a dual stub coupler is shown. In particular, a dual coupler design is presented for use in a transmission device, such as transmission device **101** or **102** presented in conjunction with FIG. **1**. In an embodiment, two or more couplers (such as the stub couplers **1104** and **1106**) can be positioned around a wire **1102** in order to receive guided wave **1108**. In an embodiment, one coupler is enough to receive the guided wave **1108**. In that case, guided wave **1108** couples to coupler **1104** and propagates as guided wave **1110**. If the field structure of the guided wave **1108** oscillates or undulates around the wire **1102** due to the particular guided wave mode(s) or various outside factors, then coupler **1106** can be placed such that guided wave **1108** couples to coupler **1106**. In some embodiments, four or more couplers can be placed around a portion of the wire **1102**, e.g., at 90 degrees or another spacing with respect to each other, in order to receive guided waves that may oscillate or rotate around the wire **1102**, that have been induced at different azimuthal orientations or that have non-fundamental or higher order modes that, for example, have lobes and/or nulls or other asymmetries that are orientation dependent. However, it will be appreciated that there may be less than or more than four couplers placed around a portion of the wire **1102** without departing from example embodiments.

It should be noted that while couplers **1106** and **1104** are illustrated as stub couplers, any other of the coupler designs described herein including arc couplers, antenna or horn couplers, magnetic couplers, etc., could likewise be used. It will also be appreciated that while some example embodiments have presented a plurality of couplers around at least a portion of a wire **1102**, this plurality of couplers can also be considered as part of a single coupler system having multiple coupler subcomponents. For example, two or more couplers can be manufactured as single system that can be installed around a wire in a single installation such that the couplers are either pre-positioned or adjustable relative to each other (either manually or automatically with a controllable mechanism such as a motor or other actuator) in accordance with the single system.

Receivers coupled to couplers **1106** and **1104** can use diversity combining to combine signals received from both couplers **1106** and **1104** in order to maximize the signal quality. In other embodiments, if one or the other of the couplers **1104** and **1106** receive a transmission that is above a predetermined threshold, receivers can use selection diversity when deciding which signal to use. Further, while reception by a plurality of couplers **1106** and **1104** is illustrated, transmission by couplers **1106** and **1104** in the same configuration can likewise take place. In particular, a wide range of multi-input multi-output (MIMO) transmission and reception techniques can be employed for transmissions where a transmission device, such as transmission device **101** or **102** presented in conjunction with FIG. **1** includes multiple transceivers and multiple couplers.

It is noted that the graphical representations of waves **1108** and **1110** are presented merely to illustrate the principles that guided wave **1108** induces or otherwise launches a wave **1110** on a coupler **1104**. The actual electric and magnetic fields generated as a result of such wave propagation may vary depending on the frequencies employed, the design of the coupler **1104**, the dimensions and composition of the wire **1102**, as well as its surface characteristics, its insulation if any, the electromagnetic properties of the surrounding environment, etc.

Referring now to FIG. 12, a block diagram 1200 illustrating an example, non-limiting embodiment of a repeater system is shown. In particular, a repeater device 1210 is presented for use in a transmission device, such as transmission device 101 or 102 presented in conjunction with FIG. 1. In this system, two couplers 1204 and 1214 can be placed near a wire 1202 or other transmission medium such that guided waves 1205 propagating along the wire 1202 are extracted by coupler 1204 as wave 1206 (e.g. as a guided wave), and then are boosted or repeated by repeater device 1210 and launched as a wave 1216 (e.g. as a guided wave) onto coupler 1214. The wave 1216 can then be launched on the wire 1202 and continue to propagate along the wire 1202 as a guided wave 1217. In an embodiment, the repeater device 1210 can receive at least a portion of the power utilized for boosting or repeating through magnetic coupling with the wire 1202, for example, when the wire 1202 is a power line or otherwise contains a power-carrying conductor. It should be noted that while couplers 1204 and 1214 are illustrated as stub couplers, any other of the coupler designs described herein including arc couplers, antenna or horn couplers, magnetic couplers, or the like, could likewise be used.

In some embodiments, repeater device 1210 can repeat the transmission associated with wave 1206, and in other embodiments, repeater device 1210 can include a communications interface 205 that extracts data or other signals from the wave 1206 for supplying such data or signals to another network and/or one or more other devices as communication signals 110 or 112 and/or receiving communication signals 110 or 112 from another network and/or one or more other devices and launch guided wave 1216 having embedded therein the received communication signals 110 or 112. In a repeater configuration, receiver waveguide 1208 can receive the wave 1206 from the coupler 1204 and transmitter waveguide 1212 can launch guided wave 1216 onto coupler 1214 as guided wave 1217. Between receiver waveguide 1208 and transmitter waveguide 1212, the signal embedded in guided wave 1206 and/or the guided wave 1216 itself can be amplified to correct for signal loss and other inefficiencies associated with guided wave communications or the signal can be received and processed to extract the data contained therein and regenerated for transmission. In an embodiment, the receiver waveguide 1208 can be configured to extract data from the signal, process the data to correct for data errors utilizing for example error correcting codes, and regenerate an updated signal with the corrected data. The transmitter waveguide 1212 can then transmit guided wave 1216 with the updated signal embedded therein. In an embodiment, a signal embedded in guided wave 1206 can be extracted from the transmission and processed for communication with another network and/or one or more other devices via communications interface 205 as communication signals 110 or 112. Similarly, communication signals 110 or 112 received by the communications interface 205 can be inserted into a transmission of guided wave 1216 that is generated and launched onto coupler 1214 by transmitter waveguide 1212.

It is noted that although FIG. 12 shows guided wave transmissions 1206 and 1216 entering from the left and exiting to the right respectively, this is merely a simplification and is not intended to be limiting. In other embodiments, receiver waveguide 1208 and transmitter waveguide 1212 can also function as transmitters and receivers respectively, allowing the repeater device 1210 to be bi-directional.

In an embodiment, repeater device 1210 can be placed at locations where there are discontinuities or obstacles on the

wire 1202 or other transmission medium. In the case where the wire 1202 is a power line, these obstacles can include transformers, connections, utility poles, and other such power line devices. The repeater device 1210 can help the guided (e.g., surface) waves jump over these obstacles on the line and boost the transmission power at the same time. In other embodiments, a coupler can be used to jump over the obstacle without the use of a repeater device. In that embodiment, both ends of the coupler can be tied or fastened to the wire, thus providing a path for the guided wave to travel without being blocked by the obstacle.

Turning now to FIG. 13, illustrated is a block diagram 1300 of an example, non-limiting embodiment of a bidirectional repeater in accordance with various aspects described herein. In particular, a bidirectional repeater device 1306 is presented for use in a transmission device, such as transmission device 101 or 102 presented in conjunction with FIG. 1. It should be noted that while the couplers are illustrated as stub couplers, any other of the coupler designs described herein including arc couplers, antenna or horn couplers, magnetic couplers, or the like, could likewise be used. The bidirectional repeater 1306 can employ diversity paths in the case of when two or more wires or other transmission media are present. Since guided wave transmissions have different transmission efficiencies and coupling efficiencies for transmission medium of different types such as insulated wires, un-insulated wires or other types of transmission media and further, if exposed to the elements, can be affected by weather, and other atmospheric conditions, it can be advantageous to selectively transmit on different transmission media at certain times. In various embodiments, the various transmission media can be designated as a primary, secondary, tertiary, etc. whether or not such designation indicates a preference of one transmission medium over another.

In the embodiment shown, the transmission media include an insulated or uninsulated wire 1302 and an insulated or uninsulated wire 1304 (referred to herein as wires 1302 and 1304, respectively). The repeater device 1306 uses a receiver coupler 1308 to receive a guided wave traveling along wire 1302 and repeats the transmission using transmitter waveguide 1310 as a guided wave along wire 1304. In other embodiments, repeater device 1306 can switch from the wire 1304 to the wire 1302, or can repeat the transmissions along the same paths. Repeater device 1306 can include sensors, or be in communication with sensors (or a network management system 1601 depicted in FIG. 16A) that indicate conditions that can affect the transmission. Based on the feedback received from the sensors, the repeater device 1306 can make the determination about whether to keep the transmission along the same wire, or transfer the transmission to the other wire.

Turning now to FIG. 14, illustrated is a block diagram 1400 illustrating an example, non-limiting embodiment of a bidirectional repeater system. In particular, a bidirectional repeater system is presented for use in a transmission device, such as transmission device 101 or 102 presented in conjunction with FIG. 1. The bidirectional repeater system includes waveguide coupling devices 1402 and 1404 that receive and transmit transmissions from other coupling devices located in a distributed antenna system or backhaul system.

In various embodiments, waveguide coupling device 1402 can receive a transmission from another waveguide coupling device, wherein the transmission has a plurality of subcarriers. Diplexer 1406 can separate the transmission from other transmissions, and direct the transmission to

low-noise amplifier (“LNA”) **1408**. A frequency mixer **1428**, with help from a local oscillator **1412**, can downshift the transmission (which is in the millimeter-wave band or around 38 GHz in some embodiments) to a lower frequency, such as a cellular band (~1.9 GHz) for a distributed antenna system, a native frequency, or other frequency for a backhaul system. An extractor (or demultiplexer) **1432** can extract the signal on a subcarrier and direct the signal to an output component **1422** for optional amplification, buffering or isolation by power amplifier **1424** for coupling to communications interface **205**. The communications interface **205** can further process the signals received from the power amplifier **1424** or otherwise transmit such signals over a wireless or wired interface to other devices such as a base station, mobile devices, a building, etc. For the signals that are not being extracted at this location, extractor **1432** can redirect them to another frequency mixer **1436**, where the signals are used to modulate a carrier wave generated by local oscillator **1414**. The carrier wave, with its subcarriers, is directed to a power amplifier (“PA”) **1416** and is retransmitted by waveguide coupling device **1404** to another system, via diplexer **1420**.

An LNA **1426** can be used to amplify, buffer or isolate signals that are received by the communication interface **205** and then send the signal to a multiplexer **1434** which merges the signal with signals that have been received from waveguide coupling device **1404**. The signals received from coupling device **1404** have been split by diplexer **1420**, and then passed through LNA **1418**, and downshifted in frequency by frequency mixer **1438**. When the signals are combined by multiplexer **1434**, they are upshifted in frequency by frequency mixer **1430**, and then boosted by PA **1410**, and transmitted to another system by waveguide coupling device **1402**. In an embodiment bidirectional repeater system can be merely a repeater without the output device **1422**. In this embodiment, the multiplexer **1434** would not be utilized and signals from LNA **1418** would be directed to mixer **1430** as previously described. It will be appreciated that in some embodiments, the bidirectional repeater system could also be implemented using two distinct and separate unidirectional repeaters. In an alternative embodiment, a bidirectional repeater system could also be a booster or otherwise perform retransmissions without downshifting and upshifting. Indeed in example embodiment, the retransmissions can be based upon receiving a signal or guided wave and performing some signal or guided wave processing or reshaping, filtering, and/or amplification, prior to retransmission of the signal or guided wave.

Referring now to FIG. **15**, a block diagram **1500** illustrating an example, non-limiting embodiment of a guided wave communications system is shown. This diagram depicts an exemplary environment in which a guided wave communication system, such as the guided wave communication system presented in conjunction with FIG. **1**, can be used.

To provide network connectivity to additional base station devices, a backhaul network that links the communication cells (e.g., microcells and macrocells) to network devices of a core network correspondingly expands. Similarly, to provide network connectivity to a distributed antenna system, an extended communication system that links base station devices and their distributed antennas is desirable. A guided wave communication system **1500** such as shown in FIG. **15** can be provided to enable alternative, increased or additional network connectivity and a waveguide coupling system can be provided to transmit and/or receive guided wave (e.g., surface wave) communications on a transmission medium

such as a wire that operates as a single-wire transmission line (e.g., a utility line), and that can be used as a waveguide and/or that otherwise operates to guide the transmission of an electromagnetic wave.

The guided wave communication system **1500** can comprise a first instance of a distribution system **1550** that includes one or more base station devices (e.g., base station device **1504**) that are communicably coupled to a central office **1501** and/or a macrocell site **1502**. Base station device **1504** can be connected by a wired (e.g., fiber and/or cable), or by a wireless (e.g., microwave wireless) connection to the macrocell site **1502** and the central office **1501**. A second instance of the distribution system **1560** can be used to provide wireless voice and data services to mobile device **1522** and to residential and/or commercial establishments **1542** (herein referred to as establishments **1542**). System **1500** can have additional instances of the distribution systems **1550** and **1560** for providing voice and/or data services to mobile devices **1522-1524** and establishments **1542** as shown in FIG. **15**.

Macrocells such as macrocell site **1502** can have dedicated connections to a mobile network and base station device **1504** or can share and/or otherwise use another connection. Central office **1501** can be used to distribute media content and/or provide internet service provider (ISP) services to mobile devices **1522-1524** and establishments **1542**. The central office **1501** can receive media content from a constellation of satellites **1530** (one of which is shown in FIG. **15**) or other sources of content, and distribute such content to mobile devices **1522-1524** and establishments **1542** via the first and second instances of the distribution system **1550** and **1560**. The central office **1501** can also be communicatively coupled to the Internet **1503** for providing internet data services to mobile devices **1522-1524** and establishments **1542**.

Base station device **1504** can be mounted on, or attached to, utility pole **1516**. In other embodiments, base station device **1504** can be near transformers and/or other locations situated nearby a power line. Base station device **1504** can facilitate connectivity to a mobile network for mobile devices **1522** and **1524**. Antennas **1512** and **1514**, mounted on or near utility poles **1518** and **1520**, respectively, can receive signals from base station device **1504** and transmit those signals to mobile devices **1522** and **1524** over a much wider area than if the antennas **1512** and **1514** were located at or near base station device **1504**.

It is noted that FIG. **15** displays three utility poles, in each instance of the distribution systems **1550** and **1560**, with one base station device, for purposes of simplicity. In other embodiments, utility pole **1516** can have more base station devices, and more utility poles with distributed antennas and/or tethered connections to establishments **1542**.

A transmission device **1506**, such as transmission device **101** or **102** presented in conjunction with FIG. **1**, can transmit a signal from base station device **1504** to antennas **1512** and **1514** via utility or power line(s) that connect the utility poles **1516**, **1518**, and **1520**. To transmit the signal, radio source and/or transmission device **1506** upconverts the signal (e.g., via frequency mixing) from base station device **1504** or otherwise converts the signal from the base station device **1504** to a microwave band signal and the transmission device **1506** launches a microwave band wave that propagates as a guided wave traveling along the utility line or other wire as described in previous embodiments. At utility pole **1518**, another transmission device **1508** receives the guided wave (and optionally can amplify it as needed or desired or operate as a repeater to receive it and regenerate

it) and sends it forward as a guided wave on the utility line or other wire. The transmission device **1508** can also extract a signal from the microwave band guided wave and shift it down in frequency or otherwise convert it to its original cellular band frequency (e.g., 1.9 GHz or other defined cellular frequency) or another cellular (or non-cellular) band frequency. An antenna **1512** can wireless transmit the down-shifted signal to mobile device **1522**. The process can be repeated by transmission device **1510**, antenna **1514** and mobile device **1524**, as necessary or desirable.

Transmissions from mobile devices **1522** and **1524** can also be received by antennas **1512** and **1514** respectively. The transmission devices **1508** and **1510** can upshift or otherwise convert the cellular band signals to microwave band and transmit the signals as guided wave (e.g., surface wave or other electromagnetic wave) transmissions over the power line(s) to base station device **1504**.

Media content received by the central office **1501** can be supplied to the second instance of the distribution system **1560** via the base station device **1504** for distribution to mobile devices **1522** and establishments **1542**. The transmission device **1510** can be tethered to the establishments **1542** by one or more wired connections or a wireless interface. The one or more wired connections may include without limitation, a power line, a coaxial cable, a fiber cable, a twisted pair cable, a guided wave transmission medium or other suitable wired mediums for distribution of media content and/or for providing internet services. In an example embodiment, the wired connections from the transmission device **1510** can be communicatively coupled to one or more very high bit rate digital subscriber line (VDSL) modems located at one or more corresponding service area interfaces (SAIs—not shown) or pedestals, each SAI or pedestal providing services to a portion of the establishments **1542**. The VDSL modems can be used to selectively distribute media content and/or provide internet services to gateways (not shown) located in the establishments **1542**. The SAIs or pedestals can also be communicatively coupled to the establishments **1542** over a wired medium such as a power line, a coaxial cable, a fiber cable, a twisted pair cable, a guided wave transmission medium or other suitable wired mediums. In other example embodiments, the transmission device **1510** can be communicatively coupled directly to establishments **1542** without intermediate interfaces such as the SAIs or pedestals.

In another example embodiment, system **1500** can employ diversity paths, where two or more utility lines or other wires are strung between the utility poles **1516**, **1518**, and **1520** (e.g., for example, two or more wires between poles **1516** and **1520**) and redundant transmissions from base station/macrocell site **1502** are transmitted as guided waves down the surface of the utility lines or other wires. The utility lines or other wires can be either insulated or uninsulated, and depending on the environmental conditions that cause transmission losses, the coupling devices can selectively receive signals from the insulated or uninsulated utility lines or other wires. The selection can be based on measurements of the signal-to-noise ratio of the wires, or based on determined weather/environmental conditions (e.g., moisture detectors, weather forecasts, etc.). The use of diversity paths with system **1500** can enable alternate routing capabilities, load balancing, increased load handling, concurrent bi-directional or synchronous communications, spread spectrum communications, etc.

It is noted that the use of the transmission devices **1506**, **1508**, and **1510** in FIG. **15** are by way of example only, and that in other embodiments, other uses are possible. For

instance, transmission devices can be used in a backhaul communication system, providing network connectivity to base station devices. Transmission devices **1506**, **1508**, and **1510** can be used in many circumstances where it is desirable to transmit guided wave communications over a wire, whether insulated or not insulated. Transmission devices **1506**, **1508**, and **1510** are improvements over other coupling devices due to no contact or limited physical and/or electrical contact with the wires that may carry high voltages. The transmission device can be located away from the wire (e.g., spaced apart from the wire) and/or located on the wire so long as it is not electrically in contact with the wire, as the dielectric acts as an insulator, allowing for cheap, easy, and/or less complex installation. However, as previously noted conducting or non-dielectric couplers can be employed, for example in configurations where the wires correspond to a telephone network, cable television network, broadband data service, fiber optic communications system or other network employing low voltages or having insulated transmission lines.

It is further noted, that while base station device **1504** and macrocell site **1502** are illustrated in an embodiment, other network configurations are likewise possible. For example, devices such as access points or other wireless gateways can be employed in a similar fashion to extend the reach of other networks such as a wireless local area network, a wireless personal area network or other wireless network that operates in accordance with a communication protocol such as a 802.11 protocol, WIMAX protocol, UltraWideband protocol, Bluetooth protocol, Zigbee protocol or other wireless protocol.

Referring now to FIGS. **16A** & **16B**, block diagrams illustrating an example, non-limiting embodiment of a system for managing a power grid communication system are shown. Considering FIG. **16A**, a waveguide system **1602** is presented for use in a guided wave communications system, such as the system presented in conjunction with FIG. **15**. The waveguide system **1602** can comprise sensors **1604**, a power management system **1605**, a transmission device **101** or **102** that includes at least one communication interface **205**, transceiver **210** and coupler **220**.

The waveguide system **1602** can be coupled to a power line **1610** for facilitating guided wave communications in accordance with embodiments described in the subject disclosure. In an example embodiment, the transmission device **101** or **102** includes coupler **220** for inducing electromagnetic waves on a surface of the power line **1610** that longitudinally propagate along the surface of the power line **1610** as described in the subject disclosure. The transmission device **101** or **102** can also serve as a repeater for retransmitting electromagnetic waves on the same power line **1610** or for routing electromagnetic waves between power lines **1610** as shown in FIGS. **12-13**.

The transmission device **101** or **102** includes transceiver **210** configured to, for example, up-convert a signal operating at an original frequency range to electromagnetic waves operating at, exhibiting, or associated with a carrier frequency that propagate along a coupler to induce corresponding guided electromagnetic waves that propagate along a surface of the power line **1610**. A carrier frequency can be represented by a center frequency having upper and lower cutoff frequencies that define the bandwidth of the electromagnetic waves. The power line **1610** can be a wire (e.g., single stranded or multi-stranded) having a conducting surface or insulated surface. The transceiver **210** can also receive signals from the coupler **220** and down-convert the

electromagnetic waves operating at a carrier frequency to signals at their original frequency.

Signals received by the communications interface **205** of transmission device **101** or **102** for up-conversion can include without limitation signals supplied by a central office **1611** over a wired or wireless interface of the communications interface **205**, a base station **1614** over a wired or wireless interface of the communications interface **205**, wireless signals transmitted by mobile devices **1620** to the base station **1614** for delivery over the wired or wireless interface of the communications interface **205**, signals supplied by in-building communication devices **1618** over the wired or wireless interface of the communications interface **205**, and/or wireless signals supplied to the communications interface **205** by mobile devices **1612** roaming in a wireless communication range of the communications interface **205**. In embodiments where the waveguide system **1602** functions as a repeater, such as shown in FIGS. **12-13**, the communications interface **205** may or may not be included in the waveguide system **1602**.

The electromagnetic waves propagating along the surface of the power line **1610** can be modulated and formatted to include packets or frames of data that include a data payload and further include networking information (such as header information for identifying one or more destination waveguide systems **1602**). The networking information may be provided by the waveguide system **1602** or an originating device such as the central office **1611**, the base station **1614**, mobile devices **1620**, or in-building devices **1618**, or a combination thereof. Additionally, the modulated electromagnetic waves can include error correction data for mitigating signal disturbances. The networking information and error correction data can be used by a destination waveguide system **1602** for detecting transmissions directed to it, and for down-converting and processing with error correction data transmissions that include voice and/or data signals directed to recipient communication devices communicatively coupled to the destination waveguide system **1602**.

Referring now to the sensors **1604** of the waveguide system **1602**, the sensors **1604** can comprise one or more of a temperature sensor **1604a**, a disturbance detection sensor **1604b**, a loss of energy sensor **1604c**, a noise sensor **1604d**, a vibration sensor **1604e**, an environmental (e.g., weather) sensor **1604f**, and/or an image sensor **1604g**. The temperature sensor **1604a** can be used to measure ambient temperature, a temperature of the transmission device **101** or **102**, a temperature of the power line **1610**, temperature differentials (e.g., compared to a setpoint or baseline, between transmission device **101** or **102** and **1610**, etc.), or any combination thereof. In one embodiment, temperature metrics can be collected and reported periodically to a network management system **1601** by way of the base station **1614**.

The disturbance detection sensor **1604b** can perform measurements on the power line **1610** to detect disturbances such as signal reflections, which may indicate a presence of a downstream disturbance that may impede the propagation of electromagnetic waves on the power line **1610**. A signal reflection can represent a distortion resulting from, for example, an electromagnetic wave transmitted on the power line **1610** by the transmission device **101** or **102** that reflects in whole or in part back to the transmission device **101** or **102** from a disturbance in the power line **1610** located downstream from the transmission device **101** or **102**.

Signal reflections can be caused by obstructions on the power line **1610**. For example, a tree limb may cause electromagnetic wave reflections when the tree limb is lying on the power line **1610**, or is in close proximity to the power

line **1610** which may cause a corona discharge. Other obstructions that can cause electromagnetic wave reflections can include without limitation an object that has been entangled on the power line **1610** (e.g., clothing, a shoe wrapped around a power line **1610** with a shoe string, etc.), a corroded build-up on the power line **1610** or an ice build-up. Power grid components may also impede or obstruct with the propagation of electromagnetic waves on the surface of power lines **1610**. Illustrations of power grid components that may cause signal reflections include without limitation a transformer and a joint for connecting spliced power lines. A sharp angle on the power line **1610** may also cause electromagnetic wave reflections.

The disturbance detection sensor **1604b** can comprise a circuit to compare magnitudes of electromagnetic wave reflections to magnitudes of original electromagnetic waves transmitted by the transmission device **101** or **102** to determine how much a downstream disturbance in the power line **1610** attenuates transmissions. The disturbance detection sensor **1604b** can further comprise a spectral analyzer circuit for performing spectral analysis on the reflected waves. The spectral data generated by the spectral analyzer circuit can be compared with spectral profiles via pattern recognition, an expert system, curve fitting, matched filtering or other artificial intelligence, classification or comparison technique to identify a type of disturbance based on, for example, the spectral profile that most closely matches the spectral data. The spectral profiles can be stored in a memory of the disturbance detection sensor **1604b** or may be remotely accessible by the disturbance detection sensor **1604b**. The profiles can comprise spectral data that models different disturbances that may be encountered on power lines **1610** to enable the disturbance detection sensor **1604b** to identify disturbances locally. An identification of the disturbance if known can be reported to the network management system **1601** by way of the base station **1614**. The disturbance detection sensor **1604b** can also utilize the transmission device **101** or **102** to transmit electromagnetic waves as test signals to determine a roundtrip time for an electromagnetic wave reflection. The round trip time measured by the disturbance detection sensor **1604b** can be used to calculate a distance traveled by the electromagnetic wave up to a point where the reflection takes place, which enables the disturbance detection sensor **1604b** to calculate a distance from the transmission device **101** or **102** to the downstream disturbance on the power line **1610**.

The distance calculated can be reported to the network management system **1601** by way of the base station **1614**. In one embodiment, the location of the waveguide system **1602** on the power line **1610** may be known to the network management system **1601**, which the network management system **1601** can use to determine a location of the disturbance on the power line **1610** based on a known topology of the power grid. In another embodiment, the waveguide system **1602** can provide its location to the network management system **1601** to assist in the determination of the location of the disturbance on the power line **1610**. The location of the waveguide system **1602** can be obtained by the waveguide system **1602** from a pre-programmed location of the waveguide system **1602** stored in a memory of the waveguide system **1602**, or the waveguide system **1602** can determine its location using a GPS receiver (not shown) included in the waveguide system **1602**.

The power management system **1605** provides energy to the aforementioned components of the waveguide system **1602**. The power management system **1605** can receive energy from solar cells, or from a transformer (not shown)

coupled to the power line **1610**, or by inductive coupling to the power line **1610** or another nearby power line. The power management system **1605** can also include a backup battery and/or a super capacitor or other capacitor circuit for providing the waveguide system **1602** with temporary power. The loss of energy sensor **1604c** can be used to detect when the waveguide system **1602** has a loss of power condition and/or the occurrence of some other malfunction. For example, the loss of energy sensor **1604c** can detect when there is a loss of power due to defective solar cells, an obstruction on the solar cells that causes them to malfunction, loss of power on the power line **1610**, and/or when the backup power system malfunctions due to expiration of a backup battery, or a detectable defect in a super capacitor. When a malfunction and/or loss of power occurs, the loss of energy sensor **1604c** can notify the network management system **1601** by way of the base station **1614**.

The noise sensor **1604d** can be used to measure noise on the power line **1610** that may adversely affect transmission of electromagnetic waves on the power line **1610**. The noise sensor **1604d** can sense unexpected electromagnetic interference, noise bursts, or other sources of disturbances that may interrupt reception of modulated electromagnetic waves on a surface of a power line **1610**. A noise burst can be caused by, for example, a corona discharge, or other source of noise. The noise sensor **1604d** can compare the measured noise to a noise profile obtained by the waveguide system **1602** from an internal database of noise profiles or from a remotely located database that stores noise profiles via pattern recognition, an expert system, curve fitting, matched filtering or other artificial intelligence, classification or comparison technique. From the comparison, the noise sensor **1604d** may identify a noise source (e.g., corona discharge or otherwise) based on, for example, the noise profile that provides the closest match to the measured noise. The noise sensor **1604d** can also detect how noise affects transmissions by measuring transmission metrics such as bit error rate, packet loss rate, jitter, packet retransmission requests, etc. The noise sensor **1604d** can report to the network management system **1601** by way of the base station **1614** the identity of noise sources, their time of occurrence, and transmission metrics, among other things.

The vibration sensor **1604e** can include accelerometers and/or gyroscopes to detect 2D or 3D vibrations on the power line **1610**. The vibrations can be compared to vibration profiles that can be stored locally in the waveguide system **1602**, or obtained by the waveguide system **1602** from a remote database via pattern recognition, an expert system, curve fitting, matched filtering or other artificial intelligence, classification or comparison technique. Vibration profiles can be used, for example, to distinguish fallen trees from wind gusts based on, for example, the vibration profile that provides the closest match to the measured vibrations. The results of this analysis can be reported by the vibration sensor **1604e** to the network management system **1601** by way of the base station **1614**.

The environmental sensor **1604f** can include a barometer for measuring atmospheric pressure, ambient temperature (which can be provided by the temperature sensor **1604a**), wind speed, humidity, wind direction, and rainfall, among other things. The environmental sensor **1604f** can collect raw information and process this information by comparing it to environmental profiles that can be obtained from a memory of the waveguide system **1602** or a remote database to predict weather conditions before they arise via pattern recognition, an expert system, knowledge-based system or other artificial intelligence, classification or other weather

modeling and prediction technique. The environmental sensor **1604f** can report raw data as well as its analysis to the network management system **1601**.

The image sensor **1604g** can be a digital camera (e.g., a charged coupled device or CCD imager, infrared camera, etc.) for capturing images in a vicinity of the waveguide system **1602**. The image sensor **1604g** can include an electromechanical mechanism to control movement (e.g., actual position or focal points/zooms) of the camera for inspecting the power line **1610** from multiple perspectives (e.g., top surface, bottom surface, left surface, right surface and so on). Alternatively, the image sensor **1604g** can be designed such that no electromechanical mechanism is needed in order to obtain the multiple perspectives. The collection and retrieval of imaging data generated by the image sensor **1604g** can be controlled by the network management system **1601**, or can be autonomously collected and reported by the image sensor **1604g** to the network management system **1601**.

Other sensors that may be suitable for collecting telemetry information associated with the waveguide system **1602** and/or the power lines **1610** for purposes of detecting, predicting and/or mitigating disturbances that can impede the propagation of electromagnetic wave transmissions on power lines **1610** (or any other form of a transmission medium of electromagnetic waves) may be utilized by the waveguide system **1602**.

Referring now to FIG. **16B**, block diagram **1650** illustrates an example, non-limiting embodiment of a system for managing a power grid **1653** and a communication system **1655** embedded therein or associated therewith in accordance with various aspects described herein. The communication system **1655** comprises a plurality of waveguide systems **1602** coupled to power lines **1610** of the power grid **1653**. At least a portion of the waveguide systems **1602** used in the communication system **1655** can be in direct communication with a base station **1614** and/or the network management system **1601**. Waveguide systems **1602** not directly connected to a base station **1614** or the network management system **1601** can engage in communication sessions with either a base station **1614** or the network management system **1601** by way of other downstream waveguide systems **1602** connected to a base station **1614** or the network management system **1601**.

The network management system **1601** can be communicatively coupled to equipment of a utility company **1652** and equipment of a communications service provider **1654** for providing each entity, status information associated with the power grid **1653** and the communication system **1655**, respectively. The network management system **1601**, the equipment of the utility company **1652**, and the communications service provider **1654** can access communication devices utilized by utility company personnel **1656** and/or communication devices utilized by communications service provider personnel **1658** for purposes of providing status information and/or for directing such personnel in the management of the power grid **1653** and/or communication system **1655**.

FIG. **17A** illustrates a flow diagram of an example, non-limiting embodiment of a method **1700** for detecting and mitigating disturbances occurring in a communication network of the systems of FIGS. **16A** & **16B**. Method **1700** can begin with step **1702** where a waveguide system **1602** transmits and receives messages embedded in, or forming part of, modulated electromagnetic waves or another type of electromagnetic waves traveling along a surface of a power line **1610**. The messages can be voice messages, streaming

video, and/or other data/information exchanged between communication devices communicatively coupled to the communication system 1655. At step 1704 the sensors 1604 of the waveguide system 1602 can collect sensing data. In an embodiment, the sensing data can be collected in step 1704 prior to, during, or after the transmission and/or receipt of messages in step 1702. At step 1706 the waveguide system 1602 (or the sensors 1604 themselves) can determine from the sensing data an actual or predicted occurrence of a disturbance in the communication system 1655 that can affect communications originating from (e.g., transmitted by) or received by the waveguide system 1602. The waveguide system 1602 (or the sensors 1604) can process temperature data, signal reflection data, loss of energy data, noise data, vibration data, environmental data, or any combination thereof to make this determination. The waveguide system 1602 (or the sensors 1604) may also detect, identify, estimate, or predict the source of the disturbance and/or its location in the communication system 1655. If a disturbance is neither detected/identified nor predicted/estimated at step 1708, the waveguide system 1602 can proceed to step 1702 where it continues to transmit and receive messages embedded in, or forming part of, modulated electromagnetic waves traveling along a surface of the power line 1610.

If at step 1708 a disturbance is detected/identified or predicted/estimated to occur, the waveguide system 1602 proceeds to step 1710 to determine if the disturbance adversely affects (or alternatively, is likely to adversely affect or the extent to which it may adversely affect) transmission or reception of messages in the communication system 1655. In one embodiment, a duration threshold and a frequency of occurrence threshold can be used at step 1710 to determine when a disturbance adversely affects communications in the communication system 1655. For illustration purposes only, assume a duration threshold is set to 500 ms, while a frequency of occurrence threshold is set to 5 disturbances occurring in an observation period of 10 sec. Thus, a disturbance having a duration greater than 500 ms will trigger the duration threshold. Additionally, any disturbance occurring more than 5 times in a 10 sec time interval will trigger the frequency of occurrence threshold.

In one embodiment, a disturbance may be considered to adversely affect signal integrity in the communication systems 1655 when the duration threshold alone is exceeded. In another embodiment, a disturbance may be considered as adversely affecting signal integrity in the communication systems 1655 when both the duration threshold and the frequency of occurrence threshold are exceeded. The latter embodiment is thus more conservative than the former embodiment for classifying disturbances that adversely affect signal integrity in the communication system 1655. It will be appreciated that many other algorithms and associated parameters and thresholds can be utilized for step 1710 in accordance with example embodiments.

Referring back to method 1700, if at step 1710 the disturbance detected at step 1708 does not meet the condition for adversely affected communications (e.g., neither exceeds the duration threshold nor the frequency of occurrence threshold), the waveguide system 1602 may proceed to step 1702 and continue processing messages. For instance, if the disturbance detected in step 1708 has a duration of 1 msec with a single occurrence in a 10 sec time period, then neither threshold will be exceeded. Consequently, such a disturbance may be considered as having a nominal effect on signal integrity in the communication system 1655 and thus would not be flagged as a disturbance requiring mitigation. Although not flagged, the occurrence

of the disturbance, its time of occurrence, its frequency of occurrence, spectral data, and/or other useful information, may be reported to the network management system 1601 as telemetry data for monitoring purposes.

Referring back to step 1710, if on the other hand the disturbance satisfies the condition for adversely affected communications (e.g., exceeds either or both thresholds), the waveguide system 1602 can proceed to step 1712 and report the incident to the network management system 1601. The report can include raw sensing data collected by the sensors 1604, a description of the disturbance if known by the waveguide system 1602, a time of occurrence of the disturbance, a frequency of occurrence of the disturbance, a location associated with the disturbance, parameters readings such as bit error rate, packet loss rate, retransmission requests, jitter, latency and so on. If the disturbance is based on a prediction by one or more sensors of the waveguide system 1602, the report can include a type of disturbance expected, and if predictable, an expected time occurrence of the disturbance, and an expected frequency of occurrence of the predicted disturbance when the prediction is based on historical sensing data collected by the sensors 1604 of the waveguide system 1602.

At step 1714, the network management system 1601 can determine a mitigation, circumvention, or correction technique, which may include directing the waveguide system 1602 to reroute traffic to circumvent the disturbance if the location of the disturbance can be determined. In one embodiment, the waveguide coupling device 1402 detecting the disturbance may direct a repeater such as the one shown in FIGS. 13-14 to connect the waveguide system 1602 from a primary power line affected by the disturbance to a secondary power line to enable the waveguide system 1602 to reroute traffic to a different transmission medium and avoid the disturbance. In an embodiment where the waveguide system 1602 is configured as a repeater the waveguide system 1602 can itself perform the rerouting of traffic from the primary power line to the secondary power line. It is further noted that for bidirectional communications (e.g., full or half-duplex communications), the repeater can be configured to reroute traffic from the secondary power line back to the primary power line for processing by the waveguide system 1602.

In another embodiment, the waveguide system 1602 can redirect traffic by instructing a first repeater situated upstream of the disturbance and a second repeater situated downstream of the disturbance to redirect traffic from a primary power line temporarily to a secondary power line and back to the primary power line in a manner that avoids the disturbance. It is further noted that for bidirectional communications (e.g., full or half-duplex communications), repeaters can be configured to reroute traffic from the secondary power line back to the primary power line.

To avoid interrupting existing communication sessions occurring on a secondary power line, the network management system 1601 may direct the waveguide system 1602 to instruct repeater(s) to utilize unused time slot(s) and/or frequency band(s) of the secondary power line for redirecting data and/or voice traffic away from the primary power line to circumvent the disturbance.

At step 1716, while traffic is being rerouted to avoid the disturbance, the network management system 1601 can notify equipment of the utility company 1652 and/or equipment of the communications service provider 1654, which in turn may notify personnel of the utility company 1656 and/or personnel of the communications service provider 1658 of the detected disturbance and its location if known.

Field personnel from either party can attend to resolving the disturbance at a determined location of the disturbance. Once the disturbance is removed or otherwise mitigated by personnel of the utility company and/or personnel of the communications service provider, such personnel can notify their respective companies and/or the network management system **1601** utilizing field equipment (e.g., a laptop computer, smartphone, etc.) communicatively coupled to network management system **1601**, and/or equipment of the utility company and/or the communications service provider. The notification can include a description of how the disturbance was mitigated and any changes to the power lines **1610** that may change a topology of the communication system **1655**.

Once the disturbance has been resolved (as determined in decision **1718**), the network management system **1601** can direct the waveguide system **1602** at step **1720** to restore the previous routing configuration used by the waveguide system **1602** or route traffic according to a new routing configuration if the restoration strategy used to mitigate the disturbance resulted in a new network topology of the communication system **1655**. In another embodiment, the waveguide system **1602** can be configured to monitor mitigation of the disturbance by transmitting test signals on the power line **1610** to determine when the disturbance has been removed. Once the waveguide system **1602** detects an absence of the disturbance it can autonomously restore its routing configuration without assistance by the network management system **1601** if it determines the network topology of the communication system **1655** has not changed, or it can utilize a new routing configuration that adapts to a detected new network topology.

FIG. **17B** illustrates a flow diagram of an example, non-limiting embodiment of a method **1750** for detecting and mitigating disturbances occurring in a communication network of the system of FIGS. **16A** and **16B**. In one embodiment, method **1750** can begin with step **1752** where a network management system **1601** receives from equipment of the utility company **1652** or equipment of the communications service provider **1654** maintenance information associated with a maintenance schedule. The network management system **1601** can at step **1754** identify from the maintenance information, maintenance activities to be performed during the maintenance schedule. From these activities, the network management system **1601** can detect a disturbance resulting from the maintenance (e.g., scheduled replacement of a power line **1610**, scheduled replacement of a waveguide system **1602** on the power line **1610**, scheduled reconfiguration of power lines **1610** in the power grid **1653**, etc.).

In another embodiment, the network management system **1601** can receive at step **1755** telemetry information from one or more waveguide systems **1602**. The telemetry information can include among other things an identity of each waveguide system **1602** submitting the telemetry information, measurements taken by sensors **1604** of each waveguide system **1602**, information relating to predicted, estimated, or actual disturbances detected by the sensors **1604** of each waveguide system **1602**, location information associated with each waveguide system **1602**, an estimated location of a detected disturbance, an identification of the disturbance, and so on. The network management system **1601** can determine from the telemetry information a type of disturbance that may be adverse to operations of the waveguide, transmission of the electromagnetic waves along the wire surface, or both. The network management system **1601** can also use telemetry information from multiple

waveguide systems **1602** to isolate and identify the disturbance. Additionally, the network management system **1601** can request telemetry information from waveguide systems **1602** in a vicinity of an affected waveguide system **1602** to triangulate a location of the disturbance and/or validate an identification of the disturbance by receiving similar telemetry information from other waveguide systems **1602**.

In yet another embodiment, the network management system **1601** can receive at step **1756** an unscheduled activity report from maintenance field personnel. Unscheduled maintenance may occur as result of field calls that are unplanned or as a result of unexpected field issues discovered during field calls or scheduled maintenance activities. The activity report can identify changes to a topology configuration of the power grid **1653** resulting from field personnel addressing discovered issues in the communication system **1655** and/or power grid **1653**, changes to one or more waveguide systems **1602** (such as replacement or repair thereof), mitigation of disturbances performed if any, and so on.

At step **1758**, the network management system **1601** can determine from reports received according to steps **1752** through **1756** if a disturbance will occur based on a maintenance schedule, or if a disturbance has occurred or is predicted to occur based on telemetry data, or if a disturbance has occurred due to an unplanned maintenance identified in a field activity report. From any of these reports, the network management system **1601** can determine whether a detected or predicted disturbance requires rerouting of traffic by the affected waveguide systems **1602** or other waveguide systems **1602** of the communication system **1655**.

When a disturbance is detected or predicted at step **1758**, the network management system **1601** can proceed to step **1760** where it can direct one or more waveguide systems **1602** to reroute traffic to circumvent the disturbance. When the disturbance is permanent due to a permanent topology change of the power grid **1653**, the network management system **1601** can proceed to step **1770** and skip steps **1762**, **1764**, **1766**, and **1772**. At step **1770**, the network management system **1601** can direct one or more waveguide systems **1602** to use a new routing configuration that adapts to the new topology. However, when the disturbance has been detected from telemetry information supplied by one or more waveguide systems **1602**, the network management system **1601** can notify maintenance personnel of the utility company **1656** or the communications service provider **1658** of a location of the disturbance, a type of disturbance if known, and related information that may be helpful to such personnel to mitigate the disturbance. When a disturbance is expected due to maintenance activities, the network management system **1601** can direct one or more waveguide systems **1602** to reconfigure traffic routes at a given schedule (consistent with the maintenance schedule) to avoid disturbances caused by the maintenance activities during the maintenance schedule.

Returning back to step **1760** and upon its completion, the process can continue with step **1762**. At step **1762**, the network management system **1601** can monitor when the disturbance(s) have been mitigated by field personnel. Mitigation of a disturbance can be detected at step **1762** by analyzing field reports submitted to the network management system **1601** by field personnel over a communications network (e.g., cellular communication system) utilizing field equipment (e.g., a laptop computer or handheld computer/device). If field personnel have reported that a disturbance has been mitigated, the network management system **1601** can proceed to step **1764** to determine from the field report

whether a topology change was required to mitigate the disturbance. A topology change can include rerouting a power line **1610**, reconfiguring a waveguide system **1602** to utilize a different power line **1610**, otherwise utilizing an alternative link to bypass the disturbance and so on. If a topology change has taken place, the network management system **1601** can direct at step **1770** one or more waveguide systems **1602** to use a new routing configuration that adapts to the new topology.

If, however, a topology change has not been reported by field personnel, the network management system **1601** can proceed to step **1766** where it can direct one or more waveguide systems **1602** to send test signals to test a routing configuration that had been used prior to the detected disturbance(s). Test signals can be sent to affected waveguide systems **1602** in a vicinity of the disturbance. The test signals can be used to determine if signal disturbances (e.g., electromagnetic wave reflections) are detected by any of the waveguide systems **1602**. If the test signals confirm that a prior routing configuration is no longer subject to previously detected disturbance(s), then the network management system **1601** can at step **1772** direct the affected waveguide systems **1602** to restore a previous routing configuration. If, however, test signals analyzed by one or more waveguide coupling device **1402** and reported to the network management system **1601** indicate that the disturbance(s) or new disturbance(s) are present, then the network management system **1601** will proceed to step **1768** and report this information to field personnel to further address field issues. The network management system **1601** can in this situation continue to monitor mitigation of the disturbance(s) at step **1762**.

In the aforementioned embodiments, the waveguide systems **1602** can be configured to be self-adapting to changes in the power grid **1653** and/or to mitigation of disturbances. That is, one or more affected waveguide systems **1602** can be configured to self-monitor mitigation of disturbances and reconfigure traffic routes without requiring instructions to be sent to them by the network management system **1601**. In this embodiment, the one or more waveguide systems **1602** that are self-configurable can inform the network management system **1601** of its routing choices so that the network management system **1601** can maintain a macro-level view of the communication topology of the communication system **1655**.

While for purposes of simplicity of explanation, the respective processes are shown and described as a series of blocks in FIGS. **17A** and **17B**, respectively, it is to be understood and appreciated that the claimed subject matter is not limited by the order of the blocks, as some blocks may occur in different orders and/or concurrently with other blocks from what is depicted and described herein. Moreover, not all illustrated blocks may be required to implement the methods described herein.

Turning now to FIG. **18A**, a block diagram illustrating an example, non-limiting embodiment of a transmission medium **1800** for propagating guided electromagnetic waves is shown. In particular, a further example of transmission medium **125** presented in conjunction with FIG. **1** is presented. In an embodiment, the transmission medium **1800** can comprise a first dielectric material **1802** and a second dielectric material **1804** disposed thereon. In an embodiment, the first dielectric material **1802** can comprise a dielectric core (referred to herein as dielectric core **1802**) and the second dielectric material **1804** can comprise a cladding or shell such as a dielectric foam that surrounds in whole or in part the dielectric core (referred to herein as

dielectric foam **1804**). In an embodiment, the dielectric core **1802** and dielectric foam **1804** can be coaxially aligned to each other (although not necessary). In an embodiment, the combination of the dielectric core **1802** and the dielectric foam **1804** can be flexed or bent at least by 45 degrees without damaging the materials of the dielectric core **1802** and the dielectric foam **1804**. In an embodiment, an outer surface of the dielectric foam **1804** can be further surrounded in whole or in part by a third dielectric material **1806**, which can serve as an outer jacket (referred to herein as jacket **1806**). The jacket **1806** can prevent exposure of the dielectric core **1802** and the dielectric foam **1804** to an environment that can adversely affect the propagation of electromagnetic waves (e.g., water, soil, etc.).

The dielectric core **1802** can comprise, for example, a high density polyethylene material, a high density polyurethane material, or other suitable dielectric material(s). The dielectric foam **1804** can comprise, for example, a cellular plastic material such as an expanded polyethylene material, or other suitable dielectric material(s). The jacket **1806** can comprise, for example, a polyethylene material or equivalent. In an embodiment, the dielectric constant of the dielectric foam **1804** can be (or substantially) lower than the dielectric constant of the dielectric core **1802**. For example, the dielectric constant of the dielectric core **1802** can be approximately 2.3 while the dielectric constant of the dielectric foam **1804** can be approximately 1.15 (slightly higher than the dielectric constant of air).

The dielectric core **1802** can be used for receiving signals in the form of electromagnetic waves from a launcher or other coupling device described herein which can be configured to launch guided electromagnetic waves on the transmission medium **1800**. In one embodiment, the transmission **1800** can be coupled to a hollow waveguide **1808** structured as, for example, a circular waveguide **1809**, which can receive electromagnetic waves from a radiating device such as a stub antenna (not shown). The hollow waveguide **1808** can in turn induce guided electromagnetic waves in the dielectric core **1802**. In this configuration, the guided electromagnetic waves are guided by or bound to the dielectric core **1802** and propagate longitudinally along the dielectric core **1802**. By adjusting electronics of the launcher, an operating frequency of the electromagnetic waves can be chosen such that a field intensity profile **1810** of the guided electromagnetic waves extends nominally (or not at all) outside of the jacket **1806**.

By maintaining most (if not all) of the field strength of the guided electromagnetic waves within portions of the dielectric core **1802**, the dielectric foam **1804** and/or the jacket **1806**, the transmission medium **1800** can be used in hostile environments without adversely affecting the propagation of the electromagnetic waves propagating therein. For example, the transmission medium **1800** can be buried in soil with no (or nearly no) adverse effect to the guided electromagnetic waves propagating in the transmission medium **1800**. In an embodiment, the propagation loss of guided electromagnetic waves in the foregoing embodiments can be 1 to 2 dB per meter or better at an operating frequency of 60 GHz. Depending on the operating frequency of the guided electromagnetic waves and/or the materials used for the transmission medium **1800** other propagation losses may be possible. Additionally, depending on the materials used to construct the transmission medium **1800**, the transmission

medium **1800** can in some embodiments be flexed laterally with no (or nearly no) adverse effect to the guided electromagnetic waves propagating through the dielectric core **1802** and the dielectric foam **1804**.

FIG. **18B** depicts a transmission medium **1820** that differs from the transmission medium **1800** of FIG. **18A**, yet provides a further example of the transmission medium **125** presented in conjunction with FIG. **1**. The transmission medium **1820** shows similar reference numerals for similar elements of the transmission medium **1800** of FIG. **18A**. In contrast to the transmission medium **1800**, the transmission medium **1820** comprises a conductive core **1822** having an insulation layer **1823** surrounding the conductive core **1822** in whole or in part. The combination of the insulation layer **1823** and the conductive core **1822** will be referred to herein as an insulated conductor **1825**. In the illustration of FIG. **18B**, the insulation layer **1823** is covered in whole or in part by a dielectric foam **1804** and jacket **1806**, which can be constructed from the materials previously described. In an embodiment, the insulation layer **1823** can comprise a dielectric material, such as polyethylene, having a higher dielectric constant than the dielectric foam **1804** (e.g., 2.3 and 1.15, respectively). In an embodiment, the components of the transmission medium **1820** can be coaxially aligned (although not necessary). In an embodiment, a hollow waveguide **1808** having metal plates **1809**, which can be separated from the insulation layer **1823** (although not necessary) can be used to launch guided electromagnetic waves that substantially propagate on an outer surface of the insulation layer **1823**, however other coupling devices as described herein can likewise be employed. In an embodiment, the guided electromagnetic waves can be sufficiently guided by or bound by the insulation layer **1823** to guide the electromagnetic waves longitudinally along the insulation layer **1823**. By adjusting operational parameters of the launcher, an operating frequency of the guided electromagnetic waves launched by the hollow waveguide **1808** can generate an electric field intensity profile **1824** that results in the guided electromagnetic waves being substantially confined within the dielectric foam **1804** thereby preventing the guided electromagnetic waves from being exposed to an environment (e.g., water, soil, etc.) that adversely affects propagation of the guided electromagnetic waves via the transmission medium **1820**.

FIG. **18C** depicts a transmission medium **1830** that differs from the transmission mediums **1800** and **1820** of FIGS. **18A** and **18B**, yet provides a further example of the transmission medium **125** presented in conjunction with FIG. **1**. The transmission medium **1830** shows similar reference numerals for similar elements of the transmission mediums **1800** and **1820** of FIGS. **18A** and **18B**, respectively. In contrast to the transmission mediums **1800** and **1820**, the transmission medium **1830** comprises a bare (or uninsulated) conductor **1832** surrounded in whole or in part by the dielectric foam **1804** and the jacket **1806**, which can be constructed from the materials previously described. In an embodiment, the components of the transmission medium **1830** can be coaxially aligned (although not necessary). In an embodiment, a hollow waveguide **1808** having metal plates **1809** coupled to the bare conductor **1832** can be used to launch guided electromagnetic waves that substantially propagate on an outer surface of the bare conductor **1832**, however other coupling devices described herein can likewise be employed. In an embodiment, the guided electromagnetic waves can be sufficiently guided by or bound by the bare conductor **1832** to guide the guided electromagnetic waves longitudinally along the bare conductor **1832**. By

adjusting operational parameters of the launcher, an operating frequency of the guided electromagnetic waves launched by the hollow waveguide **1808** can generate an electric field intensity profile **1834** that results in the guided electromagnetic waves being substantially confined within the dielectric foam **1804** thereby preventing the guided electromagnetic waves from being exposed to an environment (e.g., water, soil, etc.) that adversely affects propagation of the electromagnetic waves via the transmission medium **1830**.

It should be noted that the hollow launcher **1808** used with the transmission mediums **1800**, **1820** and **1830** of FIGS. **18A**, **18B** and **18C**, respectively, can be replaced with other launchers or coupling devices. Additionally, the propagation mode(s) of the electromagnetic waves for any of the foregoing embodiments can be fundamental mode(s), a non-fundamental (or asymmetric) mode(s), or combinations thereof.

FIG. **18D** is a block diagram illustrating an example, non-limiting embodiment of bundled transmission media **1836** in accordance with various aspects described herein. The bundled transmission media **1836** can comprise a plurality of cables **1838** held in place by a flexible sleeve **1839**. The plurality of cables **1838** can comprise multiple instances of cable **1800** of FIG. **18A**, multiple instances of cable **1820** of FIG. **18B**, multiple instances of cable **1830** of FIG. **18C**, or any combinations thereof. The sleeve **1839** can comprise a dielectric material that prevents soil, water or other external materials from making contact with the plurality of cables **1838**. In an embodiment, a plurality of launchers, each utilizing a transceiver similar to the one depicted in FIG. **10A** or other coupling devices described herein, can be adapted to selectively induce a guided electromagnetic wave in each cable, each guided electromagnetic wave conveys different data (e.g., voice, video, messaging, content, etc.). In an embodiment, by adjusting operational parameters of each launcher or other coupling device, the electric field intensity profile of each guided electromagnetic wave can be fully or substantially confined within layers of a corresponding cable **1838** to reduce cross-talk between cables **1838**.

In situations where the electric field intensity profile of each guided electromagnetic wave is not fully or substantially confined within a corresponding cable **1838**, cross-talk of electromagnetic signals can occur between cables **1838** as illustrated by signal plots associated with two cables depicted in FIG. **18E**. The plots in FIG. **18E** show that when a guided electromagnetic wave is induced on a first cable, the emitted electric and magnetic fields of the first cable can induce signals on the second cable, which results in cross-talk. Several mitigation options can be used to reduce cross-talk between the cables **1838** of FIG. **18D**. In an embodiment, an absorption material **1840** that can absorb electromagnetic fields, such as carbon, can be applied to the cables **1838** as shown in FIG. **18F** to polarize each guided electromagnetic wave at various polarization states to reduce cross-talk between cables **1838**. In another embodiment (not shown), carbon beads can be added to gaps between the cables **1838** to reduce cross-talk.

In yet another embodiment (not shown), a diameter of cable **1838** can be configured differently to vary a speed of propagation of guided electromagnetic waves between the cables **1838** in order to reduce cross-talk between cables **1838**. In an embodiment (not shown), a shape of each cable **1838** can be made asymmetric (e.g., elliptical) to direct the guided electromagnetic fields of each cable **1838** away from each other to reduce cross-talk. In an embodiment (not shown), a filler material such as dielectric foam can be added between cables **1838** to sufficiently separate the cables **1838**

to reduce cross-talk therebetween. In an embodiment (not shown), longitudinal carbon strips or swirls can be applied to on an outer surface of the jacket **1806** of each cable **1838** to reduce radiation of guided electromagnetic waves outside of the jacket **1806** and thereby reduce cross-talk between cables **1838**. In yet another embodiment, each launcher can be configured to launch a guided electromagnetic wave having a different frequency, modulation, wave propagation mode, such as an orthogonal frequency, modulation or mode, to reduce cross-talk between the cables **1838**.

In yet another embodiment (not shown), pairs of cables **1838** can be twisted in a helix to reduce cross-talk between the pairs and other cables **1838** in a vicinity of the pairs. In some embodiments, certain cables **1838** can be twisted while other cables **1838** are not twisted to reduce cross-talk between the cables **1838**. Additionally, each twisted pair cable **1838** can have different pitches (i.e., different twist rates, such as twists per meter) to further reduce cross-talk between the pairs and other cables **1838** in a vicinity of the pairs. In another embodiment (not shown), launchers or other coupling devices can be configured to induce guided electromagnetic waves in the cables **1838** having electromagnetic fields that extend beyond the jacket **1806** into gaps between the cables to reduce cross-talk between the cables **1838**. It is submitted that any one of the foregoing embodiments for mitigating cross-talk between cables **1838** can be combined to further reduce cross-talk therebetween.

FIGS. **18G** and **18H** are block diagrams illustrating example, non-limiting embodiments of a transmission medium with an inner waveguide in accordance with various aspects described herein. In an embodiment, a transmission medium **1841** can comprise a core **1842**. In one embodiment, the core **1842** can be a dielectric core **1842** (e.g., polyethylene). In another embodiment, the core **1842** can be an insulated or uninsulated conductor. The core **1842** can be surrounded by a shell **1844** comprising a dielectric foam (e.g., expanded polyethylene material) having a lower dielectric constant than the dielectric constant of a dielectric core, or insulation layer of a conductive core. The difference in dielectric constants enables electromagnetic waves to be bound and guided by the core **1842**. The shell **1844** can be covered by a shell jacket **1845**. The shell jacket **1845** can be made of rigid material (e.g., high density plastic) or a high tensile strength material (e.g., synthetic fiber). In an embodiment, the shell jacket **1845** can be used to prevent exposure of the shell **1844** and core **1842** from an adverse environment (e.g., water, moisture, soil, etc.). In an embodiment, the shell jacket **1845** can be sufficiently rigid to separate an outer surface of the core **1842** from an inner surface of the shell jacket **1845** thereby resulting in a longitudinal gap between the shell jacket **1845** and the core **1842**. The longitudinal gap can be filled with the dielectric foam of the shell **1844**.

The transmission medium **1841** can further include a plurality of outer ring conductors **1846**. The outer ring conductors **1846** can be strands of conductive material that are woven around the shell jacket **1845**, thereby covering the shell jacket **1845** in whole or in part. The outer ring conductors **1846** can serve the function of a power line having a return electrical path similar to the embodiments described in the subject disclosure for receiving power signals from a source (e.g., a transformer, a power generator, etc.). In one embodiment, the outer ring conductors **1846** can be covered by a cable jacket **1847** to prevent exposure of the outer ring conductors **1846** to water, soil, or other environmental factors. The cable jacket **1847** can be made of an insulating material such as polyethylene. The core **1842** can be used as a center waveguide for the propagation of

electromagnetic waves. A hollow waveguide launcher **1808**, such as the circular waveguide previously described, can be used to launch signals that induce electromagnetic waves guided by the core **1842** in ways similar to those described for the embodiments of FIGS. **18A**, **18B**, and **18C**. The electromagnetic waves can be guided by the core **1842** without utilizing the electrical return path of the outer ring conductors **1846** or any other electrical return path. By adjusting electronics of the launcher **1808**, an operating frequency of the electromagnetic waves can be chosen such that a field intensity profile of the guided electromagnetic waves extends nominally (or not at all) outside of the shell jacket **1845**.

In another embodiment, a transmission medium **1843** can comprise a hollow core **1842'** surrounded by a shell jacket **1845'**. The shell jacket **1845'** can have an inner conductive surface or other surface materials that enable the hollow core **1842'** to be used as a conduit for electromagnetic waves. The shell jacket **1845'** can be covered at least in part with the outer ring conductors **1846** described earlier for conducting a power signal. In an embodiment, a cable jacket **1847** can be disposed on an outer surface of the outer ring conductors **1846** to prevent exposure of the outer ring conductors **1846** to water, soil or other environmental factors. A waveguide launcher **1808** can be used to launch electromagnetic waves guided by the hollow core **1842'** and the conductive inner surface of the shell jacket **1845'**. In an embodiment (not shown) the hollow core **1842'** can further include a dielectric foam such as described earlier.

Transmission medium **1841** can represent a multi-purpose cable that conducts power on the outer ring conductors **1846** utilizing an electrical return path and that provides communication services by way of an inner waveguide comprising a combination of the core **1842**, the shell **1844** and the shell jacket **1845**. The inner waveguide can be used for transmitting or receiving electromagnetic waves (without utilizing an electrical return path) guided by the core **1842**. Similarly, transmission medium **1843** can represent a multi-purpose cable that conducts power on the outer ring conductors **1846** utilizing an electrical return path and that provides communication services by way of an inner waveguide comprising a combination of the hollow core **1842'** and the shell jacket **1845'**. The inner waveguide can be used for transmitting or receiving electromagnetic waves (without utilizing an electrical return path) guided the hollow core **1842'** and the shell jacket **1845'**.

It is submitted that embodiments of FIGS. **18G-18H** can be adapted to use multiple inner waveguides surrounded by outer ring conductors **1846**. The inner waveguides can be adapted to use to cross-talk mitigation techniques described above (e.g., twisted pairs of waveguides, waveguides of different structural dimensions, use of polarizers within the shell, use of different wave modes, etc.).

For illustration purposes only, the transmission mediums **1800**, **1820**, **1830**, **1836**, **1841** and **1843** will be referred to herein as a cable **1850** with an understanding that cable **1850** can represent any one of the transmission mediums described in the subject disclosure, or a bundling of multiple instances thereof. For illustration purposes only, the dielectric core **1802**, insulated conductor **1825**, bare conductor **1832**, core **1842**, or hollow core **1842'** of the transmission mediums **1800**, **1820**, **1830**, **1836**, **1841** and **1843**, respectively, will be referred to herein as transmission core **1852** with an understanding that cable **1850** can utilize the dielectric core **1802**, insulated conductor **1825**, bare conductor

1832, core 1842, or hollow core 1842' of transmission mediums 1800, 1820, 1830, 1836, 1841 and/or 1843, respectively.

Turning now to FIGS. 18I and 18J, block diagrams illustrating example, non-limiting embodiments of connector configurations that can be used by cable 1850 are shown. In one embodiment, cable 1850 can be configured with a female connection arrangement or a male connection arrangement as depicted in FIG. 18I. The male configuration on the right of FIG. 18I can be accomplished by stripping the dielectric foam 1804 (and jacket 1806 if there is one) to expose a portion of the transmission core 1852. The female configuration on the left of FIG. 18I can be accomplished by removing a portion of the transmission core 1852, while maintaining the dielectric foam 1804 (and jacket 1806 if there is one). In an embodiment in which the transmission core 1852 is hollow as described in relation to FIG. 18H, the male portion of the transmission core 1852 can represent a hollow core with a rigid outer surface that can slide into the female arrangement on the left side of FIG. 18I to align the hollow cores together. It is further noted that in the embodiments of FIGS. 18G-18H, the outer ring of conductors 1846 can be modified to connect male and female portions of cable 1850.

Based on the aforementioned embodiments, the two cables 1850 having male and female connector arrangements can be mated together. A sleeve with an adhesive inner lining or a shrink wrap material (not shown) can be applied to an area of a joint between cables 1850 to maintain the joint in a fixed position and prevent exposure (e.g., to water, soil, etc.). When the cables 1850 are mated, the transmission core 1852 of one cable will be in close proximity to the transmission core 1852 of the other cable. Guided electromagnetic waves propagating by way of either the transmission core 1852 of cables 1850 traveling from either direction can cross over between the disjoint the transmission cores 1852 whether or not the transmission cores 1852 touch, whether or not the transmission cores 1852 are coaxially aligned, and/or whether or not there is a gap between the transmission cores 1852.

In another embodiment, a splicing device 1860 having female connector arrangements at both ends can be used to mate cables 1850 having male connector arrangements as shown in FIG. 18J. In an alternative embodiment not shown in FIG. 18J, the splicing device 1860 can be adapted to have male connector arrangements at both ends which can be mated to cables 1850 having female connector arrangements. In another embodiment not shown in FIG. 18J, the splicing device 1860 can be adapted to have a male connector arrangement and a female connector arrangement at opposite ends which can be mated to cables 1850 having female and male connector arrangements, respectively. It is further noted that for a transmission core 1852 having a hollow core, the male and female arrangements described in FIG. 18I can be applied to the splicing device 1860 whether the ends of the splicing device 1860 are both male, both female, or a combination thereof.

The foregoing embodiments for connecting cables illustrated in FIGS. 18I-18J can be applied to each single instance of cable 1838 of bundled transmission media 1836. Similarly, the foregoing embodiments illustrated in FIGS. 18I-18J can be applied to each single instance of an inner waveguide for a cable 1841 or 1843 having multiple inner waveguides.

Turning now to FIG. 18K, a block diagram illustrating example, non-limiting embodiments of transmission mediums 1800', 1800'', 1800''' and 1800'''' for propagating guided

electromagnetic waves is shown. In an embodiment, a transmission medium 1800' can include a core 1801, and a dielectric foam 1804' divided into sections and covered by a jacket 1806 as shown in FIG. 18K. The core 1801 can be represented by the dielectric core 1802 of FIG. 18A, the insulated conductor 1825 of FIG. 18B, or the bare conductor 1832 of FIG. 18C. Each section of dielectric foam 1804' can be separated by a gap (e.g., air, gas, vacuum, or a substance with a low dielectric constant). In an embodiment, the gap separations between the sections of dielectric foam 1804' can be quasi-random as shown in FIG. 18K, which can be helpful in reducing reflections of electromagnetic waves occurring at each section of dielectric foam 1804' as they propagate longitudinally along the core 1801. The sections of the dielectric foam 1804' can be constructed, for example, as washers made of a dielectric foam having an inner opening for supporting the core 1801 in a fixed position. For illustration purposes only, the washers will be referred to herein as washers 1804'. In an embodiment, the inner opening of each washer 1804' can be coaxially aligned with an axis of the core 1801. In another embodiment, the inner opening of each washer 1804' can be offset from the axis of the core 1801. In another embodiment (not shown), each washer 1804' can have a variable longitudinal thickness as shown by differences in thickness of the washers 1804'.

In an alternative embodiment, a transmission medium 1800'' can include a core 1801, and a strip of dielectric foam 1804'' wrapped around the core in a helix covered by a jacket 1806 as shown in FIG. 18K. Although it may not be apparent from the drawing shown in FIG. 18K, in an embodiment the strip of dielectric foam 1804'' can be twisted around the core 1801 with variable pitches (i.e., different twist rates) for different sections of the strip of dielectric foam 1804''. Utilizing variable pitches can help reduce reflections or other disturbances of the electromagnetic waves occurring between areas of the core 1801 not covered by the strip of dielectric foam 1804''. It is further noted that the thickness (diameter) of the strip of dielectric foam 1804'' can be substantially larger (e.g., 2 or more times larger) than diameter of the core 1801 shown in FIG. 18K.

In an alternative embodiment, a transmission medium 1800''' (shown in a cross-sectional view) can include a non-circular core 1801' covered by a dielectric foam 1804 and jacket 1806. In an embodiment, the non-circular core 1801' can have an elliptical structure as shown in FIG. 18K, or other suitable non-circular structure. In another embodiment, the non-circular core 1801' can have an asymmetric structure. A non-circular core 1801' can be used to polarize the fields of electromagnetic waves induced on the non-circular core 1801'. The structure of the non-circular core 1801' can help preserve the polarization of the electromagnetic waves as they propagate along the non-circular core 1801'.

In an alternative embodiment, a transmission medium 1800'''' (shown in a cross-sectional view) can include multiple cores 1801'' (only two cores are shown but more are possible). The multiple cores 1801'' can be covered by a dielectric foam 1804 and jacket 1806. The multiple cores 1801'' can be used to polarize the fields of electromagnetic waves induced on the multiple cores 1801''. The structure of the multiple cores 1801' can preserve the polarization of the guided electromagnetic waves as they propagate along the multiple cores 1801''.

It will be appreciated that the embodiments of FIG. 18K can be used to modify the embodiments of FIGS. 18G-18H. For example, core 1842 or core 1842' can be adapted to utilized sectionalized shells 1804' with gaps therebetween,

or one or more strips of dielectric foam **1804'**. Similarly, core **1842** or core **1842'** can be adapted to have a non-circular core **1801'** that may have symmetric or asymmetric cross-sectional structure. Additionally, core **1842** or core **1842'** can be adapted to use multiple cores **1801''** in a single inner waveguide, or different numbers of cores when multiple inner waveguides are used. Accordingly, any of the embodiments shown in FIG. **18K** can be applied singly or in combination to the embodiments of **18G-18H**.

Turning now to FIG. **18L** is a block diagram illustrating example, non-limiting embodiments of bundled transmission media to mitigate cross-talk in accordance with various aspects described herein. In an embodiment, a bundled transmission medium **1836'** can include variable core structures **1803**. By varying the structures of cores **1803**, fields of guided electromagnetic waves induced in each of the cores of transmission medium **1836'** may differ sufficiently to reduce cross-talk between cables **1838**. In another embodiment, a bundled transmission media **1836''** can include a variable number of cores **1803'** per cable **1838**. By varying the number of cores **1803'** per cable **1838**, fields of guided electromagnetic waves induced in the one or more cores of transmission medium **1836''** may differ sufficiently to reduce cross-talk between cables **1838**. In another embodiment, the cores **1803** or **1803'** can be of different materials. For example, the cores **1803** or **1803'** can be a dielectric core **1802**, an insulated conductor core **1825**, a bare conductor core **1832**, or any combinations thereof.

It is noted that the embodiments illustrated in FIGS. **18A-18D** and **18F-18H** can be modified by and/or combined with some of the embodiments of FIGS. **18K-18L**. It is further noted that one or more of the embodiments illustrated in FIGS. **18K-18L** can be combined (e.g., using sectionalized dielectric foam **1804'** or a helix strip of dielectric foam **1804''** with cores **1801'**, **1801''**, **1803** or **1803'**). In some embodiments guided electromagnetic waves propagating in the transmission mediums **1800'**, **1800''**, **1800'''**, and/or **1800''''** of FIG. **18K** may experience less propagation losses than guided electromagnetic waves propagating in the transmission mediums **1800**, **1820** and **1830** of FIGS. **18A-18C**. Additionally, the embodiments illustrated in FIGS. **18K-18L** can be adapted to use the connectivity embodiments illustrated in FIGS. **18I-18J**.

Turning now to FIG. **18M**, a block diagram illustrating an example, non-limiting embodiment of exposed tapered stubs from the bundled transmission media **1836** for use as antennas **1855** is shown. Each antenna **1855** can serve as a directional antenna for radiating wireless signals directed to wireless communication devices or for inducing electromagnetic wave propagation on a surface of a transmission medium (e.g., a power line). In an embodiment, the wireless signals radiated by the antennas **1855** can be beam steered by adapting the phase and/or other characteristics of the wireless signals generated by each antenna **1855**. In an embodiment, the antennas **1855** can individually be placed in a pie-pan antenna assembly for directing wireless signals in various directions.

It is further noted that the terms "core", "cladding", "shell", and "foam" as utilized in the subject disclosure can comprise any types of materials (or combinations of materials) that enable electromagnetic waves to remain bound to the core while propagating longitudinally along the core. For example, a strip of dielectric foam **1804'** described earlier can be replaced with a strip of an ordinary dielectric material (e.g., polyethylene) for wrapping around the dielectric core **1802** (referred to herein for illustration purposes only as a "wrap"). In this configuration an average density of the wrap

can be small as a result of air space between sections of the wrap. Consequently, an effective dielectric constant of the wrap can be less than the dielectric constant of the dielectric core **1802**, thereby enabling guided electromagnetic waves to remain bound to the core. Accordingly, any of the embodiments of the subject disclosure relating to materials used for core(s) and wrappings about the core(s) can be structurally adapted and/or modified with other dielectric materials that achieve the result of maintaining electromagnetic waves bound to the core(s) while they propagate along the core(s). Additionally, a core in whole or in part as described in any of the embodiments of the subject disclosure can comprise an opaque material (e.g., polyethylene). Accordingly, electromagnetic waves guided and bound to the core will have a non-optical frequency range (e.g., less than the lowest frequency of visible light).

FIGS. **18N**, **18O**, **18P**, **18Q**, **18R**, **18S** and **18T** are block diagrams illustrating example, non-limiting embodiments of a waveguide device for transmitting or receiving electromagnetic waves in accordance with various aspects described herein. In an embodiment, FIG. **18N** illustrates a front view of a waveguide device **1865** having a plurality of slots **1863** (e.g., openings or apertures) for emitting electromagnetic waves having radiated electric fields (e-fields) **1861**. In an embodiment, the radiated e-fields **1861** of pairs of symmetrically positioned slots **1863** (e.g., north and south slots of the waveguide **1865**) can be directed away from each other (i.e., polar opposite radial orientations about the cable **1862**). While the slots **1863** are shown as having a rectangular shape, other shapes such as other polygons, sector and arc shapes, ellipsoid shapes and other shapes are likewise possible. For illustration purposes only, the term north will refer to a relative direction as shown in the figures. All references in the subject disclosure to other directions (e.g., south, east, west, northwest, and so forth) will be relative to northern illustration. In an embodiment, to achieve e-fields with opposing orientations at the north and south slots **1863**, for example, the north and south slots **1863** can be arranged to have a circumferential distance between each other that is approximately one wavelength of electromagnetic waves signals supplied to these slots. The waveguide **1865** can have a cylindrical cavity in a center of the waveguide **1865** to enable placement of a cable **1862**. In one embodiment, the cable **1862** can comprise an insulated conductor. In another embodiment, the cable **1862** can comprise an uninsulated conductor. In yet other embodiments, the cable **1862** can comprise any of the embodiments of a transmission core **1852** of cable **1850** previously described.

In one embodiment, the cable **1862** can slide into the cylindrical cavity of the waveguide **1865**. In another embodiment, the waveguide **1865** can utilize an assembly mechanism (not shown). The assembly mechanism (e.g., a hinge or other suitable mechanism that provides a way to open the waveguide **1865** at one or more locations) can be used to enable placement of the waveguide **1865** on an outer surface of the cable **1862** or otherwise to assemble separate pieces together to form the waveguide **1865** as shown. According to these and other suitable embodiments, the waveguide **1865** can be configured to wrap around the cable **1862** like a collar.

FIG. **18O** illustrates a side view of an embodiment of the waveguide **1865**. The waveguide **1865** can be adapted to have a hollow rectangular waveguide portion **1867** that receives electromagnetic waves **1866** generated by a transmitter circuit as previously described in the subject disclosure (e.g., see reference **101**, **1000** of FIGS. **1** and **10A**). The electromagnetic waves **1866** can be distributed by the hol-

low rectangular waveguide portion **1867** into in a hollow collar **1869** of the waveguide **1865**. The rectangular waveguide portion **1867** and the hollow collar **1869** can be constructed of materials suitable for maintaining the electromagnetic waves within the hollow chambers of these assemblies (e.g., carbon fiber materials). It should be noted that while the waveguide portion **1867** is shown and described in a hollow rectangular configuration, other shapes and/or other non-hollow configurations can be employed. In particular, the waveguide portion **1867** can have a square or other polygonal cross section, an arc or sector cross section that is truncated to conform to the outer surface of the cable **1862**, a circular or ellipsoid cross section or cross sectional shape. In addition, the waveguide portion **1867** can be configured as, or otherwise include, a solid dielectric material.

As previously described, the hollow collar **1869** can be configured to emit electromagnetic waves from each slot **1863** with opposite e-fields **1861** at pairs of symmetrically positioned slots **1863** and **1863'**. In an embodiment, the electromagnetic waves emitted by the combination of slots **1863** and **1863'** can in turn induce electromagnetic waves **1868** on that are bound to the cable **1862** for propagation according to a fundamental wave mode without other wave modes present—such as non-fundamental wave modes. In this configuration, the electromagnetic waves **1868** can propagate longitudinally along the cable **1862** to other downstream waveguide systems coupled to the cable **1862**.

It should be noted that since the hollow rectangular waveguide portion **1867** of FIG. **18O** is closer to slot **1863** (at the northern position of the waveguide **1865**), slot **1863** can emit electromagnetic waves having a stronger magnitude than electromagnetic waves emitted by slot **1863'** (at the southern position). To reduce magnitude differences between these slots, slot **1863'** can be made larger than slot **1863**. The technique of utilizing different slot sizes to balance signal magnitudes between slots can be applied to any of the embodiments of the subject disclosure relating to FIGS. **18N**, **18O**, **18Q**, **18S**, **18U** and **18V**—some of which are described below.

In another embodiment, FIG. **18P** depicts a waveguide **1865'** that can be configured to utilize circuitry such as monolithic microwave integrated circuits (MMICs) **1870** each coupled to a signal input **1872** (e.g., coaxial cable that provides a communication signal). The signal input **1872** can be generated by a transmitter circuit as previously described in the subject disclosure (e.g., see reference **101**, **1000** of FIGS. **1** and **10A**) adapted to provide electrical signals to the MMICs **1870**. Each MMIC **1870** can be configured to receive signal **1872** which the MMIC **1870** can modulate and transmit with a radiating element (e.g., an antenna) to emit electromagnetic waves having radiated e-fields **1861**. In one embodiment, the MMIC's **1870** can be configured to receive the same signal **1872**, but transmit electromagnetic waves having e-fields **1861** of opposing orientation. This can be accomplished by configuring one of the MMICs **1870** to transmit electromagnetic waves that are 180 degrees out of phase with the electromagnetic waves transmitted by the other MMIC **1870**. In an embodiment, the combination of the electromagnetic waves emitted by the MMICs **1870** can together induce electromagnetic waves **1868** that are bound to the cable **1862** for propagation according to a fundamental wave mode without other wave modes present—such as non-fundamental wave modes. In this configuration, the electromagnetic waves **1868** can propagate longitudinally along the cable **1862** to other downstream waveguide systems coupled to the cable **1862**.

A tapered horn **1880** can be added to the embodiments of FIGS. **18O** and **18P** to assist in the inducement of the electromagnetic waves **1868** on cable **1862** as depicted in FIGS. **18Q** and **18R**. In an embodiment where the cable **1862** is an uninsulated conductor, the electromagnetic waves induced on the cable **1862** can have a large radial dimension (e.g., 1 meter). To enable use of a smaller tapered horn **1880**, an insulation layer **1879** can be applied on a portion of the cable **1862** at or near the cavity as depicted with hash lines in FIGS. **18Q** and **18R**. The insulation layer **1879** can have a tapered end facing away from the waveguide **1865**. The added insulation enables the electromagnetic waves **1868** initially launched by the waveguide **1865** (or **1865'**) to be tightly bound to the insulation, which in turn reduces the radial dimension of the electromagnetic fields **1868** (e.g., centimeters). As the electromagnetic waves **1868** propagate away from the waveguide **1865** (**1865'**) and reach the tapered end of the insulation layer **1879**, the radial dimension of the electromagnetic waves **1868** begin to increase eventually achieving the radial dimension they would have had had the electromagnetic waves **1868** been induced on the uninsulated conductor without an insulation layer. In the illustration of FIGS. **18Q** and **18R** the tapered end begins at an end of the tapered horn **1880**. In other embodiments, the tapered end of the insulation layer **1879** can begin before or after the end of the tapered horn **1880**. The tapered horn can be metallic or constructed of other conductive material or constructed of a plastic or other non-conductive material that is coated or clad with a dielectric layer or doped with a conductive material to provide reflective properties similar to a metallic horn.

In an embodiment, cable **1862** can comprise any of the embodiments of cable **1850** described earlier. In this embodiment, waveguides **1865** and **1865'** can be coupled to a transmission core **1852** of cable **1850** as depicted in FIGS. **18S** and **18T**. The waveguides **1865** and **1865'** can induce, as previously described, electromagnetic waves **1868** on the transmission core **1852** for propagation entirely or partially within inner layers of cable **1850**.

It is noted that for the foregoing embodiments of FIGS. **18Q**, **18R**, **18S** and **18T**, electromagnetic waves **1868** can be bidirectional. For example, electromagnetic waves **1868** of a different operating frequency can be received by slots **1863** or MMIC's **1870** of the waveguides **1865** and **1865'**, respectively. Once received, the electromagnetic waves can be converted by a receiver circuit (e.g., see reference **101**, **1000** of FIGS. **1** and **10A**) for generating a communication signal for processing.

Although not shown, it is further noted that the waveguides **1865** and **1865'** can be adapted so that the waveguides **1865** and **1865'** can direct electromagnetic waves **1868** upstream or downstream longitudinally. For example, a first tapered horn **1880** coupled to a first instance of a waveguide **1865** or **1865'** can be directed westerly on cable **1862**, while a second tapered horn **1880** coupled to a second instance of a waveguide **1865** or **1865'** can be directed easterly on cable **1862**. The first and second instances of the waveguides **1865** or **1865'** can be coupled so that in a repeater configuration, signals received by the first waveguide **1865** or **1865'** can be provided to the second waveguide **1865** or **1865'** for retransmission in an easterly direction on cable **1862**. The repeater configuration just described can also be applied from an easterly to westerly direction on cable **1862**.

The waveguide **1865** of FIGS. **18N**, **18O**, **18Q** and **18S** can also be configured to generate electromagnetic fields having only non-fundamental or asymmetric wave modes. FIG. **18U** depicts an embodiment of a waveguide **1865** that

can be adapted to generate electromagnetic fields having only non-fundamental wave modes. A median line **1890** represents a separation between slots where electrical currents on a backside (not shown) of a frontal plate of the waveguide **1865** change polarity. For example, electrical currents on the backside of the frontal plate corresponding to e-fields that are radially outward (i.e., point away from a center point of cable **1862**) can in some embodiments be associated with slots located outside of the median line **1890** (e.g., slots **1863A** and **1863B**). Electrical currents on the backside of the frontal plate corresponding to e-fields that are radially inward (i.e., point towards a center point of cable **1862**) can in some embodiments be associated with slots located inside of the median line **1890**. The direction of the currents can depend on the operating frequency of the electromagnetic waves **1866** supplied to the hollow rectangular waveguide portion **1867** (see FIG. **18O**) among other parameters.

For illustration purposes, assume the electromagnetic waves **1866** supplied to the hollow rectangular waveguide portion **1867** have an operating frequency whereby a circumferential distance between slots **1863A** and **1863B** is one full wavelength of the electromagnetic waves **1866**. In this instance, the e-fields of the electromagnetic waves emitted by slots **1863A** and **1863B** point radially outward (i.e., have opposing orientations). When the electromagnetic waves emitted by slots **1863A** and **1863B** are combined, the resulting electromagnetic waves on cable **1862** will propagate according to the fundamental wave mode. In contrast, by repositioning one of the slots (e.g., slot **1863B**) inside the median line **1890** (i.e., slot **1863C**), slot **1863C** will generate electromagnetic waves that have e-fields that are approximately 180 degrees out of phase with the e-fields of the electromagnetic waves generated by slot **1863A**. Consequently, the e-field orientations of the electromagnetic waves generated by slot pairs **1863A** and **1863C** will be substantially aligned. The combination of the electromagnetic waves emitted by slot pairs **1863A** and **1863C** will thus generate electromagnetic waves that are bound to the cable **1862** for propagation according to a non-fundamental wave mode.

To achieve a reconfigurable slot arrangement, waveguide **1865** can be adapted according to the embodiments depicted in FIG. **18V**. Configuration (A) depicts a waveguide **1865** having a plurality of symmetrically positioned slots. Each of the slots **1863** of configuration (A) can be selectively disabled by blocking the slot with a material (e.g., carbon fiber or metal) to prevent the emission of electromagnetic waves. A blocked (or disabled) slot **1863** is shown in black, while an enabled (or unblocked) slot **1863** is shown in white. Although not shown, a blocking material can be placed behind (or in front) of the frontal plate of the waveguide **1865**. A mechanism (not shown) can be coupled to the blocking material so that the blocking material can slide in or out of a particular slot **1863** much like closing or opening a window with a cover. The mechanism can be coupled to a linear motor controllable by circuitry of the waveguide **1865** to selectively enable or disable individual slots **1863**. With such a mechanism at each slot **1863**, the waveguide **1865** can be configured to select different configurations of enabled and disabled slots **1863** as depicted in the embodiments of FIG. **18V**. Other methods or techniques for covering or opening slots (e.g., utilizing rotatable disks behind or in front of the waveguide **1865**) can be applied to the embodiments of the subject disclosure.

In one embodiment, the waveguide system **1865** can be configured to enable certain slots **1863** outside the median

line **1890** and disable certain slots **1863** inside the median line **1890** as shown in configuration (B) to generate fundamental waves. Assume, for example, that the circumferential distance between slots **1863** outside the median line **1890** (i.e., in the northern and southern locations of the waveguide system **1865**) is one full wavelength. These slots will therefore have electric fields (e-fields) pointing at certain instances in time radially outward as previously described. In contrast, the slots inside the median line **1890** (i.e., in the western and eastern locations of the waveguide system **1865**) will have a circumferential distance of one-half a wavelength relative to either of the slots **1863** outside the median line. Since the slots inside the median line **1890** are half a wavelength apart, such slots will produce electromagnetic waves having e-fields pointing radially outward. If the western and eastern slots **1863** outside the median line **1890** had been enabled instead of the western and eastern slots inside the median line **1890**, then the e-fields emitted by those slots would have pointed radially inward, which when combined with the electric fields of the northern and southern would produce non-fundamental wave mode propagation. Accordingly, configuration (B) as depicted in FIG. **18V** can be used to generate electromagnetic waves at the northern and southern slots **1863** having e-fields that point radially outward and electromagnetic waves at the western and eastern slots **1863** with e-fields that also point radially outward, which when combined induce electromagnetic waves on cable **1862** having a fundamental wave mode.

In another embodiment, the waveguide system **1865** can be configured to enable a northerly, southerly, westerly and easterly slots **1863** all outside the median line **1890**, and disable all other slots **1863** as shown in configuration (C). Assuming the circumferential distance between a pair of opposing slots (e.g., northerly and southerly, or westerly and easterly) is a full wavelength apart, then configuration (C) can be used to generate electromagnetic waves having a non-fundamental wave mode with some e-fields pointing radially outward and other fields pointing radially inward. In yet another embodiment, the waveguide system **1865** can be configured to enable a northwesterly slot **1863** outside the median line **1890**, enable a southeasterly slot **1863** inside the median line **1890**, and disable all other slots **1863** as shown in configuration (D). Assuming the circumferential distance between such a pair of slots is a full wavelength apart, then such a configuration can be used to generate electromagnetic waves having a non-fundamental wave mode with e-fields aligned in a northwesterly direction.

In another embodiment, the waveguide system **1865** can be configured to produce electromagnetic waves having a non-fundamental wave mode with e-fields aligned in a southwesterly direction. This can be accomplished by utilizing a different arrangement than used in configuration (D). Configuration (E) can be accomplished by enabling a southwesterly slot **1863** outside the median line **1890**, enabling a northeasterly slot **1863** inside the median line **1890**, and disabling all other slots **1863** as shown in configuration (E). Assuming the circumferential distance between such a pair of slots is a full wavelength apart, then such a configuration can be used to generate electromagnetic waves having a non-fundamental wave mode with e-fields aligned in a southwesterly direction. Configuration (E) thus generates a non-fundamental wave mode that is orthogonal to the non-fundamental wave mode of configuration (D).

In yet another embodiment, the waveguide system **1865** can be configured to generate electromagnetic waves having a fundamental wave mode with e-fields that point radially inward. This can be accomplished by enabling a northerly

slot **1863** inside the median line **1890**, enabling a southerly slot **1863** inside the median line **1890**, enabling an easterly slot outside the median **1890**, enabling a westerly slot **1863** outside the median **1890**, and disabling all other slots **1863** as shown in configuration (F). Assuming the circumferential distance between the northerly and southerly slots is a full wavelength apart, then such a configuration can be used to generate electromagnetic waves having a fundamental wave mode with radially inward e-fields. Although the slots selected in configurations (B) and (F) are different, the fundamental wave modes generated by configurations (B) and (F) are the same.

It yet another embodiment, e-fields can be manipulated between slots to generate fundamental or non-fundamental wave modes by varying the operating frequency of the electromagnetic waves **1866** supplied to the hollow rectangular waveguide portion **1867**. For example, assume in the illustration of FIG. **18U** that for a particular operating frequency of the electromagnetic waves **1866** the circumferential distance between slot **1863A** and **1863B** is one full wavelength of the electromagnetic waves **1866**. In this instance, the e-fields of electromagnetic waves emitted by slots **1863A** and **1863B** will point radially outward as shown, and can be used in combination to induce electromagnetic waves on cable **1862** having a fundamental wave mode. In contrast, the e-fields of electromagnetic waves emitted by slots **1863A** and **1863C** will be radially aligned (i.e., pointing northerly) as shown, and can be used in combination to induce electromagnetic waves on cable **1862** having a non-fundamental wave mode.

Now suppose that the operating frequency of the electromagnetic waves **1866** supplied to the hollow rectangular waveguide portion **1867** is changed so that the circumferential distance between slot **1863A** and **1863B** is one-half a wavelength of the electromagnetic waves **1866**. In this instance, the e-fields of electromagnetic waves emitted by slots **1863A** and **1863B** will be radially aligned (i.e., point in the same direction). That is, the e-fields of electromagnetic waves emitted by slot **1863B** will point in the same direction as the e-fields of electromagnetic waves emitted by slot **1863A**. Such electromagnetic waves can be used in combination to induce electromagnetic waves on cable **1862** having a non-fundamental wave mode. In contrast, the e-fields of electromagnetic waves emitted by slots **1863A** and **1863C** will be radially outward (i.e., away from cable **1862**), and can be used in combination to induce electromagnetic waves on cable **1862** having a fundamental wave mode.

In another embodiment, the waveguide **1865'** of FIGS. **18P**, **18R** and **18T** can also be configured to generate electromagnetic waves having only non-fundamental wave modes. This can be accomplished by adding more MMICs **1870** as depicted in FIG. **18W**. Each MMIC **1870** can be configured to receive the same signal input **1872**. However, MMICs **1870** can selectively be configured to emit electromagnetic waves having differing phases using controllable phase-shifting circuitry in each MMIC **1870**. For example, the northerly and southerly MMICs **1870** can be configured to emit electromagnetic waves having a 180 degree phase difference, thereby aligning the e-fields either in a northerly or southerly direction. Any combination of pairs of MMICs **1870** (e.g., westerly and easterly MMICs **1870**, northwesterly and southeasterly MMICs **1870**, northeasterly and southwesterly MMICs **1870**) can be configured with opposing or aligned e-fields. Consequently, waveguide **1865'** can be configured to generate electromagnetic waves with one or

more non-fundamental wave modes, electromagnetic waves with one or more fundamental wave modes, or any combinations thereof.

It is submitted that it is not necessary to select slots **1863** in pairs to generate electromagnetic waves having a non-fundamental wave mode. For example, electromagnetic waves having a non-fundamental wave mode can be generated by enabling a single slot from the plurality of slots shown in configuration (A) of FIG. **18V** and disabling all other slots. Similarly, a single MMIC **1870** of the MMICs **1870** shown in FIG. **18W** can be configured to generate electromagnetic waves having a non-fundamental wave mode while all other MMICs **1870** are not in use or disabled. Likewise other wave modes and wave mode combinations can be induced by enabling other non-null proper subsets of waveguide slots **1863** or the MMICs **1870**.

It is further submitted that the e-field arrows shown in FIGS. **18U-18V** are illustrative only and represent a static depiction of e-fields. In practice, the electromagnetic waves may have oscillating e-fields, which at one instance in time point outwardly, and at another instance in time point inwardly. For example, in the case of non-fundamental wave modes having e-fields that are aligned in one direction (e.g., northerly), such waves may at another instance in time have e-fields that point in an opposite direction (e.g., southerly). Similarly, fundamental wave modes having e-fields that are radial may at one instance have e-fields that point radially away from the cable **1862** and at another instance in time point radially towards the cable **1862**. It is further noted that the embodiments of FIGS. **18U-18W** can be adapted to generate electromagnetic waves with one or more non-fundamental wave modes, electromagnetic waves with one or more fundamental wave modes (e.g., TM₀₀ and HE₁₁ modes), or any combinations thereof. It is further noted that such adaptations can be used in combination with any embodiments described in the subject disclosure. It is also noted that the embodiments of FIGS. **18U-18W** can be combined (e.g., slots used in combination with MMICs).

It is further noted that in some embodiments, the waveguide systems **1865** and **1865'** of FIGS. **18N-18W** may generate combinations of fundamental and non-fundamental wave modes where one wave mode is dominant over the other. For example, in one embodiment electromagnetic waves generated by the waveguide systems **1865** and **1865'** of FIGS. **18N-18W** may have a weak signal component that has a non-fundamental wave mode, and a substantially strong signal component that has a fundamental wave mode. Accordingly, in this embodiment, the electromagnetic waves have a substantially fundamental wave mode. In another embodiment electromagnetic waves generated by the waveguide systems **1865** and **1865'** of FIGS. **18N-18W** may have a weak signal component that has a fundamental wave mode, and a substantially strong signal component that has a non-fundamental wave mode. Accordingly, in this embodiment, the electromagnetic waves have a substantially non-fundamental wave mode. Further, a non-dominant wave mode may be generated that propagates only trivial distances along the length of the transmission medium.

It is also noted that the waveguide systems **1865** and **1865'** of FIGS. **18N-18W** can be configured to generate instances of electromagnetic waves that have wave modes that can differ from a resulting wave mode or modes of the combined electromagnetic wave. It is further noted that each MMIC **1870** of the waveguide system **1865'** of FIG. **18W** can be configured to generate an instance of electromagnetic waves having wave characteristics that differ from the wave characteristics of another instance of electromagnetic waves

generated by another MMIC **1870**. One MMIC **1870**, for example, can generate an instance of an electromagnetic wave having a spatial orientation and a phase, frequency, magnitude, electric field orientation, and/or magnetic field orientation that differs from the spatial orientation and phase, frequency, magnitude, electric field orientation, and/or magnetic field orientation of a different instance of another electromagnetic wave generated by another MMIC **1870**. The waveguide system **1865'** can thus be configured to generate instances of electromagnetic waves having different wave and spatial characteristics, which when combined achieve resulting electromagnetic waves having one or more desirable wave modes.

From these illustrations, it is submitted that the waveguide systems **1865** and **1865'** of FIGS. **18N-18W** can be adapted to generate electromagnetic waves with one or more selectable wave modes. In one embodiment, for example, the waveguide systems **1865** and **1865'** can be adapted to select one or more wave modes and generate electromagnetic waves having a single wave mode or multiple wave modes selected and produced from a process of combining instances of electromagnetic waves having one or more configurable wave and spatial characteristics. In an embodiment, for example, parametric information can be stored in a look-up table. Each entry in the look-up table can represent a selectable wave mode. A selectable wave mode can represent a single wave mode, or a combination of wave modes. The combination of wave modes can have one or dominant wave modes. The parametric information can provide configuration information for generating instances of electromagnetic waves for producing resultant electromagnetic waves that have the desired wave mode.

For example, once a wave mode or modes is selected, the parametric information obtained from the look-up table from the entry associated with the selected wave mode(s) can be used to identify which of one or more MMICs **1870** to utilize, and/or their corresponding configurations to achieve electromagnetic waves having the desired wave mode(s). The parametric information may identify the selection of the one or more MMICs **1870** based on the spatial orientations of the MMICs **1870**, which may be required for producing electromagnetic waves with the desired wave mode. The parametric information can also provide information to configure each of the one or more MMICs **1870** with a particular phase, frequency, magnitude, electric field orientation, and/or magnetic field orientation which may or may not be the same for each of the selected MMICs **1870**. A look-up table with selectable wave modes and corresponding parametric information can be adapted for configuring the slotted waveguide system **1865**.

In some embodiments, a guided electromagnetic wave can be considered to have a desired wave mode if the corresponding wave mode propagates non-trivial distances on a transmission medium and has a field strength that is substantially greater in magnitude (e.g., 20 dB higher in magnitude) than other wave modes that may or may not be desirable. Such a desired wave mode or modes can be referred to as dominant wave mode(s) with the other wave modes being referred to as non-dominant wave modes. In a similar fashion, a guided electromagnetic wave that is said to be substantially without the fundamental wave mode has either no fundamental wave mode or a non-dominant fundamental wave mode. A guided electromagnetic wave that is said to be substantially without a non-fundamental wave mode has either no non-fundamental wave mode(s) or only non-dominant non-fundamental wave mode(s). In some embodiments, a guided electromagnetic wave that is said to

have only a single wave mode or a selected wave mode may have only one corresponding dominant wave mode.

It is further noted that the embodiments of FIGS. **18U-18W** can be applied to other embodiments of the subject disclosure. For example, the embodiments of FIGS. **18U-18W** can be used as alternate embodiments to the embodiments depicted in FIGS. **18N-18T** or can be combined with the embodiments depicted in FIGS. **18N-18T**.

Turning now to FIGS. **19A** and **19B**, block diagrams illustrating example, non-limiting embodiments of the cable **1850** of FIG. **18A** used for inducing guided electromagnetic waves on power lines supported by utility poles. In one embodiment, as depicted in FIG. **19A**, a cable **1850** can be coupled at one end to a microwave apparatus that launches guided electromagnetic waves within one or more inner layers of cable **1850** utilizing, for example, the hollow waveguide **1808** shown in FIGS. **18A-18C**. The microwave apparatus can utilize a microwave transceiver such as shown in FIG. **10A** for transmitting or receiving signals from cable **1850**. The guided electromagnetic waves induced in the one or more inner layers of cable **1850** can propagate to an exposed stub of the cable **1850** located inside a horn antenna (shown as a dotted line in FIG. **19A**) for radiating the electromagnetic waves via the horn antenna. The radiated signals from the horn antenna in turn can induce guided electromagnetic waves that propagate longitudinally on a medium voltage (MV) power line. In one embodiment, the microwave apparatus can receive AC power from a low voltage (e.g., 220V) power line. Alternatively, the horn antenna can be replaced with a stub antenna as shown in FIG. **19B** to induce guided electromagnetic waves that propagate longitudinally on the MV power line or to transmit wireless signals to other antenna system(s).

In alternate embodiments, first and second cables **1850A'** and **1850B'** can be coupled to the microwave apparatus and to a transformer **1952**, respectively, as shown in FIGS. **19A** and **19B**. The first and second cables **1850A'** and **1850B'** can be represented by, for example, cable **1820** or cable **1830** of FIGS. **18B** and **18C**, respectively, each having a conductive core. A first end of the conductive core of the first cable **1850A'** can be coupled to the microwave apparatus for propagating guided electromagnetic waves launched therein. A second end of the conductive core of the first cable **1850A'** can be coupled to a first end of a conductive coil of the transformer **1952** for receiving the guided electromagnetic waves propagating in the first cable **1850A'** and for supplying signals associated therewith to a first end of a second cable **1850B'** by way of a second end of the conductive coil of the transformer **1952**. A second end of the second cable **1850B'** can be coupled to the horn antenna of FIG. **19A** or can be exposed as a stub antenna of FIG. **19B** for inducing guided electromagnetic waves that propagate longitudinally on the MV power line.

In an embodiment where cable **1850**, **1850A'** and **1850B'** each comprise multiple instances of transmission mediums **1800**, **1820**, and/or **1830**, a poly-rod structure of antennas **1855** can be formed such as shown in FIG. **18K**. Each antenna **1855** can be coupled, for example, to a horn antenna assembly as shown in FIG. **19A** or a pie-pan antenna assembly (not shown) for radiating multiple wireless signals. Alternatively, the antennas **1855** can be used as stub antennas in FIG. **19B**. The microwave apparatus of FIGS. **19A-19B** can be configured to adjust the guided electromagnetic waves to beam steer the wireless signals emitted by the antennas **1855**. One or more of the antennas **1855** can also be used for inducing guided electromagnetic waves on a power line.

Turning now to FIG. 19C, a block diagram of an example, non-limiting embodiment of a communication network 1900 in accordance with various aspects described herein is shown. In one embodiment, for example, the waveguide system 1602 of FIG. 16A can be incorporated into network interface devices (NIDs) such as NIDs 1910 and 1920 of FIG. 19C. A NID having the functionality of waveguide system 1602 can be used to enhance transmission capabilities between customer premises 1902 (enterprise or residential) and a pedestal 1904 (sometimes referred to as a service area interface or SAI).

In one embodiment, a central office 1930 can supply one or more fiber cables 1926 to the pedestal 1904. The fiber cables 1926 can provide high-speed full-duplex data services (e.g., 1-100 Gbps or higher) to mini-DSLAMs 1924 located in the pedestal 1904. The data services can be used for transport of voice, internet traffic, media content services (e.g., streaming video services, broadcast TV), and so on. In prior art systems, mini-DSLAMs 1924 typically connect to twisted pair phone lines (e.g., twisted pairs included in category 5e or Cat. 5e unshielded twisted-pair (UTP) cables that include an unshielded bundle of twisted pair cables, such as 24 gauge insulated solid wires, surrounded by an outer insulating sheath), which in turn connect to the customer premises 1902 directly. In such systems, DSL data rates taper off at 100 Mbps or less due in part to the length of legacy twisted pair cables to the customer premises 1902 among other factors.

The embodiments of FIG. 19C, however, are distinct from prior art DSL systems. In the illustration of FIG. 19C, a mini-DSLAM 1924, for example, can be configured to connect to NID 1920 via cable 1850 (which can represent in whole or in part any of the cable embodiments described in relation to FIGS. 18A-18D and 18F-18L singly or in combination). Utilizing cable 1850 between customer premises 1902 and a pedestal 1904, enables NIDs 1910 and 1920 to transmit and receive guided electromagnetic waves for uplink and downlink communications. Based on embodiments previously described, cable 1850 can be exposed to rain, or can be buried without adversely affecting electromagnetic wave propagation either in a downlink path or an uplink path so long as the electric field profile of such waves in either direction is confined at least in part or entirely within inner layers of cable 1850. In the present illustration, downlink communications represents a communication path from the pedestal 1904 to customer premises 1902, while uplink communications represents a communication path from customer premises 1902 to the pedestal 1904. In an embodiment where cable 1850 comprises one of the embodiments of FIGS. 18G-18H, cable 1850 can also serve the purpose of supplying power to the NID 1910 and 1920 and other equipment of the customer premises 1902 and the pedestal 1904.

In customer premises 1902, DSL signals can originate from a DSL modem 1906 (which may have a built-in router and which may provide wireless services such as WiFi to user equipment shown in the customer premises 1902). The DSL signals can be supplied to NID 1910 by a twisted pair phone line 1908. The NID 1910 can utilize the integrated waveguide system 1602 to launch within cable 1850 guided electromagnetic waves 1914 directed to the pedestal 1904 on an uplink path. In the downlink path, DSL signals generated by the mini-DSLAM 1924 can flow through a twisted pair phone line 1922 to NID 1920. The waveguide system 1602 integrated in the NID 1920 can convert the DSL signals, or a portion thereof, from electrical signals to guided electromagnetic waves 1914 that propagate within cable 1850 on

the downlink path. To provide full duplex communications, the guided electromagnetic waves 1914 on the uplink can be configured to operate at a different carrier frequency and/or a different modulation approach than the guided electromagnetic waves 1914 on the downlink to reduce or avoid interference. Additionally, on the uplink and downlink paths, the guided electromagnetic waves 1914 are guided by a core section of cable 1850, as previously described, and such waves can be configured to have a field intensity profile that confines the guided electromagnetic waves in whole or in part in the inner layers of cable 1850. Although the guided electromagnetic waves 1914 are shown outside of cable 1850, the depiction of these waves is for illustration purposes only. For this reason, the guided electromagnetic waves 1914 are drawn with “hash marks” to indicate that they are guided by the inner layers of cable 1850.

On the downlink path, the integrated waveguide system 1602 of NID 1910 receives the guided electromagnetic waves 1914 generated by NID 1920 and converts them back to DSL signals conforming to the requirements of the DSL modem 1906. The DSL signals are then supplied to the DSL modem 1906 via a set of twisted pair wires of phone line 1908 for processing. Similarly, on the uplink path, the integrated waveguide system 1602 of NID 1920 receives the guided electromagnetic waves 1914 generated by NID 1910 and converts them back to DSL signals conforming to the requirements of the mini-DSLAM 1924. The DSL signals are then supplied to the mini-DSLAM 1924 via a set of twisted pair wires of phone line 1922 for processing. Because of the short length of phone lines 1908 and 1922, the DSL modem 1906 and the mini-DSLAM 1924 can send and receive DSL signals between themselves on the uplink and downlink at very high speeds (e.g., 1 Gbps to 60 Gbps or more). Consequently, the uplink and downlink paths can in most circumstances exceed the data rate limits of traditional DSL communications over twisted pair phone lines.

Typically, DSL devices are configured for asymmetric data rates because the downlink path usually supports a higher data rate than the uplink path. However, cable 1850 can provide much higher speeds both on the downlink and uplink paths. With a firmware update, a legacy DSL modem 1906 such as shown in FIG. 19C can be configured with higher speeds on both the uplink and downlink paths. Similar firmware updates can be made to the mini-DSLAM 1924 to take advantage of the higher speeds on the uplink and downlink paths. Since the interfaces to the DSL modem 1906 and mini-DSLAM 1924 remain as traditional twisted pair phone lines, no hardware change is necessary for a legacy DSL modem or legacy mini-DSLAM other than firmware changes and the addition of the NIDs 1910 and 1920 to perform the conversion from DSL signals to guided electromagnetic waves 1914 and vice-versa. The use of NIDs enables a reuse of legacy modems 1906 and mini-DSLAMs 1924, which in turn can substantially reduce installation costs and system upgrades. For new construction, updated versions of mini-DSLAMs and DSL modems can be configured with integrated waveguide systems to perform the functions described above, thereby eliminating the need for NIDs 1910 and 1920 with integrated waveguide systems. In this embodiment, an updated version of modem 1906 and updated version of mini-DSLAM 1924 would connect directly to cable 1850 and communicate via bidirectional guided electromagnetic wave transmissions, thereby averting a need for transmission or reception of DSL signals using twisted pair phone lines 1908 and 1922.

In an embodiment where use of cable 1850 between the pedestal 1904 and customer premises 1902 is logistically

impractical or costly, NID 1910 can be configured instead to couple to a cable 1850' (similar to cable 1850 of the subject disclosure) that originates from a waveguide 108 on a utility pole 118, and which may be buried in soil before it reaches NID 1910 of the customer premises 1902. Cable 1850' can be used to receive and transmit guided electromagnetic waves 1914' between the NID 1910 and the waveguide 108. Waveguide 108 can connect via waveguide 106, which can be coupled to base station 104. Base station 104 can provide data communication services to customer premises 1902 by way of its connection to central office 1930 over fiber 1926'. Similarly, in situations where access from the central office 1926 to pedestal 1904 is not practical over a fiber link, but connectivity to base station 104 is possible via fiber link 1926', an alternate path can be used to connect to NID 1920 of the pedestal 1904 via cable 1850" (similar to cable 1850 of the subject disclosure) originating from pole 116. Cable 1850" can also be buried before it reaches NID 1920.

FIGS. 20A and 20B describe embodiments for downlink and uplink communications. Method 2000 of FIG. 20A can begin with step 2002 where electrical signals (e.g., DSL signals) are generated by a DSLAM (e.g., mini-DSLAM 1924 of pedestal 1904 or from central office 1930), which are converted to guided electromagnetic waves 1914 at step 2004 by NID 1920 and which propagate on a transmission medium such as cable 1850 for providing downlink services to the customer premises 1902. At step 2008, the NID 1910 of the customer premises 1902 converts the guided electromagnetic waves 1914 back to electrical signals (e.g., DSL signals) which are supplied at step 2010 to customer premises equipment (CPE) such as DSL modem 1906 over phone line 1908. Alternatively, or in combination, power and/or guided electromagnetic waves 1914' can be supplied from a power line 1850' of a utility grid (having an inner waveguide as illustrated in FIG. 18G or 18H) to NID 1910 as an alternate or additional downlink (and/or uplink) path.

At 2022 of method 2020 of FIG. 20B, the DSL modem 1906 can supply electrical signals (e.g., DSL signals) via phone line 1908 to NID 1910, which in turn at step 2024, converts the DSL signals to guided electromagnetic waves directed to NID 1920 by way of cable 1850. At step 2028, the NID 1920 of the pedestal 1904 (or central office 1930) converts the guided electromagnetic waves 1914 back to electrical signals (e.g., DSL signals) which are supplied at step 2029 to a DSLAM (e.g., mini-DSLAM 1924). Alternatively, or in combination, power and guided electromagnetic waves 1914' can be supplied from a power line 1850' of a utility grid (having an inner waveguide as illustrated in FIG. 18G or 18H) to NID 1920 as an alternate or additional uplink (and/or downlink) path.

Turning now to FIG. 20C, a flow diagram of an example, non-limiting embodiment of a method 2030 for inducing electromagnetic waves on a transmission medium is shown. At step 2032, the waveguides 1865 and 1865' of FIGS. 18N-18T can be configured to generate first electromagnetic waves from a first communication signal (supplied, for example, by a communication device), and induce at step 2034 the first electromagnetic waves with "only" a fundamental wave mode at an interface of the transmission medium. In an embodiment, the interface can be an outer surface of the transmission medium as depicted in FIGS. 18Q and 18R. In another embodiment, the interface can be an inner layer of the transmission medium as depicted in FIGS. 18S and 18T. Turning now to FIG. 20D, a flow diagram of an example, non-limiting embodiment of a method 2040 for receiving electromagnetic waves from a transmission medium is shown. At step 2042, the wave-

guides 1865 and 1865' of FIGS. 18N-18T can be configured to receive second electromagnetic waves at an interface of a same or different transmission medium described in FIG. 20C. In an embodiment, the second electromagnetic waves can have "only" a fundamental wave mode. In other embodiments, the second electromagnetic waves may have a combination of wave modes such as a fundamental and non-fundamental wave modes. At step 2044, a second communication signal can be generated from the second electromagnetic waves for processing by, for example, a same or different communication device. The embodiments of FIGS. 20C and 20D can be applied to any embodiments described in the subject disclosure.

Turning now to FIG. 20E, a flow diagram of an example, non-limiting embodiment of a method 2050 for inducing electromagnetic waves on a transmission medium is shown. At step 2052, the waveguides 1865 and 1865' of FIGS. 18N-18W can be configured to generate first electromagnetic waves from a first communication signal (supplied, for example, by a communication device), and induce at step 2054 second electromagnetic waves with "only" a non-fundamental wave mode at an interface of the transmission medium. In an embodiment, the interface can be an outer surface of the transmission medium as depicted in FIGS. 18Q and 18R. In another embodiment, the interface can be an inner layer of the transmission medium as depicted in FIGS. 18S and 18T. Turning now to FIG. 20F, a flow diagram of an example, non-limiting embodiment of a method 2060 for receiving electromagnetic waves from a transmission medium is shown. At step 2062, the waveguides 1865 and 1865' of FIGS. 18N-18W can be configured to receive electromagnetic waves at an interface of a same or different transmission medium described in FIG. 20E. In an embodiment, the electromagnetic waves can have "only" a non-fundamental wave mode. In other embodiments, the electromagnetic waves may have a combination of wave modes such as a fundamental and non-fundamental wave modes. At step 2064, a second communication signal can be generated from the electromagnetic waves for processing by, for example, a same or different communication device. The embodiments of FIGS. 20E and 20F can be applied to any embodiments described in the subject disclosure.

While for purposes of simplicity of explanation, the respective processes are shown and described as a series of blocks in FIGS. 20A-20F, it is to be understood and appreciated that the claimed subject matter is not limited by the order of the blocks, as some blocks may occur in different orders and/or concurrently with other blocks from what is depicted and described herein. Moreover, not all illustrated blocks may be required to implement the methods described herein.

Referring now to FIG. 21, there is illustrated a block diagram of a computing environment in accordance with various aspects described herein. In order to provide additional context for various embodiments of the embodiments described herein, FIG. 21 and the following discussion are intended to provide a brief, general description of a suitable computing environment 2100 in which the various embodiments of the subject disclosure can be implemented. While the embodiments have been described above in the general context of computer-executable instructions that can run on one or more computers, those skilled in the art will recognize that the embodiments can be also implemented in combination with other program modules and/or as a combination of hardware and software.

Generally, program modules comprise routines, programs, components, data structures, etc., that perform par-

particular tasks or implement particular abstract data types. Moreover, those skilled in the art will appreciate that the inventive methods can be practiced with other computer system configurations, comprising single-processor or multiprocessor computer systems, minicomputers, mainframe computers, as well as personal computers, hand-held computing devices, microprocessor-based or programmable consumer electronics, and the like, each of which can be operatively coupled to one or more associated devices.

As used herein, a processing circuit includes processor as well as other application specific circuits such as an application specific integrated circuit, digital logic circuit, state machine, programmable gate array or other circuit that processes input signals or data and that produces output signals or data in response thereto. It should be noted that while any functions and features described herein in association with the operation of a processor could likewise be performed by a processing circuit.

The terms “first,” “second,” “third,” and so forth, as used in the claims, unless otherwise clear by context, is for clarity only and doesn’t otherwise indicate or imply any order in time. For instance, “a first determination,” “a second determination,” and “a third determination,” does not indicate or imply that the first determination is to be made before the second determination, or vice versa, etc.

The illustrated embodiments of the embodiments herein can be also practiced in distributed computing environments where certain tasks are performed by remote processing devices that are linked through a communications network. In a distributed computing environment, program modules can be located in both local and remote memory storage devices.

Computing devices typically comprise a variety of media, which can comprise computer-readable storage media and/or communications media, which two terms are used herein differently from one another as follows. Computer-readable storage media can be any available storage media that can be accessed by the computer and comprises both volatile and nonvolatile media, removable and non-removable media. By way of example, and not limitation, computer-readable storage media can be implemented in connection with any method or technology for storage of information such as computer-readable instructions, program modules, structured data or unstructured data.

Computer-readable storage media can comprise, but are not limited to, random access memory (RAM), read only memory (ROM), electrically erasable programmable read only memory (EEPROM), flash memory or other memory technology, compact disk read only memory (CD-ROM), digital versatile disk (DVD) or other optical disk storage, magnetic cassettes, magnetic tape, magnetic disk storage or other magnetic storage devices or other tangible and/or non-transitory media which can be used to store desired information. In this regard, the terms “tangible” or “non-transitory” herein as applied to storage, memory or computer-readable media, are to be understood to exclude only propagating transitory signals per se as modifiers and do not relinquish rights to all standard storage, memory or computer-readable media that are not only propagating transitory signals per se.

Computer-readable storage media can be accessed by one or more local or remote computing devices, e.g., via access requests, queries or other data retrieval protocols, for a variety of operations with respect to the information stored by the medium.

Communications media typically embody computer-readable instructions, data structures, program modules or other

structured or unstructured data in a data signal such as a modulated data signal, e.g., a carrier wave or other transport mechanism, and comprises any information delivery or transport media. The term “modulated data signal” or signals refers to a signal that has one or more of its characteristics set or changed in such a manner as to encode information in one or more signals. By way of example, and not limitation, communication media comprise wired media, such as a wired network or direct-wired connection, and wireless media such as acoustic, RF, infrared and other wireless media.

With reference again to FIG. 21, the example environment 2100 for transmitting and receiving signals via or forming at least part of a base station (e.g., base station devices 1504, macrocell site 1502, or base stations 1614) or central office (e.g., central office 1501 or 1611). At least a portion of the example environment 2100 can also be used for transmission devices 101 or 102. The example environment can comprise a computer 2102, the computer 2102 comprising a processing unit 2104, a system memory 2106 and a system bus 2108. The system bus 2108 couple’s system components including, but not limited to, the system memory 2106 to the processing unit 2104. The processing unit 2104 can be any of various commercially available processors. Dual microprocessors and other multiprocessor architectures can also be employed as the processing unit 2104.

The system bus 2108 can be any of several types of bus structure that can further interconnect to a memory bus (with or without a memory controller), a peripheral bus, and a local bus using any of a variety of commercially available bus architectures. The system memory 2106 comprises ROM 2110 and RAM 2112. A basic input/output system (BIOS) can be stored in a non-volatile memory such as ROM, erasable programmable read only memory (EPROM), EEPROM, which BIOS contains the basic routines that help to transfer information between elements within the computer 2102, such as during startup. The RAM 2112 can also comprise a high-speed RAM such as static RAM for caching data.

The computer 2102 further comprises an internal hard disk drive (HDD) 2114 (e.g., EIDE, SATA), which internal hard disk drive 2114 can also be configured for external use in a suitable chassis (not shown), a magnetic floppy disk drive (FDD) 2116, (e.g., to read from or write to a removable diskette 2118) and an optical disk drive 2120, (e.g., reading a CD-ROM disk 2122 or, to read from or write to other high capacity optical media such as the DVD). The hard disk drive 2114, magnetic disk drive 2116 and optical disk drive 2120 can be connected to the system bus 2108 by a hard disk drive interface 2124, a magnetic disk drive interface 2126 and an optical drive interface 2128, respectively. The interface 2124 for external drive implementations comprises at least one or both of Universal Serial Bus (USB) and Institute of Electrical and Electronics Engineers (IEEE) 1394 interface technologies. Other external drive connection technologies are within contemplation of the embodiments described herein.

The drives and their associated computer-readable storage media provide nonvolatile storage of data, data structures, computer-executable instructions, and so forth. For the computer 2102, the drives and storage media accommodate the storage of any data in a suitable digital format. Although the description of computer-readable storage media above refers to a hard disk drive (HDD), a removable magnetic diskette, and a removable optical media such as a CD or DVD, it should be appreciated by those skilled in the art that other types of storage media which are readable by a

computer, such as zip drives, magnetic cassettes, flash memory cards, cartridges, and the like, can also be used in the example operating environment, and further, that any such storage media can contain computer-executable instructions for performing the methods described herein.

A number of program modules can be stored in the drives and RAM 2112, comprising an operating system 2130, one or more application programs 2132, other program modules 2134 and program data 2136. All or portions of the operating system, applications, modules, and/or data can also be cached in the RAM 2112. The systems and methods described herein can be implemented utilizing various commercially available operating systems or combinations of operating systems. Examples of application programs 2132 that can be implemented and otherwise executed by processing unit 2104 include the diversity selection determining performed by transmission device 101 or 102.

A user can enter commands and information into the computer 2102 through one or more wired/wireless input devices, e.g., a keyboard 2138 and a pointing device, such as a mouse 2140. Other input devices (not shown) can comprise a microphone, an infrared (IR) remote control, a joystick, a game pad, a stylus pen, touch screen or the like. These and other input devices are often connected to the processing unit 2104 through an input device interface 2142 that can be coupled to the system bus 2108, but can be connected by other interfaces, such as a parallel port, an IEEE 1394 serial port, a game port, a universal serial bus (USB) port, an IR interface, etc.

A monitor 2144 or other type of display device can be also connected to the system bus 2108 via an interface, such as a video adapter 2146. It will also be appreciated that in alternative embodiments, a monitor 2144 can also be any display device (e.g., another computer having a display, a smart phone, a tablet computer, etc.) for receiving display information associated with computer 2102 via any communication means, including via the Internet and cloud-based networks. In addition to the monitor 2144, a computer typically comprises other peripheral output devices (not shown), such as speakers, printers, etc.

The computer 2102 can operate in a networked environment using logical connections via wired and/or wireless communications to one or more remote computers, such as a remote computer(s) 2148. The remote computer(s) 2148 can be a workstation, a server computer, a router, a personal computer, portable computer, microprocessor-based entertainment appliance, a peer device or other common network node, and typically comprises many or all of the elements described relative to the computer 2102, although, for purposes of brevity, only a memory/storage device 2150 is illustrated. The logical connections depicted comprise wired/wireless connectivity to a local area network (LAN) 2152 and/or larger networks, e.g., a wide area network (WAN) 2154. Such LAN and WAN networking environments are commonplace in offices and companies, and facilitate enterprise-wide computer networks, such as intranets, all of which can connect to a global communications network, e.g., the Internet.

When used in a LAN networking environment, the computer 2102 can be connected to the local network 2152 through a wired and/or wireless communication network interface or adapter 2156. The adapter 2156 can facilitate wired or wireless communication to the LAN 2152, which can also comprise a wireless AP disposed thereon for communicating with the wireless adapter 2156.

When used in a WAN networking environment, the computer 2102 can comprise a modem 2158 or can be connected

to a communications server on the WAN 2154 or has other means for establishing communications over the WAN 2154, such as by way of the Internet. The modem 2158, which can be internal or external and a wired or wireless device, can be connected to the system bus 2108 via the input device interface 2142. In a networked environment, program modules depicted relative to the computer 2102 or portions thereof, can be stored in the remote memory/storage device 2150. It will be appreciated that the network connections shown are example and other means of establishing a communications link between the computers can be used.

The computer 2102 can be operable to communicate with any wireless devices or entities operatively disposed in wireless communication, e.g., a printer, scanner, desktop and/or portable computer, portable data assistant, communications satellite, any piece of equipment or location associated with a wirelessly detectable tag (e.g., a kiosk, news stand, restroom), and telephone. This can comprise Wireless Fidelity (Wi-Fi) and BLUETOOTH® wireless technologies. Thus, the communication can be a predefined structure as with a conventional network or simply an ad hoc communication between at least two devices.

Wi-Fi can allow connection to the Internet from a couch at home, a bed in a hotel room or a conference room at work, without wires. Wi-Fi is a wireless technology similar to that used in a cell phone that enables such devices, e.g., computers, to send and receive data indoors and out; anywhere within the range of a base station. Wi-Fi networks use radio technologies called IEEE 802.11 (a, b, g, n, ac, ag etc.) to provide secure, reliable, fast wireless connectivity. A Wi-Fi network can be used to connect computers to each other, to the Internet, and to wired networks (which can use IEEE 802.3 or Ethernet). Wi-Fi networks operate in the unlicensed 2.4 and 5 GHz radio bands for example or with products that contain both bands (dual band), so the networks can provide real-world performance similar to the basic 10BaseT wired Ethernet networks used in many offices.

FIG. 22 presents an example embodiment 2200 of a mobile network platform 2210 that can implement and exploit one or more aspects of the disclosed subject matter described herein. In one or more embodiments, the mobile network platform 2210 can generate and receive signals transmitted and received by base stations (e.g., base station devices 1504, macrocell site 1502, or base stations 1614), central office (e.g., central office 1501 or 1611), or transmission device 101 or 102 associated with the disclosed subject matter. Generally, wireless network platform 2210 can comprise components, e.g., nodes, gateways, interfaces, servers, or disparate platforms, that facilitate both packet-switched (PS) (e.g., internet protocol (IP), frame relay, asynchronous transfer mode (ATM)) and circuit-switched (CS) traffic (e.g., voice and data), as well as control generation for networked wireless telecommunication. As a non-limiting example, wireless network platform 2210 can be included in telecommunications carrier networks, and can be considered carrier-side components as discussed elsewhere herein. Mobile network platform 2210 comprises CS gateway node(s) 2222 which can interface CS traffic received from legacy networks like telephony network(s) 2240 (e.g., public switched telephone network (PSTN), or public land mobile network (PLMN)) or a signaling system #7 (SS7) network 2270. Circuit switched gateway node(s) 2222 can authorize and authenticate traffic (e.g., voice) arising from such networks. Additionally, CS gateway node(s) 2222 can access mobility, or roaming, data generated through SS7 network 2270; for instance, mobility data

stored in a visited location register (VLR), which can reside in memory **2230**. Moreover, CS gateway node(s) **2222** interfaces CS-based traffic and signaling and PS gateway node(s) **2218**. As an example, in a 3GPP UMTS network, CS gateway node(s) **2222** can be realized at least in part in gateway GPRS support node(s) (GGSN). It should be appreciated that functionality and specific operation of CS gateway node(s) **2222**, PS gateway node(s) **2218**, and serving node(s) **2216**, is provided and dictated by radio technology(ies) utilized by mobile network platform **2210** for telecommunication.

In addition to receiving and processing CS-switched traffic and signaling, PS gateway node(s) **2218** can authorize and authenticate PS-based data sessions with served mobile devices. Data sessions can comprise traffic, or content(s), exchanged with networks external to the wireless network platform **2210**, like wide area network(s) (WANs) **2250**, enterprise network(s) **2270**, and service network(s) **2280**, which can be embodied in local area network(s) (LANs), can also be interfaced with mobile network platform **2210** through PS gateway node(s) **2218**. It is to be noted that WANs **2250** and enterprise network(s) **2260** can embody, at least in part, a service network(s) like IP multimedia subsystem (IMS). Based on radio technology layer(s) available in technology resource(s) **2217**, packet-switched gateway node(s) **2218** can generate packet data protocol contexts when a data session is established; other data structures that facilitate routing of packetized data also can be generated. To that end, in an aspect, PS gateway node(s) **2218** can comprise a tunnel interface (e.g., tunnel termination gateway (TTG) in 3GPP UMTS network(s) (not shown)) which can facilitate packetized communication with disparate wireless network(s), such as Wi-Fi networks.

In embodiment **2200**, wireless network platform **2210** also comprises serving node(s) **2216** that, based upon available radio technology layer(s) within technology resource(s) **2217**, convey the various packetized flows of data streams received through PS gateway node(s) **2218**. It is to be noted that for technology resource(s) **2217** that rely primarily on CS communication, server node(s) can deliver traffic without reliance on PS gateway node(s) **2218**; for example, server node(s) can embody at least in part a mobile switching center. As an example, in a 3GPP UMTS network, serving node(s) **2216** can be embodied in serving GPRS support node(s) (SGSN).

For radio technologies that exploit packetized communication, server(s) **2214** in wireless network platform **2210** can execute numerous applications that can generate multiple disparate packetized data streams or flows, and manage (e.g., schedule, queue, format . . .) such flows. Such application(s) can comprise add-on features to standard services (for example, provisioning, billing, customer support . . .) provided by wireless network platform **2210**. Data streams (e.g., content(s) that are part of a voice call or data session) can be conveyed to PS gateway node(s) **2218** for authorization/authentication and initiation of a data session, and to serving node(s) **2216** for communication thereafter. In addition to application server, server(s) **2214** can comprise utility server(s), a utility server can comprise a provisioning server, an operations and maintenance server, a security server that can implement at least in part a certificate authority and firewalls as well as other security mechanisms, and the like. In an aspect, security server(s) secure communication served through wireless network platform **2210** to ensure network's operation and data integrity in addition to authorization and authentication procedures that CS gateway node(s) **2222** and PS gateway node(s) **2218** can

enact. Moreover, provisioning server(s) can provision services from external network(s) like networks operated by a disparate service provider; for instance, WAN **2250** or Global Positioning System (GPS) network(s) (not shown). Provisioning server(s) can also provision coverage through networks associated to wireless network platform **2210** (e.g., deployed and operated by the same service provider), such as the distributed antennas networks shown in FIG. **1(s)** that enhance wireless service coverage by providing more network coverage. Repeater devices such as those shown in FIGS. **7**, **8**, and **9** also improve network coverage in order to enhance subscriber service experience by way of UE **2275**.

It is to be noted that server(s) **2214** can comprise one or more processors configured to confer at least in part the functionality of macro network platform **2210**. To that end, the one or more processor can execute code instructions stored in memory **2230**, for example. It should be appreciated that server(s) **2214** can comprise a content manager **2215**, which operates in substantially the same manner as described hereinbefore.

In example embodiment **2200**, memory **2230** can store information related to operation of wireless network platform **2210**. Other operational information can comprise provisioning information of mobile devices served through wireless platform network **2210**, subscriber databases; application intelligence, pricing schemes, e.g., promotional rates, flat-rate programs, couponing campaigns; technical specification(s) consistent with telecommunication protocols for operation of disparate radio, or wireless, technology layers; and so forth. Memory **2230** can also store information from at least one of telephony network(s) **2240**, WAN **2250**, enterprise network(s) **2270**, or SS7 network **2260**. In an aspect, memory **2230** can be, for example, accessed as part of a data store component or as a remotely connected memory store.

In order to provide a context for the various aspects of the disclosed subject matter, FIG. **22**, and the following discussion, are intended to provide a brief, general description of a suitable environment in which the various aspects of the disclosed subject matter can be implemented. While the subject matter has been described above in the general context of computer-executable instructions of a computer program that runs on a computer and/or computers, those skilled in the art will recognize that the disclosed subject matter also can be implemented in combination with other program modules. Generally, program modules comprise routines, programs, components, data structures, etc. that perform particular tasks and/or implement particular abstract data types.

FIG. **23** depicts an illustrative embodiment of a communication device **2300**. The communication device **2300** can serve as an illustrative embodiment of devices such as mobile devices and in-building devices referred to by the subject disclosure (e.g., in FIGS. **15**, **16A** and **16B**).

The communication device **2300** can comprise a wireline and/or wireless transceiver **2302** (herein transceiver **2302**), a user interface (UI) **2304**, a power supply **2314**, a location receiver **2316**, a motion sensor **2318**, an orientation sensor **2320**, and a controller **2306** for managing operations thereof. The transceiver **2302** can support short-range or long-range wireless access technologies such as Bluetooth®, ZigBee®, WiFi, DECT, or cellular communication technologies, just to mention a few (Bluetooth® and ZigBee® are trademarks registered by the Bluetooth® Special Interest Group and the ZigBee® Alliance, respectively). Cellular technologies can include, for example, CDMA-1x, UMTS/HSDPA, GSM/GPRS, TDMA/EDGE, EV/DO, WiMAX, SDR, LTE, as

well as other next generation wireless communication technologies as they arise. The transceiver **2302** can also be adapted to support circuit-switched wireline access technologies (such as PSTN), packet-switched wireline access technologies (such as TCP/IP, VoIP, etc.), and combinations thereof.

The UI **2304** can include a depressible or touch-sensitive keypad **2308** with a navigation mechanism such as a roller ball, a joystick, a mouse, or a navigation disk for manipulating operations of the communication device **2300**. The keypad **2308** can be an integral part of a housing assembly of the communication device **2300** or an independent device operably coupled thereto by a tethered wireline interface (such as a USB cable) or a wireless interface supporting for example Bluetooth®. The keypad **2308** can represent a numeric keypad commonly used by phones, and/or a QWERTY keypad with alphanumeric keys. The UI **2304** can further include a display **2310** such as monochrome or color LCD (Liquid Crystal Display), OLED (Organic Light Emitting Diode) or other suitable display technology for conveying images to an end user of the communication device **2300**. In an embodiment where the display **2310** is touch-sensitive, a portion or all of the keypad **2308** can be presented by way of the display **2310** with navigation features.

The display **2310** can use touch screen technology to also serve as a user interface for detecting user input. As a touch screen display, the communication device **2300** can be adapted to present a user interface having graphical user interface (GUI) elements that can be selected by a user with a touch of a finger. The touch screen display **2310** can be equipped with capacitive, resistive or other forms of sensing technology to detect how much surface area of a user's finger has been placed on a portion of the touch screen display. This sensing information can be used to control the manipulation of the GUI elements or other functions of the user interface. The display **2310** can be an integral part of the housing assembly of the communication device **2300** or an independent device communicatively coupled thereto by a tethered wireline interface (such as a cable) or a wireless interface.

The UI **2304** can also include an audio system **2312** that utilizes audio technology for conveying low volume audio (such as audio heard in proximity of a human ear) and high volume audio (such as speakerphone for hands free operation). The audio system **2312** can further include a microphone for receiving audible signals of an end user. The audio system **2312** can also be used for voice recognition applications. The UI **2304** can further include an image sensor **2313** such as a charged coupled device (CCD) camera for capturing still or moving images.

The power supply **2314** can utilize common power management technologies such as replaceable and rechargeable batteries, supply regulation technologies, and/or charging system technologies for supplying energy to the components of the communication device **2300** to facilitate long-range or short-range portable communications. Alternatively, or in combination, the charging system can utilize external power sources such as DC power supplied over a physical interface such as a USB port or other suitable tethering technologies.

The location receiver **2316** can utilize location technology such as a global positioning system (GPS) receiver capable of assisted GPS for identifying a location of the communication device **2300** based on signals generated by a constellation of GPS satellites, which can be used for facilitating location services such as navigation. The motion sensor **2318** can utilize motion sensing technology such as an

accelerometer, a gyroscope, or other suitable motion sensing technology to detect motion of the communication device **2300** in three-dimensional space. The orientation sensor **2320** can utilize orientation sensing technology such as a magnetometer to detect the orientation of the communication device **2300** (north, south, west, and east, as well as combined orientations in degrees, minutes, or other suitable orientation metrics).

The communication device **2300** can use the transceiver **2302** to also determine a proximity to a cellular, WiFi, Bluetooth®, or other wireless access points by sensing techniques such as utilizing a received signal strength indicator (RSSI) and/or signal time of arrival (TOA) or time of flight (TOF) measurements. The controller **2306** can utilize computing technologies such as a microprocessor, a digital signal processor (DSP), programmable gate arrays, application specific integrated circuits, and/or a video processor with associated storage memory such as Flash, ROM, RAM, SRAM, DRAM or other storage technologies for executing computer instructions, controlling, and processing data supplied by the aforementioned components of the communication device **2300**.

Other components not shown in FIG. **23** can be used in one or more embodiments of the subject disclosure. For instance, the communication device **2300** can include a slot for adding or removing an identity module such as a Subscriber Identity Module (SIM) card or Universal Integrated Circuit Card (UICC). SIM or UICC cards can be used for identifying subscriber services, executing programs, storing subscriber data, and so on.

In the subject specification, terms such as “store,” “storage,” “data store,” data storage,” “database,” and substantially any other information storage component relevant to operation and functionality of a component, refer to “memory components,” or entities embodied in a “memory” or components comprising the memory. It will be appreciated that the memory components described herein can be either volatile memory or nonvolatile memory, or can comprise both volatile and nonvolatile memory, by way of illustration, and not limitation, volatile memory, non-volatile memory, disk storage, and memory storage. Further, non-volatile memory can be included in read only memory (ROM), programmable ROM (PROM), electrically programmable ROM (EPROM), electrically erasable ROM (EEPROM), or flash memory. Volatile memory can comprise random access memory (RAM), which acts as external cache memory. By way of illustration and not limitation, RAM is available in many forms such as synchronous RAM (SRAM), dynamic RAM (DRAM), synchronous DRAM (SDRAM), double data rate SDRAM (DDR SDRAM), enhanced SDRAM (ESDRAM), Synchlink DRAM (SLDRAM), and direct Rambus RAM (DRRAM). Additionally, the disclosed memory components of systems or methods herein are intended to comprise, without being limited to comprising, these and any other suitable types of memory.

Moreover, it will be noted that the disclosed subject matter can be practiced with other computer system configurations, comprising single-processor or multiprocessor computer systems, mini-computing devices, mainframe computers, as well as personal computers, hand-held computing devices (e.g., PDA, phone, smartphone, watch, tablet computers, netbook computers, etc.), microprocessor-based or programmable consumer or industrial electronics, and the like. The illustrated aspects can also be practiced in distributed computing environments where tasks are performed by remote processing devices that are linked through a com-

munications network; however, some if not all aspects of the subject disclosure can be practiced on stand-alone computers. In a distributed computing environment, program modules can be located in both local and remote memory storage devices.

Some of the embodiments described herein can also employ artificial intelligence (AI) to facilitate automating one or more features described herein. For example, artificial intelligence can be used in optional training controller 230 evaluate and select candidate frequencies, modulation schemes, MIMO modes, and/or guided wave modes in order to maximize transfer efficiency. The embodiments (e.g., in connection with automatically identifying acquired cell sites that provide a maximum value/benefit after addition to an existing communication network) can employ various AI-based schemes for carrying out various embodiments thereof. Moreover, the classifier can be employed to determine a ranking or priority of the each cell site of the acquired network. A classifier is a function that maps an input attribute vector, $x=(x_1, x_2, x_3, x_4, \dots, x_n)$, to a confidence that the input belongs to a class, that is, $f(x)=\text{confidence (class)}$. Such classification can employ a probabilistic and/or statistical-based analysis (e.g., factoring into the analysis utilities and costs) to prognose or infer an action that a user desires to be automatically performed. A support vector machine (SVM) is an example of a classifier that can be employed. The SVM operates by finding a hypersurface in the space of possible inputs, which the hypersurface attempts to split the triggering criteria from the non-triggering events. Intuitively, this makes the classification correct for testing data that is near, but not identical to training data. Other directed and undirected model classification approaches comprise, e.g., naïve Bayes, Bayesian networks, decision trees, neural networks, fuzzy logic models, and probabilistic classification models providing different patterns of independence can be employed. Classification as used herein also is inclusive of statistical regression that is utilized to develop models of priority.

As will be readily appreciated, one or more of the embodiments can employ classifiers that are explicitly trained (e.g., via a generic training data) as well as implicitly trained (e.g., via observing UE behavior, operator preferences, historical information, receiving extrinsic information). For example, SVMs can be configured via a learning or training phase within a classifier constructor and feature selection module. Thus, the classifier(s) can be used to automatically learn and perform a number of functions, including but not limited to determining according to a predetermined criteria which of the acquired cell sites will benefit a maximum number of subscribers and/or which of the acquired cell sites will add minimum value to the existing communication network coverage, etc.

As used in some contexts in this application, in some embodiments, the terms “component,” “system” and the like are intended to refer to, or comprise, a computer-related entity or an entity related to an operational apparatus with one or more specific functionalities, wherein the entity can be either hardware, a combination of hardware and software, software, or software in execution. As an example, a component may be, but is not limited to being, a process running on a processor, a processor, an object, an executable, a thread of execution, computer-executable instructions, a program, and/or a computer. By way of illustration and not limitation, both an application running on a server and the server can be a component. One or more components may reside within a process and/or thread of execution and a component may be localized on one computer and/or dis-

tributed between two or more computers. In addition, these components can execute from various computer readable media having various data structures stored thereon. The components may communicate via local and/or remote processes such as in accordance with a signal having one or more data packets (e.g., data from one component interacting with another component in a local system, distributed system, and/or across a network such as the Internet with other systems via the signal). As another example, a component can be an apparatus with specific functionality provided by mechanical parts operated by electric or electronic circuitry, which is operated by a software or firmware application executed by a processor, wherein the processor can be internal or external to the apparatus and executes at least a part of the software or firmware application. As yet another example, a component can be an apparatus that provides specific functionality through electronic components without mechanical parts, the electronic components can comprise a processor therein to execute software or firmware that confers at least in part the functionality of the electronic components. While various components have been illustrated as separate components, it will be appreciated that multiple components can be implemented as a single component, or a single component can be implemented as multiple components, without departing from example embodiments.

Further, the various embodiments can be implemented as a method, apparatus or article of manufacture using standard programming and/or engineering techniques to produce software, firmware, hardware or any combination thereof to control a computer to implement the disclosed subject matter. The term “article of manufacture” as used herein is intended to encompass a computer program accessible from any computer-readable device or computer-readable storage/communications media. For example, computer readable storage media can include, but are not limited to, magnetic storage devices (e.g., hard disk, floppy disk, magnetic strips), optical disks (e.g., compact disk (CD), digital versatile disk (DVD)), smart cards, and flash memory devices (e.g., card, stick, key drive). Of course, those skilled in the art will recognize many modifications can be made to this configuration without departing from the scope or spirit of the various embodiments.

In addition, the words “example” and “exemplary” are used herein to mean serving as an instance or illustration. Any embodiment or design described herein as “example” or “exemplary” is not necessarily to be construed as preferred or advantageous over other embodiments or designs. Rather, use of the word example or exemplary is intended to present concepts in a concrete fashion. As used in this application, the term “or” is intended to mean an inclusive “or” rather than an exclusive “or”. That is, unless specified otherwise or clear from context, “X employs A or B” is intended to mean any of the natural inclusive permutations. That is, if X employs A; X employs B; or X employs both A and B, then “X employs A or B” is satisfied under any of the foregoing instances. In addition, the articles “a” and “an” as used in this application and the appended claims should generally be construed to mean “one or more” unless specified otherwise or clear from context to be directed to a singular form.

Moreover, terms such as “user equipment,” “mobile station,” “mobile,” subscriber station,” “access terminal,” “terminal,” “handset,” “mobile device” (and/or terms representing similar terminology) can refer to a wireless device utilized by a subscriber or user of a wireless communication service to receive or convey data, control, voice, video,

sound, gaming or substantially any data-stream or signaling-stream. The foregoing terms are utilized interchangeably herein and with reference to the related drawings.

Furthermore, the terms “user,” “subscriber,” “customer,” “consumer” and the like are employed interchangeably throughout, unless context warrants particular distinctions among the terms. It should be appreciated that such terms can refer to human entities or automated components supported through artificial intelligence (e.g., a capacity to make inference based, at least, on complex mathematical formalisms), which can provide simulated vision, sound recognition and so forth.

As employed herein, the term “processor” can refer to substantially any computing processing unit or device comprising, but not limited to comprising, single-core processors; single-processors with software multithread execution capability; multi-core processors; multi-core processors with software multithread execution capability; multi-core processors with hardware multithread technology; parallel platforms; and parallel platforms with distributed shared memory. Additionally, a processor can refer to an integrated circuit, an application specific integrated circuit (ASIC), a digital signal processor (DSP), a field programmable gate array (FPGA), a programmable logic controller (PLC), a complex programmable logic device (CPLD), a discrete gate or transistor logic, discrete hardware components or any combination thereof designed to perform the functions described herein. Processors can exploit nano-scale architectures such as, but not limited to, molecular and quantum-dot based transistors, switches and gates, in order to optimize space usage or enhance performance of user equipment. A processor can also be implemented as a combination of computing processing units.

As used herein, terms such as “data storage,” “data storage,” “database,” and substantially any other information storage component relevant to operation and functionality of a component, refer to “memory components,” or entities embodied in a “memory” or components comprising the memory. It will be appreciated that the memory components or computer-readable storage media, described herein can be either volatile memory or nonvolatile memory or can include both volatile and nonvolatile memory.

What has been described above includes mere examples of various embodiments. It is, of course, not possible to describe every conceivable combination of components or methodologies for purposes of describing these examples, but one of ordinary skill in the art can recognize that many further combinations and permutations of the present embodiments are possible. Accordingly, the embodiments disclosed and/or claimed herein are intended to embrace all such alterations, modifications and variations that fall within the spirit and scope of the appended claims. Furthermore, to the extent that the term “includes” is used in either the detailed description or the claims, such term is intended to be inclusive in a manner similar to the term “comprising” as “comprising” is interpreted when employed as a transitional word in a claim.

In addition, a flow diagram may include a “start” and/or “continue” indication. The “start” and “continue” indications reflect that the steps presented can optionally be incorporated in or otherwise used in conjunction with other routines. In this context, “start” indicates the beginning of the first step presented and may be preceded by other activities not specifically shown. Further, the “continue” indication reflects that the steps presented may be performed multiple times and/or may be succeeded by other activities not specifically shown. Further, while a flow diagram indi-

cates a particular ordering of steps, other orderings are likewise possible provided that the principles of causality are maintained.

As may also be used herein, the term(s) “operably coupled to”, “coupled to”, and/or “coupling” includes direct coupling between items and/or indirect coupling between items via one or more intervening items. Such items and intervening items include, but are not limited to, junctions, communication paths, components, circuit elements, circuits, functional blocks, and/or devices. As an example of indirect coupling, a signal conveyed from a first item to a second item may be modified by one or more intervening items by modifying the form, nature or format of information in a signal, while one or more elements of the information in the signal are nevertheless conveyed in a manner than can be recognized by the second item. In a further example of indirect coupling, an action in a first item can cause a reaction on the second item, as a result of actions and/or reactions in one or more intervening items.

Although specific embodiments have been illustrated and described herein, it should be appreciated that any arrangement which achieves the same or similar purpose may be substituted for the embodiments described or shown by the subject disclosure. The subject disclosure is intended to cover any and all adaptations or variations of various embodiments. Combinations of the above embodiments, and other embodiments not specifically described herein, can be used in the subject disclosure. For instance, one or more features from one or more embodiments can be combined with one or more features of one or more other embodiments. In one or more embodiments, features that are positively recited can also be negatively recited and excluded from the embodiment with or without replacement by another structural and/or functional feature. The steps or functions described with respect to the embodiments of the subject disclosure can be performed in any order. The steps or functions described with respect to the embodiments of the subject disclosure can be performed alone or in combination with other steps or functions of the subject disclosure, as well as from other embodiments or from other steps that have not been described in the subject disclosure. Further, more than or less than all of the features described with respect to an embodiment can also be utilized.

What is claimed is:

1. A method, comprising:

generating, by a waveguide system, instances of first electromagnetic waves that combine to form a combined electromagnetic wave having a fundamental wave mode, wherein a non-fundamental wave mode is at least substantially absent from the combined electromagnetic wave, and wherein the combined electromagnetic wave has a non-optical operating frequency; and

directing, by the waveguide system, the combined electromagnetic wave to an interface of a transmission medium for guiding propagation of the combined electromagnetic wave without utilizing an electrical return path.

2. The method of claim **1**, wherein the waveguide system comprises waveguide slots that generate the instances of the first electromagnetic waves.

3. The method of claim **2**, wherein a pair of the waveguide slots are configured to have a relative position to each other to generate a pair of the first electromagnetic waves having electric field orientations of substantially opposing directions to produce the combined electromagnetic wave having the fundamental wave mode.

4. The method of claim 2, wherein a first instance of the instances of the first electromagnetic waves is radiated by a first slot of the waveguide slots, and wherein a second instance of the instances of the first electromagnetic waves is radiated by a second slot of the waveguide slots.

5. The method of claim 4, wherein the waveguide slots are located on a cover of the waveguide system, wherein a surface of the cover is divided into an inner median region and an outer median region, wherein currents flowing on the surface in the inner median region differ from currents flowing on the surface in the outer median region, and wherein placement of the first slot and the second slot at certain locations relative to the inner median region and the outer median region having a certain circumferential distance between the first slot and the second slot, results in first electric fields of the first instance of the first electromagnetic waves being substantially symmetrical to second electric fields of the second instance of the first electromagnetic waves, thereby producing the combined electromagnetic wave having the fundamental wave mode.

6. The method of claim 1, wherein the waveguide system comprises transmitters positioned around the transmission medium for generating the instances of the first electromagnetic waves.

7. The method of claim 6, wherein first and second transmitters of the transmitters are adapted to generate first and second instances of the first electromagnetic waves having substantially symmetrical electric fields that enable generation of the fundamental wave mode.

8. The method of claim 7, wherein the first and second transmitters are symmetrically positioned around the transmission medium.

9. The method of claim 6, wherein each transmitter of the transmitters comprises a microwave transmitter.

10. The method of claim 1, wherein the waveguide system comprises a waveguide structure for directing the combined electromagnetic wave to the interface of the transmission medium.

11. The method of claim 10, wherein the waveguide structure has a tapered cross-section.

12. The method of claim 10, wherein the waveguide structure has a cylindrical cross-section.

13. The method of claim 1, wherein the interface of the transmission medium comprises a core, and wherein the combined electromagnetic wave is guided and bound to the core.

14. The method of claim 1, wherein the interface of the transmission medium comprises an outer surface of an insulated conductor.

15. The method of claim 1, wherein the interface of the transmission medium comprises an outer surface of an uninsulated conductor.

16. The method of claim 1, further comprising receiving, by the waveguide system, second electromagnetic waves guided by the transmission medium.

17. A system, comprising:

a plurality of microwave transmitters for launching instances of first electromagnetic waves that combine to produce a combined electromagnetic wave substantially having a fundamental wave mode; and

a waveguide for directing the combined electromagnetic wave to an interface of a transmission medium for guiding propagation of the combined electromagnetic wave without utilizing an electrical return path.

18. The system of claim 17, wherein the waveguide comprises first and second slots that radiate the instances of the first electromagnetic waves with substantially symmetrical electric fields which when combined produce the combined electromagnetic wave substantially having the fundamental wave mode.

19. The system of claim 17, wherein the plurality of microwave transmitters surround the transmission medium for generating the instances of the first electromagnetic waves.

20. The system of claim 17, wherein a first and a second of the plurality of microwave transmitters are adapted to adjust phases of first and second instances of the first electromagnetic waves to generate the first and the second instances of the first electromagnetic waves having substantially symmetrical electric fields which when combined produce the combined electromagnetic wave substantially having the fundamental wave mode.

21. The system of claim 17, further comprising a receiver for receiving, via the waveguide, second electromagnetic waves.

22. The system of claim 17, wherein the transmission medium comprises a core, an insulated conductor, or an uninsulated conductor, and wherein the combined electromagnetic wave are guided by the core, the insulated conductor, or the uninsulated conductor.

23. A non-transitory machine-readable storage medium, comprising executable instructions that, when executed by a processor of a waveguide system, facilitate performance of operations, comprising:

obtaining operational parameters for configuring a plurality of launchers of the waveguide system; and

configuring the plurality of launchers according to the operational parameters to generate instances of electromagnetic waves that combined to produce a combined electromagnetic wave having a selected wave mode and a non-optical operating frequency, wherein the waveguide system comprises a waveguide structure to direct the combined electromagnetic wave to an interface of a transmission medium for guiding propagation of the combined electromagnetic wave without utilizing an electrical return path.

24. The non-transitory machine-readable storage medium of claim 23, wherein the plurality of launchers comprise a first slot and a second slot, wherein the first slot radiates a first instance of the instances of the electromagnetic waves, wherein the second slot radiates a second instance of the instances of the electromagnetic waves, and wherein electric fields of the first instance of the instances of the electromagnetic waves and the second instance of the instances of the electromagnetic waves are approximately symmetrical.

25. The non-transitory machine-readable storage medium of claim 23, wherein the plurality of launchers comprise a first launcher and a second launcher, wherein the first launcher adjusts a first phase of a first instance of the instances of the electromagnetic waves, wherein the second launcher adjusts a second phase of a second instance of the instances of the electromagnetic waves, and wherein electric fields of the first instance and the second instance are approximately symmetrical.

26. The non-transitory machine-readable storage medium of claim 23, wherein the selected wave mode is substantially a fundamental wave mode.